OFFICE OF THE CITY ATTORNEY CHARLES PARKIN, City Attorney 411 West Ocean Boulevard, 9th Floor Long Beach, CA 90802-4664

FIFTH AMENDMENT TO AGREEMENT NO. 33938

THIS FIFTH AMENDMENT TO AGREEMENT NO. 33938 is made and entered, in duplicate, as of May 19, 2021 for reference purposes only, pursuant to a minute order adopted by the City Council of the City of Long Beach at its meeting on May 18, 2021, by and between HDR ENGINEERING, INC., a Nebraska corporation ("Consultant"), with a place of business at 3230 El Camino Real, Suite 200, Irvine, California 92602, and the CITY OF LONG BEACH, a municipal corporation ("City").

WHEREAS, City and Consultant (the "Parties") entered into Agreement No. 33938 (the "Agreement") whereby Consultant agreed to provide design services for the Shoemaker Bridge replacement project; and

WHEREAS, the Parties entered into a First Amendment to the Agreement to decrease the Agreement amount by \$739,654.27 for a total not to exceed amount of \$3,960,345.73 and attach a revised scope of work and a revised rate sheet; and

WHEREAS, the Parties entered into a Second Amendment to the Agreement to extend the term to August 30, 2019 and add \$2,491,104.24 to the Agreement for a total not to exceed amount of \$6,451,449.97; and

WHEREAS, the Parties entered into a Third Amendment to extend the term to August 30, 2020; and

WHEREAS, the Parties entered into a Fourth Amendment to the Agreement to add \$524,937 for a total not to exceed amount of \$6,976,386.97 and attach an additional scope of work and a revised rate sheet; and

WHEREAS, the Parties desire to add \$22,550,235 to the Agreement for a total not to exceed amount of \$29,526,622, extend the term one (1) additional four-year period, revise the Additional Costs and Redesign language, attach an additional scope of work and a revised rate sheet, and update the City's representative;

NOW, THEREFORE, in consideration of the mutual terms, covenants, and conditions herein contained, the Parties agree as follows:

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

22

23

24

25

26

27

28

1. Section 1.A of the Agreement is hereby amended to read as follows:

Consultant shall furnish specialized services more particularly "A. described in Exhibit "A", attached to the Agreement and incorporated by this reference, in accordance with the standards of the profession, and City shall pay for these services in the manner described below, not to exceed Twenty-Nine Million Five Hundred Seventy-Six Thousand Six Hundred Twenty-Two Dollars (\$29,526,622), at the rates or charges shown in Exhibit "B"."

- 2. Section 2 of the Agreement is hereby amended to read as follows:
- "2. TERM. The term of this Agreement shall commence at midnight on August 31, 2015, and shall terminate at 11:59 p.m. on August 30, 2024, unless sooner terminated as provided in this Agreement, or unless the services or the Project is completed sooner."
- 3. Section 13.B. of the Agreement is hereby amended to read as follows:
 - "B. If the Project involves construction and the scope of work requires Consultant to prepare plans and specifications with an estimate of the cost of construction, then Consultant may be required to modify the plans and specification, any construction documents relating to the plans and specifications, and Consultant's estimate, at Consultant's direct labor rates including overhead but with no additional profit, when the lowest bid for construction received by City exceeds by more than ten (10%) of Consultant's estimate. This modification shall be submitted to the City within four (4) months after the date on which the original construction bids were received by the City. Approving agency review and approval time for the modification is not included in the four (4) months. This requirement shall not apply if the City receives only one (1) construction bid for the Project or if the modifications include changes to the Bridge Types."
- The Scope of Work in Exhibit "A" to the Agreement, Exhibit "A-1" to the First Amendment and Exhibit "A-2" to the Fourth Amendment is hereby amended to

include additional services more particularly described in Exhibit "A-3", attached hereto and incorporated by this reference.

- 5. The Rates in Exhibit "B-2" are hereby amended in accordance with Exhibit "B-3", attached hereto and incorporated by this reference.
- 6. The City Representative named in Exhibit "C" to the Agreement is hereby amended in accordance with Exhibit "C-1", attached hereto and incorporated by this reference.
- 7. Except as expressly modified herein, all of the terms and conditions contained in Agreement No. 33938 are ratified and confirmed and shall remain in full force and effect.

///

///

| | | '

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

||||

///

///

///

17 | ///

18 ///

19 ///

20 ///

21 ///

22 | ///

23 ///

24 ///

⁻⁻ ∥″

25 | ///

26 ///

27 | ///

28 | ///

OFFICE OF THE CITY ATTORNEY CHARLES PARKIN, City Attorney 411 West Ocean Boulevard, 9th Floor Long Beach, CA 90802-4664


IN WITNESS WI	HEREOF, th	e Parties have caused this document to be
duly executed with all formalitie	s required b	y law as of the date first stated above.
		HDR ENGINEERING, INC., a Nebraska corporation
 5/26/20211	_, 2021	Name_Thomas T. Kim, P.E. Title Sr. Vice President
 5/26/2021	, 2021	By Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z
		"Consultant" CITY OF LONG BEACH, a municipal corporation
4	, 2021	By Sinda J. Jahim City Manager EXECUTED PURSUANT "City" TO SECTION 301 OF THE CITY CHARTER.
 This Fifth Amend 6-2		THE CITY CHARTER. eement No. 33938 is approved as to form on
		By Deputy

IN WITNESS WHEREOF, the Parties have caused this document to be 1 duly executed with all formalities required by law as of the date first stated above. 2 3 HDR ENGINEERING, INC., a Nebraska corporation 4 5/26/2021 , 2021 5 Βv Name Thomas T. Kim, P.E. 6 Title Sr. Vice President 7 5/26/2021 , 2021 By_ Name Kip Field 8 Title Sr. Vice President 9 "Consultant" 10 CITY OF LONG BEACH, a municipal 11 corporation OFFICE OF THE CITY ATTORNEY CHARLES PARKIN, City Attorney 411 West Ocean Boulevard, 9th Floor Long Beach, CA 90802-4664 12 , 2021 By City Manager 13 "City" 14 This Fifth Amendment to Agreement No. 33938 is approved as to form on 15 , 2021. 16 17 CHARLES PARKIN, City Attorney 18 Ву ___ 19 Deputy 20 21 22 23 24 25 26 27 28

4

ARW:bg A15-00965 01231442.DOC

Exhibit A-3 Scope of Work






Revised Scope of Services

Shoemaker Bridge Replacement Project
Final Design and Bid Phase Support Services

City of Long Beach, CA
March 23, 2021





City of Long Beach Scope of Work for Final Design Services for Shoemaker Bridge Replacement Project March 2021

Introduction

HDR is pleased to present the following scope of work for the completion of final design services for the Shoemaker Bridge Replacement Project. HDR will be supported by a team of specialty subconsultants to assist HDR in completing this scope of services as listed below:

Firm Name	Certification	Role/Responsibility
HDR		PM, roadway, structures (LA River Bridge, roundabout structure independent check, LA River Bridge bike/ped structure), urban design, bridge architecture
Guida	SBE	Surveys and mapping
Twining		Geotechnical
Evans and Walker	WSBE/VSBE	Oil field impact assessment
TY Lin		Structures (roundabout structure, LA River Bridge independent check)
IDC	DBE	Structures (7 th Street pedestrian bridge, retaining walls)
LIN	DBE/SBE/VSBE	Electrical design, traffic control design
AirX	WBE/SBE	Potholing
PGI	DBE/SBE	ACM and LBP surveys
Interphase Environmental	DBE/SBE	Soil and groundwater sampling
Orange Coast Analytical	VSBE/SBE/WBE	Environmental laboratory analytical
Southwest Geophysics		Underground utility clearance
TMI	MBE	Traffic control
American Integrated Services	MBE	Investigation-derived waste disposal
MBI Media	DBE/SBE	Public outreach
RVA	DBE/SBE	USACE coordination
Tatsumi & Partners	DBE	Landscape/irrigation design

When HDR is referenced in the scope below, it is referencing HDR Team as outlined above meaning any of the above members of the HDR team could be completing the work depending upon its nature.

A map prepared by the City of Long Beach showing the limits of the Shoemaker Bridge Replacement Project and the adjacent Shoreline Drive Realignment Project is included in **Attachment 1**. The construction contract package for the Shoreline Drive Realignment Project is being developed under a separate final design contract by the City, with the final design work





assumed to be conducted concurrently with work covered within this scope. It is assumed that the Shoreline Realignment Project will be constructed in advance of the Shoemaker Bridge Replacement Project, and the improvements included as part of that project (see **Attachment 1**) will serve as the base condition for this project. The major elements of the Shoemaker Bridge Replacement Project to be covered as part of this scope of services include the following:

- Removal of existing Shoemaker Bridge over LA River and joining local street connectors on east and west sides of river
- Construction of new LA River Bridge to provide new connection from SR 710 to the west to downtown Long Beach to the east
- Construction of new SR 710 connector and associated freeway modifications along SR 710 on the west side of the LA River
- Construction of new roundabout structure on east side of LA River to provide access from SR 710 connector to adjoining local streets
- 5. Construction of street modifications along adjoining local streets tying into roundabout including
 - Shoreline Drive (proposed per Shoreline Realignment Project) from north of Broadway to roundabout
 - b. Sixth Street from existing West Shoreline Drive to Daisy Avenue (Sixth Street will not connect to roundabout)
 - c. Seventh Street from roundabout to Daisy Avenue
- 6. Construction of bike/ped structure to connect the Observation Platform (future bike/ped path) on new LA River Bridge to the existing LA River Trail along east bank of LA River
- 7. Construction of new pedestrian bridge over 7th Street to replace the existing bridge located at Maine Avenue.
- 8. Demolition of existing SD-1 Pump Station to accommodate roundabout and Construction of new SD-1 Pump Station to replace existing
- Construction of park improvements within Cesar Chavez park including bike/ped paths, new landscape/hardscape elements, water quality features, and associated grading
- 10. Utility relocations needed to accommodate all local street work and park improvements included as part of Item 9 above.

Based on discussions with the City, it is assumed for the purpose of this scope that the City will break the construction of the Project as outlined above into the following construction contract packages:

Construction Contract Package	Work item Number (see list above)	Tasks in Which Design Work is Covered Within Scope of Services
Package 1	Items 1-7	Tasks 2, 3A-5A
Package 2	Items 8-9	Tasks 2, 3B-5B
Package 3	Item 10	Tasks 2, 4C-5C



It is assumed that the city will award, advertise, and administer all three construction contract packages separately. The following is an outline of the tasks included within this scope of services:

- Task 1: Project Management, Coordination, and Administration (covers work to be done as part of all three contract packages)
- Task 2: Preliminary Design & Bridge Type Evaluation/Selection (includes preliminary design of all project elements 1-10 as identified above)

Task 3A-5A cover preparation of construction contract package for Package 1

- Task 3A: Draft PS&E (65%) Submittal for Caltrans Work
- Task 4A: Initial PS&E (95%) Submittal for Caltrans Work
- Task 5A: Final PS&E (100%) Submittal for Caltrans work

Task 3B-5B cover preparation of construction contract package for Package 2

- Task 3B: Draft PS&E (65%) Submittal for Pump Station, Landscaping, and Urban Design Work
- Task 4B: Initial PS&E (95%) Submittal for Pump Station, Landscaping, and Urban Design Work
- Task 5B: Final PS&E (100%) Submittal for Pump Station, Landscaping, and Urban Design Work

Task 4C-5C cover preparation of construction contract package for Package 3

- Task 4C: Initial PS&E (95%) Submittal for Early Action Utility Relocations
- Task 5C: Final PS&E (100%) Submittal for Early Action Utility Relocations

Work in Tasks 6-8 cover all three contract packages

- Task 6: Right of Way Appraisal and Acquisition Services
- Task 7: Permitting Services and Other Support Services
- Task 8: Bid Support Services

The following scope of services will be organized according to the task listing/work breakdown structure noted above with additional subtasks included under these eight main tasks to sufficiently describe the work to be done as part of this contract by discipline. Under each task or subtask heading, the nature of the work being described is included along with listings of deliverables to be prepared and any associated assumptions and/or exclusions related to the work being done.

Several tasks within the scope are identified as optional, which means these tasks will be complete only upon prior approval from the City. The fee proposal included in **Attachment 2** also identifies these tasks and breaks out their associated costs.

Cost Estimating

As part of the preparation of the Engineer's Estimate of Probable Construction Cost, completed as part of Tasks 3A-5A as described below, the HDR Constructability team will perform an independent, bottoms up review the Engineer's Estimate. The review will be performed by a Senior Construction Management professional. The purpose of the review is to provide an independent check of the estimate to allow greater confidence that contractor bids will be within ten percent of the estimate. The review will:





- Verify quantity calculations for key bid items
- Evaluate key unit costs
- Consider lump sum items for reasonableness
- Evaluate regulatory issues on contractor pricing
- Identify potential risk items impacting contractor pricing

At the conclusion of each review, HDR will prepare a summary technical memorandum to document their findings and submit to the City as part of each milestone submittal.

Task 1: Project Management, Coordination, and Administration

HDR will provide overall project management, coordination, and supervision of the project staff to facilitate the performance of the work in accordance with the scope and requirements of the City of Long Beach, Caltrans, and other jurisdictional agencies.

This task involves the work related to managing the project on behalf of HDR, including the preparation of the required project initiation documentation, conducting internal and external meetings and coordination, the development and implementation of appropriate project controls, and the preparation of monthly invoices and progress reports. Project management hours are based on a 36 month final design schedule (NTP to approval of all final design documents by the governing jurisdictions).

1.1: Coordination and Administration

This task covers all formal internal and external project meetings as well as administrative activities, including the preparation and maintenance of a project risk register, preparation and maintenance of the project files, and preparation and maintenance of a project design phase schedule.

1.1.1: Coordination and Meetings

This task includes all meetings with both the City and third-party agencies as well as internal regular project team meetings throughout the duration of the project. Unless directed otherwise, HDR will be responsible for scheduling all meetings and preparing meeting agendas, presentation materials, and meeting minutes. The table below outlines the meetings covered as part of this task.

Meeting Description	Meeting Purpose	Meeting Occurrence	Meeting Assumptions
PDT Meetings with Caltrans	Meeting is specific to Package 1 package development and intended to allow for regular coordination with Caltrans on project status and discussion/resolution of technical issues requiring Caltrans input.	Monthly	Thirty three (33) meetings to be attended by PM and discipline leads as necessary. PM and up to three (3) discipline leads to attend in person; others to participate virtually.
Meetings with City of Long Beach staff	Meeting is intended to allow for regular coordination with City on project status and discussion & resolution of technical issues requiring City input, especially regarding Packages 2 and 3.	Biweekly	Sixty six (66) meetings to be attended by PM and discipline leads as necessary





Other Agency/Third-pa	rty Coordination Meetings		
Meetings with Los Angeles County Dept. of Public Works and US Army Corps of Engineers (USACE)	To coordinate with agencies about work being done within limits of County and USACE jurisdiction, including the LA River which will require their approval.	Quarterly	Ten (10) meetings to be attended up to three (3) HDR staff and two (2) RVA staff
Crime Prevention through Environmental Design (CPTED) meetings	To review CPTED principles with local law enforcement and identify which are most applicable and feasible for implementation, and as the design develops, review to insure integration.	As appropriate during preparation of Package 2	Three (3) meetings with Long Beach Police and other law enforcement officials attended by three (3) HDR staff
Meetings with US Fish and Wildlife Service (USFWS)	To coordinate with USFWS on bridge design to address their concerns raised during PA/ED phase and obtain agency concurrence.	As necessary during preparation of Package 1	Four (4) meetings total attended by up to three (3) HDR staff
Coordination meetings with Shoreline Realignment and LB Must Project staff	To coordinate designs among three design teams to facilitate consistency and integration among projects.	Monthly	Twenty four (24) meetings total attended by up to four (4) HDR staff as appropriate. Assumes portion of meetings will be devoted to project visioning and integration
Focused workshops with Caltrans and/or City staff	To review and obtain input/resolution on technical issues requiring Caltrans and/or City input.	As needed	Three (3) meetings per month for twenty (20) months attended by up to three (3) HDR staff as appropriate
Other Meetings		I m	
Internal project team meetings	To facilitate coordination amongst the project team, to review status of work completed by each discipline, and discuss interdisciplinary technical issues requiring resolution.	Biweekly	Sixty six (66) meetings total attended by PM and discipline leads as necessary
Constructability and Safety Review Workshops	Workshops to be led by Caltrans as part of review of Package 3 as dictated by Caltrans PS&E workflow standards. Constructability review workshops will be held as part of 65% and 95% PS&E phases and safety review workshops will be held as part of 65% and 100% PS&E phases.	Prior to 65%, 95%, and 100% PS&E submittals as required by Caltrans	Each workshop duration will be a half day and will be attended by Package 1 discipline leads

Task 1.1.1 Deliverables:

 Meeting agendas, formal minutes or email records of discussion as appropriate, presentation materials

Task 1.1.1 Assumptions:

- See table above for specific meeting assumptions
- It is assumed that all meetings will be held virtually until September of 2021 due to the current COVID-10 panedemic situation.

1.1.1. Administration





Risk Register – HDR will develop and maintain a project risk register as required by Caltrans throughout the project's design phase. The risk register will be organized by package and will identify potential design and construction phase risks that may arise throughout the life of the project so that appropriate mitigation or avoidance plans can be identified and monitored throughout the design duration. The Package 1 risk register will be reviewed with Caltrans at monthly PDT meetings while the Package 2 and 3 risk registers will be reviewed with the City on a monthly basis at the biweekly coordination meetings with City staff. The format of the risk register will be in accordance with Caltrans risk management policy guidelines.

Project files - HDR will develop a project filing system for use throughout the duration of the project which will be consistent with Caltrans and/or City filing guidelines as appropriate. The filing system will be submitted to the City for approval. All project files will be stored electronically utilizing HDR's ProjectWise software. City staff can be provided access to specific ProjectWise folders as appropriate to access certain project files. This will be coordinated with City staff upon NTP.

A document control log will be developed and utilized throughout the life of the project to document incoming and outgoing project materials. A copy of this log can be furnished to the City at any time upon request.

Schedules – HDR will develop and submit be a Critical Path Method (CPM) draft project schedule, which will be prepared using Microsoft Project and presented in Gantt chart format. The schedule will identify the anticipated start/end dates and durations for each task identified within the scope of work and will identify the critical path. Upon approval by the City and Caltrans, the schedule will be set as the project baseline. The schedule will be updated on a monthly basis to track the project status against the baseline and advise the City and Caltrans on the project status at coordination meetings. Copies of the monthly status schedules will be provided to the City each month in conjunction with each invoice and progress report.

Task 1.1.2 Deliverables:

- Baseline and updated risk register
- Document control log
- Approved baseline schedule and monthly status schedules

Task 1.1.2 Assumptions:

- Risk register to be prepared in accordance with Caltrans formatting requirements for all three packages
- All project files to be stored electronically in ProjectWise.
- Schedule to be prepared in Microsoft Project with status schedules to be prepared on a monthly basis. Single master schedule covering the preparation of all three packages to be prepared.

1.2: Progress Reports and Invoices

Invoices will be generated on a monthly basis in accordance with City invoicing guidelines. Progress reports will be generated to accompany each invoice, which will include the following information:



- Work completed over the reporting period by task
- Work to be completed over the upcoming reporting period by task
- Progress schedule which will compare the status of each activity against the baseline
- Issues or concerns related to the schedule or budget.

Task 1.2 Deliverables:

Monthly invoices and progress reports (36 total)

1.3: Prepare Design Quality Management Plan

HDR will develop a comprehensive Quality Management Plan that will outline the quality assurance and control procedures that will be implemented throughout the project by HDR and its subconsultants to facilitate the preparation of quality deliverables. A designated Quality Assurance Manager will be responsible for presenting the defined quality control (QC) procedures to the project staff at project initiation and conducting audits of deliverables throughout the project to check that the specified quality control procedures have been implemented and documented.

The Quality Management Plan will identify a designated quality control reviewer for each deliverable. It will also identify the estimated start and end dates that each QC review will be completed based on the baseline schedule. This information will be input into HDR's project controls monitoring system so that these QC reviews can be tracked and monitored to check that they are being completed and documented. The quality control process typically involves the following three main steps, which will all be documented to confirm completion:

- 1. Detailed Check Reviews: Individual disciplines will complete internal detailed checks of their responsible portions of each deliverable (i.e. plans, specifications, and estimates). The detailed check will be completed by the discipline lead and will involve a comprehensive review of the deliverable to confirm technical accuracy, completion, compliance with relevant engineering and plan formatting standards, and satisfaction of the scope of services. The detailed check will be completed in accordance with published HDR quality standards, documented, and filed in ProjectWise.
- 2. Intradisciplinary QC Reviews: Upon completion of the detailed checks and any revisions to the deliverables to address detailed check comments, the formal quality control process will be initiated. The first step in this process is the completion of quality control reviews of each discipline making up a multidisciplinary deliverable similar to the completion of the detailed checks. Instead of being completed by a member of the project team, technical experts within each discipline outside the project team will be assigned to complete these reviews. The names of these reviewers will be identified in the Quality Management Plan. The quality control reviews will be conducted at a higher level than the detailed checks but will still check for appropriate level of completeness consistent with the milestone submittal, consistency among the various elements of the deliverable (i.e. different plan sheets), correct formatting, technical accuracy, etc. QC review comments will be submitted to each discipline lead for review and acknowledgement (if agreed to) or response (if disagreed with), and the deliverables will then be revised to address the review comments. Updated copies of the deliverables





- will then be back checked by each reviewer to confirm the comments have been adequately addressed.
- 3. Interdisciplinary QC Reviews: This step will be completed for any deliverable requiring input from multiple disciplines (i.e. plans, specifications, and engineer's estimates), with these reviews being conducted upon completion of Step 2. For the project plans, interdisciplinary reviews will be conducted in a workshop type format that will be attended by all discipline leads. This review consists of conducting a collective page-turn review of each plan sheet. The intent of this review to look for inconsistencies with other disciplines or major formatting or technical errors/omissions.

As noted, all reviews will be documented, with evidence of the review (i.e. markups generated) filed in ProjectWise. The Quality Assurance Manager will then confirm that all reviews have been completed and documented in accordance with the Quality Management Plan prior to submittal.

Task 1.3 Deliverables:

 Draft and Final Quality Management Plan (hard copies provided to each project team task manager and to City of Long Beach Project Manager).

Task 1.3 Assumptions:

Subconsultants will be responsible for implementing the quality control procedures as
defined in the Project Quality Management Plan for any deliverables (or portions thereof)
for which they are responsible.

1.4: Prepare Project Management Plan and Financial Plan

HDR's Project Manager will update the existing Shoemaker Bridge Project Management Plan (PMP) for this contract, which will outline the following information related to the work:

- Scope of work and schedule for completion
- Project team and client contact information
- Communication Plan
- Invoicing requirements and templates
- Project team roles and responsibilities
- Document control procedures
- Financial plan which will outlay projected expenditures by month based on draft project schedule

This document will be distributed to all project team members and the City and will act as a living document throughout the life of the contract. It will be updated periodically to reflect any changes in protocol or other information included and redistributed.

Task 1.4 Deliverables:

- Draft project-specific Project Management Plan to be distributed to project team members and City staff (PDF copies)
- Updates to Project Management Plan, if required during course of project, will be distributed via email to project team and City (PDF)



Task 2: Preliminary Design & Bridge Type Evaluation/Selection

This task covers the completion of preliminary design for all elements of the Project (Items 1-10) as outlined in the Introduction. In addition, this task includes supplemental surveys, geotechnical exploration work, and hazardous materials surveys and studies needed to complete final design.

2.1: Conduct Geometric Workshop

HDR will conduct a workshop with Caltrans District 7 staff, the Caltrans Safety Review Committee representatives, Caltrans District 7 Design Liaison, Caltrans Headquarters Project Development Coordinator, and City staff to review and obtain consensus on the geometrics for the proposed portion of the project design within State right of way as previously defined within the Project Report. HDR will identify and clarify and major nonstandard features included within the design.

Task 2.1 Deliverables:

Workshop agenda, minutes, presentation materials, concept exhibits, etc.

Task 2.1 Assumptions:

One workshop assumed to be attended by four (4) HDR staff

2.2: Prepare Supplemental Design Standard Decision Document (if needed)

HDR will prepare a supplemental Design Standard Decision Document (DSDD), if necessary, for any nonstandard design features not included in the approved DSDD prepared as part of the PA/ED phase or to reflect any design modifications resulting from the geometric workshop conducted as part of Task 2.1.

Task 2.2 Deliverables:

- Draft and Final Supplemental DSDD prepared in accordance with Caltrans requirements.
- Responses to comments on Draft DSDD

2.3: Supplemental Field Surveys

This task covers the supplemental field surveys needed to complete final design, including the surveys of utility potholes and any associated exposed utilities

2.3.1: Complete Design Surveys

The current topographic mapping prepared as part of the PA/ED phase will be utilized to prepare the final design plans. HDR's surveyor will complete supplemental field surveys as necessary to allow the project team to complete final design. This will include detailed field surveys of existing street and drainage features. Cross sections and tie-in surveys will ensure accurate design fit and smooth transitions from existing roadway and infrastructure features.

HDR's surveyor will verify survey results and then transmit them in Microstation 3D and DTM formats, along with ASCII point and station-offset files of all field survey ties. All work and files will be based on project coordinate control and in accordance with Caltrans Surveys and Right





of Way Manuals and Caltrans District 7 R/W Engineering requirements for the preparation of documents and maps.

2.3.2 Complete Potholing Surveys

HDR surveyors will support the utility potholing work be completing the following services:

- Locating proposed pothole or exploratory trench locations in the field for potholing contractor
- Documenting any utilities exposed as part of trenching excavations.

Survey locations of any exposed utilities will be submitted to the project team in both Microstation and ASCII formats.

Task 2.3 Deliverables:

- Survey data submitted in both Microstation and ASCII formats
- Field-marked locations of all proposed utility potholes and trenches

Task 2.3 Assumptions:

- The topographic mapping prepared to support the Project's PA/ED phase will be used for final design. New aerial topographic mapping will not be prepared to support final design.
- Preparation and recording of public street easements in the Cesar Chavez Park are not included.

2.4: Geotechnical Explorations

The HDR team will complete supplemental geotechnical explorations needed to support the subsequent geotechnical analysis and design recommendations to be prepared in later tasks including the following:

- Structure foundation types
- Proposed roadway and park grading
- · Pavement sections for new or widened roads

This task includes the completion of all field explorations and geotechnical boring work as well as subsequent laboratory analysis.

HDR will prepare and submit a geotechnical review and exploration plan for City and Caltrans for review. HDR will obtain permits to enter any private properties prior to exploration. HDR will conduct subsurface investigation and evaluate the results in accordance with Caltrans testing criteria.

Task 2.4 Deliverables:

- Geotechnical Exploration Plan
- Right of entry permits
- Water Pollution Control Plan



Task 2.4 Assumptions:

 Cost for the completion LA River and pavement borings for Shoreline Drive is accounted for under current City contract however, requirements of LA River geotechnical exploration may result in additional scope.

2.5: Prepare Supplemental Geometric Review Drawing

If geometric revisions/refinements to the project elements within State right of way are required as a result of the geometric workshop conducted as part of Task 2.1, HDR will prepare a supplemental Geometric Review Drawing and submit to Caltrans for review and approval.

Task 2.5 Deliverables:

- Draft and Final Geometric Review Drawing (GRD)
- Responses to comments on Draft (GRD), if applicable

Task 2.5 Assumptions:

 GRD to be prepared and submitted on single sheet large size plot showing proposed geometric layout, profiles, typical sections, and proposed nonstandard features consistent with Caltrans Highway Design Manual (HDM) requirements

2.6: Prepare Preliminary Foundation Reports

HDR will utilize the analysis compiled as part of Task 2.4 to prepare a Preliminary Foundation Report for the project to assist in Structure Type Selection. Separate reports will be prepared for the structures within Caltrans jurisdiction and those outside Caltrans jurisdiction as follows:

Caltrans Structures

- New LA River Bridge
- New roundabout structure
- Bike/ped bridge connecting observation platform on LA River Bridge to existing LA River Trail along east bank of LA River
- All retaining walls supporting local roadways adjoining roundabout structure

Local Structures

- New pedestrian bridge at 7th Street
- New pump station
- Any retaining walls needed to support Cesar Chavez park improvements or new pump station

These reports will be prepared in accordance with Caltrans Office of Structural Foundations requirements. These reports shall include a summary of the exploration program, description of the site geotechnical issues, and recommendations for foundation designs for all structures listed above.

Task 2.6 Deliverables:

- Draft and Final Preliminary Foundation Report for Caltrans structures
- Draft and Final Preliminary Foundation Report for Local structures
- Responses to comments on draft reports





Task 2.6 Assumptions:

 Due to poor soil conditions within the project limits, all retaining walls are assumed to be nonstandard, special design walls that will require foundation recommendations

2.7: Structures Type Selection

This work includes the development of structure type selection for each of the structures listed in Task 2.6 above and the preparation of the associated reports. In addition, this task includes the completion of the study in coordination with City of Long Beach staff to develop the architectural themes for the LA River and roundabout structures to be incorporated into the design of these structures.

2.7.1: Architectural Concepts

This task involves the development of up to three (3) potential architectural concepts for the LA River Bridge and roundabout structure and working with City staff to select a preferred concept to be carried into final design. The steps comprising this task are outlined below:

Step 1 - Initial Theme Development and Scoping

HDR will conduct up to three (3) workshops with City staff and stakeholder/community groups to work jointly to develop an overall architectural theme for the project that will be carried into structure aesthetics and other project elements. HDR will develop initial concept sketches, renderings, etc. to facilitate input by City and stakeholder groups at these workshops. Sketches will be modified or refined based on input received after each workshop. Once an aesthetic theme is determined based upon input received at the workshops, HDR will document this theme in an aesthetic guidelines document to show how the aesthetic theme chosen by the City and stakeholders is to be incorporated into the various project elements including bridges and retaining walls.

Step 2 - Prepare Bridge Aesthetics Alternatives Review and Renderings (Optional Task)
Based on the aesthetic guidelines outlined in Step 1, HDR will develop 3D digital renderings of three optional separate aesthetic treatments for the LA River Bridge and roundabout structure. The existing site conditions within the limits of the structures will also be digitally rendered to serve as a background for the renderings. The renderings will be simple and non-photorealistic in nature. A comparison matrix will be prepared to outline the various features of the three options, including opportunities and constraints associated with each. The matrix will be used as a tool to facilitate the selection of a preferred option by the City and stakeholders.

Step 3 - Stakeholder Workshops and Constraints Identification

HDR will work with City staff to conduct workshops with key project stakeholders that will have a say in the bridge aesthetics to review the three concepts developed as part of Step 2. Participating stakeholders to be invited to the workshop in addition to City staff include:

- Caltrans
- US Army Corps of Engineers
- US Fish and Wildlife Service

The intent of the workshops will be to obtain stakeholder input on the aesthetic treatment options to assist the City in determining the most suitable option to be carried forward. Up to





four (4) stakeholder workshops are assumed to be conducted, with refinements to the concepts made after each workshop if needed to address comments received.

Step 4 - Alternatives Development, Costing and Preferred Alternative Selection (Optional Task)

Upon the completion of Step 3, HDR will advance the development of each of the three aesthetic options to a conceptual level that will facilitate the development of a rough order of magnitude cost estimate and allow for a detailed evaluation. HDR will then prepare a report to summarize the work completed as part of Task 2.7.1. The report will present the three aesthetic concepts, evaluate each of the three concepts over a range of criteria including construction maintenance costs, and provide a recommendation of the preferred option to the City. The report will be submitted to the City and participating stakeholders for review and concurrence with the preferred option.

Task 2.7.1 Deliverables:

- Initial concept sketches, renderings, etc.
- Workshop agendas, minutes, meeting materials
- 3D existing conditions digital site model (Optional Task)
- 3D models of each bridge option including deck treatments (Optional Task)
- Bridge option comparison matrix (Optional Task)
- Developed renderings for each option for both Shoemaker Bridge over the LA River and roundabout structure (Optional Task)
- Rough order of magnitude cost estimates for each bridge option (Optional Task)
- Draft and final summary reports (Optional Task)

Task 2.7.1 Assumptions:

- Architectural treatments to the LA River Bridge main spans and roundabout structure will be cosmetic in nature including limited surface treatments (<4" depth additional concrete)
- Assumes three (3) City workshops with Public Involvement and stakeholder groups as part of Step 1
- For facilities designed by others within project vicinity to be included in overall assessment, HDR is to receive 3D models for these items (i.e. LB MUST)
- Design fees reflect a baseline design of the LA River Bridge and elevated roundabout only
- The LA River Bridge type is assumed to be concrete segmental with architectural elements that do not significantly impact the structural performance of the bridge structures and two piers located within the ordinary high water limits.
- Roundabout structure is assumed to be cast-in-place concrete with a maximum of 3-ft of soil with vegetation in the center. Baseline design assumes no design for a monument of any kind.
- Four (4) stakeholder workshops assumed as part of Step 3
- Assume up to three (3) options for both the LA River and roundabout structures to be fully developed and considered in summary report.





2.7.2: Prepare Supplemental Advance Planning Studies for LA River and Roundabout Structure (Optional Task)

If required by Caltrans, HDR will prepare Supplemental Advance Planning Studies (APS) in accordance with Caltrans requirements for the LA River Bridge, the roundabout structure, or both to reflect any required design refinements to either structure resulting from the outcome of Tasks 2.1, 2.5, and 2.7.1.

Task 2.7.2 Deliverables:

- Draft and Final APS for LA River Bridge (if required)
- Draft and Final APS for roundabout structure (if required)

Task 2.7.2 Assumptions:

The current 36 month schedule assumes that this task is not required.

2.7.3: Prepare Structure Type Selection Reports

In accordance with Caltrans OSFP requirements, the HDR team will prepare and process the Structure Type Selection package for review and approval by OSFP. This package will include type selection reports for the following structures:

- LA River Bridge
- Roundabout structure
- Bike/ped structure connecting LA River Bridge to bike path on east bank of LA River (if applicable)
- All nonstandard retaining walls within State jurisdiction

Since Caltrans considers the Structures Type Selection process to be a fundamental step in the design of structures within State right of way, this step must be completed before extensive structures design work can be performed. The Type Selection process involves the following primary elements: 1) preparation and submittal of Type Selection Documents; 2) Type Selection Meeting and Approval; and 3) Updated General Plan submittal and distribution.

The initial stage in the Type Selection process involves identification of parameters that govern the design of the new bridge. These parameters are contained in the following documents which must be submitted before a Type Selection Meeting can be scheduled: 1) Bridge Site Data Submittal Package (BSDS), and 2) a Type Selection Report. The Type Selection Report will follow the format described in the Caltrans Bridge Memos to Designers Manual (in affect upon NTP). The report will include a discussion of the structure types considered and reasons for the selection of the proposed structure. The HDR team will prepare a General Plan Estimate of structure construction cost as part of the Type Selection Report. The HDR team will submit the BSDS and the Type Selection Report to OSFP for review.

In addition to the Type Selection Reports, the following will also be prepared as part of this task:

- Bridge deck drainage design and summary memorandum
- Conceptual Bridge Removal Plan for existing Shoemaker Bridge and walls

Although not within Caltrans jurisdiction, a similar report utilizing the Caltrans standard format described above will be prepared for the pedestrian bridge at 7th Street. This will be submitted



to City staff only for review and comment and not included with the package submitted to Caltrans for review and approval.

Task 2.7.3 Deliverables:

- Bridge Site Data Submittal per Caltrans requirements
- Type Selection Reports for structures within Caltrans jurisdiction (to be submitted to Caltrans)
- Type Selection Report for pedestrian bridge at 7th Street (to be submitted to City only)
- Bridge Deck Drainage Design Memorandum
- Conceptual removal plans for existing Shoemaker Bridge

Task 2.7.3 Assumptions:

- Elevated roundabout structure and LA River Bridge are Ordinary Nonstandard bridges and pedestrian bridges are Ordinary Standard bridges per Caltrans SDC
- Existing soils are anticipated to be improved for bridge foundation analysis/design
- Study/use of base isolation is not included.

2.7.4: Bridge Type Selection Meeting and Approval

A Type Selection Meeting will be scheduled with Caltrans OSFP a minimum of two (2) weeks following the submittal of the Type Selection Report and related documents. The meeting is likely to be held in Sacramento at the OSFP Headquarters; however, it is assumed that the meeting will be conducted virtually. At the meeting, the HDR team will present the proposed structures within Caltrans jurisdiction and shall briefly discuss issues pertinent to the selection of the structure type, particularly requirements for foundations, construction, seismic design, retrofit strategy, aesthetics, traffic handling, and other information needed to support the selection of the proposed structure type. The HDR team will prepare summary meeting minutes and provide a copy to the OSFP Liaison Engineer within one week of the meeting. The summary meeting minutes may be used to update or supplement the information in the Type Selection Report to address pertinent questions or comments raised at the meeting. Within one week of receipt of the summary meeting minutes and resolution of any outstanding issues or comments, the OSFP Liaison Engineer will issue written approval of the proposed structure type.

Following Type Selection Approval, the HDR team will submit to OSFP the required number of copies of the updated Structures General Plans and General Plan Estimates for distribution to the other Caltrans functional units. The HDR team will incorporate pertinent comments resulting from the distribution into the final structures design and PS&E.

Task 2.7.4 Deliverables:

- Type selection meeting agenda and minutes
- Updated Type Selection documents revised to address Caltrans comments (if necessary)

Task 2.7.4 Assumptions:

- Type selection meeting will be held virtually with Caltrans OSFP staff
- Type selection meeting will cover Caltrans structures only; no type selection will be held for pedestrian bridges unless requested separately by City staff.





2.7.5: Conduct Updated Hydraulic/Scour Analysis of LA River Bridge

The purpose of this task is to determine impacts to the flow characteristics and water surface elevation within the Los Angeles River associated with the construction of the new LA River Bridge. Any changes in the Los Angeles River flood risk management channel or the right-of-way requires approval from several divisions/departments of both the Los Angeles County Flood Control District (LACFCD) and the U.S. Army Corps of Engineers (USACE). This analysis will be conducted based upon the proposed bridge design that is to be carried forward into Structures Type Selection.

The HDR team has obtained the current HEC-RAS model and supporting documentation from the USACE. Utilizing this model, HDR will use a 3 phased approach based upon previous coordination with USACE on this work:

- 1. 1D HEC-RAS modeling for each alternative (completed during PA/Ed phase)
- 2. 2D ADH modeling, as needed
- 3. 3D Physical model, if needed (not included in this scope)

Our team will start with the 1D model and progress to the other 2 only if needed to satisfy the USACE that the existing water surface elevation could be maintained.

The USACE directive has long been that modifications or replacement of bridges must result in 0% change in water surface elevation. The HDR team will first model the changes in the water surface elevation based on the proposed LA River Bridge design and reduce the impact as much as possible. The HDR team will then explore offsetting or compensating the net water surface elevation change by modifying the channel walls or adding higher walls on top of the levees. Our assumption is that USACE would be open to further discussion of this approach. The desired outcome would be conceptual approval of the preferred alternative based on the preliminary design. This is the most crucial element related to obtaining the approvals from the LACFCD and the USACE. Designs that result in a 0% change in the water surface elevation would likely be considered minor modifications to the flood risk management project and would be approved at the local District offices.

Modifications to the channel geometry or heights of the parapet walls would likely be deemed major and would require the local District to submit the design and complete package to the regional and then national headquarters for approvals. Major modifications would require an additional 6-12 months for reviews at the higher level headquarters within USACE. Such major work is not included in this scope of work.

Similar to the Section 214 agreement process, close coordination with the LACFCD and the USACE is critical to gaining responses from the two agencies. The first meeting would be to brief the project and schedule and discuss the agencies' expectations. The second meeting would review the computer modeling, designs, findings to date and options on how to compensate for a rise in water surface elevation. A third meeting would review the changes ensuing from the agencies' comments from the second meeting. Finally, a meeting would be established to obtain conceptual approval of the preferred design. Notes of the discussion, key points, decisions and action items would be prepared within 7 days of each meeting. HDR would incorporate the action items into the tracking matrix for the project.





Task 2.7.5 Deliverables:

- Detailed scope of work to the LACFCD and the USACE.
- Results of the HEC-RAS model runs for proposed bridge design.
- Results of the ADH model runs, if required by the USACE and LACFCD.

Task 2.7.5 Assumptions:

- A scaled physical model, if required by the USACE and LACFCD, is not included in this scope of work.
- Work applies to LA River Bridge only.
- Assumes no mitigation measures or risk & uncertainty analysis for levee freeboard

2.8: Pump Station Preliminary Design

This task covers all preliminary design work related to the relocation of the SD-01 Pump Station as part of the project. This work involves the removal of the existing SD-01 Pump Station and the construction of a new pump station at a location that is compatible with the ultimate Shoemaker Bridge Project conditions. The existing SD-01 is currently owned and operated by the City of Long Beach.

2.8.1: Pre-Design Activities

This task covers the up-front activities to facilitate the design of the relocation of the SD-01 Pump Station as part of the Shoreline Drive Realignment project.

Data Gathering and Review

HDR will obtain and review information on the City's previous and current planning efforts along with their standards and design guidelines. This task will also include the review of the Shoemaker Bridge Project Preliminary Drainage Report (HDR, 8/16/2019) and preliminary roadway realignments.

Site Reconnaissance

HDR will conduct one (1) initial field site visit to identify specific physical features associated with the Project. It is assumed the field site visit will be four (4) hours in duration and include four (4) design team members. City Staff may participate in the field visit, if desired. HDR shall prepare draft and final field notes for the site visit.

Preliminary Hydrology and Drainage Study

HDR will conduct a preliminary hydrology and drainage study to support the pump station preliminary design work to determine approximate pipe and pump sizing for the proposed pump station. A detailed drainage design report will be prepared as part of Task 3A.

Facility Siting Considerations

HDR shall conduct an evaluation of various potential SD-01 Pump Station siting/location configurations (two minimum) for the selected siting area. HDR shall summarize the advantages and disadvantages of each site configuration, considering: proximity to existing and future planned facilities, existing utilities, planned utilities, ultimate street/site improvements, temporary and permanent easements, traffic, safety, permits, construction cost, site access, community impacts, potential environmental constraints, etc.





Task 2.8.1 Deliverables:

- Technical Memorandum summarizing the work completed as part of this task.
- SD-01 alternative site plan exhibits, select section views, and details to be included in the memorandum.

Task 2.8.1 Assumptions:

 A maximum of three (3) locations will be considered as part of the technical memorandum produced as part of this task.

2.8.2: Prepare Pump Station Geotechnical Design Report

A separate GDR will be prepared for the construction of the new SD-01 Pump Station once the location has been determined as part of Task 2.8.1. This document will provide foundation design recommendations for the pump station structure as well as trenching recommendations for the piping entering/exiting the facility.

Task 2.8.2 Deliverables:

Draft and Final Pump Station Geotechnical Design Report

2.8.3: Prepare Preliminary Plans

Preliminary pump station drainage plans will include the following drawings:

- Site layout drawings
- · Mechanical plans and sections
- Instrumentation and control diagrams
- Electrical single line diagrams
- · Architectural elevations

The preliminary design depicted in these plans will be prepared in accordance with the requirements set forth within the Preliminary Design Report prepared as part of Task 2.8.3.

Task 2.8.3 Deliverables:

Preliminary pump station plans (single alternative)

Task 2.8.3 Assumptions:

- Existing SD-01 Pump Station force mains and outfall will be utilized and there will be no modifications or improvement design required.
- No computational fluid dynamic (CFD) modeling will be necessary.
- No pressure transient (surge) analysis will be required.
- SCADA requirements will be identified in coordination with the City of Long Beach Maintenance Staff
- No physical modeling will be constructed for SD-01
- An automated trash screen will not be included.

2.8.4: Prepare Pump Station Preliminary Cost Estimate

HDR will develop a preliminary estimate of the construction cost based upon the preliminary design plans and include with the 35% milestone submittal. The estimate will be prepared using either a standard costing template provided by the City, or one can be developed by HDR. If one is prepared by HDR, it will be submitted to the City for review and approval prior to





developing the estimate. The estimate will be based upon the pay items and quantities identified within the project plans. The cost estimate will list all pay items and their associated unit costs to calculate a total cost for each item. Unit costs will be obtained from available resources, including recent bid data on similar projects, and from the 2019 (or most current) Caltrans Cost Data. Lump sum costs will be assigned to cover items not yet designed as part of the 35% design phase but known to be needed.

"Below the line" soft costs to cover City implementation costs and construction management can be added to the construction estimate if requested by the City. It is assumed that these costs would be calculated as a percentage of the construction cost based on industry standard values or those provided by the City.

It is assumed that right of way acquisition costs will be prepared by the City based upon the preliminary right of way needs included in the plans. These can be included by HDR in the overall project implementation cost estimate if requested by the City.

Task 2.8.4 Deliverables:

Preliminary pump construction cost estimate

Task 2.8.4 Assumptions:

- Soft costs to be included in cost estimate if requested by City
- Determination of right of way acquisition costs is assumed to be responsibility of the City

2.8.5: Prepare Pump Station Preliminary Design Report

In accordance with City standards and guidelines, HDR will develop the design criteria for SD-01 to form the basis of the design. The preliminary design shall serve as the basis for final design of the Project and will address the following Project components:

Facility Siting and Layout/Configuration	Aesthetics- Architectural, Landscaping
Building Type and Configuration (equipment access)	Equipment Selection and Specifications
Coordination with other Agencies (Port of Long Beach, County of Los Angeles, Caltrans, others as required)	Materials of Construction
Corrosivity and Corrosion Protection Surge Analysis	Facility Operations/Control Strategy
Electrical Load Requirements and Standby Power Requirements	SD-01 Pumping Unit Selection and Configuration
Constraints Analysis	Pipeline Connections and Valves





Other Encumbrances (e.g. Flood Zone, coordination with Los Angeles County Flood Control District)	
Fencing, and Gates	Site and Facility Security
Electrical Plan of Service	Site Grading, Access, and Drainage
Project Schedule (critical path) and Estimated Costs	Project Phasing

HDR shall prepare a Preliminary Design Report (PDR) that documents the basis of design and presents the design criteria associated with the pump station facilities, including the information and results from the scope of work tasks described above. The PDR shall represent a 50% design-level effort. The PDR shall include:

- Results and recommendations of the hydraulic evaluation refinement, including facility sizing, configuration, and requirements
- Results and recommendations of the facility siting analysis and selection, including development of preliminary layout for the selected site, inventory of improvements, materials and equipment selection, environmental and community impacts, etc.
- Preliminary list of permits, and other agency clearances
- Budgetary-level estimate of probable construction costs (AACE Class 3) and schedule of probable construction duration(s) for each potential phasing strategy
- All backup data, calculations, layout drawings, equipment catalogue data/cut-sheets, pump performance curves, etc. (included as an Appendix to the PDR)

Task 2.8.5 Deliverables:

Draft and Final Preliminary Design Report (PDF copy and 5 hard copies)

2.8.6: Preliminary Design Workshop

HDR shall prepare for and lead one 3-hour-duration workshop with City staff at the draft, preliminary design level to discuss and confirm the Project design basis (hydraulics, site layouts, transmission main alignment, materials of construction, equipment selection and specifications, construction schedule, estimated costs, constraints, property and easement acquisitions, transition plan to final design, etc.). Four (4) HDR design team representatives will attend the Task 3.2 preliminary design review workshop. A detailed (PowerPoint) presentation of the Draft PDR will be prepared and presented to City staff to encompass all Project facility components.

HDR shall prepare and submit the workshop agenda and presentation to the City three working days prior to meetings, and workshop minutes shall be submitted within five (5) working days following each meeting. HDR shall incorporate City comments and will issue minutes for distribution and record.

Task 2.8.6 Deliverables:

Workshop agenda, presentation materials, and minutes



Task 2.8.6 Assumptions:

• Four (4) hour workshop to be attended by pump station design lead and discipline leads (total of 4) along with City staff.

2.8.7: LEED Certification

HDR shall provide the City with copies of all agreements required by the Certifying Authority to register the Project and pursue Certifying Authority Certification. The City and HDR shall review and confirm that the terms of those agreements are acceptable to the City before proceeding with registering the project with the Certifying Authority.

HDR, as agent for the City, shall register the Project with the Certifying Authority. HDR will provide the project team with access to Certifying Authority tools and resources. HDR will act as the Certifying Authority Online portal "Project Administrator" whose responsibilities include team organization, assignment of roles and responsibilities, and project information application:

- Facilitate one (1) Sustainable Design Meeting to discuss all sustainable / Certifying Authority
- Facilitate one (1) Energy Efficiency Meeting with the project team to discuss the USGBC requirements for demonstrating energy performance savings for buildings with high process loads.
- Develop, with the assistance of the design team and the City, a Sustainability Plan based on the sustainable objectives and measures from the Sustainable Design Meeting to achieve Certifying Authority.
- Review and modify the City's Project Requirements ("CPR") as it relates to building performance and sustainability.

Task 2.8.7 Deliverables:

- Certifying authority agreements.
- Draft and Final Sustainability Plans (PDF copy and 5 hard copies)
- Meeting agendas, presentation materials, and minutes

Task 2.8.7 Assumptions:

- City is responsible for payment of any Certifying Authority registration and review fees unless otherwise specifically stated in this scope. Registration and any other fees charged by the Certifying Authority, and paid by HDR, shall be a Reimbursable Expense. These fees are subject to change at any time by the Certifying Authority. These fees are anticipated to be \$1,200 for Project Registration, \$2,325 for the LEED Design Submission, and \$775 for the LEED Construction Submission, based on a project square footage of less than 5,000 square feet and the rates published by the Certifying Authority as of 9/25/2020.
- In the event the City elects to pursue third-party certification or the equivalent for the Project, City acknowledges that the U.S. Green Building Council® ("USGBC") LEED® Green Building Rating System, Green Business Certification Inc. ("GBCI") Guiding Principles Assessment, WELL™ Building Standard, International Living Future InstituteSM ("ILFI") Zero Energy Certification, ILFI Petal Certification, ILFI Core





Certification, ILFI Living Building Certification, Green Building Initiative® ("GBI") Green Globes®, GBI Guiding Principles Compliance, and Fitwel® (collectively the "Certifying Authority") use certain design, construction and usability guidelines or recommendations in order to promote environmental responsibility and/or energy efficiency. In addressing these guidelines or recommendations, the Architect shall perform its services with the degree of skill and care ordinarily exercised by similarly situated members of its profession involved in the design of similar projects at the same time and in the same locale as the Project. The City further acknowledges and understands that Certifying Authority are subject to various and possibly contradictory interpretations and that achieving and maintaining compliance with Certifying Authority involves factors beyond HDR's control, including without limitation, City's use and operation of the completed Project. HDR will use reasonable care, consistent with the foregoing standard, in interpreting and designing in accordance with the Certifying Authority, but does not warrant or represent that the Project will actually achieve or maintain Certifying Authority certification. HDR shall not be responsible for the Contractor's failure to adhere to the Contract Documents and any applicable laws, codes and regulations incorporated therein, nor for any changes to the design made by the City without the direct participation and written consent of HDR. Likewise, HDR shall not be responsible for any environmental, energy, health, and/or wellness issues arising out of the City's use and operation of the completed Project.

The City acknowledges that pursuing Certifying Authority certification of the Project may
necessitate the incorporation of new or innovative products, technologies or methods
into the Project and that such products, technologies or methods may not realize their
intended objectives or may even involve collateral consequences. The City further
acknowledges that it has evaluated the potential risks and rewards in connection with
the use or application of such products, technologies and methods and assumes any
associated risks.

2.9: Utilities

This task covers the identification of utilities in conflict with the proposed project based upon the project's preliminary design, the initiation of coordination with impacted third-party utility owners, and the potholing work to confirm locations of key utilities to facilitate final design activities.

2.9.1: Update Existing Utilities Base Map

The base mapping prepared as part of the PA/ED phase of the Project will be utilized for the final design phase and supplemented to cover project areas outside the limits of the current mapping, including the limits of 6th and 7th Streets east of Maine Avenue where proposed signal infrastructure will need to be installed in order to convert these streets to two-way traffic. The existing base mapping will be carefully reviewed to identify any other areas within the project that may fall outside the limits of current base mapping. For the purpose of this scope, it is assumed that only the limits of 6th and 7th Streets as noted above fall outside the limits of the current mapping.

HDR will obtain and review available as-built street improvement plans from the City for the noted segments of 6th and 7th Streets and identify existing utilities that are to be added to the





base map. Based on the review of the as-builts and information obtained from Underground Service Alert, HDR will identify a list of third-party owners determined to have facilities within the 6th and 7th Street corridors beyond the current limits of the mapping.

HDR will update the composite existing utility base map and inventory matrix to include the additional utilities along the 6th and 7th Street corridors.

The inventory matrix to be utilized and updated throughout the design phase will include the following information:

- Utility ownership, type, location, and depth
- Ownership rights, easements, and franchise agreements
- High or low risk determinations
- · Disposition of each utility
- Utility conflicts
- Removal and relocation requirements (lengths and limits)
- Estimated relocation costs
- Reconstruction and adjustments of manholes, handholes, vaults, and other surface appurtenances

The Utility Matrix will also track the progress and schedule of each impacted utility, including all correspondence with each owner in order to have the utilities relocated prior to the start of the roadway construction. Any relocation plans prepared by owners will be obtained and included in the contract bid documents for reference.

Preparation and distribution of utility information request letters to owners

As part of the recently completed Shoemaker Bridge Project preliminary engineering effort, utility information request letters were sent out to third-party utility owners known to have utility facilities within the Shoemaker Bridge Project limits in June 2019 to request facilities mapping. The existing utilities base mapping was then supplemented to incorporate the information provided by the utility companies. Based on how recently this information was obtained from utility owners, HDR only intends to repeat this process for the utilities outside the limits of the current mapping.

HDR will prepare notification letters to utility owners with facilities within the expanded project limits to notify them of the project, identify the facilities currently identified within the expanded project limits that fall under their ownership and provide the final design schedule. HDR will also request that they verify the location of their facilities as shown on the current existing utilities plans and/or provide facilities mapping for any facilities within the project limits.

Update composite existing utility plans and corresponding utility matrix

Any facilities mapping received from utility owners in response to the notification letters will be cross checked against the existing utilities composite. The utility base map and inventory matrix will be updated to reflect the facilities mapping within the expanded project limits.

Task 2.9.1 Deliverables:

Updated existing utility composite map and inventory matrix





Utility information request letters (sent out on City letterhead if permitted by City)

Task 2.9.1 Assumptions:

- The only additional areas where supplemental base mapping is needed is along 6th and 7th Streets from Maine Avenue to Daisy Avenue, including all intersections within these limits.
- Assumes preparation of up to ten (10) letters and review of as-built plans for up to five
 (5) projects.
- HDR will coordinate with Shoreline Realignment Project team to facilitate joint discussions with impacted third-party owners and to share utility information.

2.9.2: Conflict Identification

HDR will review the updated existing utilities base against the updated project geometrics and urban design plan for the park elements developed as part of Task 2 to conduct a supplemental evaluation of existing in conflict with the proposed Package 1 and Package 2 construction. A conflict map will be prepared to document all utilities to be found in conflict and the inventory matrix will be supplemented to indicate which utilities are in conflict. HDR will conduct prior rights research for all utilities identified to be in conflict and include this information within the matrix.

Task 2.9.2 Deliverables:

Updated conflict map and inventory matrix

2.9.3: Utility Coordination

HDR will notify and impacted third-party utility owners found to have facilities with the proposed Package 1 and 2 construction. HDR will schedule meetings with each impacted property owner to present the conflicts and discuss potential relocation strategies. HDR will then work with the impacted owners to develop acceptable relocation concepts and obtain their written concurrence on the agreed upon strategies as well as the final design and construction schedules for the completion of the relocation work. HDR will conduct up to three (3) meetings with each impacted owner to develop relocation concepts and obtain concurrence.

Task 2.9.3 Deliverables:

- Meetings agendas, minutes, presentation materials
- Relocation concept exhibits
- Letters of concurrence to document agreed upon relocation concepts

Task 2.9.3 Assumptions:

- Assume up to three (3) meetings each utility owner, six (6) owners with two (2) HDR attendees.
- HDR will coordinate with Shoreline Realignment Project team to facilitate joint discussions with impacted third-party owners and to share utility information.

2.9.4: Utility Potholing

HDR will work jointly with City and Caltrans staff to identify critical existing utilities that warrant potholing to positively confirm their locations. These locations will be shown in a Pothole Needs



Plan. Once an agreed upon list has been developed, HDR will generate potholing work plans (if required) to define the nature of the work to be completed, work schedule, and traffic control requirements. HDR will prepare traffic control plans (if needed) for the completion of the work and obtain agency approval. These approved traffic control plans will be included within the work plans.

Upon work plan approval and obtaining the necessary encroachment permits to complete the work, HDR's potholing contractor will complete the potholing of the selected utilities using vacuum extraction technology.

Task 2.9.4 Deliverables:

- Pothole Needs Plan
- Pothole Work Plans (one for work in City jurisdiction and one for work in State jurisdiction, if required)
- Traffic Control Plans
- Pothole Data Reports

Task 2.9.4 Assumptions:

- · Thirty (30) potholes assumed
- Fifteen (15) traffic control plans assumed
- One work plan per agency (if needed)

2.10: Hazardous Materials Investigations

This task covers the completion of the hazardous materials investigations within the project limits as mandated within the project Environmental Document that may be encountered during construction. The purpose of these investigations will be to determine whether the following hazardous materials are present within the project limits:

- Aerially deposited lead (ADL): typically found within the shallow soil adjacent to roadways that were heavily used prior the prohibition of leaded gasoline and can present a health issue if this soil is disturbed/excavated as part of construction.
- Asbestos-containing materials (ACM): Typically found in older bridge structures and buildings can present a health issue if structures containing these materials are demolished.
- Lead-based paint (LBP): Typically found in old roadway striping or on structures built
 prior to the prohibition of lead-based paints and can present a health issue when
 removed.

2.10.1: Complete Aerially Deposited Lead (ADL) survey

HDR will conduct field surveys to collect soil samples within areas identified to potentially contain ADL. Samples will be analyzed to determine concentrations of lead in the soil. If ADL is found in the soil samples, appropriate protocols for its handling and proper disposal during construction will be developed and included within the specifications for each construction package.

Task 2.10.1 Deliverables:

ADL Survey Workplan





ADL Survey Report

Task 2.10.1 Assumptions:

- Three (3) days of field sampling at twenty (20) total locations
- One (1) day of GPS surveying
- Hand auger boring only, to a maximum depth of 5 feet
- · Four (4) samples per boring
- Borings located in unpaved landscaping within the project area only
- Excludes the areas of the Shoreline Realignment and LB-MUST projects
- Lab analysis for lead and pH only, per Caltrans ADL survey requirements and their soil reuse variance with DTSC
- No offsite disposal of investigation derived waste. Borings will be backfilled with cuttings.
 Decon water will be poured on plants and landscaping.
- No permits are required to access unpaved areas or dig with hand tools only
- No traffic control will be required to access sampling locations

2.10.2: Complete Asbestos Containing Materials (ACM) and Lead Based Paint (LBP) surveys

Field surveys will be performed and the appropriate post-survey analysis to determine the presence of ACM and LBP within the project limits. If their presence is confirmed, appropriate protocols for their handling and proper disposal during construction will be developed and included within the specifications for each construction package.

Task 2.10.2 Deliverables:

- Eight ACM and LBP Survey Letter Reports (one for each structure)
- Eight ACM and LBP Compliance Plans (one for each structure)

Task 2.10.2 Assumptions:

- Eight structures require surveys for ACM and LBP:
 - o Main Span of Shoemaker Bridge
 - Westbound 9th Street ramp
 - Eastbound 9th Street ramp
 - 7th Street ramp
 - o 6th Street ramp
 - Northeastern bike path overcrossing
 - Southwestern bike path overcrossing
 - Existing SD-01 Pump Station
- Other structures, such as the Golden Shore Overpass are outside the project area and will be surveyed by others
- Reporting will conform to SCAQMD and Caltrans requirements
- Surveys will be conducted by a contractor licensed to perform lead and asbestos surveys.
- Permits are not required for crews to access the structure for sampling
- Field survey will take up to five (5) days to complete
- An HDR field engineer will oversee survey activities



2.10.3: Prepare Health and Safety Plan, a Contaminated Materials Management Plan, a Construction Contingency Plan, and a Lead Compliance Plan

Plans will be prepared by HDR prior to the completion of the field surveys conducted as part of Tasks 2.10.1, 2.10.2, and 2.10.4 to outline the health and safety measures to be taken by the field crews to address hazards that may be encountered during the field activities as a result of handling these potentially hazardous substances.

Task 2.10.3 Deliverables:

- · Health and Safety Plan
- · Contaminated Materials Management Plan
- Construction Contingency Plan
- Lead Compliance Plan

Task 2.10.3 Assumptions:

- Health and Safety Plan and Lead Compliance Plan will need to be prepared and stamped by a Certified Industrial Hygienist
- The LCP can only be completed after The ADL survey is complete
- No intrusive work on structures containing lead-based paint is included, and safety training for lead work is not required
- The Contaminated Materials Management Plan will be based on previously available data
- Plans are for HDR's investigations related to PS&E, not for project construction or other contractors' use

2.10.4: Conduct Phase II Site Investigation

The main objective of the Phase II Site Investigation (SI) is to provide an assessment of potentially contaminated sites to evaluate whether there would be an apparent impact from the potential contaminants identified from the Phase I ISA. The Phase II SI will present information regarding the understanding of the subsurface conditions, contaminant source areas, types of contaminants, media involved, and distribution of the contaminants.

Prior to conducting the Phase II SI, HDR will prepare a Work Plan and submit it to the City and Caltrans for review and comment. The Work Plan will outline procedures, standards, and required certifications for performing the investigation, statistical data evaluation, laboratory sample handling and testing, quality assurance/quality control, decontamination and disposal, permitting, and right of entry.

Proposed sampling areas will be cleared for underground utilities prior to beginning work. Southwest Geophysics will provide an independent sweep for underground obstructions. Interphase Environmental will collect soil samples with a direct-push Geoprobe rig. Groundwater may also be sampled, if construction activities on a particular site are expected to encounter groundwater. Samples will be submitted to Orange Coast Analytical for analysis. HDR will prepare a Phase II SI Report, which will summarize the findings and recommendations based on the laboratory results.



Task 2.10.4 Deliverables:

- Phase II SI Workplan
- Phase II SI Report
- Hazardous Materials Disclosure Documents (if needed)

Task 2.10.4 Assumptions:

- Four sites will be investigated:
 - 1. Site 1: California Resources Corp (west of LA River north of Shoemaker)
 - 2. Site 2: California Resource Corp (West of LA River at proposed bridge abutment)
 - 3. Site 5: 960 Deforest Ave. (UPRR Bulk Terminal)
 - 4. Site 6: 970 West Chester Pl. (former MTA Div. 12 bus terminal)
- Other sites listed in the Environmental Document will be investigated by others
- No additional or site-specific Phase Is (ISAs) will be conducted
- Cleanup/remediation of discovered conditions is not included.
- Maximum of 10 days of field sampling
- Maximum of 2 days of geophysical surveys for USTs
- Maximum of 26 borings across all 4 sites, 3 samples per boring
- Up to 15 groundwater samples
- · Geophysical clearance of all borings prior to drilling
- · Maximum of 4 days of traffic control for work in right of way
- Each sample analyzed for TPH, VOCs, and Title 22 Metals
- Up to 12 soil samples analyzed for PCBs, as needed
- Drilling permits will be necessary from the City of Long Beach at their normal cost
- City of Long Beach will provide encroachment permits in-kind at no cost
- · Up to 4 drums of investigation-derived waste will be disposed of
- The City will provide a secure site for staging drums for disposal

2.10.5: Prepare Traffic Control Plans to Support Field Work

HDR will prepare site-specific traffic control plans per Caltrans and CAMUTCD standards for the completion of any field work conducted as part of Task 2.10 that requires vehicles to be parked or work to be completed within any active roadways. These traffic control plans will be submitted to Caltrans or the City for review and approval, as appropriate, prior to the initiation of any field work.

Task 2.10.5 Deliverables:

- Draft and Final Traffic Control Plans
- Responses to agency comments on draft plans

Task 2.10.5 Assumptions:

 Up to seven (7) sheets of engineered and stamped temporary traffic control plans will be prepared to support field work

2.11: Urban Design and Aesthetics

This task involves the development of an overall urban design and aesthetics concept plan for the entire project which will cover park areas within the existing Cesar Chavez Park and graded





slopes at bridges and along roadways. Specifically this concept plan will focus on the park elements to be constructed as part of Construction Package 2 but will also include aesthetic lighting for the bridges and other structures. It also includes the completion of a study to evaluate the potential for Envision Certification.

2.11.1: Conduct Study to Evaluate Potential for Envision Certification (Optional Task)

HDR Envision experts will conduct a study to determine which elements of the project (Packages 1 and 2) are candidates for Envision certification by the Institute for Sustainable Infrastructure. The study will identify how each element can be constructed to obtain Envision credits under the Envision Certification Program, how many credits would be obtained, and the rough order of magnitude construct cost associated with doing so compared to standard construction. A report will be prepared to document this study and submitted to the City for review and consideration. HDR will then conduct a half-day workshop with City staff to review and discuss the study findings. HDR will prepare an updated version of the report to document any construction items selected by the City for Envision Certification for incorporation by the Project, the associated cost, and the total Envision credits obtained.

Task 2.11.1 Deliverables:

- Draft and Final Summary Report
- Workshop agenda, minutes, presentation materials

2.11.2: Prepare Overall Urban Design, Landscaping, Contour Grading and Bikeway Concept Plan

HDR will work jointly with City staff to develop an overall concept plan for the urban design, landscaping, and bikeway elements of the project which will be constructed as part of Construction Package 2. This work will include the preparation and review of concept sketches with the City staff in the development of the overall plan. Once concurrence is obtained on the plan at a conceptual level, a rough order of magnitude cost estimate for these project elements will be developed and a technical memorandum will be prepared to formally document the concept plan ant its associated cost. This memorandum will be submitted to the City for review and approval prior to initiating any final design activities.

Task 2.11.2 Deliverables:

- Concept sketches, conceptual plans
- Rough order of magnitude cost estimate
- Draft and final summary memorandum

Task 2.11.2 Assumptions:

All landscaping and aesthetics to be consistent with LA River Master Plan

2.11.3: Prepare Lighting Concept Plans

In conjunction with the work completed as part of Task 2.11.2, HDR will develop lighting concepts for the park elements of the project, including bike/ped paths, as well as for aesthetic lighting of the bridges and other structures. Standard street lighting is not included as part of this task. Conceptual layouts of the areas to be lighted will be developed to identify the type and location of all lighting elements. These lighting concepts will be incorporated into the





concept sketches and plans developed as part of Task 2.11.2 as appropriate. Similarly, the project costs of these lighting features will be calculated and included in the cost estimate prepared as part of Task 2.11.2. City-selected lighting concepts will be documented within the technical memorandum prepared as part of Task 2.11.2 as well.

Task 2.11.3 Deliverables:

Conceptual lighting concept strip maps and construction cost estimate

2.12: Complete Occidental (Oxy) Oil Field Impact Assessment and Facility Relocation Plan

The objective of this task will be to identify and assess any project impacts to the Oxy Oil Facility along the west bank of the LA River within the project limits, and to work with Oxy Oil to develop the necessary mitigations and associated costs. A key project goal will be to minimize or avoid impacts to the existing Oxy Oil facility located between SR-710 and the LA River. It is HDR's understanding that this facility is owned by Long Beach Gas and Oil (an arm of the City), and the operation of the facility is licensed to Oxy Long Beach, Inc.

Evans and Walker will support the HDR team in identifying the value of potentially impacted wells early on the design development process. If project impacts cannot be avoided, Evans and Walker will work with the City, the design team and both Oxy Oil and Long Beach Gas and Oil to identify specific impacts to their facilities and develop the appropriate mitigations. This will include the development of the appropriate mitigation costs to not only cover the physical mitigations but also the loss of future revenue. HDR will summarize the assessment completed as part of this task, the proposed mitigations, and associated mitigation costs in a relocation plan technical memorandum and submit to the City for review and concurrence. It is assumed that any negotiations with Oxy Oil and Long Beach Gas and Oil on mitigation costs will be conducted by the City, although HDR can provide technical support during this process.

Task 2.12 Deliverables:

Draft/final oil facility impact assessment report and mitigation plan.

Task 2.12 Assumptions:

 The detailed design and construction of any mitigations to the Oxy Oil facility will be completed separately by Oxy Oil Inc.'s own contractor. This work will not be part of the City's Shoemaker Bridge Replacement Project final design and/or construction contract.

2.13: Prepare Constructability Plan

The purpose of this task is to complete a constructability evaluation of the refined project alternative selected for implementation as part of Task 2 and to identify issues and concerns that could potentially be addressed or mitigated as part of final design and within the final PS&E package. In addition, this task will involve the development of a high level construction staging approach for project that outlines overall staging/phasing approach for completing construction.

HDR's Construction Services staff will provide general support during the geometric refinement and structures type selection process included as part of Task 2 to identify potential constructability issues and concerns that may impact the feasibility and costs of designs being considered. Upon geometric approval and prior to the initiation of Structures Type Selection,



HDR Construction Services staff will perform a constructability review of the preliminary project plans, construction schedule, and construction cost estimate and identify potential design changes that would enhance overall constructability. Review comments will be prepared, formalized in a memorandum, and submitted to the City and Caltrans for review. The reviewer will subsequently participate in a workshop with the HDR design team and appropriate agency staff to review and discuss comments in detail and to facilitate obtaining consensus on the implementation of any suggested design changes. A draft version of the review memo will be generated to address pertinent agency comments received or to address the discussion at the review workshop.

Agreed-upon project changes resulting from the constructability review will be incorporated into the design package during the subsequent final design phase.

HDR will also develop a high level conceptual phasing approach for the construction of the various project elements included within the three assumed construction packages and outline the approach in a series of phasing exhibits highlighting the specifics of the work to be done as part of each contract package.

Task 2.13 Deliverables:

- Draft/Final Constructability Review Technical Memorandum
- · Construction phasing layout exhibits

Task 2.13 Assumptions:

 The constructability review described above will be conducted on the selected project alternative only.

2.14: Obtain E-76 Authorization for Utilities and Right of Way

The objective of this task is to facilitate obtaining the necessary State and Federal authorization to utilize Federal funds for construction and right of way activities. Since the City will likely seek Federal funds for construction, the HDR team can assist the City in streamlining and obtaining authorization (E-76) for Right of Way and Utilities during the initial stages of final design and obtaining authorization (E-76) for construction to prepare the project for the bid phase. Assuming that the City is using federal dollars to pay the cost of right of way, utilities, and construction, authorization for use of these funds would be processed through Caltrans District 7 Office of Local Assistance. This process will be conducted in compliance with the Caltrans Local Assistance Procedures Manual. Temporary construction easements and replacement utility easements, if any, will be noted. Also, because the project includes State owned right of way, identification of known utility prior rights will be addressed. It is important to note that an approved construction encroachment permit must be obtained prior to approval of the final E-76 (Construction).

Task 2.14 Deliverables:

Completed E-76 applications

2.15: Conduct Edison Middle School Vehicle Circulation/Drop off Study

Vehicular access to the Edison Middle School between 6th and 7th Streets will be impacted by the 6th and 7th Street modifications included as part of the project. Staff parking for the school is





located along Maine Avenue between 6th and 7th Streets, and vehicle turnouts are provided along existing 7th Street to allow vehicles to pick up and drop off students. HDR will conduct a focused traffic study to assess the circulation and parking impacts to the school due the 6th and 7th Street modifications. Based on the findings of the Study, HDR will propose any specific improvements than be incorporated as part of the project to mitigate these impacts. HDR will prepare a technical memorandum to document the scope of the evaluation any proposed mitigations. A draft of this memorandum will be submitted to City staff for review and consideration. The final version of the memo will be prepared to document the specific mitigations agreed upon by the City to be implemented as part of the project.

Task 2.15 Deliverables:

· Draft and final technical memorandum

2.16: Environmental Revalidation/Addendum (Optional Task)

The project was formally environmentally cleared in 2020 with the City approval of the EIR in April and Caltrans approval of the EA in June. As part of Task 2, HDR will reevaluate the validity of the final Environmental Document (ED), in compliance with CEQA and NEPA, and prepare supplemental environmental technical studies if required to address minor changes in project design.

Since the newly constructed bridge will fall under Caltrans jurisdiction after completion of construction, and a portion of project funding will be provided through the Federal Highway Administration (FHWA), environmental clearance of the proposed project will fall under both Caltrans and FHWA requirements.

The HDR team will prepare supplemental technical studies and CEQA/NEPA revalidation/addendum documentation in accordance with Caltrans' Standard Environmental Reference (SER) guidelines to address new or altered impacts related to the human, physical, and biological environments resulting from refinements during final design. HDR will submit the supplemental technical studies and Supplemental ED to the City, Caltrans, and FHWA, as appropriate, for review and approval.

The HDR team understands the City's desire to revalidate the environmental document without the need for a Supplemental EIR/EA which would require recirculation. However, in the event a more complex and iconic bridge design is considered during the PS&E phase, additional studies may be required.

Task 2.16 Deliverables:

- Supplemental Environmental Technical Studies (if needed) up to 6 months
- CEQA Addendum and NEPA Revalidation Form 2 months (after the completion of technical studies)

Task 2.16 Assumptions:

- Only minimal changes are anticipated in the design refinements for the PS&E phase;
 therefore, it is assumed that the revalidation of the document will not require public recirculation.
- The City will pay all required permit fees.





2.17: Value Analysis Support Services

Due to the estimated construction cost of the work to be completed within Caltrans jurisdiction as part of the project, Caltrans will be required to conduct a formal Value Analysis (VA) Study. This study typically includes the completion of a one-week workshop by the VA lead to review the current project design and discuss potential design modifications/refinements that will increase the project value (reduce construction cost/duration, improve safety, reduce impacts, etc.) This study will be led by Caltrans but will require the participation of the HDR team's discipline leads involved in the Package 1 project design including the roadway/civil lead, structures lead, traffic lead, and drainage/utilities lead. It is assumed that this VA study will be completed upon geometric approval and prior to the initiation of Structures Type Selection and will require participation by the Package 1 discipline leads for four (4) days. It is assumed that as part of their participation, HDR may be required to consider and evaluate design proposed refinements/options during the course of the VA workshop.

Task 2.17 Assumptions:

- · VA Study to be led by Caltrans/others.
- Assumes participation in VA workshop by four (4) discipline leads for four (4) full days.
- Assumes no major design revisions come out of VA Study

Tasks 3A – 5A: Preparation of Plans, Specifications and Estimates for Package 1

Tasks 3A through 5A cover the preparation of the Package 1 PS&E package. This package will be prepared in accordance with Caltrans standards as outlined in the current editions of the following manuals and others as appropriate and will require Caltrans approval:

- Caltrans Highway Design Manual
- AASHTO LRFD Bridge Design Specifications, 8th Edition incl. Interim Revisions with California Amendments
- Caltrans Division of Engineering Services Structures Manuals, including Information and Procedures Guide, Design Details, Aids, Practice and Memo to Designers Manuals
- Caltrans Project Development Procedures Manual
- Caltrans Plans Preparation Manual
- Caltrans CADD User's Manual
- Caltrans Highway Planting and Irrigation Manual
- Caltrans Guide for Submittal of PS&E
- Caltrans Construction Contract Development Guide
- Caltrans Standard Plans and Specifications
- Caltrans Storm Water Quality Handbooks
- Caltrans Signal and Lighting Guidelines
- Caltrans published Structures Technical Policies

The assumed milestone submittals follow those as prescribed in the Workplan Standards Guide and are assumed to be made at the 65%, 95%, and 100% design phases. The specific elements to be included in each package are as outlined in the manuals listed above.





Task 3A-5A Assumptions:

One review cycle per agency assumed for each deliverable

Task 3A: Draft PS&E (65%) Submittal for Package 1

This task involves the preparation of a 65% Caltrans PS&E package for Construction Contract Package 1. This package includes unchecked structures plans for the structures within State jurisdiction and outline Caltrans Specification Special Provisions and Nonstandard Special Provisions to supplement the Caltrans Standard Specifications. All plan preparation tasks included below include the development of the associated quantities for the construction items shown on the plans, which will be shown within the quantity summary sheets.

It is assumed that Caltrans will conduct separate constructability and safety review workshops of the 65% plans prior to their formal submittal for review. Attendance by project team staff at these workshops are covered under Task 1.1.1. Any comments generated by Caltrans as part of these reviews are assumed to be addressed prior to the 65% PS&E submittal.

Task 3A Assumptions:

- Twenty (20) hard copies and one PDF copy of plans, specifications, and estimates to be submitted to Caltrans for review
- Ten (10) hard copies and one PDF copy of plans, specifications, and estimates to be submitted to City for review

3A.1: Prepare 65% Roadway Plans

HDR will utilize the Caltrans-approved geometrics per Task 2.5 as the basis for the development of the 65% roadway plans. Plan sheets to be prepared as part of this task are listed below.

Task 3A.1 Deliverables:

- Title Sheet
- Typical Sections
- Key Map and Line Index
- Layout Plans
- Profiles and Superelevation Diagrams
- Construction Details
- Contour Grading
- Summary of Quantities

3A.2: Prepare 65% Drainage Plans

This task includes the preparation of the Draft Project Drainage Report, the Draft Caltrans Stormwater Data Report, and the 65% Drainage and Stormwater Plans.

3A.2.1: Prepare Reports

HDR will prepare the Draft Drainage Report to address the existing drainage conditions within the project limits and the proposed drainage modifications and new drainage systems that will be needed to accommodate the project runoff. The Drainage Report will be prepared to cover the full limits of the project, including the areas both inside and outside Caltrans jurisdiction.





The report will be organized such that the drainage recommendations for the work in State jurisdiction and the work within City jurisdiction will be separated to facilitate the reviews by each agency. The drainage report will also provide the necessary final design recommendations for the design of the new SD-01 Pump Station, the design of which is covered under Tasks 3B through 5B.

The report will present a narrative of the hydrologic and hydraulic assumptions, analyses, and designs required for the proposed improvements. The report will include summary tables of pre- and post-project condition hydrologic and hydraulic analyses of sub-catchments and storm water conveyances within the project limits. The report will present the design flow rates, proposed inlet geometrics, and hydraulic grade lines. The engineering calculations relevant to the hydrologic analysis and hydraulic design of the proposed drainage improvements and a set of the draft drainage improvement plans prepared as part of Task 3A.2 will be included in the report appendices.

To address storm water quality requirements (NPDES & Caltrans) for the work within State jurisdiction, HDR will prepare a Caltrans Storm Water Data Report (SWDR) in accordance with Caltrans preparation guidelines.

Task 3A.2.1 Deliverables:

- Draft Drainage Report (20 hard copies and 1 PDF copy)
- Draft Storm Water Data Report (10 hard copies and 1 PDF copy)

Task 3A.2.1 Assumptions:

- Draft Project Drainage Report will be a single report that covers entire project and all project elements, including pump station
- Hydrology and Hydraulic calculations for facilities in State jurisdiction will be per Caltrans standards. Calculations for facilities within City jurisdiction will be per City of Long Beach and Los Angeles County Department of Public Works Standards.
- No temporary or interim drainage analysis is included in this scope of work
- No tidal influence will be analyzed on the project storm drain systems
- · SWDR covers limits of improvements within State jurisdiction only

3A.2.2: Prepare Plans

HDR will prepare plans for the new onsite and offsite drainage systems as well as modifications/upgrades to the existing drainage systems within State jurisdiction based on the recommendations in the Drainage Report. In addition, both Temporary Water Pollution Control Plans and Erosion Control Plans will be prepared for the areas within State jurisdiction in accordance with Caltrans requirements. The proposed BMPs shown in the Water Pollution Control Plans will reflect the SWDR recommendations.

Task 3A.2.2 Deliverables:

- Drainage Plans, Profiles, Details, and Quantities
- Temporary Water Pollution Control Plans
- Erosion Control Plans





Task 3A.2.2 Assumptions:

- Temporary Water Pollution Control Plans will be prepared for each construction stage
- Plans to cover work within Caltrans jurisdictions and adjoining local streets only. All park drainage features will be covered under Package 2
- Assumes all runoff is to be conveyed to LB MUST facility or new SD-01 Pump Station
- Determination of runoff to LB MUST and/or pump station to be made in coordination with City and LB MUST project team.

3A.3: Prepare Stage Construction, Traffic Handling, Detour, and Construction Area Sign Plans, and TMP

This task involves the development of a construction staging approach in coordination with Caltrans and City staff, the development of detailed design plans to convey this approach, as well as the Caltrans Traffic Management Plan for Package 1 construction.

3A.3.1: Staging Concept Development and Approval

HDR will work jointly with City and Caltrans staff to develop an acceptable construction staging approach that will be carried forward into final design and construction. HDR will prepare an initial construction staging/maintenance of traffic concept to review with City and Caltrans staff. This concept will be presented in a set of high level schematic staging layouts for the Package 1 construction (one sheet per stage). These exhibits will show areas open to traffic and those under construction in each stage. If any detours or temporary roadways are needed to maintain traffic during each stage, these will be shown conceptually in the exhibits. These exhibits and a narrative describing the proposed staging strategy will be included in the summary memorandum.

HDR will submit these exhibits to the City and Caltrans for review and subsequently conduct a joint workshop with both agencies. The goal of the workshop will be to reach a consensus on the construction staging approach to be carried forward into final design. Based on the comments generated at the workshop, HDR will refine the concept and recirculate to both Caltrans and the City for written concurrence.

Task 3A.3.1 Deliverables:

- Draft and final construction staging exhibits
- Workshop agenda, minutes, presentation materials

3A.3.2: Prepare Draft Transportation Management Plan (TMP)

HDR will develop a Transportation Management Plan (TMP) to address traffic detours and operations during the construction phase. The TMP will be coordinated with the City of Long Beach, Caltrans, and other stakeholders, including the California Highway Patrol. Traffic studies conducted as part of the final environmental document will be reviewed in advance of developing the TMP to ensure that any specific mitigation is incorporated.

Task 3A.3.2 Deliverables:

Draft TMP (10 hard copies and 1 PDF copy)

3A.3.3: Prepare Plans





HDR will prepare Construction Staging/Traffic Handling Plans, Detour Plans, and Construction Area Sign Plans for Package 1 construction to reflect the agreed upon approach developed as part of Task 3A.3.1.

Task 3A.3.3 Deliverables:

- Stage Construction/Traffic Handling Plans
- Detour Plans (including layouts, profiles, superelevation diagrams as needed)
- Construction Area Sign Plans

3A.4: Prepare 65% Pavement Delineation Plans

HDR will prepare pavement delineation plan to identify locations of painted and thermoplastic stripes and markings, pavement markers, and delineators for all roadway work completed as part of Package 1.

Task 3A.4 Deliverables:

Pavement Delineation Plans, Details, and Quantities

3A.5: Prepare 65% Sign Plans

HDR will prepare Sign Plans to show existing and proposed new signs. The plans will include sign details and quantity sheets.

Task 3A.5 Deliverables:

· Sign Plans, Details, and Quantities

Task 3A.5 Assumptions:

All sign and lighting design assumed to be based on current Caltrans Standard Plans.
 Nonstandard designs are not included in this scope.

3A.6: Prepare 65% Electrical Plans

HDR will conduct street lighting analysis to determine the locations and types of safety lighting along the proposed roadways within Caltrans jurisdiction and abutting local streets to be modified as part of the Package 1 construction. Based on this analysis, HDR will prepare Lighting Plans that show the locations and details of this safety lighting as well as the aesthetic lighting along the bridges and other locations within the Package 1 limits as defined as part of Task 2.11.

HDR will prepare traffic signal plans for the traffic signal modifications required along 6th and 7th Streets within the project limits as well as to potential modifications of the traffic signal at Shoreline Drive/Broadway intersection.

Task 3A.6 Deliverables:

- Lighting calculations
- · Lighting Plans and Details
- Traffic Signal Plans and Details

Task 3A.6 Assumptions:

Assumes no ramp metering or electrical system plans are required





 All bridge/aesthetic lighting to be based on guidelines and concepts developed as part of Task 2

3A.7: Geotechnical and Foundation Reports

This task involves the preparation of the necessary reports to provide recommendations regarding the design of structural foundations, embankment slopes, grading, and pavement structural sections.

3A.7.1: Geotechnical Design Report (GDR)

HDR will utilize the data generated as part of Task 2 to prepare a report discussing the geotechnical basis of the project and provide recommendations for design and construction standard earth retaining structures, cut and fill slopes, pavement, and drainage facilities. The report will cover the work to be completed as part of both Packages 1 and 2. The report will be submitted to Caltrans for review. All calculations supporting the recommendations will be included in the appendix to the GDR. The report will include infiltration testing for any potential BMP infiltration basins.

Task 3A.7.1 Deliverables:

Draft and Final Geotechnical Design Report

Task 3A.7.1 Assumptions:

- Separate GDRs will not be prepared for Package 1 and Package 2 construction
- The preparation of the GDR to support the SD-01 pump station design is covered under Task 2.8.2.

3A.7.2: Foundation Reports for Structures

HDR will build upon the Preliminary Foundation Report prepared as part of Task 2 to prepare a Foundation Report based upon the Type Selection comments and additional information from the GDR analysis. The report will provide foundation recommendations for all Package 1 structures including bridges, special design retaining walls, stand-alone overhead sign structures, and traffic signals. Log of test borings will be included in 11 inch by 17 inch plans. This report will be submitted to Caltrans for review.

Task 3A.7.2 Deliverables:

Draft and Final Foundation Reports

3A.7.3: Materials Report

HDR will prepare a report discussing the pavement structure recommendations and/or pavement studies for the project. This report will be submitted to Caltrans for review. HDR will address any comments stemming from this review and prepare a final draft. All calculations supporting the recommendations will be included in the report appendix.

Task 3A.7.3 Deliverables:

· Draft and Final Materials Report

3A.8: Bridge and Nonstandard Retaining Wall Plans (Unchecked Details)



This task includes the plan preparation for all Package 1 structures including the bridges, pedestrian bridges, and any nonstandard retaining walls. In addition, quantities and cost estimates for all structures will be generated based upon the designs included in the plans.

3A.8.1: Prepare Structures Plans

HDR will prepare bridge and retaining wall layout plans, profiles, and structural details for the LA River Bridge and associated roundabout structure, the LA River Bridge bike/bed connection bridge, the replacement 7th Street Pedestrian Bridge, as well as all nonstandard retaining walls. Plans will incorporate aesthetic details consistent with the agreed upon concepts generated as part of Task 2. In addition, schematic removal plans for the existing Shoemaker Bridge will be prepared. Although the 7th Street Pedestrian Bridge is outside of Caltrans jurisdiction, it will be designed in accordance with Caltrans plan formatting standards.

Bridge design will be in accordance with Caltrans Seismic Design Criteria, Bridge Design Specifications, Memos to Designers, and Bridge Design Details Manual. Details and construction specifications will be prepared in accordance with Caltrans Standard Plans, Standard Specifications, and Standard Special Provisions.

Task 3A.8.1 Deliverables:

Unchecked Structure Plans

Task 3A.8.1 Assumptions:

- Design to be initiated immediately upon Type Selection Report submittal.
- Elevated roundabout structure and LA River Bridge are Ordinary Nonstandard bridges and pedestrian bridge are Ordinary Standard bridges per Caltrans SDC.
- Existing soils are anticipated to be improved for bridge foundation analysis/design.
- Study/use of base isolation is not included.
- Bridge removal plans will be schematic in nature, with supporting specifications to
 indicate acceptable means and methods, monitoring requirements, etc. Detailed removal
 plans for the existing Shoemaker Bridge will be prepared and submitted by the
 successful bidding Contractor and subject to review and acceptance by the Engineer.
- 7th Street Pedestrian Bridge to be designed in accordance with Caltrans structural design and plan formatting standards.

3A.8.2: Prepare Updated Structures Cost Estimate

HDR shall developed updated quantity summaries and cost estimates for each structure based upon the designs included in the Unchecked Structures Plans.

Task 3A.8.2 Deliverables:

Updated structure quantity summaries and cost estimate.

3A.9: Prepare Utility Plans

This task will involve updating the existing utilities composite to reflect the potholing data obtained as part of Task 2.9. It will also include the coordination with impacted third-party utility owners to facilitate their development of final design plans for the necessary relocations of their





facilities, and the preparation of Utility Plans to show all pothole locations and the identify the disposition of utilities determined to be in conflict.

3A.9.1: Update conflict maps and matrix based on potholing results

HDR will review the pothole data reports prepared as part of Task 2.9 and update the existing utilities base, conflict maps, and matrix to reflect the pothole findings.

Task 3A.9.1 Deliverables:

· Updated existing utilities base, conflict map, and matrix

3A.9.2: Utility Coordination

HDR will issue formal Notice to Relocate letters to all impacted third-party owners on the City's behalf, which will initiate relocation process by the owners.

HDR will coordinate regular coordination with the impacted utility owners to confirm that they have the necessary information and materials needed to complete the detailed relocation design of their facilities and to check on the status of their final design work to confirm they are meeting the agreed upon design schedule outlined as part of Task 2.9.

HDR will review the relocation plans prepared by the impacted owners to confirm that they are consistent with the proposed project improvements and are compatible with other existing and relocated utilities within the limits of the work. HDR will conduct workshops with each owner if necessary to discuss any comments generated based on these reviews.

Task 3A.9.2 Deliverables:

- Notice to Relocate Letters
- Final design plans for all third-party utility relocations (by others)
- Review comments of draft relocation plans
- Meeting agendas, minutes, presentation materials

Task 3A.9.2 Assumptions:

 All impacted third-party owners will complete the relocation designs for their own facilities

3A.9.3: Prepare 65% Utility Plans

HDR will prepare Utility Plans to show all existing utilities within the Package 1 limits and the disposition of any utilities determined to be in conflict. Disposition shall include the utility company name, facility type, original location, and proposed location for each utility. Plans will show pothole locations.

Task 3A.9.3 Deliverables:

- Updated Utility Conflict Matrix
- Updated Utility Plans Sheets

3A.10: Prepare Outline Specifications

HDR will prepare outline technical specifications for the work to be completed as part of Package 1. It is assumed that all work within Caltrans jurisdiction completed as part of Package 1 will completed in accordance with the current version of the Caltrans Standard Specifications.





Any work along 6th and 7th Streets outside of Caltrans jurisdiction may be subject to Green Book Standard Specifications and any associated City supplements or addenda. HDR will identify any project elements requiring Standard or Nonstandard Special Provisions to the Caltrans Standard Specifications and list these in an outline format consistent with the organization of the Caltrans Standard Specifications. HDR will complete the same exercise for any project elements along 6th and 7th Streets that will be subject to the Green Book Standard Specifications.

Task 3A.10 Deliverables:

- Outline of any required SSPs and NSSPs to Caltrans Standard Specifications
- Outline any technical specifications for work in City jurisdiction that is not covered within Green Book Standard Specifications or any applicable City supplements or addenda.

Task 3A.10 Deliverables:

 Team to use the latest Caltrans Standard Specifications and Green Book Standard Specification, available at the initiation of the PS&E

3A.11: Prepare Draft Engineer's Estimate of Probable Construction Cost

HDR will assemble the quantities generated as part of Task 3A to develop a Draft Engineer's Estimate of Probable Construction Cost. Unit costs will be obtained from the latest Caltrans Cost Data Book and recent available bid data. The cost estimate will be organized in accordance with the Caltrans BEES cost estimate formatting standard unless otherwise dictated by the City.

Once the Draft Engineer's Estimate has been prepared, HDR will conduct an independent review of the estimate as discussed in the introduction and prepare a memorandum to summarize their findings.

Task 3A.11 Deliverables:

- Draft Engineer's Estimate of Probable Construction Cost
- Independent cost estimate review summary of findings memorandum

Task 3A.11 Assumptions:

 Estimate format to be consistent with Caltrans BEES formatting standards unless otherwise directed by City

3A.12: Envision Certification (Optional Task)

Based upon the outcome of Task 2.16, it is assumed the City will want to pursue Envision Certification for the Project. For the purpose of the Envision Certification, the "Project" will constitute the work being done as part of Packages 1 and 2 excluding the SD-01 Pump Station construction. As part of this task, an HDR Envision Certification Specialist will work with the project team to incorporate the City-directed Envision-eligible project elements identified as part of Task 2.16 into the 65% bid set for the Package 1 construction. Upon the completion of the 65% PS&E package, the Certification Specialist will conduct an audit of the bid set to confirm the Envision-eligible elements have been appropriate incorporated and will prepare the necessary Envision compliance audit documentation.





Task 3A.12 Deliverables:

Envision compliance audit documentation

Task 3A.12 Assumptions:

 It is assumed that the City will pursue Envision Certification for the Project, and the appropriate envision elements will be incorporated into the Package 1 bid set.

Task 4A: Initial PS&E (95%) Submittal for Package 1

This task involves obtaining resolution on the disposition of the 65% agency review comments, updating the PS&E package to address the comments received, and advancing the PS&E package to a draft level of completion. A second Caltrans Constructability Review will be conducted as part of this design phase, with the comments addressed by the project team prior to the formal submittal of the 95% PS&E package.

Task 4A Assumptions:

- Twenty (20) hard copies and one PDF copy of plans, specifications, and estimates to be submitted to Caltrans for review
- Ten (10) hard copies and one PDF copy of plans, specifications, and estimates to be submitted to City for review

4A.1: 95% Roadway PS&E

This task covers the Task 4A work described above for the roadway portion of the Package 1 bid set. The roadway portion covers all portions of the bid set aside from the structures component, including the following:

- Roadway/Civil
- Drainage and Stormwater
- Construction Staging
- · Pavement Delineation and Signage
- · Lighting and Electrical

- Utilities
- Hazardous Materials
- Environmental Compliance

The following describes the process that will be followed to address agency review comments:

- Upon receipt of the 65% agency review comments, HDR will review the comments and develop draft responses. All responses will be documented in a series of commentresponse matrices (one per reviewer).
- HDR will submit the draft comment-responses matrices to the various agency reviewers for review.
- HDR will conduct a series of comment-response review workshops with each reviewing agency (one per agency). The goal of these workshops will be to review HDR's draft responses and to reach consensus on the disposition of each comment.
- HDR will revise the comment-responses to reflect the agreed-upon disposition per the workshops and submit the revised comment-response matrices to the reviewers for signoff.

4A.1.1: 95% Roadway Plans



HDR will complete the process described above to reach consensus with the reviewing agencies on the disposition of the 65% review comments. HDR will the revise the roadway plans to address the comments and advance the plans to a draft level of design completion. The draft 95% plans will be submitted to Caltrans for the purpose of the 95% constructability review. HDR will then update the 95% plans to address the constructability review comments and compile the revised 95% plan set in preparation for the formal milestone submittal.

4A.1.2: Prepare 95% Roadway Quantities and Cost Estimate

HDR will revise the Engineer's Estimate to address any City review comments. Since the City will be advertising, awarding, and administering the Package 1 construction contract, it is assumed that Caltrans will have no interest in reviewing the Engineer's Estimate in detail. HDR will then update the quantity summaries for each discipline to reflect the updated designs. Updated quantities will then be incorporated into the Engineer's Estimate in order to update the estimate to reflect the 95% plans.

Once the Engineer's Estimate has been updated, HDR will conduct an independent review of the estimate as discussed in the introduction and prepare a memorandum to summarize their findings.

4A.1.3: Prepare Draft Specification Special Provisions

HDR will prepare a complete set of Draft Specification Special Provisions and Nonstandard Special Provisions to act as a supplement to the Caltrans Standard Specifications for all work in Caltrans jurisdiction. Similarly, HDR will prepare draft technical specifications for all work along 6th and 7th Streets within City jurisdiction to supplemental the Green Book Standard Specifications and any City supplements or addenda.

HDR will assist the City in preparing the General Provisions for project specifications. It is assumed that the City will be responsible for preparing "up front" provisions and the complete set project specifications.

Task 4A.1 Deliverables:

- Draft/final 65% submittal comment- response matrices
- 95% Plans
- Updated Engineer's Estimate of Probable Construction Cost
- Independent Cost Estimate Review Summary of Findings Memorandum
- Draft technical specifications

Task 4A.1 Assumptions:

 The City will be responsible for preparing up-front provisions and compiling project specification package.

4A.2: Checked Bridge and Nonstandard Retaining Wall PS&E

This task covers the Task 4A work described above for the structures portion of the Package 1 bid set. As part of this task, an Independent Check of the draft structures design will be conducted, per Caltrans requirements, for the LA River Bridge and the roundabout structure only. All agency comments resulting from the review of the Unchecked Structures PS&E will be addressed in accordance with the process outlined above under Task 4A.1.





4A.2.1: Prepare Checked Structures Plans

HDR will revise the structures plans to address the 65% agency review comments and will then conduct an independent check of the design for the LA River Bridge and the roundabout structure only. HDR will then resolve any inconsistencies resulting from the independent check and compile a set of updated structures plans in preparation for the 95% constructability review. HDR will then update the 95% plans to address the constructability review comments and compile the revised 95% structures plan set in preparation for the formal milestone submittal.

4A.2.2: Prepare Draft Specification Special Provisions

HDR will prepare a complete set of Draft Specification Special Provisions and Nonstandard Special Provisions to act as a supplement to the Caltrans Standard Specifications for all structures work included as part of Package 1. These specifications will reflect the design included in the 95% structures plans. It is assumed that the 7th Street Pedestrian Bridge will utilize Caltrans structural specifications even though the structure is outside Caltrans jurisdiction.

4A.2.3: Prepare 95% Structures Quantities and Cost Estimate

HDR will update the quantity summaries for each structure to reflect the updated designs. Updated quantities will then be incorporated into the Engineer's Estimate in order to update the estimate to reflect the 95% plans. HDR will also conduct an independent check of the quantity calculations for the LA River Bridge and the roundabout structure only.

4A.2.4: Prepare Structural Calculations

HDR will compile the structural calculations developed as part of the design of each structure into binders in preparation for inclusion with the 95% PS&E submittal.

Task 4A.2 Deliverables:

- · Checked Structures Plans
- Updated structures quantities to be included in Engineer's Estimate
- Independent check of structures quantities for the LA River Bridge and the roundabout structure only
- Draft Structures Technical Specifications (SSPS)
- Structural design calculations
- Independent structural design check calculations for the LA River Bridge and the roundabout structure only
- Quantity Summary Sheets
- Memo to Specification Engineer

Task 4A.2 Assumptions:

- Independent Check of elevated roundabout and LA River Bridges and 95% Design to be initiated immediately upon 65% PS&E submittal.
- Elevated roundabout structure and LA River Bridge are Ordinary Non-standard bridges and pedestrian bridge is Ordinary Standard bridge per Caltrans SDC.
- Existing soils are anticipated to be improved for bridge foundation analysis/design.
- Study/use of base isolation is not included.





- Bridge removal plans will be schematic in nature, with supporting specifications to
 indicate acceptable means and methods, monitoring requirements, etc. Detailed removal
 plans for the existing Shoemaker Bridge will be prepared and submitted by the
 successful bidding Contractor and subject to review and acceptance by the Engineer.
- 7th Street Pedestrian Bridge to utilize Caltrans Structures Specifications.

4A.3: Prepare Construction Schedule

HDR will prepare a draft master construction schedule for the Project that includes all three construction packages, which will be prepared in Microsoft Project. The draft construction schedule will be included as part of the 95% submittal package.

Task 4A.3 Deliverables:

Draft construction schedule (20 hard copies and one PDF copy)

Task 4A.3 Assumptions:

- · Schedule will cover all three construction packages
- Schedule to be prepared in Microsoft Project

4A.4: Update Storm Water Data Report

HDR will work with Caltrans to address the comments received as part of the review of the Draft SWDR submittal. The procedure outlined as part of task 4A.1 will be followed to address the comments received. HDR will update the SWDR if necessary to reflect the advanced design of the stormwater elements and include the updated SWDR as part of the 95% submittal package.

Task 4A.4 Deliverables:

- Draft/final comment- response matrix
- Final SWDR (10 hard copies and 1 PDF copy)

4A.5: Prepare Environmental Commitments Record (ECR)

HDR will prepare an updated Environmental Commitments Record to confirm that all mitigations recorded within the Project Environmental Documented have been incorporated into the PS&E package. As part of this task, HDR will prepare a report to document project environmental compliance.

Task 4A.5 Deliverables:

- Updated ECR
- Environmental commitment tracking system
- Draft and final report on project compliance

4A.6: Update Transportation Management Plan

HDR will work with Caltrans to address the comments received as part of the review of the Draft TMP submittal. The procedure outlined as part of task 4A.1 will be followed to address the comments received. HDR will update the TMP to reflect the advanced design of the construction staging elements and will include the updated TMP as part of the 95% submittal package.

Task 4A.6 Deliverables:

Draft/final 65% submittal comment- response matrices





Final TMP (10 hard copies and 1 PDF copy)

4A.7: Envision Certification (Optional Task)

As part of this task, an HDR Envision Certification Specialist will work with the project team to confirm the appropriate incorporation the City-directed Envision-eligible project elements identified as part of Task 2.16 into the 95% bid set similar to what was done for the 65% PS&E package. Upon the completion of the 95% PS&E package, the Certification Specialist will conduct an audit of the bid set to confirm the Envision-eligible elements have been appropriate incorporated and will prepare the necessary Envision compliance audit documentation.

Task 4A.7 Deliverables:

• Envision compliance audit documentation

Tasks 5A: Final PS&E (100%) Submittal for Package 1

This task involves obtaining resolution on the disposition of the 95% agency review comments, updating the PS&E package to address the comments received, advancing the PS&E package to completion, and obtaining the necessary approvals for construction. A second Caltrans Safety Committee Review will be conducted as part of this milestone phase, with the comments addressed by the project team prior to the formal submittal of the 100% PS&E package. In addition, this task includes the preparation of ancillary items required by the City and Caltrans needed for construction including the final construction schedule, Resident Engineer's File, Materials Handouts, the Paleontological Mitigation Plan, and the Project Survey File.

5A.1: Final PS&E

This task covers the preparation of the Final PS&E package and obtaining Caltrans and City approval of the final bid package. This work will include the following:

- Preparing responses to 95% review comments and obtaining consensus with the reviewers on the disposition of each comment.
- Updating the PS&E package to address agency comments.
- Finalizing the design, if necessary.
- Submitting the Draft-Final PS&E package to Caltrans for the second Safety Committee Review
- Revising the PS&E to address the Safety Review comments.

Once the Engineer's Estimate has been updated, HDR will conduct an independent review of the estimate as discussed in the introduction and prepare a memorandum to summarize their findings.

5A.1.1: Final Roadway PS&E

This task covers the preparation of the roadway portion of the Final PS&E package as described above.

5A.1.2: Final Structures PS&E



This task covers the preparation of the structures portion of the Final PS&E package as described above. This will also include the preparation of a 1"=4' scale Deck Contour Plot.

5A.1.3: Update Construction Schedule

The draft construction schedule prepared as part of Task 4A will be updated as necessary to reflect the completed design and to address any comments received as part of the draft submittal.

Task 5A.1 Deliverables:

- Draft/final 95% submittal comment- response matrices
- Final approved PS&E package
- Updated construction schedule
- Independent Cost Estimate Review Summary of Findings

Task 5A.1 Assumptions:

- Final Design to be initiated immediately upon 95% PS&E submittal.
- Elevated roundabout structure and LA River Bridge are Ordinary Non-standard bridges and pedestrian bridges are Ordinary Standard bridges per Caltrans SDC. Existing soils are anticipated to be improved for bridge foundation analysis/design.
- Study/use of base isolation is not included.

5A.2: Prepare Resident Engineer's (RE) File

HDR will meet with the Package 1 Resident Engineer (RE) and provide the following information for the RE File:

- Permits
- Survey notes
- Geotechnical and Foundation Reports
- Hydrology/Hydraulics Report and calculations
- Relevant correspondence and memoranda
- Engineering calculations (horizontal and vertical alignments, earthwork quantities, etc.)
- Environmental agreements and reports
- TMP and supplements
- SWDR
- Right of way maps and agreements (see Task 6)
- Utility relocation plans and agreements
- Safety review report
- List of project personnel
- Cooperative agreements
- Working cross sections

Hours for the preparation RE packages for Package 2 and 3 construction bid packages are covered under this task.

Task 5A.2 Deliverables:

RE File (1 hard copy and 1 PDF copy) for each construction package





5A.3: Prepare Materials Handout

HDR will prepare materials handout information per Caltrans Highway Design Manual Section 111.3: Materials Information Furnished to Prospective Bidders.

Hours for the preparation Materials handouts for Package 2 and 3 construction bid packages are covered under this task.

Task 5A.3 Deliverables:

Materials handouts for each construction package

5A.4: Prepare Paleontological Mitigation Plan (PMP)

HDR will prepare a Paleontological Mitigation Plan consistent with Caltrans and County requirements. The PMP will be implemented as part of excavation activities during construction of all 3 packages.

Hours for the preparation PMPs for Package 2 and 3 construction bid packages are covered under this task.

Task 5A.4 Deliverables:

Paleontological Mitigation Plan (1 per construction package)

5A.5: Assist City in Preparing Bid Documents

HDR will provide technical assistance to the City in the preparation of the construction bid documents for each construction package.

Task 5A.5 Assumptions:

 City will be responsible for preparing non-technical portions of bid documents for each bid package.

5A.6: Prepare Survey File

HDR will prepare materials and compile documentation to be included in Survey File for use by the lead surveyor assigned to each construction package prior to construction. The following documentation will be included in the Survey Files as prescribed by the Project Development Procedures Manual Appendix QQ - Preparation Guidelines for Survey Files:

- Contact list
- Datum listing
- Project reference list
- Additional instructions
- Contract plans
- Project control
- Topography and base maps
- Horizontal and vertical alignments
- Profiles
- Cross sections roadway cross sections at 50' intervals (Package 1 only)
- Slope staking notes/grid grades (Package 1 only)
- Right of way appraisal maps





- Right of way coordinate geometry
- Right of way monument perpetuation documentation
- Digital design model

Hours for the preparation Survey Files for Package 2 and 3 construction bid packages are covered under this task.

Task 5A.6 Deliverables:

Survey Files (1 per construction package)

5A.7: Envision Certification (Optional Task)

As part of this task, an HDR Envision Certification Specialist will work with the project team to confirm the appropriate incorporation the City-directed Envision-eligible project elements identified as part of Task 2.16 into the final Package 1 bid set similar to what was done for the 65% and 95% PS&E packages. Upon the completion of the Final PS&E package, the Certification Specialist will prepare a Certification Compliance Report to document the Envision-eligible project elements included in the Package 1 bid set. The report will tally up the Envision Certification points obtained by the incorporation of these elements. This report will be submitted along with the report prepared as part of the Package 2 PS&E preparation to obtain Envision Certification for the Project.

Task 5A.7 Deliverables:

- Envision compliance audit documentation
- Certification Compliance Report

Tasks 3B - 5B: Preparation of Plans, Specifications and Estimates for Package 2

Tasks 3B through 5B cover the preparation of the Package 2 PS&E package, which includes the relocation of the SD-01 Pump Station and the construction of the park elements within the portion of Cesar Chavez Park bounded by Broadway to the South, future Shoreline Drive to the west, the existing Cesar Chavez park elements fronting Golden Avenue to the east, and the LB MUST facility to the north as depicted in **Attachment 1**. The work included within Package 2 all falls within City of Long Beach jurisdiction; and as such, the construction bid package will be formatted in accordance with City of Long Beach formatting standards for PS&E preparation. The designs to be advanced within these tasks are based upon the concepts and preliminary design work completed as part of Task 2 and approved by the City.

Similar to the work covered under Package 1, three milestone submittals to the City and other impacted agencies/stakeholders are assumed:

- 65% design
- Draft PS&E (90% design completion)
- Final PS&E (100% complete)

Task 3B-5B Assumptions:

One review cycle per agency assumed for each deliverable





Task 3B: 65% Package 2 PS&E Submittal

This task involves the preparation of a 65% PS&E package for Construction Contract Package 2, including the urban design work and the SD-01 Pump Station relocation. It also includes the preparation of the existing utility composite plans and the plans for any necessary relocations of sewer and water facilities needed to accommodate all proposed improvements east of the LA River. The sewer and water relocation design will be broken off and advanced to completion as part of Package 3, the preparation of which is covered under Tasks 4C and 5C. Package 3 is meant to be an early utility relocation construction bid package which is to occur in advance of the Package 1 and 2 construction.

The SD-01 Pump Station relocation design work will be advanced based upon the selected location per the Preliminary Design (Task 2.8) and will involve the preparation of final design plans, the preparation of draft Engineer's Estimate of probable construction cost, and the development of an outline of the technical specifications that will be required.

Task 3B Assumptions:

 Ten (10) hard copies and one PDF copy of plans, specifications, and estimates to be submitted to City for review

3B.1: Prepare 65% Plans

The plan production work included as part of this task is outlined in the table below:

Substask No.	Plan Description	Plan Details	Plan Scale
3B.1.1	General/Front End	Cover sheet, Notice to Contractor, List of abbreviations, legend & symbols, key map	NA
3B.1.2	Drainage/stormwater	Key map and notes, Layouts Profiles Details	1"=40' 1"=20
3B.1.3	LID Report (see below for details)	See description below	NA
3B.1.4	Landscaping	General notes, abbreviations, symbols, and key map; landscape layouts, planting details	1"=20' layouts
3B.1.5	Irrigation	Notes & legend, standard details, layouts	1"=20' layouts
3B.1.6	Bike path/hardscaping	Layouts, details	1"=20' layouts
3B.1.7	Lighting & electrical	Layouts, wiring diagrams	1"=40' layouts
3B.1.8	Contour grading	Rough grading Fine grading	1"=40' 1"=20'



3B.1.9	Utilities	Sower kov man 9 notes	***************************************
SD. 1.9	Othities	Sewer key map & notes	411 001
		Sewer plan/profile	1"=20'
	***************************************	Sewer standard plans & details	
		Water key map & notes	
		Water plan/profile	1"=20'
	1	Water details	
		Composite utility layouts	1"=40'
3B.1.10	Wayfinding/Signage	Layouts, details	1"=40'
			layouts
3B.1.11	Pump Station:		
	General Sheets	Location and vicinity maps, sheet	NA
		index and general notes,	
		symbols, legend & abbreviations	
	Demolition Sheets	Layouts and photos	NA
	Site Civil, Piping and	Horizontal control plan, site plan,	As
	Force Mains Plans and	piping plan	appropriate
	Details	11.05	- Inter-allegeness
	Architectural plans	Notes & schedules, floor plan,	As
	,	pump pit plan, roof plan,	appropriate
		elevations, sections and details	app.op.iato
	Structural plans	General notes, standard details,	As
	Otractara plane	inspection notes, floor plan,	appropriate
	,	sections and details, pump wet	appropriate
		well plan and details, concrete	
		•	
		and reinforcing details, railing and	
		ladder support details, pump bay	
		plan and section; flow walls plan,	
		section, and details; trash rack	
	<u> </u>	details	
	Mechanical	Floor plan, pump pit plan,	As
		sections, enlarged plan, details	appropriate
	Cathodic Protection	Details	
	HVAC Plans	Legend & abbreviations, notes,	As
		layout, section, schedules and	appropriate
		details	
	Electrical Plans	Symbology, single line diagrams,	As
		cabinet elevations, site plan,	appropriate
		grounding plan, floor plan, pump	Personne
		pit plan, Area Classification,	-
		wiring diagrams, schedules,	
		lighting & receptacle plan,	
		photometrics, Title 24 Forms	
	P&ID Plans	Symbology, SCADA Architecture,	As
	1 015 ; 1010	PLC control panel layout and	appropriate
		Li Fo control barier layout and	appropriate





	power distribution, ventilation and gas detection systems, building alarms, standby power & security, details	
COLB forms		
Standard plans	Standard Plans – Public Works	

Budget allocated to the work included within Task 3B.1 is assigned within the fee estimate to the subtasks identified above. The plan set will be formatted in accordance with City of Long Beach standards.

3B.1.3: Prepare Draft Low Impact Development (LID) Report

A Draft LID Report will be prepared to identify the specific proposed BMPs for the Package 2 construction. The evaluation supporting the selection and the calculations supporting the BMP sizing will be provided. Coordination with the LB MUST Project is assumed to be needed for the selection of BMPs for the project. The LID plans/exhibits to be prepared in support of this report will include locations of BMPs, elevations, drainage patterns, size and capacity. Upon approval of this report and direction from the City, approved BMPs will be incorporated into the final drainage plans prepared as part of this task.

3B.1.11: Prepare Pump Station Plans (includes optional LEED Certification)

Plans for the relocation of the SD-01 Pump Station will be prepared as listed in the table above. If directed by the City, HDR will pursue LEED Silver certification for the new pump station. The following activities will be completed related to the LEED Silver Certification if requested:

- Revise the Sustainability Plan (LEED Checklist) based on the progress of the building design.
- Provide the project team with direction in meeting the requirements outlined in the 2019
 California Green Building Standards Code (CalGreen).
- Provide a preliminary Daylight analysis for the private office space included in the building design.
- Provide guidance in editing specification sections for the project team to ensure the incorporation of agreed upon Certifying Authority or sustainability requirements such that the City can obtain accurate bids for the specific scope of work required.
- Conduct a quality control review of the project documents and specifications for inclusion
 of the building elements needed to meet the sustainable and building performance goals.
- Facilitate sustainability and energy efficiency meetings with the project team as needed to satisfy the LEED and/or energy efficiency goals.
- Provide one (1) baseline and design bundled energy model. The baseline energy model shall be based on the ASHRAE 90.1-2010 energy standard.

Task 3B.1 Deliverables:

- 65% plans (20 hard copies and 1 PDF copy)
- Draft LID Report (PDF copy and 3 hard copies)
- Baseline and design bundled energy model for pump station





Task 3B.1 Assumptions:

- All plans to be prepared in accordance with City of Long Beach formatting standards
- Drainage and Stormwater:
 - Includes design of storm drainage and water quality features for park elements only.
 - BMP calculations will be for pre-treatment devices only to protect the pump stations draining the storm drain systems being designed for this project
- SD-01 Pump Station:
 - Based on the City's approval of the Sustainability Plan and any approved changes to the Sustainability Plan, the City shall perform those sustainable measures identified as the responsibility of the City in the Sustainability Plan, or as otherwise required by the Contract Documents. The City shall require its contractors and consultants to perform their services in accordance with the Sustainability Plan.
 - City shall provide all documents and information reasonably necessary for HDR to perform its services.
 - City agrees to execute all documents required by the LEED Certifying Authority to be executed by the City, including any documentation required to establish the authority of HDR as an agent of the City for the limited purpose of pursuing Certifying Authority Certification.
- Hardscape plans assume no mechanical fountains or water features
- HDR to prepare plans for all City owned utilities including sewer and water.

3B.2: Prepare Outline Specifications (includes Optional LEED Certification for pump station)

It is assumed that the City of Long Beach utilizes the "Green Book" Standard Specifications for Public Works Construction as the basis for preparing technical specifications for public works infrastructure contracts. HDR will request a sample set of recently prepared contract specifications for a similar roadway improvement project released by the City to use as a reference in preparing technical specifications for this project. It is assumed that the City will be responsible for the ultimate preparation of the project specifications but will rely on HDR to provide technical and specifications and input to the City's general specifications.

Based on the project elements and pay items included in the 65% plans and the review of the reference contract specifications, HDR will prepare a table outlining the applicable standard technical specifications for each pay item per the Green Book. The table will also identify whether special provisions or additional/new technical specifications need to be developed for each item listed. HDR will review the General Provisions section of the reference contract specifications and identify modifications/revisions that may be required for this project. A summary of the suggested revisions will be prepared based upon this review and provided to the City along with the technical specifications outline table.

Due to the unique nature of the pump station work, many of the specifications required will need to be prepared from HDR standard sections or will be based on manufacturer's specifications (i.e. pumps, electrical, and other mechanical equipment). HDR will review the general





provisions section of the reference contract specifications and identify modifications/revisions that will be needed to fit the pump station project. A summary of the necessary revisions will be prepared based upon this review and provided to the City along with the technical specifications outline table.

Task 3B.2 Deliverables

- Technical specifications outline table (PDF copy and 10 hard copies)
- Summary of revisions required to General Provisions (PDF copy and 10 hard copies)

Task 3B.2 Assumptions:

- HDR is responsible for preparing supplemental specifications to the Green Book Standard Specifications or special provisions to the Standard Specifications as well as the bid list.
- City will provide boilerplate copy of general provisions to be reviewed and edited by HDR to fit this project.
- City will be responsible for the preparation of the overall project specifications to be included in construction bid package.

3B.3: Prepare Quantities and Engineers Estimate

HDR will pull quantities and prepare a Draft Engineer's Estimate for the Package 2 construction based upon the design and the associated pay items depicted within the 65% Plans. The Engineer's Estimate will incorporate any City comments regarding the preliminary estimate generated as part of Task 2.

Task 3B.3 Deliverable:

Draft Package 2 Engineer's Estimate (PDF)

Task 3B.3 Assumptions:

 Estimate format to be consistent with City formatting standards unless otherwise directed by City

3B.4: Envision Certification (Optional Task)

As noted in Task 3A.12, it is assumed the City will want to pursue Envision Certification for the Project. For the purpose of the Envision Certification, the "Project" will constitute the work being done as part of Packages 1 and 2 minus the SD-01 Pump Station construction. It is assumed that the City will pursue LEED Silver certification for the pump station as described in Task 3.1. As part of this task, an HDR Envision Certification Specialist will work with the project team to incorporate the City-directed Envision-eligible project elements identified as part of Task 2.16 into the 65% bid set for the Package 2 construction. Upon the completion of the 65% PS&E package, the Certification Specialist will conduct an audit of the bid set to confirm the Envision-eligible elements have been appropriate incorporated and will prepare the necessary Envision compliance audit documentation.

Task 3B.4 Deliverables:

Envision compliance audit documentation



Task 3B.4 Assumptions:

 It is assumed that the City will pursue Envision Certification for the Project, and the appropriate envision elements will be incorporated into the Package 2 bid set.

Task 4B: 90% Package 2 PS&E Submittal (includes Optional LEED Certification for pump station)

This task involves obtaining resolution on the disposition of the 65% agency review comments, updating the PS&E package to address the comments received, and advancing the PS&E package to a draft level of completion. Note that the sewer and water relocations included within the 65% PS&E package will be removed from the 95% package as it is assumed that the City intends to release an early bid package for sewer and water relocations. This work will be covered as part of Tasks 4C and 5C as described below.

The following describes the process that will be followed to address agency review comments on the 65% Package 2 PS&E submittal:

- Upon receipt of the 65% agency review comments, HDR will review the comments and develop draft responses. All responses will be documented in a series of commentresponse matrices (one per agency).
- HDR will submit the draft comment-responses matrices to the various agency reviewers for review.
- HDR will conduct a series of comment-response review workshops (one per agency)
 with each reviewing agency. The goal of these workshops will be to review HDR's draft
 responses and to reach consensus on the disposition of each comment.
- HDR will revise the responses to reflect the agreed-upon disposition per the workshops and submit the revised comment-response matrices to the reviewers for sign-off.

Separate comment-response matrices will be prepared for each deliverable submitted as part of Task 4B, including the plans, specifications, cost estimate, etc.

Task 4B Assumptions:

 Ten (10) hard copies and one PDF copy of plans, specifications, and estimates to be submitted to City for review

4B.1: Prepare 90% Plans

HDR will complete the process described above to reach consensus with the reviewing agencies on the disposition of the 65% review comments. HDR will the revise the 65% Plans to address the comments and advance the plans to a draft level of design completion. The plans will be updated to include the City-approved stormwater treatment BMPs per the Final LID Report to be prepared as part of this task.

SD-01 Pump Station LEED Certification (Optional Task)

The following activities will be conducted as part of this task related to obtaining LEED Silver Certification for the pump station:

Finalize the Sustainability Plan based on the progress of the building design.





- Finalize specification sections to ensure the incorporation of agreed upon Certifying Authority or sustainability requirements.
- Architect shall make adjustments to the Sustainability Plan as the design and construction of the project progresses and request the City's approval.
- Conduct a quality control review of the project documents and specifications for inclusion
 of the building elements needed to meet the sustainable and building performance
 goals.
- Finalize the Daylight analysis for the private office space included in the building design.
- Provide, if required, a CalGreen checklist that may be included with the G-Sheets on the project contract documents.
- Update the one (1) baseline and design bundled energy model to reflect the current building design.

Task 4B.1 Deliverables:

- Draft/final 65% submittal comment- response matrices (PDF)
- 90% Plans (20 hard copies and 1 PDF copy)
- Final LID Report (PDF copy and 3 hard copies)
- Final Pump Station Sustainability Plan
- Updated baseline and design bundled energy model

4B.2: Prepare Draft Specifications

This task will involve the preparation of a full set of draft general and technical provisions to be included within the Project Specifications to be assembled by the City based upon the outline table prepared and approved as part of Task 3B. HDR will prepare supplemental technical specifications for items not fully covered within the Green Book Standard Specifications. Suggested Special Provisions to standard specifications will also be prepared. HDR will amend the City's boilerplate general provisions as necessary to match the specific requirements of this project. HDR will generate the draft bid list to include in the Project Specifications based upon the pay items and quantities generated in support of the Engineer's Estimate prepared as part of Task 4B.3.

Task 4B.2 Deliverables:

- Draft/final 65% submittal comment- response matrices (PDF)
- Draft Technical Specifications and amended General Provisions (PDF copy and 10 hard copies)
- Draft bid list (PDF copy and 10 hard copies)

Task 4B.2 Assumptions:

- HDR is responsible for preparing supplemental specifications to the Green Book Standard Specifications or special provisions to the Standard Specifications as well as the bid list.
- City will provide boilerplate copy of general provisions to be reviewed and edited by HDR to fit this project.
- City will be responsible for the preparation of the overall project specifications to be included in construction bid package.





4B.3: Prepare Updated Quantities and Engineers Estimate

HDR will update the quantities list prepared as part of Task 3B.3 and prepare an updated Engineer's Opinion of Probable Construction Cost based on construction drawings prepared as part of Task 4B.1.

Deliverables

- Draft/final 65% submittal comment- response matrices (PDF)
- 95% Package 2 Engineer's Opinion of Probable Construction Cost (PDF)

4B.4: Envision Certification (Optional Task)

As part of this task, an HDR Envision Certification Specialist will work with the project team to confirm the appropriate incorporation the City-directed Envision-eligible project elements identified as part of Task 2.16 into the 95% bid set similar to what was done for the 65% PS&E package. Upon the completion of the 95% PS&E package, the Certification Specialist will conduct an audit of the bid set to confirm the Envision-eligible elements have been appropriate incorporated and will prepare the necessary Envision compliance audit documentation.

Task 4B.4 Deliverables:

Envision compliance audit documentation

Task 5B: Final PS&E (100%) Submittal for Package 2 (includes optional LEED Certification for pump station)

This task involves obtaining resolution on the disposition of the 95% agency review comments, updating the PS&E package to address the comments received, advancing the PS&E package to completion, and obtaining the necessary approvals for construction. The preparation of ancillary items required by the City needed for construction including the final construction schedule, Resident Engineer's File, Materials Handouts, the Paleontological Mitigation Plan, and the Project Survey File are assumed to be prepared as part of Task 5A.

HDR will follow the same process outlined in Task 3B.1 to reach a resolution with the City and other reviewing agencies on the disposition of the comments received as part of the 95% PS&E submittal. Separate comment-response matrices will be prepared for each deliverable submitted as part of Task 5B, including the plans, specifications, cost estimate, etc.

5B.1: Prepare 100% Plans

This task covers the preparation of the 100% Plan set and obtaining City approval of the final bid package. This work will include the following:

- Preparing responses to 95% review comments and obtaining consensus with the reviewers on the disposition of each comment.
- Updating the plans to address agency comments.
- · Finalizing the design, if necessary.
- Packaging the 100% plans and submitting to the City for formal approval and sign-off.

The project team will sign/stamp all plans within the set and coordinate with the City to obtain signatures on the plans.





Pump Station LEED Certification (Optional Task)

The following activities will be conducted as part of this task related to obtaining LEED Silver Certification for the pump station:

Design Documentation and Submittal

- Collect documentation from the project team and organize information into correct format
 for submission for Certifying Authority credits not assigned to specific team members.
 Track team progress toward completion of required documentation, develop and
 maintain a list of the required information, and review with the project team. Project
 team members will be responsible for gathering documentation and completing forms
 using Certifying Authority Online portal for credits for which they are responsible. This
 includes responses to comments or questions from the Certifying Authority.
- Provide necessary documentation as it pertains to selected Certifying Authority credits the Certifying Authority Project Administrator is responsible for providing.
- Submit the Certifying Authority Design credits for review for the certification process.
- Craft questions to Certifying Authority for clarification or interpretation of credit language as it pertains to the Project.
- Prepare responses to comments or questions received from Certifying Authority after original submission and submit additional required documentation, track the Certifying Authority review progress, resubmit documentation with additional information as required to obtain final approval of the requested credits. Manage the credit appeals process if required.

Construction Documentation and Submittal

- Track team progress toward completion of required documentation, develop and
 maintain a list of the required information and review with the project team. Project team
 members and Contractor will be responsible for gathering documentation and
 completing forms using Certifying Authority Online portal for credits for which they are
 responsible. This includes responses to comments or questions from the Certifying
 Authority.
- Provide necessary documentation as it pertains to selected Certifying Authority credits that the Certifying Authority Project Administrator is responsible for providing.
- Submit the Certifying Authority Construction credits for review for the certification process.
- Craft questions to Certifying Authority for clarification or interpretation of credit language as it pertains to the Project.
- Provide tools for the Contractor to track progress on its assigned credits. Review Certifying Authority-related submittals as identified in the project specifications during construction.
- Prepare responses to comments or questions received from Certifying Authority after original submission and submit additional required documentation, track the Certifying Authority review progress, resubmit documentation with additional information as required to obtain final approval of the requested credits. Manage the credit appeals process if required.



Task 5B.1 Deliverables:

- Draft/final 95% submittal comment- response matrices (PDF)
- 100% Construction Drawings (1 PDF copy and 10 hard copies)
- LEED documentation submittal to Certifying Authority

Task 5B.1 Assumptions:

The following items are excluded from the LEED Certification scope:

- Certifying Authority technical submission documents The project design and construction team members shall complete the Certifying Authority documentation required for credit submissions that are directly related to the design and construction responsibilities for their discipline.
- HDR can provide a general post-occupancy survey to assist in certain Certifying Authority credit compliance, however, the administration of Thermal Comfort Verification is excluded.
- Computational Fluid Dynamics ("CFD") analysis, wind tunnel analysis, or air containment studies.
- Cost estimation for sustainable measures.
- Performance Verification services for Certifying Authority.
- Commissioning Services (to be provided by Owner).
- California Savings by Design Program Submission.
- California Title 24 Part 6 Energy Code Energy Model.
- Life Cycle Cost Analysis for Proposed sustainable design measures.
- Travel. All sustainable design and energy services project work that may ordinarily involve travel will be executed virtually.

5B.2: Prepare Final Specifications

HDR will update the Draft Technical Specifications and Amended General Provisions to address pertinent agency comments received as part of the 95% PS&E submittal. The final specifications will be submitted to the City for incorporation into the final specification package. The bid list will be updated to reflect the final quantities and submitted along with the specifications.

Task 5B.2 Deliverables

- Draft/final 95% submittal comment- response matrices (PDF)
- Final Technical Specifications and Amended General Provisions (10 hard copies and 1 PDF)
- Final bid list (PDF)

5B.3: Prepare Final Quantities and Engineers Estimate

HDR will update the Final Engineer's Estimate to reflect any quantity changes associated with addressing pertinent agency comments received as part of the 95% PS&E submittal and submit to the City.

Task 5B.3 Deliverables

- Draft/final 95% submittal comment- response matrices (PDF)
- Final Package 2 Engineer's Opinion of Probable Construction Cost (PDF)





5B.4: Envision Certification (Optional Task)

As part of this task, an HDR Envision Certification Specialist will work with the project team to confirm the appropriate incorporation the City-directed Envision-eligible project elements identified as part of Task 2.16 into the final Package 2 bid set similar to what was done for the 65% and 95% PS&E packages. Upon the completion of the Final PS&E package, the Certification Specialist will prepare a Certification Compliance Report to document the Envision-eligible project elements included in the Package 2 bid set. The report will tally up the Envision Certification points obtained by the incorporation of these elements. This report will be submitted along with the report prepared as part of the Package 1 PS&E to obtain Envision Certification for the Project.

Task 5B.4 Deliverables:

- Envision compliance audit documentation
- Certification Compliance Report

Tasks 4C - 5C: Preparation of Plans, Specifications and Estimates for Package 3

Tasks 4C and 5C cover the preparation of an advanced utility relocation/construction bid package (Package 3). This package will cover the relocation of existing City-owned sewer and water facilities needed to accommodate the Package 1 and 2 project improvements as well as the construction of any new large facilities required to service the new SD-01 pump station and urban design improvements included as part of Package 2. The City intends to release Package 3 as an early construction package ahead of the Package 1 and 2 construction.

Since the 65% PS&E for the utilities work was completed as part of Task 3B, Tasks 4C and 5C involve the preparation of a separate, stand-alone PS&E package for this work; with Task 4C covering 95% PS&E development, and Task 5C covering 100% PS&E preparation.

Task 4C: 95% Package 3 PS&E Submittal

This task involves obtaining resolution on the disposition of the 65% agency review comments on the utilities portion of the Package 2 PS&E and the development of a stand-alone PS&E package for the sewer and water work.

The following describes the process that will be followed to address agency review comments on the utilities portion of the 65% Package 2 PS&E submittal:

- Upon receipt of the 65% agency review comments related to the City owned utility work,
 HDR will review the comments and develop draft responses. All responses will be documented in a comment-response matrix.
- HDR will submit the draft comment-responses matrix to the City reviewers for review.
- HDR will conduct a comment-response review workshop with the City. The goal of this
 workshop will be to review HDR's draft responses and to reach consensus on the
 disposition of each comment.
- HDR will revise the comment-responses to reflect the agreed-upon disposition per the workshop and submit the revised comment-response matrix to the City reviewers for sign-off.





The sewer and water design will then be advanced to a draft level of completion, and draft specifications and an Engineer's Estimate of Probable Construction Cost will be prepared.

4C.1: Prepare 95% Plans

HDR will complete the process described above to reach consensus with the reviewing agencies on the disposition of the 65% utilities PS&E review comments. HDR will the revise the 65% water and sewer plans to address the comments and advance the plans to a draft level of design completion. The plans will be updated to include the City-approved stormwater treatment BMPs per the Final LID Report to be prepared as part of this task.

Specifically, the 95% plans will consist of the following sheets:

Up-Front Sheets

- Cover sheet
- Notice to contractor
- List of abbreviations, legend and symbols, key map
- Construction notes summary

Utility Plans

- Sewer key map & notes
- Sewer plan/profiles (20 scale)
- · Standard Plans and Sewer details
- Water key map and notes
- Water plan/profile (20 scale)
- Water details
- Composite utility plans

Task 4C.1 Deliverables:

- Draft/final 65% submittal comment- response matrices (PDF)
- 95% plans (20 hard copies and 1 PDF copy)

4C.2: Prepare Draft Specifications

This task will involve the preparation of a full set of draft general and technical provisions to be included within the Project Specifications to be assembled by the City based upon the outline table prepared and approved as part of Task 3B. HDR will prepare supplemental technical specifications for items not fully covered within the Green Book Standard Specifications. Suggested Special Provisions to standard specifications will also be prepared. HDR will amend the City's boilerplate general provisions as necessary to match the specific requirements of this project. HDR will generate the draft bid list to include in the Project Specifications based upon the pay items and quantities generated in support of the Engineer's Estimate prepared as part of Task 4C.3.

Task 4C.2 Deliverables:

- Draft/final 65% submittal comment- response matrices (PDF)
- Draft Technical Specifications and amended General Provisions (PDF copy and 10 hard copies)
- Draft bid list (PDF copy and 10 hard copies)





Task 4C.2 Assumptions:

- HDR is responsible for preparing supplemental specifications to the Green Book Standard Specifications or special provisions to the Standard Specifications as well as the bid list.
- City will provide boilerplate copy of general provisions to be reviewed and edited by HDR to fit this project.
- City will be responsible for the preparation of the overall project specifications to be included in construction bid package.

4C.3: Prepare Draft Engineers Estimate

HDR will update the quantity summaries for the sewer and water work to address any 65% review comments and to reflect the 95% plans prepared as part of Task 4C.1. HDR will then prepare a Draft Engineer's Estimate for Construction of Package 3.

Task 4C.3 Deliverables

- Draft/final 65% submittal comment- response matrix (PDF)
- Draft Package 3 Engineer's Opinion of Probable Construction Cost (PDF)

Task 5C: Final PS&E (100%) Submittal for Package 3

This task involves obtaining resolution on the disposition of the 95% agency review comments, updating the PS&E package to address the comments received, advancing the PS&E package to completion, and obtaining the necessary approvals for construction. The preparation of ancillary items required by the City needed for construction including the final construction schedule, Resident Engineer's File, Materials Handouts, the Paleontological Mitigation Plan, and the Project Survey File are assumed to be prepared as part of Task 5A.

HDR will follow the same process outlined in Task 3B.1 to reach a resolution with the City and other reviewing agencies on the disposition of the comments received as part of the 95% PS&E submittal. Separate comment-response matrices will be prepared for each deliverable submitted as part of Task 5B, including the plans, specifications, cost estimate, etc.

5C.1: Prepare 100% Plans

This task covers the preparation of the 100% Plan set and obtaining City approval of the final bid package. This work will include the following:

- Preparing responses to 95% review comments and obtaining consensus with the reviewers on the disposition of each comment.
- Updating the plans to address agency comments.
- Finalizing the design, if necessary.
- Packaging the 100% plans and submitting to the City for formal approval and sign-off.

The project team will sign/stamp all plans within the set and coordinate with the City to obtain signatures on the plans.



Task 5C.1 Deliverables:

- Draft/final 95% submittal comment- response matrices (PDF)
- 100% Package 3 Construction Drawings (1 PDF copy and 10 hard copies)

5C.2: Prepare Final Specifications

HDR will update the Draft Technical Specifications and Amended General Provisions to address pertinent agency comments received as part of the 95% PS&E submittal. The final specifications will be submitted to the City for incorporation into the final specification package. The bid list will be updated to reflect the final quantities and submitted along with the specifications.

Task 5C.2 Deliverables

- Draft/final 95% submittal comment- response matrices (PDF)
- Final Package 3 Technical Specifications and Amended General Provisions (10 hard copies and 1 PDF)
- Final bid list (PDF)

5C.3: Prepare Final Quantities and Engineers Estimate

HDR will update the Final Engineer's Estimate to reflect any quantity changes associated with addressing pertinent agency comments received as part of the 95% PS&E submittal and submit to the City.

Task 5C.3 Deliverables

- Draft/final 95% submittal comment- response matrices (PDF)
- Final Package 3 Engineer's Opinion of Probable Construction Cost (PDF)

Task 6: Right of Way Services

This task includes the right of way engineering services needed to formally document the project right of way needs, the post-project jurisdictional limits between the State and City, and all temporary construction and permanent utility easements that will be needed. It also includes the property appraisal and acquisition services to assist the City in obtaining the necessary rights of way to construct the project. These services are meant to support the right of way requirements for all three construction packages.

6.1: Right of Way Engineering

Right of way engineering services included as part of this task include any updates to the existing right of way and parcel mapping prepared as part of the PA/ED phase, the documentation of project right of way requirements, the mapping of post-project jurisdictional boundaries between Caltrans and the City, the preparation of the necessary property acquisition documents, and the preparation of the right of way certification documents needed for Caltrans to certify the work included as part of Package 1.

6.1.1: Review Existing Right of Way Mapping and Supplement as Necessary





HDR's surveyor will conduct a comprehensive review of the current digital composite map depicting existing rights of way and parcel boundaries that was prepared as part of the PA/ED Phase to check it for accuracy and completeness against available source data. HDR's surveyors will work with Caltrans and the City to obtain the latest available source data to review against the current mapping and obtain any other source data that may be available through other means. The composite map will be updated/supplemented as necessary to reflect these reviews and will be expanded if necessary to cover the limits of the work along the local streets both west of SR-710 and east of the LA River.

A copy of this base map will be provided to Caltrans if requested for them to confirm its accuracy regarding the depiction of State rights of way within the project limits.

Task 6.1.1 Deliverables:

· Updated digital composite right of way and parcel mapping

Task 6.1.1 Assumptions:

Digital mapping file shall be prepared in Microstation format

6.1.2: Document Right of Way Requirements

Various full and partial fee takes, permanent and temporary construction easements will be needed throughout the project limits. All acquisitions will be documented on Right of Way Maps as described below in accordance with the following Caltrans reference documents:

- Caltrans Right of Way Manual (with special attention to Chapter 6 R/W Engineering)
- Caltrans Surveys Manual
- Caltrans Plans Preparation Manual, Chapter 4 Right of Way Engineering

Specific activities to be completed as part of this task are outlined below.

Perform Record Data Search:

Search ownership of impacted properties, analyze ownership deeds, field notes, and survey maps contained in State, County, and City files.

Obtain Title Reports:

Obtain title reports for all parcels impacted by the proposed right of way requirements. Obtain updated title reports prior to the approval of the right of way appraisal mapping.

Perform Land Net Recovery and Field Ties:

Field and related survey effort necessary to search, recover, describe, and tie-in controlling land survey monuments

Prepare Land net Map – "Before Condition" Record of Survey:

This activity is required by the Professional Land Surveyors Act and involves the production and filing the "Before Condition" Record of Survey

Prepare Right of Way Maps

Prepare various types of Right of Way Maps as dictated by the project need. Various types of maps may include but are not limited to:

Right of way Requirements Maps



- · Appraisal Maps
- Right of Way Record Maps

Prepare Property Acquisition Documents

- Prepare property acquisition documents, including Plats & Legal Descriptions for all temporary and permanent property needs.
- Prepare deeds for conveyance of right of way to Caltrans, City, other public entities, and utility companies for the closeout of the project.

Prepare Parcel Files

For each impacted property, prepare a parcel file.

Task 6.1.2 Deliverables:

- · Title reports for impacted properties
- Survey data
- Record of Survey
- · Right of Way Requirements Maps
- Plats & Legal Descriptions for R/W needs
- Appraisal Maps
- Cover Letters
- Parcel Files
- Deeds

Task 6.1.2 Assumptions:

Does not include the preparation of any monument perpetuation surveys

6.1.3: Right of Way Certification

HDR will compile all the materials required for Right of Way Certification and prepare the certification binder for submittal to the Caltrans right of way staff for review and approval. Right of Way Certification is required by Caltrans before they will approve the bid package and issue an encroachment permit for construction and is meant to certify that any land being transferred to the State as part of the project is free from any encumbrances.

Task 6.1.3 Deliverables:

Right of Way Certification Binder

6.1.4: Right of Way Design Support

HDR will perform the following activities as part of this task:

- Support the acquisition of right of way requirements, HDR's surveyor will prepare right of
 way exhibits per impacted parcel that display right of way needs on both aerial photo
 and design topography. Cover letters that describe the Temporary Construction
 Easement (TCE) needs in detail, and coordinate with the Caltrans Design Group on the
 preparation of right of way mapping and appraisal maps.
- HDR's surveyor will participate in up to three (3) right of way workshops with the City and Caltrans
- HDR's surveyor will perform field staking of right of way requirements upon request





 HDR's surveyor will coordinate with Caltrans Right of Way Engineering for the review of right of way appraisal mapping and legal descriptions for approval.

Task 6.1.4 Deliverables:

Right of Way Exhibits

6.2: Right of Way Appraisal and Acquisition Services

This task includes the activities associated with supporting the City of Long Beach in the appraisal and acquisition of the properties needed to accommodate the Shoemaker Bridge Project, including all work included as part of Construction Packages 1 through 3. Specific activities included as part of this task are outlined below.

6.2.1: Right of Way Mapping Review

HDR right of way staff will work closely with City staff as well as HDR engineers and right of way engineers to conduct a comprehensive review the right of way needs documentation prepared as part of Task 6.1 to gain a clear understanding of the property requirements and to formulate the necessary approach for the completion of the appraisal and acquisition process.

6.2.2: Conduct Property Appraisals

For all properties and property interests to be acquired, HDR will provide appraisal services to determine the fair market value of properties and review appraisals services to assure just compensation to property owners.

HDR will provide qualified appraisers and review appraisers to prepare appraisals, appraisal reviews, fixture & equipment appraisals, and goodwill valuation to the Project delivery schedule.

Based on the information provided by the appraisal and appraisal review, HDR will prepare a Determination of Just Compensation, or similar document, for City concurrence and signature.

HDR will provide expert witness testimony to defend the conclusions reached in the appraisal and/or legal support, if required.

Task 6.2.2 Deliverables:

- · Property appraisals and appraisal reviews
- Determination of Just Compensation documents (one per parcel or larger parcel/ownership as determined by appraiser)

6.2.3: Preparation and Approval of Offer Packages

HDR will prepare acquisition packages, including recommendation of amount of just compensation and negotiate with property owners. HDR will prepare and maintain a parcel negotiator's log (parcel diary) for each parcel.

HDR will prepare and develop the Informational Letter and Offer Letter and deliver those letters to property owners upon review and approval by the City.

HDR will prepare all applicable forms, secure grantor's approval and signature, and submit the forms to the City for review and acceptance.



HDR will establish and maintain an acquisition file for each property owner or property interest acquired and maintain a file checklist pursuit to the City's policies and procedures.

As may be required, HDR will secure Right of Entry Agreements, and licenses or permits from property owners for purposes of performing appraisals and inspections.

HDR will provide bilingual acquisition agents as needed.

HDR will prepare right of way cost estimates, as needed.

Task 6.2.3 Deliverables:

- Acquisition packages and files for each parcel to be acquired
- · Informational and offer letter to each impacted property owner
- Real Estate Acquisition and Management Plan
- · Right of way cost estimate for each parcel to be acquired

6.2.4: Provide Support to City in Good Faith Negotiations

HDR will meet personally and present offers to each property owner and inform them of the City's right of way acquisition process. HDR does not have the authority to negotiate settlements on behalf of the City but will maintain a Record of Negotiations documenting that all elements of the acquisition process and transactions were performed in accordance with applicable Federal, State, and local laws and regulations.

Task 6.2.4 Deliverables:

Records of negotiations with each impacted property owner

6.2.5: Condemnation Support

HDR will assist the City in Eminent Domain Support – if requested, HDR will provide expert testimony in any court or administrative proceedings, and assist as required in legal matters as directed by City legal staff, especially in the litigation of cases for or against the City, including but not limited to gathering of documents and information.

6.2.6: Escrow Coordination

HDR will obtain preliminary title reports and support the City with coordination of title and escrow services necessary for the acquisition of real property.

HDR will develop and maintain an escrow schedule; deliver documents and checks to the escrow companies; review all documents for submission and delivery to escrow companies; review title and escrow documents; ensure that the City is acquiring good title and/or the property rights needed for the completion of the Project; free and clear of any and all liens and encumbrances that may affect or hinder the development of future consideration; coordinate escrow closings and file all applicable forms and documents with the County Assessor's Office.

HDR will prepare all necessary documents to the title and escrow companies for approval by the City. HDR will be responsible for managing and monitoring the title and escrow companies to ensure timely delivery.

Task 6.2.6 Deliverables:

Escrow schedule





Task 6.2.6 Assumptions:

 The City shall be responsible to pay title/escrow company directly for additional services which include, but are not limited to, litigation guarantees, policies of title, title searches, document searches, document preparation, and closing costs.

6.2.7: Secure Legal Possession

HDR will support the City in securing legal possession of all acquired properties or portions thereof for the construction of the Project.

HDR will coordinate and provide support to the City legal staff to clear title, if necessary.

Upon completion of Project, HDR will provide Policy of Title insurance to the City.

Upon completion of the acquisition process for each property or property interest, or at Project completion, HDR will provide the City with the original acquisition file.

6.2.8: Property Owner Coordination Meetings

HDR right of way staff will attend up to ten (10) property owner coordination meetings total for all properties to be acquired.

Task 7: Permitting and Other Support Services

This task covers preparing and obtaining all of the necessary third-party permits needed to execute both the design and construction for all three construction packages. This task also covers public outreach, grant application preparation to seek project funding, and cost/benefit analysis support services.

7.1: Prepare Caltrans Encroachment Permits for PS&E phase

At project initiation, HDR will work the City and Caltrans District 7 staff to facilitate obtaining the necessary "parent" encroachment permit needed to complete field reviews, surveys, inspections, borings, and other activities within Caltrans right of way during the final design phase of the project. Additional permits may be required under the parent permit to authorize special tasks within Caltrans right of way that may require traffic control or temporary closures. The HDR team will work closely with Caltrans District 7 staff to identify any specialized work activities that may trigger the need for any supplemental permits.

Task 7.1 Deliverables:

- Encroachment permit application
- Secured/approved encroachment permit

7.2: Prepare National Pollutant Discharge Elimination System (NPDES) General Construction Activity Stormwater Permit

HDR will work to secure the RWQCB NPDES permit for the discharge of waste and pollutants into surface waters. This permit is Issued to maintain the quality of surface waters and check that project actions do not reduce the quality of the water. Submittal of the application would occur at approximately the 60% level of design and requires many of the same supporting documents as the 401 Permit covered under Task 7.3.





Task 7.2 Deliverables:

Permit application and secured permit

7.3: Prepare Environmental Regulatory Permits for Construction

This task includes the preparation of the following permits and securing their approval:

Section 401: Regional Water Quality Control Board (RWQCB) Clean Water Act Section 401 Water Quality Certification for Project Activities in Waters of the U.S. A Water Quality Certification is required when a Section 404 permit will be issued for a project, to confirm that project activities will not result in adverse effects to water quality as defined by the RWQCB. Submittal of the application would occur at approximately the 60% level of design and requires many of the same supporting documents as the 404.

Section 404: U.S. Army Corps of Engineers (USACE) Clean Water Act Section 404 permit for the placement of dredged or fill materials into waters of the U.S., including wetlands, below the Ordinary High Water Mark (OHWM). The application would also address tidal waters protected under Section 10 of the Rivers and Harbors Act of 1899. Submittal of the application would occur at approximately the 60% level of design and requires many of the same supporting documents as the 408.

<u>Section 408</u>: U.S. Army Corps of Engineers (USACE) Modifications to USACE Structures (Section 408 permit) for any modifications or connections to USACE constructed facilities. Submittal of the Section 408 permit requires a minimum of 60% plans, supporting geotechnical, hydrology, hydraulics, structural, design, real estate, and environmental documents, as well as the elements expected for operations and maintenance.

Section 1602: California Department of Fish and Wildlife (CDFW) Streambed Alteration Agreement (Section 1602 permit) for project activities that would affect the bed, channel, or banks of a stream, river, or lake, or the adjacent floodplain to the landward extent of riparian vegetation. Submittal of the application would occur at approximately the 60% level of design and requires some of the same supporting documents as the 404.

<u>Harbor Development Permit</u>: **Harbor Development Permit through the Port of Long Beach** for the project will be prepared in accordance with the California Coastal Act for the portion of the project located within the coastal zone on the east side of Los Angeles River, south of Anaheim Street. Submittal of the application would occur at approximately the 60% level of design and requires some of the same supporting documents as the 408.

Task 7.3 Deliverables:

The HDR team will prepare the permit application forms and coordinate the information required by the agencies to issue said permits or approvals. Each of these regulatory agencies has separate processes by which they review permit application materials. This requires the submission of pre-construction notifications and permit applications in a timely and coordinated manner. The HDR team will prepare the required agency notifications and coordinate permit processing to include the following tasks:

Prepare Draft Clean Water Act (CWA) Section 404 Individual/Nationwide Permit Application





Prepare draft 404 Permit application to include the following items:

- Cover letter addressed to the USACE Los Angeles District local contact.
- · Complete the USACE standard ENG FORM 4345 form and additional pages.
- Detailed description of the proposed project, including grading plans, landscaping
 plans or restoration plans (if applicable). Description of the jurisdictional areas to be
 impacted by the project. This is generally accomplished by submittal of the
 jurisdictional delineation report.
- Preparation of an operations and maintenance matrix describing the types of activities, frequency, duration, and types of equipment to be used. This will be prepared after discussions with the City.
- Copy of the conceptual compensatory mitigation plan (mitigation proposal) or detailed description of how the impacts to jurisdictional areas will be mitigated prepared by HDR for the project.
- Preparation of the USACE Mitigation Ratio Worksheet in coordination with HDR.
- Financial plan for long-term management of the mitigation area. The City will assist in the preparation of this document.
- Discussion of approvals and certifications being obtained from other federal, State, or local agencies.
 - California Fish and Game Code Sections 1600 (Lake or Streambed Alteration) Notification package submitted to the CDFW.
 - Clean Water Act Section 401 Request for a Water Quality Certification package submitted to the RWQCB.
- Copy of the biological resources technical report prepared for the project.
- Copy of the cultural resources technical report prepared for the project.
- Copy of the hydrology/water resources report prepared for the project.
- · Copy of the jurisdictional determination/delineation report prepared for this project.

Prepare Draft CWA Section 401 Request for Water Quality Certification Application Prepare draft 401 Request for Water Quality Certification, including the following items:

- Materials required for the 404 Permit listed above.
- Cover letter addressed to the Los Angeles RWQCB.
- Complete 401 Request form and additional pages.
- Copy of Water Quality Management Plan, Drainage Plan and/or Stormwater Management Plan for the project.
- Detailed description of the proposed construction and operation (Best Management Practices, including the project's Storm Water Pollution Prevention Plan, if available).
- Copy of the project's final CEQA documentation.
- Permit application fees to be paid by the City.

Prepare Draft Fish & Game Code 1602 Streambed Alteration Notification Application Prepare draft 1602 Notification of Lake or Streambed Alteration Agreement, to include the following items:

- All materials required for the 404 Permit listed above.
- Cover letter addressed to the South Coast CDFW local contact.



- Complete 1602 Notification form and additional pages.
- Detailed description of the specific vegetation communities or habitat types to be impacted.
- Discussion of other biological resources associated with the affected area.
- Discussion of how the impacts to CDFW jurisdictional areas will be mitigated.
- Copy of the project's final CEQA documentation.
- Permit application fees to be paid by the City.

Prepare Harbor Development Permit Application

The HDR team will prepare and submit a Harbor Development Permit Application in compliance with the California Coastal Zone program through the Port of Long Beach.

- Discussion of the project impacts to areas within the project limits
- Information necessary to complete the Harbor Develop Permit application
- Copy of the project's final CEQA/NEPA documentation.
- Permit application fees, if necessary, to be paid by the City.

Prepare Final Permit Applications

The HDR team will forward each of the draft applications to the City and Caltrans for review. Following the reviews, the HDR team will prepare one set of revisions to the draft permit applications described above based on comments received from City and Caltrans. The HDR team will submit the final applications to each of the respective agencies to begin the regulatory review process for each permit.

Permit Processing Meetings

The HDR permitting team will participate in meetings with the overall project team, City, Caltrans, Port of Long Beach, and/or regulatory agencies during the regulatory permitting process. The meetings would include both in-person meetings and conference calls. Hours for these meetings are captured under Task 1.

Coordination of Permit Processing

HDR will coordinate with the City, other members of the project team, and the regulatory agencies. Specific coordination tasks include communicating information needs, providing status updates and progress reports, and communicating important and time-sensitive information to the project team. The team will coordinate with the regulatory agencies to facilitate efficient processing of the project's permits. Throughout the process, the team will communicate via e-mail and phone with the regulatory agencies and project team and provide the City with debriefs of agency consultations and meetings. The team will notify the City of requests by the agencies for additional project information and will facilitate preparation of additional information submittals with the collaboration of the City.

7.4: Facilitate Execution of Cooperative Agreement between City and Caltrans

HDR will support the City with the execution of a cooperative agreement between City and Caltrans for both the final design and construction phases of the project.

Task 7.4 Deliverables:

· Executed cooperative agreement





7.5: Execute Section 214 agreement between City/Metro and USACE

The HDR team will provide the City a draft Section 214 agreement using the current model from the USACE. The Section 214 agreement will provide the City with the mechanism to fund the USACE for their staff time to meet, discuss, review, and make decisions on the replacement of the Shoemaker Bridge. Section 214 agreements are not required for all actions; rather they provide funding to establish a priority for attention and actions on the part of the USACE. Without this funding mechanism, the project will be dealt with as any other unfunded project; and the USACE will meet, discuss, and review as they have time.

The HDR team and the City will meet with USACE and several other key reviewers of the project to discuss the City's proposed project, alternatives, and schedule. Key reviewers would include specific members from hydraulics, hydrology, design, structural, geotechnical, environmental, regulatory, asset management, operations, and counsel. The HDR team will address questions from the USACE to assist them in preparing an estimate for their time to participate in meetings, discuss items on the phone or in person, read and review products, have internal meetings and prepare their decision papers/documents. The appropriate USACE staff will prepare their estimates for their Sections.

Section 214 agreements typically require several months to process. The coordination with the USACE would be initiated immediately after issuance of the NTP and the kick-off/scoping with the City and the HDR team.

Task 7.5 Deliverables:

Executed Section 214 Agreement.

7.6: Obtain Utility Owner Approvals and Agreements for Construction

The Right of Way Certification Package prepared as part of Task 6 will identify utilities or other encumbrances that must be cleared from any private properties or municipal land that are to be relinquished to the State as part of the project. This includes the identification any associated utility relocations to be completed by others as part of the project, with signed agreements by the respective owners that the work will be done prior to relinquishment of any land to the State. HDR will work with the owners and Caltrans to facilitate the preparation of any such agreements.

Task 7.6 Deliverables:

Third-party utility owner agreements

7.7: Obtain Public Agency Approvals and Agreements for Construction

Once the final PS&E package is approved, HDR will work with the City and Caltrans to facilitate obtaining the formal approvals needed to authorize construction. For Caltrans, this approval involves obtaining an encroachment permit for construction, which won't be issued until the PS&E is approved by the district and OSFP and the Right of Way Certification package is approved. HDR will work with the City and Caltrans to facilitate the issuance of the encroachment permit. Other permits that HDR will seek to obtain will be the City building permit for the pump station, the Construction Work Discharge Permit from the LA County Sanitation District, and the HDP Permit from the Port of Long Beach.



Task 7.7 Deliverables:

- Caltrans encroachment permit application for construction and secured permit
- · City of Long Beach building permit application for pump station and secured permit
- HDP permit application from Port of Long Beach and secured permit
- Construction Work Discharge Permit application from the LA County Sanitation District and secured permit

7.8: Public Outreach and Social Media Support Services

The intent of this task is to support the City in conducting the community outreach to obtain public input and support for the project. HDR understands the importance of effective community outreach on a project such as this which has the potential to benefit and enrich the local community in a myriad of ways. HDR technical leads will be available attend public outreach and community group meetings to present or answer questions. HDR staff can also assist the City in the development of boards and exhibits to facilitate this public outreach effort. The HDR team will also support the City in this effort by working with the City to provide public outreach services through available social media platforms such as Facebook, Twitter, and the City's website.

Task 7.8 Deliverables:

- · Presentation boards, meeting exhibits, etc.
- Project pages set up on social media platforms to communicate project information to the public

Task 7.8 Assumptions:

- Public outreach effort is assumed to be led by the City
- Includes participation at three (3) public outreach meetings by three (3) HDR technical staff

7.9: Grant Application and Cost/Benefit Analysis Support Services

HDR will assist the City in seeking available granting funding for the project and preparing the necessary grant applications needed to be eligible for this funding. In addition, HDR will assist the City in conducting cost/benefit analysis services in support of the Project.

Task 7.9 Deliverables:

- Grant applications
- Cost/benefit analysis worksheets, summaries, etc.

Task 8: Bid Support Services

This task covers the technical support services to be provided by the HDR Team during the bid phases of the three construction contracts for Packages 1-3. This work is broken up between the Package 1 construction contract, which is covered as part of Task 8.1; and the work for Packages 1 and 2, which is bundled together and covered under Task 8.2.





8.1: Package 1 Construction

HDR will provide technical support to the City during the bidding phase of the Package 1 construction contract, which may include the following activities:

- Pre-bid meeting attendance
- Field walks
- Preparation of addenda to bid documents as necessary.
- Responding to bidder inquiries regarding the contract documents
- Providing analysis of bid results
- Furnishing a recommendation on the award of the construction contract

Task 8.1 Deliverables:

- Bidder inquiry responses
- Bid addenda

8.2: Package 2 Construction

HDR will provide technical support to the City during the bidding phases of the Packages 2 and 3 construction contracts, which may include the following activities:

- · Pre-bid meeting attendance
- Field walks
- Preparation of addenda to bid documents as necessary.
- Responding to bidder inquiries regarding the contract documents
- · Providing analysis of bid results
- Furnishing a recommendation on the award of the construction contract

Task 8.2 Deliverables:

- · Bidder inquiry responses
- · Bid addenda



Exhibit "B-3" Fee Schedule

Shoemaker Bridge PS&E

Fee Estimate Summary by Company - January 2021

Firm Name	Certification	Responsibility		Labor Cost	R	eimbursable Cost		Labor Escalation	Total Cost	Percent of Total Cost
HDR		PM, roadway, structures	1 \$	13,751,339	\$	214,185	\$	883,111	\$ 14,848,635	65.8%
Guida	SBE	Surveys and mapping	\$	465,000					\$ 465,000	2.1%
Twining		Geotechnical	\$	488,650					\$ 488,650	2.2%
Evans and Walker	WSBE/VSBE	Oil field impact assessment	\$	120,000	П				\$ 120,000	0.5%
TY Lin		Structures	\$	4,623,714	\$	50,000			\$ 4,673,714	20.7%
IDC	DBE	Structures/civil/drainage	\$	923,146					\$ 923,146	4.1%
LIN	DBE/SBE/VSBE	Electrical design, traffic control design	\$	216,640					\$ 216,640	1.0%
AirX	WBE/SBE	Potholing	\$	60,000					\$ 60,000	0.3%
PGI	DBE/SBE	ACM and LBP surveys	\$	95,000				***************************************	\$ 95,000	0.4%
Interphase Environmental	DBE/SBE	ADL testing	\$	62,700					\$ 62,700	0.3%
Orange Coast Analytical	VSBE/SBE/WBE	ADL testing	\$	39,900	T				\$ 39,900	0,2%
Southwest Geophysics		Phase II site investigations	\$	11,000					\$ 11,000	0.0%
TMI	MBE	Traffic control	\$	10,000					\$ 10,000	0.0%
American Integrated Services	MBE	Phase II site investigations	\$	1,500					\$ 1,500	0.0%
MBI Media	OBE/SBE	Public outreach	\$	75,400	Г	.,			\$ 75,400	0,3%
RVA	D8E/SBE	USACE coordination	\$	118,640					\$ 118,640	0.5%
Tastsumi & Partners	D8E	Landscape/irrigation & urban design	\$	340,310			Í		\$ 340,310	1.5%
		Tata	1 \$	21,402,939	\$	264,185	\$	883,111	\$ 22,550,235	100%
		OBE Percentag	e							8.6%

City of Long Seach Showtaker Bridge PS&E Fee Summery

2.6,7	28.5	2.6.4				20.0	28.2					28	27.5			27.4		1	***************************************					273	27.2	27.1.4	27.1.3			-			2.7.1.2	27.1.1	27.1	27	26	2.5	24	2.3.7	23	2.2	2.1	2	1.4	: :			12			1.1.2	Ī	Ī	Ī				T			1.6.1	11	- CONTRACTOR OF THE			
LEED Cartification - Silver	Projume Pump Station Plannings (Jedign Report	Prepare pump station construction cost estimate	Architectural elevations	Instrumentation and control diagrams	Stochanical Stoca	Cvil ste leyout drawings	Prepare pump station geolecanical design report	Fediny Sting Considerations	Conduct preliminary tryrostopy and disastega study to support pump station stang & string	Sila Reconnaisance	Date Sathering and Review	5.1	Conduct updated hydrauliciscour analysis of UA River for satarded alternative bridge convepts	Prepare and submit meeting proceedings Under thos selector reports to address meeting comments and submit for approva	Adend Type Selection Meeting	Bridge Type Selection Meeting and Approved	Propere Bridge Type Date Submittel	Prepare Bridge Dack Changete Design and Memo	Courses Constitute States Regular (an open per cyletter Strongsker Bridge and water	Kapar	Selection Report (blke/pe	Prepare Type Selection Report (roundebout structure)	span)		ance Planning Study for Roi	Allernatives Development, Costing and Preferred Alternative Salection	Stakeholder Workshops and Constraints Montillowion	Propere Bridge Rendering (3 views 10bs)	Postage Bridge Allectebra Abbets	Develop 30 including of principles principles and principles and principles developed transportations.	Develop Co model of the	Public Involvement coordination and content	Propers Bridge Allematives Review and Renderings	Initial Fireme Development and Scoping	Bridge Architectural Concepts	Structures Type Selection	Prepare Pre mkosty Foundation Report	Prepare Geometric Review Crawing	Geology Provided to the Control of t	Constale pathole sulveys	Suppermental Field SUVe/s	Prepare Supplemental Design Standard Decision Cocument (if needed)	Conduct Geometric Walkahap	35% Daxign & Bridge Type Evaluation/Selection	Prepere Project Management Ylan and Penanola Pien	Prepare Dealign Causally Management Flas	Propare monthly progress reports	Prepare monthly involcas	Presers Progress Reports	Maintein Project Files and autocontracts	Prepare and Update Risk Register	3	Constructibility and Sofety Sayley Weekshabs (86%, 95%, and 100%)	1	۱P	Monthly coordination meetings with GHO and US MUST staff			Coordination Meetings with LACPVV and USACE	Blaveldy City meetings	PCT Meetings (monthly)	Conditation and Meetings	Coordination and Administration	Project Manuscriment, Coordination, and Administration	ADE SANDERS		
30 5	32 5	\$ 36	104 5	104 \$	\$ 92	39 \$	2 20	0 \$	198	\$ 25	88 \$	2965	372 \$	2 2 2	\$ 23	186 5	58	256	S 100	3 3	640 5	450 \$	7428 5	\$ 0005	248 5	\$ 80E	80 5	34.	82 5	200	270 4	200	0	264 \$	1932 \$	11878 \$	\$ 016	218 5	360	28 \$	106	176 \$	86	21523 \$	1,0	1 72 S	105	364 5	1269 \$	548 \$	3 97.0	364 3	148	700	0	266 \$	100 \$	42 \$	196	0.00	1222 \$	\$ 1917	5/28 3	2	-	TOTAL HOR HOURS	-
2,300 \$	7,688 5			5,368 5	5,084	2.793	27 703 5		10,802	2,490	127.1	18 019	19.462	5,407	6,300	13,264	3,738 \$	13.527	18 200	904.2	40,652		450,480 3		13,408 \$	22,420 3	6,331	8,825	5,925	\$ 909 2	4 067 4	0,728	ŀ	18,176	128,164	751.595	\$0.573	12,663	23,363	1,084	14,947	12,363	5.672 3		277,21	220	41,833	47 122	89.056	26,403	14 785	56,317	12.004	B 050		24,247	8,764	3,247	12,057	(8,49)	119,611	416,844	173 160	581,219		TOTAL HOR DTI.	
6345		19,925		¥ E	13,970	7,705	76	ľ	29,798	6,869	13,041	49,709	53,638	14,917	17,381	36,648	10,313	37,595	50 209	202					36,963		17,465	24,347	16,346	16.301		10,302		50,160	353,656	2,073,463	166,941	34,835	64,452	5,500	30,717	34,108	18		00,62	17, 195	115,682	128,997	245,660	72,839	40,787		33,116	102,230		88,890	24,178		38,229	ACT, ALT	33D,529	1,149,988	1,305,332	1,903,440		TOTAL HOR BURDENED FEE	
\$,	5	۰ .	*	,		,	-	. 5		, .	,			,	*	,	•	, ,		,			,	. \$,			-	,			3		20,000	4 000,000	* ***		\$ 100,000				,		, ,	\$						·	*						3	CONTROL OF THE PERSON	Quida Survey	5
,			\$	ن د		ça ,			5	,	3	1,000	\$		\$	5	**		4	*		,		\$			5	,	•	,						-			\$ 475,000			, ,	,	3 498,656	,		-	,			,	٦				-	\$,			-				Twining	
				,						,	5 - 5	,			ž		\$											\$ · S																120,000 \$				- 5			-	3												- 4		Evans and Walker	1
						٠,			- 5	,	- \$		• •	25,300 3	5,827	24,400 \$	- 5	- 8		.	,	707 AUU 5		767,400 5			,	- 5			× .	,				791,689 \$	5		2					791,089 \$			21,600 5	43 200 \$	\$4,806		,	-		2000				Lin	,	,	6.508 15	11.506	11,506 3	78,306 S		ΥΥ⊔n	
. 18						•	٠,٠	,		. 8		٠				٠ 5	. 3	. 8		95,200 \$				151,300 \$,	- 3	,	- \$,				ļ,	. 10		151,300 \$								151,300 \$			5,400 5	10,600 S	16,200 \$			-				. 5		. \$,		ļ. •	٠	16,200 \$	390	EDC (DBE)	
,	, ,	- 55								. \$, 5									. -	,	,					. 5	- 3	, 5		, ~		•			- 25			35,000 \$,			ļ.	1 090,001			5.400	10,800 \$	16,200 \$			5		. . • •		-	, 5							15,200 \$		LIN (OBE)	_
. \$				40					. "	, 8	- 5	 u c		. . "			. s			.						ļ.	. 5	- 5				,	١.			,	. 5	٠	"				ļ.	\$ 990,02			-	. 5	-	٠.				, ,	,				٤	-	, 5	5		· *	380 380	Potholog Sul (DBE)	_
		\$		5	1					ļ.	- 5		-		. 4		\$. 5	,	, ,		•		\$	- 5		- 8	. 5		. "	5		. -			. 5	107		3		. 9		-	\$ 000.56	***************************************			- -	-		,	4	, \$. .			,	٠,	,	ļ.	,	-	٠	- 5	BWBE DBENB	PGI (DBE/SWB	4
\$			3	 "	,	•	* 1	,	- 5	,	, \$		· ~~	- š	, n 40	,	. 8	\$	•	, , ,	* *	,	. *			5	,		- 5	, •	· ·	- (· ·	,	5	4	-		\$	- 2	, s			62,700 \$	1		1		*	, , •• •		5	٠.	. . s		. "	,		, of			. -		•	PENSON SPEC	Environmenta (OBE/MBE/WE Orange Coast	Æ)
		, , ^ ~	,	•	. "	\$	-		1.	5				*		5		. 5		-		^ -			- 44	5		. 8	. 5		•		1					5	*		•	· ·	· **	35,000 5 1	-		· ·		-			· 5			,	-	,	•	. 8	-		· -	٠	-	MANAGE	Analytical (VSGE/SBE/WE Southwest	1
64	, UT (2 8	5	5						50		, . 		5						*		*		-	. 4	•		5		4	•		1			,	. 8	s	•	8	8					٠,	· ·		*	• •		3		, .					, ss	***************************************	•	-		ï	0.0	Geophysics TMI (DBE)	1
-	· s	5	8	. 5						"			***************************************		A 64		\$		\$	-	1	1	•			"	5		- 3	5	-	,					<u> </u>		5	•		٠		П			1		*	· ·	, "	3	s	•	1	ļ.				-		-	5		MINISTRAL PROPERTY.	American Integrated	_
5			*	* 1			•	-	•	"		\$	-	3	1 1 1		\$	5	4	5				,		\$ 20,000	ı	4	5	4	*	9	,	,	\$ 26,000	1			3	*	"	, '	1	1,500 \$ 20,000	***************************************				Ш		, "	•	-	9	,		5	S	. 8	-	,		5	۱	d	Services (MBI MBI (DBE)	E)
3	3		*	5		•	*		. "	5			,	3	n «	5	\$,		*		*		,		\$.	·	40	\$	\$	*	,	"		\$ 000		-	·	\$, ,		-	1			· ·	П	3,500 \$ 4,800	"		*	. S .	, 5	*	, .	•			\$ 13,600				"	5,400 \$ 21,184	8	RVA (IVBE)	
\$ 2,700	۳	ue (4	\$,		\$	\$			-	s	١,	\$ 2	•••		,	\$	\$	5	•o		†	,	, -		1	s .	5	s -	5 .	5	us i	.		5	, p		,	\$	۵۰	60	•	4 M	\$ 8,760	Н		5 9,000	"	84 \$ 27,000		1.		Н	3.840	7 7200	5 9,800	ļ.		*	- 1	2 7 7 7	14	145	84 \$ 61,720		Tetsomi & Partners	
×		\$ 19,928 \$ 35,282						78 .	ı	ı	5 13,041		-	\$ 30.21	1	l			1	\$ 103.50	5 63744	1		l.	30,95		1	1			\$ 115.776				3/3,65	L	36.92	\$ 34,935	П		110.213	Π.	5 20		П	\$ 35,23	1	•		\$ 41,737	T	1	10	"	8	1	ľ		S	1	1	<u>٦</u>	2 1,366,158	_		Total Team Fee Inciduling Subconsultants	
9	35	0)	7		6	5	+		9		Ī	Ĭ	100			Ī	-	Š	ž	-	- 1		Ť	1		-		7	-	1	~	-	1	15	8	2		\$	2 5 125,000		-	1	2	8 139,700		- 1		1	٦	1		3	f		1	-	,	Ť	4		- 10					obc:	
								1						***************************************								1																	ğ					0 S 3,510		1							\$ 1,232		\$ 12.780		5 1,040	\$ 585	\$ 2,280		15 600			\$ 47,975		Traval	

34.7.3	34.7.1	34.7	3A.6.2							3A 6 f	34.6	3A.5.2	3A.5.1	34.5	y 42	3A.4.1	34.4				34.3.3	34.3.2	34,3.1	34.2					34.22			34.21	34.2	34.1.3	34,1.2	38.1.1	34.1	Ä	Calbana PSAE		217		7 6 7	2161	3 6	3	314	2.12	61.0	2112	2,11,1	211	2.10.5	210,4	2.10,3	210.2	2.10.1	210				29.4	2.9.3	2.9.2	2.9.†	20	Tauxito	
Piopara Materials Report	Prepare Geotachystal Design Report	Geolephnical and Foundation Reports	Propers Queralbes	Propert Temporary Electrical Plays	Property Electrical Services (Integration) System Plans	Prepare Changeable Message Sign System Plans	Prepare Traffic Signal Plans	Prepare Ramp Melating Plans	Propert Lighting Plans	Plebare Plints	Propers 65% Electrical Plans	Proposo Ouanidice	Presides Plans	Papare \$5% Sign Plans	Prepare Cuertiles	Prepare Plans	Prepare 65% Payement Calingation Plans	Propare Greatles	Probare construction area stor olars	Prepare Stede Construction and Traffic Handlard Plans	Pispara Plant		n Compant De	Prepare Stage Constitution. Traffic Handling, Delour, and Constitution Area Sign Plans, and TMP	Prepare Cuestulists	Control	Prepare Weler Politaton Control Plans	Prepare Chainage Pinns	Propare Plans	Propura Draft Storth Water Data Report	Propare Crainage Report	Propose Reports	Prepare 65% Drainage and Stormwater Plans	Pressee Quantities	Prepare Consour Grading Plone		Proporte Roseway Pilana	att PSBE (65%) :	Package for Work in Caltrana Right of Way and Adjacent Local Streets		VA SUPPOR Selected	and the state of t	Provide Provide Carallel Caral	Process Street and the british Studies	Control Edison blinds School Associated Levels for signal	Conduct Edition Middle School vestoke purulation/dres off stude	Obtain 5-78 authorization for utilities and RAV	Computation Control in part assessment and raising relocation plan	Propare Lighting Concept Plans	Prepare oversa urbus design, landscapling, water features and sixeway concept plan	sion Certification	Urban Cesupn end Aestholics	Prepare Iratic control plans to support field work (assume T sheets)	Conduct Phase (I investigations for four sites	Prepare H&SP, CMMP, CCP, and LCP	Complete ACM and LPB saveys	Complete ADL survey	Hazardous (Majerials Investigations	Prepare traffic control plana (assume 15 plans, 32 hours each)	Prepare patholing week plant	Prepare politoje needs plan	Unity Patholing	Utility Countination (3 meetings each enpacted contact assume 6 contacts)	Canflict identification	Update Existing Unites Base Map	Utildes	7an Perripion	
750 3	275 3	1875 3	4 5	5 fo	0 5	0 3	12 5	0	\$ 8	28 \$	32	3 85	386	394 \$	36	126	B	24	2	707	852 4	S44 5	‡ <u>\$2</u>	1,888,5	ô	8	182 5	528 5	3-56.5	3.08	542 1	850 5	1685 5	8	204 5	422	726	20227 \$	3,000,0		100	0.0	. 000	1000	100	24.	64 1	394	920	Į.	126	714 5	20 \$	577 \$	358 4	132 3	332 4	1353 \$	60 5	134.\$	108 3	300 3	234 \$	236 \$	172 \$	942 \$	TOTAL	IRS
19 407	18,704	122,049	302				906		1,208	2114	2.416	7,897	18,528	20,525	1.897	7,163	9.091	2,598	5.483	40 572	48,623	25,269	30,639	104 532	2,020	4,959	10,715	30,398	48,101	23,258	40,849	64,108	112,200	5,436	15,007	10,655	51,098	1,278,773	2,199,085		13,480	41,004	200,00	66.001	107 /05	11 12	200	22 110	£ 050,77		10,009 \$	15,976 5	1,510 \$	36,479 \$	26,199 \$	9.435 5		97.536 \$	4,973 \$	8,189 \$	6,929 \$	21,091	17.151	13,129	9,360 \$	60.732	A	WT HOW DILL
136,302	51,598	336,702	222		Ĭ.		\$ 2,499		1333	5,632	286.9	5.234	51,390	56,624	5,234	19.817	25,051	7,167	5.044	111.929	34,140	69,710	84,526	266,377	5,573	13,707	29,559	5 83,867	5 132,700	64,164	112,893	176,857	\$ 309,557	14,997	45,400	84,570	140,987	1,530,576	6,088,731		38,834	14,990	101,000	181 620	L'CS SIDE			61 817	100		Ę			JO.	72.277	26,030	65,840	369,050		25,350		58,185	47,317	36.221	25,821	167,544	BURDENED FEE	TOTAL HOR
	, ,	-	,		5	\$	\$ -	,			\$			·	•			5	•	\$		•	•		, ,		\$		\$	\$	\$.	•		\$	*	\$		•	\$ 10,000		,	,		1		,		^ "				\$	\$	\$	\$ -	\$	\$	s	\$	- 5	\$ -	2 .	. 8		\$. \$	Guida S	
5	,			5	S - 1						2		٠	,			,	٥	,			\$,		,			\$			\$,	5 - 3	,				-		,	* 1		,						,			\$. 5	, ,	- 5	•		- 5	\$ - 5	4 - 5	. 2	, ,	\$. s	Twis	ing
		-	,	\$	47	,	. 2	. 5	. \$,	5			-	-			8				. 5	, 5	-		. 5	5						-	- 5		·										, ww.			, 55				. 5	, *			. 5	. 5			. 5				Evene W4li	and ker
- 5	,	,	. 8	5	,	- 5	, m	. 5	. 8	,			5	. \$,	•	, **						. 5						43	, 8	. 5		. 5	, 9	,	, s	1,283,368 \$	2,740,060 3		,		•		, ,					1	-	. 5	,			,	- 5	. 5	,	. 2	- 8		. 5		, 5		171	
							. 5		*	. 8	*		•	, S	,	۰,	, \$	\$,	. \$	4	1 25	-	,		. \$		-	1 25	,			es	, 5	,		15	526,841 5 5	r	T	. °			. . -		*	3		-			. 8	. 6		. \$. 45		. 5	. \$. 3				IDC (E	
· ·		5	8,850 \$, un	ua	- 5	20,460 5	. 8	4.320 \$	1 800 S	53.760 \$,	- 3	•	, 8	s		57	- 3		,		*			•	,	, en		•			*			55,360 \$	70,000 \$				•	*	,		*		•	^ 0	· •	*	6.550		- 69		, S	26,560 \$	8,000.	. 5	- 5	\$ 60	. 5	, 5	5	68,800 5 60	Pathalir (OB	ng Sub
\$,		5	5			5	s	\$	*	5	· "	*	5	, s		\$	\$	· s	•	\$	•	\$. \$	\$. 5	. 3	. 3 .	. 5	, 41		\$	\$	5	5	\$	5	*								5	69		,	4	, 10	5	5	5	٠	· S 95,000	s	s 95,000	5	8	_	900 \$	tri	*		50,000 \$	PG1 (DBE	
s			9	49	·	\$ -	5		•	,	,	ند د		5	8	\$		ton	,	1	5 -		8 .		*		en		8 -	**		8	\$	ş	5	\$.	-			+	,		,	,	4	5		, .	,	,		6	-	9 57,000	ş	S		8 2	"	\$	57	3 -		5	44	6	Interp Environ (OBE/MB	mental :
5					-	ŀ		s .	,	,	5	٠	4	,	*		s .			5		5	\$	\$	*		5	\$			3	-	*	*	*	,	,		•		1	,	•	,		,	\$,		\$ 31,000	\$.	\$ -	\$ 8,500	\$ 39,900		,						tn	Orange Analy (VSBE/SB	rtical .
9				,		S	- 9		\$ - 5						*	\$	- 2	,				5 - 5	\$ - 5	S - S	. 2		4 - 5	3 - 5	•			9	. 2	- 2			5					<u>`</u>		5		,					5			\$ 11,000 \$	\$	\$ - 5		5 11,000 \$,						\$. \$,	South Geoph	
- \$,					٠ -			٠	,			٠,				. 5		,				. \$					- 8		,		-				,		,									••[•		٠,٠					10,000 \$				10,000			ŀ			٠.	- 5	,	YMI (I	
				. 5	. 5	,	. \$,		•			- \$. s		,		\$, \$		- 8		,			- 3	5	. \$,	,		,	-			,		,		1 2				•	, ,	-	, 5		1,500	. 5		. 8	1,500 5		- 5	5	·		,	. 5		Integr Services	rated : (MBE)
			. 5	,	,			. s	\$. \$. 8		٠ - ٤	, s	, 8	. 5	. 8		٤ -	٠,	- 5	. 8	٠ 5	so so		- 2	ş	,	,	1		. 5	, s	. 8	. \$		•	1	,		1	, ,			2			, ,		. 5	s	5	. 5			. \$. 5					40	, 5	. "	MBI (I	
\$	7	,	1	1 42	68	·	5		ı.		ı.		1 91	. 3	. 8			ss			. 5	. 5	s		. 64	. 5	. 5	5	. 25	5	59			103			-			-	6		4		9	*			-			- 5 60		. 5	8	•	. 5			*	- 4	\$	3	*	49	i ia	Yatsu Parir	int 5
\$ 130		1	-	-	-	-	\$ 2	*	· \$ 27	. £ 50	· \$ £		\$ 51	· ×		· \$ 19	\$ 22	. 3	- 5 16	· \$ 101	. \$ 134	. 5 65	\$ 84	· \$ 286	45	· 5	- 5 25	1 83	\$ 13:	, 2	- 2 574	5 17%	\$ 30	5 1,	5 4		\$ 140,957	- 4 5,380	* 10,548,010		,	1	1	\$ 161	298	\$ 30	· .	9		1	9	6,000 S 132	*	5 211	s 72	5 121	. 8 00	5 515	5 62	5 25	5 18	\$ 116	\$ 47	. \$ 36	. 8	5 298	subconsultants	
136,302	200	5702	9.793		ľ	•	22.979	,	27.653	7,632	2.425	234	.390	5,624	234	9,617	5,051	7,167	3,044	929	1,140	770	526	3777	5,573	7,707	9,559	3,867	2,700	200	7,693	5,857	9,557	1997	1,400	9.570	0,967	5,146	2,010		100		e i	529	524	711	534	017	200	168	27,613	2,835	1,726	5	7,277 \$	8	540 S	5,710	1,521	350	114	110,185	317	1221	25,621	344	phic opera	
	1																					H							-							1	l	•	ŀ						+				1	+	1	1		11,200	Ŀ	-	2,500	_	<u> </u>				5					
		-	-	-													L								L	L												1,170					1												L		L		L				3,510				3	<u> </u>

Shormaker Bridge PS&E For Summary

	¥.	£	Š	2	4,23	44,22						-	44.21	14.2								48.7.3							4A12			Ī			100.00	4.	Ä		34 12	34.11	3A_10.9	3A-10.6	3A.10.7	3A, 10.6	3A 10.5	34.10.3	34.10.2	3A,10.1	34.10	34.03			30,92	34.0.1	6 VE	34.6.2							34.0	Task No.		
The state of the s	Exylaton Cardication	Piepare Environmental Committeants Record (ECR)	Update Storm Water Data Report	On the second	Charle Studiolog distribute and contracts (see that Article of high costs)	dual provi	Stidge Removal Plans for existing Shoumaker Bridge	Shoemaker Bridge Architectural Plans	Nonstandard Rateining Wall Plans	7st Smet ped bridge sians	LA River Bigg Part Structure Pixon	Objective Origin False (LA TAME Spary	Mapare Checker attenues mans	Bridge and Streets Design Respiring Wall Plans	Prepare onvitonmental cultine specifications	H82 mg/	LUJIKION	Uphting and Glectical	Pavement Delineation and Signage	Construction Stating	Problems and Streetwales	Princes Light Specification Special Princessas		Lighting and Electrical	Pevement Delineation and Signage	Construction Stapling	Crainage and Stormyeler	Roddway	Prepare 95% Roadway Cuantifies and Cast Estimate	Lully Plane	Lightha and Eilectical Plans	Construction and Sine Plans	Constitution Charles Plans	Process and Chambolas Close	Dyachar Diane	Princers 95% condway plants	nital Page (35%) Submitte for Cantains work		Envision Certification	Prepare Draft Engineer's Estimate of Probable Construction Cost	Prepare architectural apecifications	Prepare sinuctures outline apecalications	Property onwitten specifications	Proper haz met culine specifications	Propere utity gutting specifications	Prepare planting adding specifications	Prepare drainage and atornwater outling specifications	Propere roadway outline specifications	Prepare Cuttine Specifications		issue relocation feiters to impacted utility owners	Review resonation plans prepared by impaided 3rd party owners	Charles Departs relication plans for singuised utilities (by others)	Lipdate conflict maps and matrix based on potholing results	Propers Utility Plans	Prepare Updated Structures Cost Estimate	Prepare Bridge Architectural Plans	Propers Relating Wall Plans Propers Bridge Removal Plans for exeting Stoemsker Bridge and wallo	Prepare Bridge Plans (7th Street pad bridge)	Propare Bridge Plans (blike/ped effucture)	Propare Bridge Plans (nundeficed shurbare)	Prepare Endge Plene (LA River span)	Bridge and Special Design Retaining Wall Plans (Unchecked Details) Provide Plans	Task Description		
	60 5	120 5	90 \$	36 3		52 4	76 \$	0 3	8	12:3	627 3		1907017	18.K/Z/	21 5	77 \$	31 4	5	48.5	80 3	45 5	20	15 5	3.5	38 4	30 3	29 \$	48 3	183	2	1	256.5	2	200	8	1778	E SCALE		2 00	39 \$	41 \$		12 %	\$	ž.	. 6	20 5		196 \$	1306	24 \$			2 00 5			9	162 4	88	2985 3	752 4	8510			TOTAL HDR HOURS	
	4,543	6,997	6,525	4 387	701	5,218	4.212		5.020	121	37.271	60 160	764,064	204.723	1424	1 153	2.370	£04	2,538	4 539	7.655	4,04,0	875	227	2,042	1,558	1,513	3.201	9.525	5,356	1.057	14 249	27 289	20 272	34 508	105.712	200,000		1 343	2,984	3,332	1.831	799	2.164	1.084	307	1,516	1,719	14,210	7,941	1,882	2.072	2 189	12.660	28,174	9,994		9,589	8,031	178,753	75,458	517,533	870,752		TOTAL HOR DT. PEE	
	11,992	24,794		12,097	1,707	14,394	11,519		16,055	11,525	102.671	165 967	1,300,340	7,45,407	_	11,457	8,537	1,586	9,759	12,521	10.087	100.00	2,418	525	5,633	4,294	4,257	9,050	\$ 75,278	14,776	2,915	39.340	58 677	857.08	95,199	297.634	7,00,000,		3 77,982	8,233	3 9.191	5,052	\$ 2,205	5,970	2,992	27.0	\$ 4,190	\$ 4,742	\$ 39,203	\$ 21,907	5,192	\$ 7,923	\$ 6,040	\$ 34 926	72,207	\$ 27,670	\$	3 23,696	\$ 24,913	\$ 493,024	\$ 208,164		5 2,207,438 S		TOTAL HOR BURDENED FEE	
								•	•	,								Ĭ								8		,		,	,	,									s	,									,				ľ	,					\$			•	Guida Survey	rs.
	,	100		•						,																					,	,		,							s - 11						,					,	,	, .						,	,	,			Twining	
									,					,					٠											- 13		,								- 5																									Eyans and Walker	
	, ,			ļ	B1 KRR 4	117,342 \$,	5	,		- 8	1.161.905 \$	202,242	9 050,050.2		- 5	, 2	, 2	, 5	-	,	,		. *	,	. 5	,	- 2	. 5	- 3	****		3				3 000,000,2				- 5	3.824 \$. 5	44		,	,		3,824 \$,	- 4		,	22.795 \$,	1,256,750 \$	*	1,256,750 \$	4	TYLIs	
			,	5			. 5	. 5	8E,300 S	68,000 S	,		4	134,300	,	\$,	<u>.</u>	,					,	,		. 3	- \$	*						000,000		- 5	. 5	. 5	957 S	- 5	. 5	,				957 \$				<u>.</u>			5,344 \$	-	\$ 210.673	391,000		,		520,540 \$		IDC (DBE)	_
_				61		ŀ	. 5					,			,	. 0		7,880 S					765	1,900					4,960 \$		21,760 \$,	,	,		22			3		. 5	, s	- 4			8			1.600 \$							- 8						. *			11K (D&E)	4
_		- -	,	. 57		,	. 5	. \$. *		,		,	,			. 5					,	ļ.			-			. \$	•				-	*		1			- 5		٤ ،	, s	,				٠			. 8			. 5		. 5	. ,		. 5					Patholing Su (DBE)	à
l				40		ļ,	,	4	. 5		,			-	, ,	-	ļ,			4	, m	,			,		5		-		۰							+	5	,		- \$				-		-		, ,		,	.		, , ,	,	5				5	·		,	interphase	
	,				, ,		,		٠.	, ú	,		4	,				S				, ,			. 5	. 8	,		,	,		,	•			, 			. 8	. 8		. \$. 5		. 9	-		ļ. "	چ			,	· .	, ,	·		8					- 5		. "	Environment DBE/MBE/WI Grange Coas	tel BE) st
						. "		•	. 8				^ •	. ,						. \$,			,	•	,				, ,		-		3	. *		. 5	*						 un c		ss		, ,	,	, \$0		, ,			5	. 15		ŀ	Analytical VSBE/SBE/W	配
-	, 5	, . M 49	- 6	4		,		5	٠,	3		-	,	• •		- 5			,	-	,		· ·			5		4	. "	,	,	*	•			•	, ,			,	,	,		. 5		, "						. 8		, .		چ	\$	on (. . * *	,	,	,	. ,	1	Geophysics	-
$oldsymbol{\mid}$	\$, . s s	5	\$. \$. 5	-	,		1	.			٠		٠,	\$	•		.			٠	,		. 5	•	*	•	*		3					-	٠	, "		*		•		3	s	, s						. 8	-	-	. -					1	TAA: (OBE)	\dashv
\mathbf{F}	*			*	,	ŀ	,	- *		*	r		*		,	,	- 15	- 5	;	\$, *	, ,	, ,		<u> </u>			9	- 5		1		•		*	* *		1	- 3	ļ.	. 2	ça	- 5	-	, 8	*		, 's	٠.	· ·		\$, "	: . •			5	**	٠ ٠					1	Integrated Services (M8 M8I (DBE)	IE)
\mid				-			·	•	. \$. \$		5		2	,			. \$	٠.		·	,	<u>- </u> -	,	1,	. \$. 5	- 5	•	<u> </u>	٠	•	•	•	-		1		-	, ,		. 5	-	- \$	\$		<u> -</u>	, se	, %		. 8	-		\$	\$	5	5	٠ ٠		-	•		1	RVA (WBE	
\mid	-		į	-		-		- 3		\$		3					-	5	. 5	*	5			. .			3	. 5		,	7	,	•	-	•	•		+	in	-	•				5	2	3 0	,	*	8	, . " "	5	*	۰ .	1		-	şa (500	٠	***		Talsumi & Pariners	
\mid	-		-	•	, i	,	5	S	. 8	1.0	5 12	\$ 1.32	1	1	ı	L	5	Г	. 5		- 	5	5 6	1	*	3	"	5	*	, n	3	4	<u>:</u>	· 6.	-	· ·	٠ د د		3				3			-			. 3	-		-	-	1	+	-	1		' '		3 1,484	5 1.4.	3.82		Total Team Fee Including Subconsultants	4
rack	1,962	42,926	18,000	2,067	1.653	31./3b	11 619	,	82,365	79,626	72,821	77.873	ő	200	7,320	10,407	6,537	9.346	9,759	12,521	10,082	2 601	76 231	2418	2,033	4.294	4,257	9,050	11,236	14.776	74.676	19,310	10,677	6.738	75, 199	34	6 462	1	11.562	8,233	8,191	9,822	2,205	5.970	2,992	2.433	4 028	1,742	95,594	11,907	5 772	7,923	6,040	34,926	72,207	55,709		23,696	10,873	33,024	94,953	27,746	984,728	727.01		\dashv
-												***************************************			***************************************					Н				+												+				1						+	+				-	-	Н	+	_			H		1	-				8,000	-
L						-																																													1 170														Travel	

Shoemaker Bridge PS&E Fee Summary

#.Z.BE	39.26	38.2.7	9 C BE	38.24	38.23	38.2.2	38.2.1	3왕 2														38 1.11	38,1,10	9,1,8	36,1.8	38,1,7	38.1.6	39.5.5	38.5.4	36.1.9	38.1.2	38.5.1	28		City PS&E Pack		5A.7	Š	SAS	54.	563	Š	32	r V								54.1.3						541.12						4000	54 7 7 7	5	52	A. Carrier		
Very learning a segrenge	Ukiles	Contour grading	Enchind & Electronic	STANDARD TO THE STANDARD TO TH	Landscapping	Drainsgal/Stormwater	General Provisions	Prepare Outline Specifications	LEED Cartifeation - Silver	Standard plans	COLBioms	P&ID Plans	Electrical Pitas	HVAC Plans	Cathodic Protection	%echanical	Structural plans	Architectural plans	Sue Civil, Piping and Farze Warts Plans and Details	Demokton Sheets	General Sheek	Prepare Pump Station Plans	Prepate wayfindingitigrage plans	Prepare utility phora	Prepare continut grading plans	Prepare United & Electrical Plans	Prepare Blka Path/Hardscapo Plans	Propore Impalian Plans	Prepare Landscaping Plans	Prepare Craft LID Report	Prepare Cramage/Stophyster Plans	Propers General/Front End Plans	Prepare 65% Pians	아마라 PSEC (65%) Submitted for Pump Station, Landscaping, and Lichan Design Work	Rage for Pump Station, Landscaping, and Urben Design Work		Entration Certification	Prepare Survey File		Prepare Paleontological Mitgation Pibn	Prepere šástenels Handouts	Prepare Resident Engineer's File	Upxere Construction Schedule	Food Structures PS&E (SPS&E)	Prepare environmental outline specifications	HX mpt	Children Central	Indian and Fartiral	Construction stepling	Crainage and Stormwater	Roadway	Project Final Specific Special Provisions	Ullillee	Lighting and Diedrical	Cerson Singing	Danage and Stornwator	Readyayy	Propore 100% Roadway Quantities and Cost Estimate	Utility Plants	Uphlang and Sectrical Plans	Povement Delineaton and Sign Plans	Contact and State of States	Chainage and Stormyster Plant	Roadway Physic	Propage 100%, readway plans	Final Roadway RSZE	Pinal PSEE (1998) Submittal for California work	The same state of the same sta	TOTAL HO	
101	2	đ			9		42 5		95 5		2		152 \$	72.5	32 3	112 \$	188 \$	258 \$	2	80 S	<u>s</u>	1320 \$	144		16		162	1 6		330 \$	210 5	78 5	2828 \$	3	8176 2		8	1.	Ŷ	ò	8	228 4	24 5	1952	8.5	23	=		3 6	100	24	150	5 2	9	3 6		15/5	62 3	44 5	4	110 \$	188	772	240	736	848	3620 \$	1	HOURS	
1,147	1,699	501	3,050	0.00	***************************************	7,808 1	3,366 1	29,180	6,854 . 1	1,390	1,390 3	5,793	7.820	4,529 1	1.653 3	7,295 1	13.528 3	14.433	6,376	5,064	4,395 \$	80,314 \$	9,541 \$	17,922	8,140	6,630	11,851	986	057	24,675	16,510	1,849	184,278	235.222 6	357,240		4.343 3	6.714 \$	5,697 3	2,665 \$	9,447	15,161	1,901 3	125,577 4	537 3	1,715 4	1,049	202	1 460	1,519	1,936	10,727 \$	267 3		137	624	1,019 3	3,937 \$	3,192 5	302 \$	6,338 \$	9,811	10,166			81 208 \$	199,797		TOTAL HOR DYL.	
0,740	4,687	\$ 1,381	2,914	2078	,	4,989	9,287	\$ 80,500	1 18.358	1,834	3,834	15,981	\$ 21.572	\$ 12,494	\$ 4.561	29,125	37,320	39,816	17,589	13,970	12,114	\$ 221,568	\$ 26,322	19,442	22,457	18,290	32,141	2,726	11,192	68,073	\$ 42,787	13,376	508,373	649,520	1,837,247		11,982	24,040	15,717	7,351	26,045	41,825	5,245	346,435	1,470	4,730	2,894	822	4.000				727		2.404		2.812	19,844	9.606	633	17,485	26,514	20		128.423	166 659	530 E47	ı	TOTAL HOR BURDENED FEE	
ľ	*	°		,	֓֟֟֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֟֟ <u>֚</u>			\$	\$	5	*	5 -		,	,	3					tn				ľ	3				\$,	"	•	"				\$ 10,000	•		4		\$		5	•	֓֟֟֓֟֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֟֓֓֓֓֓֟֓֓֓֓֓֓֓֓֓	֓֓֓֓֓֓֓֓֓֓֓֟֓֓֓֓֓֟֓֓֓֓֓֟֓֓֓֓֓֓֓֓֓֓֓֓֟֓֓֓֓		1	\$	-	"			֓֟֝֟ <u>֚</u>		ő		•		*		֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓		֓֟֟֟֓֟֓֓֓֓֓֓֓֓֓֓֟֟֓֓֓֓֟֓֓֓֓֓֓֟֓֓֓֓֓֟֓֓֓֓	10,000		Guida Surv	eys
	,	\$	*			-	4	\$,	S	- 8	15 .	5	5	5		,		is.			ő	8	,		6 9	*	\$	\$.	5	.	\$	\$	١,	1			\$.	9	4 4	•	\$ -	. 3	* -	•	•	5	,		,	ş	5	4		,		\$,					•	,	,	,		Twining	
,	\$	\$	٠.		۱		5	\$			٠.					5							\$,			,		\$	\$	\$	•	5	\$	3				5							S						ľ				\			,		,	*			-	֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓	ļ		Eyans an Walker	
		-	00		,		00	5	5	9		67	\$.	5		\$	5 -	5	5	\$	49	\$	5	\$.	\$	5 -		.5	8 -	5	s -	5 -	.9 .	5	2		,		\$ -	5			\$	\$ 351,596	\$.	\$	en e	8				5	\$,	5	\$.		,	•	-	, ,	361.50	302 206	ŦY LIn	
1		<u>,</u>	-			-	-	,		\$	*		\$	in .	-		°	\$	5							\$,	•	5	\$ -	5 .	\$ -		•		5			•	4	*	•	\$ 94,505		5	-			*	\$	5			^ •	5			•				•	•	*		505 Pe	2	loc (cee	3
		. 8	\$ 1			,			8		\$	\$. 5		\$	3			5			- 5	5	, ,	\$ - E					. 5	9 - 2	\$	5		5 · S	,	\$. \$	\$. 5	5 . 5			,		\$		3.280 \$				3,200 \$		1,920 \$			- 8	1,920 \$	-	\$ 9,600 \$. 3				9,800	14 720	1 147.14		LIN (OBE)
	,			, .		ŀ	ŀ	·	·	·		·	٠		ļ		,	ŀ	,			ŀ	ŀ		Ŀ							٠	,	-			1	,		,	٠	٠	,		·	١	,	٠	, .		,	-					ŀ				,			٠,					Potholing 6 (DBE)	юb
		5 . \$	<u>.</u>				\$	- 2	\$ - S	\$ \$				5	- 2		,				1						. 5	- 2		2		5														\$,											- \$	\$							1	PGI {DBE/SW	
		,	•		,							, ,		. \$,						\$,					,	,	,	. 3		. 5	. 5			- \$	٠ \$. s	2 .5	- 5	. 5	,				,	,					- 3	- 5					,		٠	,			ioterphas Environnes (DBE/MBE/V	ntal
ļ	,			.	_].	ŀ	,	·	-			,	-	ļ	ŀ		ļ.		ŀ	,	ŀ			Ŀ	,	1	,	•	ŀ	,	2	ŀ				ľ	٠	\$		٠		,	- 8	- 5		,						- 8	2									ŧ			,	,	ı	Orange Co: Analytica (VSBE/SBE/V	d i
	-	,			1		-		,			5		,	,		5	ŀ	ļ.		,	,	,	,	ľ	_	•			,	,	Ľ	-	•	3		•				,					-	,	***************************************		,									,				,	•			٠.		Southwer Geophysic	
				,	• •						\$,		,	-			,			,			ľ			φη	5		,		,		1				,			,				\$		•	-			5	,	S			,			*	•	\$	•	•		*	.		TM! (086	a)
	* *	\$,	1	5	-		. \$,	,	49	3	5			Ī.		,			,				\$		s	5			\$	3			٠ .	•	,		٠,	,	*	· ·	5	,	*			,	S	. s	5		1					. \$	3 -				-	,		American Integrate Services (M	×d bx
		,	49		5				,	-	\$	2		5		,		,			*			-		,	\$	*	*	5	,	\$	5	•	*		\$	•	,	\$	\$	\$.	\$ -	\$,	2	3	,		5		8	3	\$					-			•	•						WBI (086	3
	7	٠	S	5	-	,	1	,	in.		3 .	*						,			ŀ		3	5	5	5	5		٠	-	<i>"</i>	2	ŗ,	<u>۔</u>	*				2	5	ŕ	5 .		-		s		5	s ·			5		5		1		5	-	*	•	*	٠	~		,	" -	*	RVA (WB	E)
Ì	,	L	\$ 640	-1	1	ı	-	1	\$ 8,000	ı	۶	4		-			-		,	ŀ		5 8,000	5 21 600			5 1,600	Ļ	ļ,	\$ 49,800		5	- 2		142.530	\$ 269,000		·		ė.	5		\$		- 3	,		۵ ,	5	59			61		S	5	7				\$		\$	\$	*			5	-	Tatsumi Parloun	٠
	\$ 4,687		ž	5	"	1	5,287	4	*	4	\$ 3,834		\$ 21,572	12494	4.567	3 20.125	37,320	38,016	71,000	3 17,970	77.116		۳		\$ 22,457	۳	ľ	٦	4	۳	١	-	ľ	\$ 791,550	ľ		\$ 11,982	\$ 54,040	\$ 15717	\$ 7,351	\$ 26,045	\$ 41,825	5 5,245	5 802.537	\$ 1,470	5 4,730	\$ 2,694	2 4 033	\$ 4,026	4 593	5 0,349	32,792	\$ 737	3 3,920	5 2.087	3	2.012	\$ 12,784	3 8,806	\$ 10,433	\$ 17,485	3 26.514	\$ 28,045	\$ 46,740	\$ 108,023	\$ 180,579	3 991,360	\$ 1.128.370	Total Team Fee inciduing Subconsultants	-
					,		*	1			Ī									T	Ť	ĺ	ľ					-			ĺ													ľ									ĺ						ľ										apc's	
																								-																															1														Travel	

48.3,7	4B.3.6	4B.3.4	4B.3.3	46.32	AR 1									4929	77.84	49.2.6	48.2.5	4B.2.4	48.23	4B.2.2	48.21	492		Ī	Ī	I	Ţ								48.1.9	46.18	6	4B.1.5	48.1.4	48.13	46.12	4B.1.1	48.1	à	36.4	T						30.04	38.3.8	39,3.7	38.3.6	38.3.5	38.3.4	36.3.2	38.3.1	383								20.7.00	36.210	ļ	
Wayfinding & Signage	Cantour station	Bike paturardacape	Irrigation	andscaping	Propera Updated Cushillos and Engineers Estimate Database Stromuster	P&ID	Electrical	HVAC	Methodic Serioches	Structural	Architectural	Site civil	General/Front end	Pump station	Coxour grading	Lighting & Gectarge:	Blive path/hardscape	Ingelien	Landscaping	Crainage/Stormwater	Generalificant end	Propare Draft Specifications	LEED Confilmation - Silver	CALS IDING	PALDPIENS	Electrical results	HVACTAINS	Cathodic Protection	Mechanical	Structural plans	Architectural plans	Site Civil, Piping and Force Name Piene and Details	Demoision Sheets	General Sheets	Prepare Plump Station Plans	Probate equical grading plants	Propare Lighting & Electrical Plans	Prepare Bike Path/Hardscape Plans	Prepare Impetion Plans	Prepare Landscaping Plans	Prapara Drainage/Stornweier Plane	Prepare General/Floot End Plans	Property 95% Plans	andscaping and Lithar	Envision Certification	Electrical	HVAC	Cathodia Protection	Machanical	Skruckirel	Architectural	Site call	Paylinding & signage	Utilitias	Coxtour grading	Lighting & Electrical	Bisa palivirandscape	Injurion	Oral nage/Stormwater	Propare Quantities and Expineers Eathnate	PaiD	Electrical .	HVAC	Carhedic Protection	Mechanical	Structural	Architectural	Sto dyl	Pumb station		
						***************************************																	-	***************************************											7	3		3		1	2	***************************************		Work																2									2	TOTAL ROI HOURS	R.
9 3	3 6		0 \$	6 (4 4	12 \$	12 \$	to e	20 3	9	\$ 1	_		143 5		L	د	***************************************	0.5	S	76 \$	36 3	36 5	100	70.3	00	100	12 5	98 3	48 \$	8	90 5 5	30 \$ 1	32 \$ 2	\$ 47	22 \$ 22		382 \$ 27	S	02 5 8	08 \$ 15	*	2122 \$ 145	11	5 6	3 6	12	o s	26 \$ 2		20 \$ 1		16 3	30 5	15 3 1	15 3	22 \$	D C	28 5	18		Ļ			64 5 5	\$ 2	53 5		59 5 18	TOTAL HOR DTL PEE	
\$ 289	2 350	548 5	٠.	, ;	787 5	926 \$	628 \$	187 5		909 \$	\$ \$05	.395 \$		3771 3	3	760.5	277 3	-	3	.092 3	J16 1	772 3	312 3	507	1 199	2	100	524 3	749 3	\$ +29	075 \$	952 3	895 5	743 \$	132 5 1	164 5	308	330 \$	٣	\$	٣	5	*	•	֓	636 3	•	•			265 \$		200	676 \$		706 3	997		151	871 3	901 3	878 5	986 \$	421 3	102 5	509 \$	330 \$	\$ 520	529 5	DTL TOTAL HOR BURDENED FEE	-
1,882 5	2,637 \$	1,513 \$, ee	\$	2000	1.727 5	1.727 \$	1,326 \$	0,403	2.497 \$	1,152 \$	3,848 \$	7,966 \$	29.715	1.00	10,344 \$,	11,289 \$	16,045 \$	90,409 \$	25,890 \$	1757	X,M3	107.21	4,797	1,721 \$	38.620 S	9,996 8	16,760 \$	16,420 \$	5,228 \$	5,911 \$	30,653 \$	61,200 \$	11,686 3	75,396 \$	2,726 \$	19,086 \$	43,785 \$	10,210 5	00,678 \$	24.212 5	7,588 \$	2312 3	2,396 5		6.70H S	2,719 5	3,489 \$		10 772 5	4,623 \$	3,522 \$	1,948 \$	1,028		. 003		5,326 \$	5,180 S	8,237 \$	1,162 \$	14,078 5	6,820 \$	6.427 \$		51 118 5	Golds Surve	es/s
			\$	- 8		-	- 2	5	.		•	- 3	*	. .	•	,	•	· "		•	, •	\$,	,				,	,					•			ŀ				4	· S	\$		* (, ,	-		4		3		1		5	5	, "	 n	1		5	· «		,	. 3	\$	*		5	Twining	-
			, s	8		5		S		\$	٠ .	*	*	"		***************************************	*	\$	٠ ٧		· *	*			* *	•		,	,	*	5			,			,			- 8 -			•	•	*			100		. 3	- 3	, ,	***	· •	· •	\$		· ·		,	*	5	5	5	· .	•	*	5	5	Evans and Walker	d
				*	, ,	\$	\$.			5	,	.		*		-		ļ,	*		.	-		-		1			ļ.		•	•			,					,		v		,		,		,	5		3					.			•			*		• •	4	•	5	٠,	,	TYLIN	-
				*		S	\$, ,	,		,	•		•			,	,	5	*			*		,			*										*	\$	\$,		5					5	,	*		"	,			5			,		-			65	,			•	loc (DBE)	,
			, ,	,	, ,		, ,		. ,		-					,		· •	, 5				,		,					,		-											,	,							٠.		,		,							,						.	•	UN (D名詞	,
	. ,	 -	. \$,					, ,				*	.												. .		,		. 5	, "	. \$,				. *		•													•			,			s	. \$, s	٠,		. 5	Potholing S (DBE)	ub
	-			,	, . u					,	-	,	•	.					-					-		. .			-				- 3	- *				-		, 2			*								3						S	, .	-				. \$	- 5		, 3	, 8		, 9	PG! {DBE/SW	
*	· ·	. "	5	, u		- -	٠,	. 5		,		3		-		,		•	-			•	•	•	,	•	•	ŀ			-	•	*		*	\$	1	•			- \$	5		*	\$, ,		,		٠	٠,				*		*				, 5			5		. 5	٠ \$	· *	۳	Environmen (DRE/MRE/W Crange Coa Analytical	VBE) ast
				*		-	. \$.	\$		69							*	*	*		*	•	•	*					'		- 8	-	•	•	•		1		5	•	*		*	<u>.</u>					-	\$	· •		,		\$	•	*	· :				5	5	·		97	. \$	•	5	Southwes Geophysic	nt .
5	\$		ş	y			5 .	5	, ,			59	*				*	-	\$	* -	*	*	*	*	,		*	,	,		-	5			5	-		,	•	•	*	5	5	•	*			,		5	s		. ,	5	S	\$	*	, ,			,	5	\$	4		**		· •	4	ты (ове	\dashv
,	,			ا.	. .			S	.				,		•	1		1					,		.		1		<u> </u> .	ŀ		,	•	\$.			1	,		,		,	۶ ,	,			-		,	ŀ	5							.			ļ		,		\$ -		·	,	5	American Integrated Services (At	a i
s . s	,		,				, 8	\$.	3		•		-		,		3		,		3 - 5		•	,									*	*		1			- 4	,	,	5 . 5	-			1				\$,								3 . 5	*			-	3 . 3	ı	,	MSI (DBT)
	~		,	\$		ļ.	,	\$,			- 5				-							,										- 3							- 19		,	. 8	·].	ŀ	٠				ŀ						ŀ	ŀ					,			RVA (NBI	
-	*	-	1,050 \$. 40			- 3			,	ļ.	,	0 4		- -	2,400 \$	6,120 \$	7,740 \$, 40	٠.	t6.280 s	, 5			.	. ,			- -			-	. 4	0.5		8	48	32 700 \$	31,800 3	. 3		70,800 3		5					,	. \$		1		,	°	- 4	1,050 \$	2,850 \$		5	ļ,	4		·			-	٠	Totsumi a Partners	۱ ا
1.862	2.831	1,513	1.050	1,350	2.099	1,727	1.727	1.325	9,747.0	2,491	4,152	3.646	7.966	29.715	40 495	10,364	11,440	6.520	7,740	11,269	18,045	108,669	25,690	1757	257	947	790 64	1,721	70,079	9,998	16,760	16.420	5,228	5,911	130.053	61,200	77.700	60,796	35,425	50,665	43,785	10,210	471.478	\$13,672	7 866	3 251	2 262	3 -	8,104	2,719	3,489	10,501	30.774	4,623	3,522	1,948	3,026	1,950	2,850	014,26	5.326	5.180	8.237	1,162	14,076	8,920	8.427	3,759	51,116	Total Team Fee DO's Incidents ODO's Subconsultants	_
L		1			1	+			1	1						1									1						-	-				1	-							-							H								-			<u> </u>		-						O's Travel	_
L						1		Ц			L																					L		Ц			-	1		L						\perp					L												L	L	L					產	

	ľ	21	12	2013	1		2.3	4023	Ĉ	40.21	22	r C L	212	ű.		7 P 3 S.E. P No.	2	59,3.8	58,3.7	5B.3.8	58.3.5	58.3.4	58.3.3	58.3.2	58.3.3	8.3	58.29	\$9,28	58.2.7	58,26	59.25	58.24	8.73	27.00	22,23	H		ŀ												3H.1.9	58.1.8	58.1.7	58.1.6	59,1,5	261.	60 13	8 2	6 -		10,4									49.38	(distant)		
Orangers Firnel Guardities and Empireers Estimate Propers Firnel Guardities and Empireers Estimate	Erosian control	i/Front end	Frepare Finel Specifications	Printing Cardian Plant	Prepare 160% Prints	Final PSSE (196%) Submittal for Early Action Utility Relocations	橡		Elakon conita	GeneralFrontend	Prepare Confidence	Prepare utility plans	Prepare Control/Front End Plans		(nitted PS&E (95%) Submitted for Early Action Utility Relocations	LAWY Relocations	Envision Certification, includes certification pedrage preparation	Pump station	Waylinging & Signage	Contour grading	Lighting & Electropi	Blke psth/hardscape	Engravien .	Landcaping	Distriago/Stotmisster	Piegare Final Ottorities and Engineera Estimate	Pump station	WayInding & Strage	Contaur grading	Lightesg & Electrical	Bika pativnardscape	mgaten	Langecaping	Lizinaperbicankolei	Gentleder (on end	Prepare Hina Specifications	LEED Certilipticas - Sayer	Standard Mess	COLDIDRAS	PALUPIANS	Electrical vieta	コマメン・コンフ	CAN INHU P CONTROL	MECINIDA	Mochanical	City charal plane	AT MACHINE PINE	Silo Divid Divido and Force Mains Plans and Catalla	Carried States	Prepare Prung Station Plans	Prepara wayfiinding-vignoge plans	Prepare contour grading plans	Prepare Lighting & Electrical Plane	Ріврата Вине Рациліначоворе Рівля	Propora Intgetion Plants		Dispute College Commenter Clare	Dispute Consequence and Clare	Drenam 100% Plans	Charles Control of the late of the Control of the C	POLICE	E eculos	HYAG	Countries Protection	Mochanical	Sirvonal	ACDRECUTO	Site grafi	Pump station	Test Description		
5 5	1 2	19 5	£6	2	200	197 5	13:1	46 3	10 3	4	102	218 \$	B7 S	305 \$	420 \$	817 \$,	102	4.5	61	-	+	0.5	0.5	7] 1	127 3	110 \$	23/3	÷	22.5	20.5	9	9			6		9	9 6	1	1		10 1	2 5	2	2 04	2	8	2	46 2	2	102 3	35	194 5	*	16.5	110 \$	201	1387 5			•	5 6 n b		i d	,	Ĉ	2 2	200		TOTAL HOR HOURS	
230	235	1,532	3,193			13,170			812		8,030				28,091	41,251	10,134	7,348	295	501	175	158	٠			6.872	7,838			1,677			į	1.(24	200	2,070	23.00	100	200	3,737	2 797	2 77 0	770	1 240	0.55	3 220	6 6	2 191	817	760,74		7,092		13,901	494	1.668	8 244	357.1			2 404	220	420	277	//0	101	2	3,500	5,486	-	TOTAL HOR DTL FEE	
*	-	٠ ٠	5 0	5 10		ĺ	3 13		1 2.239			\$ 36.6		\$ 53.4		1 173,1	\$ 27,5	\$ 20,2		3 1,3	3	4		1	•	34.3	\$ 21,6	13		4.0			1	, ,			27,304		1	,,,,			2 2	3.1	108	5	3 166	3 253	22	1 200	۱	3 19,5	4 8.0	\$ 36,350	3 1,3	\$ 4.6	\$ 22.7	47	26	1	7.0						1.5		3 15,139		TOTAL HOR BURDENED FEE	
574 5	4 5	225 \$	6,809 \$	8	2 2	\$ 255	972 S	265 \$	239 \$	\$ 84	163	\$ 995	765 \$	\$	197 \$	29 5	157 \$	272 : \$	315	181 5	2			5	923 S	309 \$	\$	5	\$	020	24)		1				7	9	79 6	200	000	000	25.5	24 6	2	40	5	2 90	55 5	5 6	8	8	5	\$ 65	63	2	5	788 5	740 S		2	2 4	4 0	1	200	,	1		- W	T	Guida Surve	,,
s	A 60	5	5	"							• •		· ·				5	"		#		9	*	-	· •	\$	5				•		1					,	,		a (*	9	9	2	8	50	5		,			-	5		ca		5	5	The second	^ •		,	•	,			•		-	Twining	1
s	7 5	\$	3	51	2	١	•	•				*	45	*	*	3	"	9	5	5	5	57	cri	8	5	5	5	.,			,	,	*	1		1		,	^ '		•		,	5	5	5	\$	٠,	"	ys (-	5	\$	60	*	5			,	1	,	,	,		1	,	* *		Evans and Walker	
5	2 10	\$	8	5	*		*		5	3 .	3	*	\$	#	ļ	-	s	5	5	6 0	8	5	5	5	\$ -	5	5	ű.	,	ŀ	-		1	•	+	•	7	,	^ (1				-	-	3	5	<u>.</u>	*	9	,		5	5	\$		•	-	16		,	1					1	,		•	TYLin	
*	, ,	\$	*	-	,		2	5	5	4 7			55	•	57	•	5		,	69	57	5	Į¢	2	5	<i>\$</i>	ş.	į,		,	-					•			^			,		5	,		•		•		<u> </u>		5	\$	5						,	,		,	,				7	1	(DC (OSE)	٦
5	s 5	5	5			•	,		-	*	•	5		*	5	*	1	\$	*	8	5	5	5		,	*	5	ľ	ő	,	• 0	•	1	1	,	1		†	,	•	2	*	5	•		¥	-	5	\$,			5	\$.	.	5	•		1	,	1		†	7		1	*		1	CIN (OBE)	1
ý	5 .	5	ıs ,	5			,		•	*	ş		65		,		5	٥ .	*	65	5	5			\$,	,	ŀ			•	*		1	,	7 6				,	,	,	,	5	· ·	*	5	*	9	, ,	,		- -	ş	-	s			***************************************		*	,	,	,	,		1	,	THE STREET	Potholing Si (DBE)	ub
1	9 49	s	47	\$	•	1	ř		~	**	5	•	s	~	-	•	ľ	\$	1	5	5	5	\$	\$	5	2		,				•	,	*	2		,	1	,	,	,	-	5	-	\$	5	\$			*	и 4	1.		5	\$	٠	5			*	,	,			1			^	<i>"</i>	,	PGI (OBE/SW	BE)
S			27	5	,					*		4		*			5	1	,	,	,	18			5	4			,	,			,		,	,		1		,			- -		•	,	-			*					5	19		,	9		5				<u></u>				1		(nterphase Environment DBE/MBE/W	ui l
١,		5	s	s			-	*	*	*	*	*			-		7			5	\$	5	5	3		,							1	,		*					3		\$		5				5	5		1		,	\$			*		-			,	,		*	*		,	1	Orange Coa Analytical VSBE/SBE/W	. ,
"	v (*		ъ ,	۶	*	,	ľ	Ī	- -	•		•	<u>د</u>	ľ	-		ľ				5	,	-	,	5	5	ŀ	†°	,				,	,			,		,		5	۰	٠	"	-	\$	4		•	-	,						s ·	5		1	8	,	5			*				1	Southwest Geophysics	
*	4 .				,	,				,	*		5			*	-		5		,			5		5		,	,	,	,	1		3	4	5	4		ça ,	\$	5		۱,				5					.				÷	*	\$	*	determine steered		*	٠		-			,	ا.		TMI (08E)	
	, ,			,	,					-	-	,		-	,	5			ŀ	5			*	3	-	,		Ţ.	•	•	5		5	5	•	5		*	s .	•	2		S		•	,	\$,		5		•	Ī		,	\$	\$	S	\$	"	5	5			5		5		9		American Integrated Services (Mi	. 1
í							Į.			-		٠	ŀ	-		\$	ŀ		ŀ			•		ŀ	,	-	ľ		Ī		*		١	<u>ا</u> "		5		2			,		٠	,	59		\$ -	-		\$°	,	***	•	-			3			•	•	•	,	·		٠	,		5	•	MBI (OBE)	,
Ŀ		ŀ		5			ŀ	•			,	Ŀ	,	Ŀ	,		ŀ	5	Į.	5				ŀ					1		٠			,	•				,		\$,	50		*		\$							\$. \$	s .	5	\$ - 4	1		*			\$		5		"		RVA (WBE	3
	, ,			·	,	.	֓֞֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓	,		,			ŀ			A 347 # 244		,		,	,		500	500	ŀ	100		<u> </u>					8	8			8		*	\$ - S		- 4	,	,	s -	·	·		,	\$,	5	500	\$ 1,200 \$	14.700	1			31,300	37 800					*	·		,	٠ [2 D	Talsumi & Pariners	
Ш	3 3,934				-	١	1		ł			l	l	ļ	l	ı	ı	l	250	1,367	4	1,50	ļ	l	١			l			-	1	1			7,618					1		ļ				18,851													Management				-	Ì	۱		ļ	4,989	15.139	Total Team Fee Inciduing Subconsultants	
ĺ	- 0	1	-	-			ľ	ľ		,	ĺ				***************************************					ĺ		,		Ť	ĺ													-														-		ľ	Ī													1			000*	
-	1					+	1															+	+		+			1			1																					1	+	\dagger	+	-	-		-				-							1	Travel	

City of Long Beach Shoemaker Bridge PS&E Fee Surrenary

				5,2,3	82,2	821	8.2	\$ 13	B12		2	=	6	7.8	7.7	7.5	7.5	7.4	7,3	7.2	7.1	7		6.2.8	8.2.7	226	62.5	624			\$23				\$2.2	62.1	6.2	51.4	6.1.3								6.7.2	61.3	5	90	
		Contract Profit:		Prapara Bid Addenda	Respond to Bidder inquiries	Attend Pra-Bid Meeting	City Construction Contract	Propere 3ad Addenda	Respond to Bidder Inquirem	Alland Pro-Bid Maning	Celians Constaution Contract	Construction Bidding Phase	Provide grant apparation preparation support saylings and controllers and provide the support saylings.	Public Outreach and Social Media Support Services	Objain public agency approvals and apreaments for construction	Oblain utary owner approvals and agreements for construction	Execute Section 214 agreement between Citylifiatro and USACE	Facilitate execution of cooperative agreement between City and California	Prepare Environmental Clearance Permille for Construction	Prepagre NPDES General Construction Activity Stormwater Permit	Prepare Californs Enroschizent Permils for PSSE phase	Permitting Services and Other Support Services		Property owner occidination meetings	Secure Legal Possesson	Escrow Coordination	Condenmosaijon Support	Provide support to City in good faith negotations	Coordingte with City in review and approval of offer packages	Prepare draft offer packages and submit to City	Preparation and Approval of Offer Packages	HCXX reviews externel appears and independent appraisal review	Appraisal Coordination - Independent Appraise Review	Appraised Coordination - Peo Appraise	Conduct Property Appraisals	Right of Way Mapping Review	Right of Way Appraisal and Acquistion Services	Right of Way Design Support	Propers ROW/Ottay Centification documents	Denote Demonstr According Communication	Practice Dunkt at Minu Mana	Presson Manument Persellution Surveys	Prepare Land Net Mao - "Before Condition" Record of Survey	Perform Land Net Recovery and Field Ties	Acquire Tild Reports	Perform Record Date Search	Document Right of Way Requirements	Review Existing Right of Way Mapping and Supplement as Nacessary	Right of Why Employering		Tan Despipala
Section Sect	Other Expanses	Travol (milauga en Reprol	1	l			324 3	88	106 \$	20 \$	186 4	\$ 016	- Did	8 0	120:5	78 5	0 8	<u>8</u>	368 5	72 5	<u>\$5</u>	990 5		170 5	40 5	 	9D &	100 \$	t)	\$ 03	\$ 021	30 \$	30 \$	S OF	\$ 06	30 \$	\$ 069	170 \$	324 5	118 3	776	9	0	2	76 3	120	436 \$	74 3	1006	1696 3	HOURS
## A CONTROLLED STATE OF THE PRODUCT	Sublistal S	appetises	300,024	8,000	15,988 \$	3,541 \$	27,506 \$	5.131 \$	9.818 5	1,990 S	16 939 1	28.12	10,020	7,731 \$	9,993 \$	5,587 \$	-	4,607 3			3,508 5	76,399 \$	L	14.298 3	1,963 \$		4 187 5		1,963 4					1,538 \$		1,538 4	39 285 \$	11,948 \$		7 624 4	9000		,					4.640 \$	84 452 3	103/37 \$	
Section 1	138,700 214,185	53,446 17,000	4	22,058 \$	44,046 \$											15,413 \$		12,710 \$	77,810 5	16,299 5	9,678 \$	210,762 \$	Ш		5.414 \$	7,780 \$	11.552 \$	12,451 \$	\$ 1545	10,105 \$	15,520 \$			4,242 \$				32,957 S				2	٠,	. s	12,044 \$	16.968 \$	74,788 \$				TAL HOR DENED PEE
Section 1			4 nnvient			. 8	. \$			9 1							5	, UB		ea		, ,		,	- \$	ι φ	, 4		- %	-	, U	, ,	, 41	- 5		,	. 3	30,000 \$		100 000	10000	-	\$ 000 3	50,000 \$	10,000	10.000	285,000 \$			355,000 \$	Guida Surveys
Section 1			displaying 4			. 3	٠.	,	٠,	, ,	٠						,	,				- 5		. \$	- 8	. 8	,	\$		•	,	,	, \$, \$, S	٠,	. \$,			,	٠	,	٠,	,	,			
## ## ## ## ## ## ## ## ## ## ## ## ##			To annual			. 5		;		.	,	-				,							Н		. \$. *	, u			. *	,	. \$					•	,								, 5	Eyans and Walker
LM (ORE) Company	50,000				. 5	. 5				٠					- 5		,	, 5	. "	,	-	*			,	,		49	,	,	, 5	,	. 5	•	, 5	. \$		•	- 8		,		,							, ,	TY Un
Perchanged by Pe	-		ı.		. *	. \$, s	*			"	-	,			,		60	. 8	. *				,	. 8		. 5							- 8	. \$		-	٤ -	*		•		,	*	, 9	*			,	. \$	
[Control of Control of			10,000	S	, \$. \$	٠	5			, 5	<u>:</u>	-	ŀ	,	5	,		5	*	- 45			so	,	. 3		,			·			. 8	. 5			, 5		,	,	. 8	, \$	*	, sc	•	9	- \$	-	- 4	Patholina Sub
## OF STATE			1	Ł			. 3	4	, M		•	-			1		•	, ço	5	- 15	· s	,	-		, 3	* \$				•	٠		. \$. \$. s	. 8	. \$. 8							, s		. 8			- 2	
Grange Loyal Cystal Cys			١Js	4			•		*		•	1	ľ					•	5	5	2	•		S		. 8	1 34			6	G	· s		. \$				s			ın I	·	٠	*		-	so		W		Interphase Environmental
Southwest Georgian III			ŀ	ŧ		L	Ш		, ca	*	┙	_1	•				ľ	5	,			•		i So	. 2	. \$	- 8	٠	,		- \$	\$	- 3	٠ \$	S		- 3	- \$	3	,	5	-1	Į			١		٠.			Orange Eoast Analytical
That (pher) That	H		ľ	ľ	L	\$	5	¢.	\$	·	٠ د	*			5		П	2	, vs	· ·	úì	•		in	. 15	. 5	· ca	,	,			. 5	- 5	. 5		. 2	- 5	. \$	-	,	-	-	4	5		-1	ı			*	Southwest
American Integrated Americ			ŀ	ľ	s	*	•	5	50	5	"	*		,	,	5	3	5	5	5	6	-		65	. s	. s		ü			- 8	,	- 15					. 5	5	·	,	5	\$	3	· S	*			, 4	*	
MGG(EBE) MGG(EB	H		ŀ	ľ		5	٠	*	*		"	-	-		6		3	5		5				5		*	· ·			5					\$. 5 .			9	-	9	·	10	2	5	. 5 .	• •	•	integrated
Reviewed A Fractions Total Team Fee Reviewed A Fractions S	H		ŀ	ľ	1	50		*		49	•	-		Į,	,	5	3	S	l	\$	L	*		8	L.		9	П	6				Ц	5	50		5	\$ -	S		8	*	**	4	6	*	-	8 -	·	*	
Patients Teal Team Fax Document Association Services (1997) Security	11		F	Ŧ		s	5	\$ 1		5	5	-	1		8	8	1		Į.	\$	ľ	1		\$		ş	\$	41	ب	*	. s	\$.	3	°	s		S .	s .	•		,	*		8		5		5			RVA (WBE)
Manage ODDS's Lating to the La	3		1	1	\$	19	\$,			•		1		,	,			,	er ,	5			,	\$.	\$	\$	φ	\$	¢¢		\$.	ş	69	4 9	φ	\$.	\$	*			*	*	5		·	°		69	-	
1 187111 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1			a william	1								\$ 138,073	0	20 000	ľ	1	l	\$ 12,710		ľ											\$ 15,520		\$ 3,580	\$ 4,242							\$ 74,992	-	\$ 85,000	\$ 59,000	\$ 22,044	\$ 28,966	l	\$ 52,802	\$ 532,607	\$ 841,185	Total Team Fee Inciduing Subconsultants
			Í						-		-								-	_	-			~		-	~			Ŭ.	1	7	Ü	-			-	`		-	_		ŭ	Ÿ	_			~			
<u> </u>				1	***************************************									+	***************************************							<u> </u>		5 1,95%																1											Travel

7 017

Attachment 2
Shoemaker Bridge PS&E
PS&E Task Listing and Responsibility Matrix (Revised January 2021)

2.5	14	2.3.1 2.3.2	2.3	2.2	2.1	*	1,4	1.3	ı.				E						010 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0					***************************************	1.1.1	Ľ,	1
Prepare Supplemental Geometric Review Drawing	Geographical Experience	Complete design surveys Complete pothole surveys	Supplemental Field Surveys	Prepare Supplemental Design Standard Decision Document (if needed)	Conduct Geometric Workshop	Prolininary Design & Bridge Type Evaluation/Selection	Prepare Project Management Pian and Financial Pian	Prepare Design Quality Management Plan	Prepare Pragress Reports and Invoices	Schedules	Maintain Project Files	Prepare and Update Risk Register	Administration	Constructability and Safety Review Workshops (65% and 95%)	Biweekly internal project team meetings	Focused workshops with Caltrans and/or City staff	Utility owners meetings (see Tasks 3A-5A)	Hes smy 61 pie CHS (4) sellssall consulptions Apturen	Coordination Meetings with USFWS		Coordination Meetings with LACDPW and USACE	Agency/Third Party Coordination Meetings	Stunding	PDT Meetings (monthly)	Coordination and Meetings.	Conditation and Administration	Project Management, Coordination, and Administration
Prepare GRD to reflect any agreed upon geometric design modifications per Task 2.1 and submit to Caltrans for approval.	Canolact peakschnical applicration and borings nasoled to appoint the protectinical analysis and deptyri- recommendations		Complete supplemental design surface needed to support final design work	Document any supplemental design exceptions that may require Caltrans approval	Conduct workshop with Caltrans to review preliminary project geometrics and discuss any potential modifications that Caltrans may want to incorporate		Prepare and maintain Project Management Plan	Prepare and maintain Project Management Plan	Prepare monthly progress reports and invoices to City for work completed.	Prepare baseline and monthly status final design schedules for both construction contracts	Set up project fling system and document all incoming and outgoing documents throughout project. File all incoming documents.	See task description	repaire and maintain project lisk register (froughous meat design design) To prepaire document control system and maintain project files throughout project. Files throughout project and monthly project status schedules.									issues is with the same	Meeting is intended to allow for regular coordination with City on project status and discussion/resolution of technical issues convictor (The input	Meeting is specific to Caltrans PS&E package dovelopment and intended to allow for regular coordination with Caltrans on project status and discussion/resolution of technical issue requiring Caltrans input.	Conduct meetings with City, Calitrans, and other 3rd party stakeholders as well as regular internal project team meetings.	The state of the s	
Draft & Final GRD showing layouts, profiles, and typical sections	Gentectinial Explication Flan, Water Politicion Control Plan	Field survey data (CADD, ASCI)		Draft & Final DSDD	Workshop agenda, minutes, presentation materials, concept exhibits, etc.	***************************************	Project Management Plan, Financial Plan	Design Quality Management Plans	A CONTRACTOR OF THE CONTRACTOR	Approved baseline project schedule and monthly status schedules	Project file log	Baseline risk register and monthly updates throughout PS&E		- Avoration Avor								WE WELL AND		25	Meeting notices, agendas, minutes, and presentation materials		
Assume single sheet exhibit consistent with Caltrans requirements	Our purront contact metaded LA River Barings and Pavernent bathys for Shareline: Held to held ide walf and povement boring an the sunt side at LA River			or projection in the second se	One workshop assumed with four (4) HDR staff		r project which will cover final design work for	Single plan to be prepared for project which will cover final design work for both construction contracts.	Assumes 3 year final design duration	Single master schedule to be prepared that covers final design work for both construction contracts.		initial risk register will be developed in coordination with City and Caltrans staff and will be updated monthly and reviewed at PDT meetings.		Assumes Caltrans will require these and will be led by Caltrans. Assume that each workshop is half a day and will be attended by discipline leads.		Assume 3 meetings per month for 20 months, 60 total attended by up to three [3] HDR staff as appropriate		Assume 3 year design schedule, 24 meetings total attended by up to four (4) HDR staff as appropriate. Assumes portion of meetings will be devoted to project visioning and intregration.	200	LBPD and other law enforcement officials	Assume 10 meetings total attended by up to three (3) HDR staff and two (2) RVA staff	W	Assume 3 year design schedule, 66 meetings total. To be attended by PM and up to three discipline/task leads as necessary.	, ,			
\$ 34,935	\$ 574,452	\$ 110,217 \$ 25,500	\$ 135,717	\$ 34,108	\$ 18,240	\$ 5,234,328 \$	s	\$ 17,195	\$ 387,480	\$ 41,737	\$ 72,939	\$ 40,787	\$ 155,763	\$ 33,116	\$ 250,511	\$ 194,438	\$	5 76,490	\$ 24,178	635.31	\$ 51,829	S,	\$ 776,839	\$ 337,035	\$ 1,209,794		\$ 1,800,450

2.6.1	2,7.5	2.7.4		27.3	271.4	271.3	2.5 2.7 2.7.1 2.7.1.1 2.7.1.1
Pump Storon in Patininary Parajan Pump Storon in Patininary Parajan Data Gathering and Bashew Site Reconsistance Conduct preliminary hydrology and dialings knoty to support pump station siting & staing Facility Sting Considerations Facility Sting Considerations design report Propuse pump station geovernment design report	Attend Type Selection Neeting. Propiere and submit meeting proceedings. Updated type selection reports to address meeting comments and submit for approval Updated type selection reports to address meeting comments and submit for approval Conduct updated hydraulic/scour analysis of I.A. Biver for selected alternative bridge concept.	Prepare addidgo Deck Drainage Design and Memo Prepare Sindge Site Data Sub-mitted Bridge Type Selection Meeting and Asproval	Prepare Type Selection Report (Daukábbolt structure) Prepare Type Selection Report (Daikábbolt structure) Prepare Type Selection Report (Daik Rever Bakapas birdge) Prepare Type Selection Report (Daik Street ped birdge replatement) - non-Contrors Prepare Chype Selection Report (Daik Street ped birdge replatement) - non-Contrors Prepare Conceptual Bridge Removal Plan for existing Streemaker Bridge and walls Prepare Conceptual Bridge Removal Plan for existing Streemaker Bridge and walls	Prepare Structure Type Selection Reports Prepare Structure Type Selection Reports Brease Two Selection Report I & River esson	Alternatives Development, Costing and Proferred Alternative Selection Prepare Supplemental Advance Planning Studies for U.A. River and, floundations Structure	Public troobseriest coordination and consens Develog 3D model of Scheenwise Bridge and raundabout Structure. Develog 3D model of Scheenwise Bridge and raundabout Structure. Develog 3D model of Scheenwise Bridge and raundabout Structure. Develog 3D model of Scheenwise Bridge and raundabout Structure deak treaments. Prepare Bridge Amendment (3 views total) Prepare Bridge Rendering (3 views total) Stakeholder Workshops and Constraints (sentification)	Description Prepare Preliminary Foundation Reports Structures Tipe Selection Architectural Concepts Architectural Concepts Initial Theme Development and Scoping Initial Theme Development and Scoping Initial Structural Concepts In the Concepts of Scoping Initial Theme Development and Scoping Initial Theme Development Action Initial Theme Development Action Initial Theme Development Initial Theme Dev
Conduct necessary activities and obtain information needed to complete preliminary design of pump station Conduct study to determine preliminary pump station Drovide geoterinical recommendations needed to complete pump station design based on boring data	Conduct updated hydraulic/scour analysis of LA River for selected alternative bridge concept in accordance with Olirans requirements	Propage Bridge Deck Drinhage Design and Mexico. To prepage BSDS for Calitrans structures and submit to Calitrans Conduct type selection meeting with Calitrans for LA River and roundabout structures to review type selection reports and obtain comments.	To be submitted to California and City To be submitted for California and City To be submitted or California and City To be submitted to City anly To be submitted to City anly	structure concept and LA River and roundabout bridges and any nonstandard retaining walls with State jurisdiction will be submitted to Colleran for rolleran "Type selection documents for City bridges to be submitted to City for review for he submitted to City for review to be submitted to City for review."	Advance development of bridge design options and develop ADM costs for each. APPRIARY report to document options and associated costs and abbinit to City and stakeholders. AVO's with City and stakeholders to determine preferred cridge internatives to be incorporated into final design. Propose applementatio Chimina APPS in preferred available of Propose applementation.	lor City consideration Build a 3D model of the site context, size TBD Build a 3D models of each treatment. Build 3D models of each treatments. Coverop simple renderings (non-photorealistic) of the deck treatments. Conduct workshops with stakeholder to review initial concepts to be considered and obtain input.	Discription of key Activities Prepare Preliminary Foundation Report to provide foundation design recommendations for proposed broligas and retaining wills: When the control of the cont
reshices Memorardum summarting the work completed as part of this task. SD-01 alternative site plan exhibits, select exciton views, and details to be included in the memorandum. Aurija station gestechnical design report	Meeting, seanch Meeting, gentalus Updated type selection reports Oraft & final summary report	1	Cultiens Typs Selection Report format to be used for bridge	Type Selection Reports for each Bridge and Nonstandard Walt	Opvisioned reinderings for each alternative for both LA River and roundabout structures. ### ### ############################	Descring conditions site mode! Do procure mode! Do prode! Bridge sitemative modes. Concept sketches, renderings, etc. Vondring agendas, minutes, meeting materials	Deliverables Ordit & Final Preliminary Foundation Report Include the Control of
Purps settion to be LEED Sheer system to the immediate light on exhibits, select section, views, and details to be included in the memorandum.	Meeting assumed to be virtual. Applies to LA River span bridge only. Assumes no mitigation measures or USACE risk & uncertainty analysis for levee freeboard		Detailed removal plan to be prepared and submitted by Control on; subject to review by the Engineer.	Campleted if Caltrarks requires; in: Sobedule does not assume supplemental APSs are required. Bit Elementer forundations structure and LA River bridge are Ordinary Non- tstandard bridges and pedestries in ridges are Ordinary Standard Infriges per Caltrars SDC. Essings polis are anticopneted to be imposed for bridge foundation analysis/sessign. Study/use of base Isolation is not Included.	333	To receive 30 models for these ferms. Design feer prifers a baseline design of the LA Ruler bridge and selvenzed counterboat only. The LA Ruler bridge type is assumed to be concrete segmental with principle than the design of the principle and	Votes/Assumptions Separate reports to be propered for each structure, including City ped bridge: Control of the separate for each structure and reports to the LA flower bridge main spans and roundabout carchitectural (rearments to the LA flower bridge main spans and roundabout carchitectural incarcere). Assume three (3) City workshops with Public involvement and stakeholder groups.
5 13,044 5 2,07,09 5 2,07,09 5 2,07,09 5 7,1,13	\$ 53	\$ 37,595 \$ 10,313 \$ 61,137	\$ 891,966 \$ 112,148 \$ 62,744 \$ 103504 \$ 50,209	v v	5	5 177.465 49 49 49	
					36,983	16,982 34,935 115,7778 18,807 21,947 21,947	243,024 305,041

2.10.1	2.9.4	2.9.3	2.9.2	2.9.1	2.9	2.8.7	23.6	2.8.5	2.8.4				2.8.3	No.	PS&E Task I
Complete Artibly Poposited Land (AOL) Have your control of the Complete of the	Utility Potholing	Usliry Caordination	Conflict identification	Update Eristing Utilities Base Map	Utilities	IEED Certification - Silver	Preliminary Design Workshop	Prepare Fump Station Freliminary Design Report	Prepare pump station construction cost estimate	Architectural elevations	Instrumentation and control diagrams	Civil site iayout drawings	Propure Prolingsary Flans	Description	PS&E Task Listing and Responsibility Matrix (Revised January 2021)
Complete survey to determine presence of ADL within project Aerially Deposited Lead Survey Workplan area; and if so; define necessary pre-autions/mitigations to Aerially Deposited Lead Survey Report be completed by contractor.	Conduct potholing of selected existing utilities to positively locate	Conduct coordination and meeting with City and impacted 3rd party utility owners to present utilities in conflict with project and discuss potential relocation strategies.	-Conduct supplemental evaluation of existing utilities in conflict with proposed project -Canduct prior rights research for impacted utilities	Prepare and submit tetter to 3rd parry utility companies to request updated utilities mapping Orbith and releve may as-builts for recently completed City project within project timits -Update exhibits utilities have mapping and marrix to reflect any new feelites identified		Develop considerations and a sustainability plan sating LEED Sheer Cardification is pursued for the pump station.	To discuss and confirm the Project design basis (hydroalitics det Japouts, transmission main alignment, materials of construction, equipment selection and psecifications, construction, equipment selection and psecifications, and construction schedule, estimated costs, constraints, property and exserment acquisitions, transition plan to final design, etc.).						Prepare preliminary design plans for propised pump station facility	Description of Key Activities	
ct Aeribily Deposited Lead Survey Workplan Aeribily Deposited Lead Survey Report	Pothole needs plan, utility investigation work plans (if needed) for agency approval, pothole data reports, traffic control plans for potholing	Coordination meeting agendas, minutes, and presentation materials; utility relocation documents	Conflict matrix to identify any newly discovered utilities in conflict with project. Prior rights information to be added to matrix.	Existing utility verification request letters, updated existing utilities base map and associated matrix		-Certifying authority agreementsOrath and final Sustainabilly Plans -Meeting agricias, minutes, and presentation materials		Oraft & Final Preliminary Design Report	Preliminary construction cost estimate				Prulminary pump station pians	Deliverables	
-3 days of field sampling at 20 total locations 1 day of 075 surveying Hard auget boring only, to a maximum depth of 5 feet 4 samples per boring 5 samples per boring 6 samples per boring 6 samples per boring 6 samples 6 sam	Assume 30 potholes; 15 traffic control plant, 1 work plan	Assume up to 3 meetings each utility owner, 6 owners with 2 HDR attendess. HDR will coordinate with Shoreline Realignment Project team to faillints joint discussions with impacted 3rd party owners and to share utility information.	,	Assumes preparation of up to \$1 letters and review of as-built plans for up to \$1 polysts. APR will condinate with shoreline Realignment Project team to facilitate joint discussions with impacted 3d party owners and to share utility information.			Half say workshop to be attended by pump station design lead and discipline leads; (total of 4) along with City staff.	City is responsible for payment of any Certifying Authority registration and review fees unless otherwise specifically stated	Soft costs to be included in cost estimate it requested by City Determination of right of way acquisition costs is assumed to be responsibility of the City		An automated trash screen will not be included.	Beach Maintenance Staff No physical modeling will be constructed for SD-01	Easting 20-04. Pump Station force mains and outfall will be utilized and these will be no modifications of improvement design required, we computerional shall dynamic (ECI) modeling will be necessary, the pressure versalism (uses) analysis will be explained. SCACA requirements will be identified in coordination with the CDy of Long.	Notes/Assumptions	
in (\$ 118,185	\$ 47,317 to	\$ 36,221	5 25,821 im	\$ 296,344	\$ 9.045 10.045 1	\$ 7,415	nd \$ 35,282	٠		5 2922	S 7,705	5 10 10 10 10 10 10 10 10 10 10 10 10 10	Cost	
	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,								, and the second		700 (dg)	3		Cost	

Attachment 2
Shoemaker Bridge PS&E
PS&E Task Listing and Resp.

2.12	2113	2.11.2	21411		2.10.5	2.0.4		2,103	2,101.	Task
Camplete Occidental Oil Field impact assessment and facility relocation plan	Prepare Lighting Concept Plans	Prepare overall urban design, landscaping, contour gradings and bikeway concept plan.	Conduct study to evaluate potential for Envision Certification	Urban Design and Aesthetics	Prepare traffic control plant to support field work	CORDUCT PRISE II INVESTIGATORI TO TOUT SILES.	Conduct Obaca III pusetinations for four sites	Prepare, Hashh and Safety Plan, a Contaminated Manerials Management Plan, a Construction Contingency Plan, and a Lead Compliance Plan	Omplete Adoeses Containing Maserials, (ACM) and Load States Paint (LBF) surveys	Task Task
identify scope of project impacts to Occidental oil field along west side of LA River within project limits and associated mitigation costs and submit to City for review.	Work with City to develop concept plan for bridge and park lighting elements of project	Work with City to develop concept plan for proposed bileway, urban design, and park elements to be implemented as part of Project.	Determine steps to be taken and elements to be incorporated Workshop agents, materials, and minutes; summary into project to be eligible for privision certification and submit documenting workshop. to City of consideration, includes proparation of City and Coltrarie.		Prepare traffic control plans	uchino i devenim i esservici i man ava van within project initigation strategias to remediate hazardous solls.	Conduct studies to confirm existence of hazardous soils	Prepare plant for use by the field craw to address various hazardous magnitals that may be encountered juming field activities.	Description of Key Activities Compete survey to determine presence of ACM and LEP ACM and LEP Survey Works with refrictures to the demolshed within project area; and if ACM and LEP Survey Weyse so, define necessary presentions/initigations to be completed by contractor.	
impact assessment summary memo, relocation plan		Conceptual plans, root estimate, and summary technical dimemorandum	workshop agenda, materials, and ministers summary report in documenting workshop.		Approved traffic control plans	Phase II (PS) Report to all four sizes. Hazardous Materials Disclosure Documents (if needed)	Phase II (PSI) Workplan for all four sites	Health and Safety Plan, a Contaminated Materials Management Plan, a Construction Contingency Plan, and a Lead Compiliance Plan	ACM and LP Survey Nobotics ACM and LP Survey Report.	The state of the s
Assumes linal design of any miligations to be completed by owner.	-	All photoscaping and absorberch to be continuously that we were mouse it and			-Up to 7 sheets of engineered and stamped temporary traffic control plans will be prepared to support field work -Plans will conform to MUTCD standards	Site 1: California Resources Corp (west of LA River north of Shoemaiker) Site 2: California Resources Corp (West of LA River north of Shoemaiker) Site 5: 950 Destonest Ave. (UPRR Bulk Terminal) Site 6: 950 Destonest Ave. (UPRR Bulk Terminal) Site 6: 950 Destonest Ave. (UPRR Bulk Terminal) Other sites listed in the Environmental Document will be investigated by others (Cleanup/Immediation of sitcovered conditions is not included. Cleanup/Immediation of sitcovered conditions is not included. Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days and geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for USTs Abazimum of 2 days of geophysical surveys for days Abazimum of 2 days of geophysical surveys for days Abazimum of 2 days of geophysical surveys for days Abazimum of 2 days of geophysical surveys for days Abazimum of 2 days of geophysical surveys for days Abazimum of 2 days o	-Four sites will be investigated:	Health and Sefery Pan and Lead Compliance Plan will need to be prepared and stamped by a Certified Industrial Hygeriats. The LIZ can only be completed after The AD Lurvey is complete. As increases when the interior is complete and safety relating for lead work is not required and safety relating for lead work is not required. The Contempared Materials Management Plan will be based on previously available data. Plans are for HOTs investigations related to PS&E not for project construction or other contractors? Use	- Albh stouchurs require a surveys for ACM and Life - Nach Span of Shoemaker Bridge - wastbound 9th Street ramp - eastbound 9th Street ramp - eastbound 9th Street ramp - orthosatern bike path overcrossing - rombeatern bike path overcrossing - combeatern bike path overcrossing - combeatern bike path overcrossing - purp station Other streatures, such as the Golden Short Overpass are outside the project zera and will be surveyed by others! - purp station Other streatures, such as the Golden Short Overpass are outside the project zera and will be conducted by a sontractor leseked to perform lead and schemos surveys. - Reporting will conform to SCLQhyto and claims requirements - Reporting will conform to SCLQhyto and claims requirements - Reporting will conform to SCLQhyto and claims requirements - Reporting will conform to SCLQhyto and claims requirements - Reporting will be conducted by a sontractor leseked to perform lead and schemos surveys. - Reporting will be conducted by a sontractor leseked to perform lead and schemos surveys. - Reporting will be conducted by a sontractor leseked to perform lead and schemos surveys. - Reporting will be conducted by a sontractor leseked to perform lead and schemos surveys. - Reporting will be conducted by a sontractor leseked to perform lead and schemos surveys. - Reporting will be conducted by a sontractor leseked to perform lead and schemos surveys. - Reporting will be conducted by a sontractor leseked to perform lead and schemos surveys. - Reporting will be conducted by a sontractor leseked to perform lead and schemos surveys. - Reporting will be conducted by a sontractor leseked to perform lead and schemos surveys. - Reporting will be conducted by a sontractor leseked to perform lead and schemos surveys. - Reporting will be conducted by a sontractor leseked to perform lead and schemos surveys. - Reporting will be conducted by a sontractor leseked to perform lead and schemos surveys. - Reporting will be conducted by a sontractor leseked to perf	
C34,244				\$ 105,723 \$ 27,613	s \$ 30,726		\$ 211,138	9 S 77,277	S 1	0

Attachment 2
Shoemaker Bridge PS&E
PS&E Task Listing and Respo

				accordance with Caltrans plan formatting requirements and develop quantities		
•		Assumes no ramp metering or electrical system plans. All bridge lighting to \$\displais\$ be based on project aesthetic guidelines prepare in Task 2.		Prepare lighting, traffic signal, and electrical plans for all work with Caltrans right of way and adjoining local streets in	Prepare 65% Electrical Plans	34,6
		_	Signage quantity summary		Prepare Quantitles	3A.5.2
	51,390	\$	Signage layouts		Prepare Plans	3A,S,1
				formatting requirements and develop quantities		
	50,024	•		adjoining local streets in accordance with Caltrans plan	rispans and algorithms	č
		2	ravement destreation quantity summary	Brooms sim sims for all work with Culture sight of way and	Prepare Con Disco	34.4.2
	19,817		Pavement delineation layouts	-	Prepare Plans	3A.4.1
				Cattrans plan formatting requirements and develop		
				right of way and adjoining local streets in accordance with		
	25,051	10		Prepare pavement delineation plans for all work with Caltrans	Prepare 65% Pavement Delineation Plans	34.4
		***************************************	Construction Area Sign Plans	upon preferred staging approach.		
			-Detour Plans	accordance with Caltrans formatting requirements based		******
	134,140	to.	-Construction Staging/Traffic Handling Plans	Prepare construction staging plans and develop quantities in	Prepare Plans	34.3.3
	•			construction and develop associated costs		-
	e3,71,00	project.		implemented to minimize impacts to traveling public during	rispeis of each adiopolismone general mentions and	37.5
		1		Orange Draft 1940 to public procific many to he	Drange Drafe Transportation Management Dive	24 2 7
				construction stagnig/moli approach that is to be carried forward into final delen		
	34,546		initial/revised concept exhibits, workshop agendas and	Work with City and Californis to develop preferred	Staging Concept Development and Approval	JA, J, 1
		3			Prepare Stage Construction, Traffic Handling, Detour, and Construction Area Sign Plans, and TMP	34.3
			-Erosion Control Plans			
			-Temporary Water Poliution Control Plans			
		to	-Drainage plans		Prepare Plans	34.2.2
			er Data Report		Prepare Draft Storm Water Data Report	
		Report covers entire project, including pump station.			Prepare Draft Drainage Report	
		3			Prepare Reports	34.2.1
				as part of project		
				permanent storm water treatment BMPs to be implemented		
-				-Prepare Draft Storm Water Data Report to identify		
		coordination with City and LB MUST project team.		plan formatting requirements		
		station. Determination of runoff to LB MUST and/or SD-10 to be made in		elements within State jurisdiction in accordance with Caltrans		
		Assumes all runoff is to be conveyed to LB MUST facility or to SD-01 pump		-Prepare drainage plans and develop quantities for drainage		
				scope of project drainage improvements for entire project		
	309 557	includes design of storm drainage and water quality features for street and S		-Conduct hydrology and hydraulic analysis to determine	Presare 65% Drainage Pians	34.2
	_			actual managed at the property of the second section of the second second section of the second seco		
				automing reconstruct work arong our above to make in		*****
		standards. There is no landscaping/intigation component to Califiens work		elements raining within Centralis Junisdiction as well as		
	140,567			Prepare roadway plans and develop quantities for project	Piepare Rodoway Fibris	Ž
\$ 11,982	51	5			Oraft PS&E (65%) Submittal for Caltrans Work	A
-8:	E	3.			Caltrons PS&E Package for Work in Caltrans Right of Way and Adjacent Local Streets	Caltrans PS&E Pa
				assumed to be completed by third party consultant		
	39,984	VA to be led by others. Assumes participation in VA sessions by discipline 5	Anna Campaint II and Property Campaint	Project team to provide technical support to VA study	VA Support Services	2.17
1	_		existing setting or passage of time.	Professional deciment	LABORE THAN ON MEASUREMENT AND COMMENTARY	4.10.1
			Provided to to detend to capture changes in decion	project if scope and/or isotyring or project a mounted.	Donnes Southannestal David Idation / Addarding	7167
	_		Revaildation/Addendum	may be needed to support environmental revalidation of		
\$ 181,529		Scope of supplemental technical studies required TBD.	Supplemental Technical Studies to support the	Complete supplemental environmental technical studies that	Prepare Supplemental Technical Studies	2.16.1
\$ 296,524					Environmental Revalidation/Addendum	2.16
				submit to City for review and consideration.		
			Class of this securical manufacture	Confinence and a second	Chigath and a south south at manufactor or same	ł
	30,744	9		co obtain rederat funding for construction,		
	16,534	•	E-76 application	Work with City to prepare Caltrans 5-76 Application required 15-76 application	Obtain E-76 authorization for utilities and R/W	2.14
	-			construction,		
				that outlines overall staging/phasing approach for completing		-
				-Develop high level construction staging approach for project		
				and review with Caltrans and City.		•
	Vajva.	THE COURT PARTY COURT COURT COURT COURT	COLOR RECOGNITY HATHAG BINARIS BIN WALLAND	construction and develop strategies for successful completion	t labour volum organish busis	
Visitation (College)	The second secon		Costo stability more conduction and author	Houselful for construct ability feeting associated with associated	Name of the last o	
Cost	Cost	Note: Assumptions	Deliverables	Description of Key Activities		No.
					Logic Leav manifestion vestionismit induly (vestion regime) 5-05-1	FOOL 163K
					listing and Decempibility Matrix (Deviced Issuery 2021)	DCS.ETack

44.2	44,1,3		44,1,2	44.1.1	44.1		2LVE	3A.11	3A.10.9	3A.10.7	3A.10.6	3A.10.5	3A.10.4	34.10.2	34.10.1	3A.10	3A.9.3					34.5.2	3A.9.1	34.9	3A.8.2							50		34.8	3A.7.3	3A.7.1		3A,6.2		3A.6.1	Task No.
Bridge and Special Design Retaining Wall PS&E	Prepare Droft Specification Special Provisions	The state of the s	Prepare 95% Roadway Quantities and Cost Estimate	Prepare 95% roadway plans	95% Roadway Plans	Switch BERG (BERG) Submitted for Califrant Mork	Emission Certification	Prepare Draft Engineer's Estimate of Probable Construction Cost	Prepare architectural specifications	Prepare structures outline specifications	Prepare has met outline specifications	Prepare utility outline specifications	Prepare electrical outline specifications	Propose traffic outline specifications	Prepare roadway outline specifications	Prepare Outline Specifications	Prepare 53% Utility Plans	Conduct workshops with impacted owners to review comments on relocation plans	issue relocation letters to impacted utility owners	Review relocation plans prepared by impacted 3rd party owners	Owners prepare relocation plans for impacted utilities (by others)	Ошту кометоного	Update conflict maps and matrix based on potholing results	Prepare Utility Plans	Prepare Updated Structures Cost Estimate	Prepare removal plans for existing Shoemaker Bridge	Prepare Retaining Wall Plans	Prepare Bridge Plans (7th Street pas bridge)	Prepare Bridge Plans (bike/ped bridge)	Prepare Bridge Plans (roundabout structure)	Prepare Bridge Plans (IA River span)	Prepare Plans		Bridge and Special Design Retaining Wall Plans (Unchecked Details)	Prepare Materials Report	Prepare Georechnical Design Report	To the state of th	Prepare Quantities Generalization Reports		Propure Plans	PSKE I SKK LISTING RITH OF KANDEN STATE OF THE SKYLLEN TO SKYLLEN SKYL
T. T	dentified as part of Task 3A, 11	design.	Update quantities and cost estimate consistent with updated	Modify roadway design elements to address review		311073000	Cartified Envision specialist to work with project team to incorporate City-directed Envision elements into project design and PS&E mackage	Develop overall engineer's estimate for construction in Caltrans BEES format	The state of the s							Identify SSPs and NSSPs to be included within project	Prepare Littity pians for all work with Cattrans right of way and adjoining local streets in accordance with Caltrans plan formatting requirements					owners in the development of detailed design plans (or necessary relocations (to be prepared by third parties)	Update conflict maps and matrix based on potholing results		Develop quantities and prepare cost estimate for all structural elements							require innecess pans to all wavans and vity inage and retaining walls in accordance with Galtrans plan formathing requirements and develop quantities	The same of the sa				materials reports to support project grading, roadway, and structural design	Prepare draft and final geotechnical, foundation, and			Description of Key Activities
The state of the s	or our place incorporate in programme of the control of the contro		Updated quantity summaries and Engineer's Estimate for	Completed plans with construction details	- Constitution of the Cons		Envision compliance audit documentation	Draft Engineer's Estimate of Probable Construction Cost In BEES format				- Additional and the second se				Outline technical specifications	Culty ayouts	Workshop agenda, minutes, presentation materials, etc.	Notice to Relocate letters	Comments on draft relocation plans	Draft utility relocation plans (by others)		Updated existing utilities base, conflict maps & matrix		Quantity summary, cost estimate	Layouts	General plan, layouts, LOTBs		LOTOS, Grant Gevalls	labutment plans, bent plans, typical section, girder plans,			· · · · · · · · · · · · · · · · · · ·		Draft/Final Materials Report	Draft/Final Seotechnical Design Asport	1-0-0-0-0-0-0-0-0-0-0-0-0-0-0-0-0-0-0-0	Electrical quantity summary	-trectness years	sne	Deliverables
A TOTAL TOTA					AND ADDRESS OF THE PARTY OF THE			Estimate shall be in bees format unless insurvised onlinewise by city.			THE PROPERTY OF THE PROPERTY O	THE PERSONNELLE AND THE PE	A THE STATE OF THE	***************************************	FI OVERS OF SHIRE NEEDS &	Caltrans package will utilize Caltrans Standard Specifications, HDR to		Assume 1 meeting each utility owner, 6 owners					impacted 3rd party owners responsible for development of detailed design			betaled remove plan to be prepared and submitted by controlled, subject to review by the Engineer:	-	1,000	Bridge talk buttele of Coltrant luntsdiction and will be reviewed by City only		HER DONNERS OF THE STATE OF THE	- 4	<u> </u>	upno completion of Caltrans	Ц	The state of the s	The state of the s				Notes/Assumptions
		\$ 76,231	\$ 31,236	\$ 313,394	\$ 386,462	\$ 4,106,071 \$ 11,987	3 11,582	9,400		5 9,833	\$ 2,205	\$ 2,992	\$ 2,433	\$ 4,028	\$ 4,190	5 45,584 6 A 742		21 907	5 5,192	5 7,923	\$ 6,040		34.5	\$ 72,207	\$ 55,709		-			\$ 493,024	\$ 1,427,746		5 3,984,728		\$ 136,302	\$ 1,48,802	74 5.00	\$ 336,702	\$ 9.793	\$ 50,632	Baseline Optional Cost Cost

Attachment 2 Shoemaker Bridge PS&E PS&E Task Listing and Respo insibility Matrix (Revised January 2021)

547	5A,6	54.5	SA.4	Š		6 73	SALLA		SA 1.1.3	3/1.1.2	54.1.1.1	54.1.1		SA.J		44.7	4A.6	4A.S	4A,4	4A.3	40.2.4	4A.2.3	4A.2.2							44.2.1	No.
Envision Contilication	Prepare Survey File	Assist City in preparing bild documents	Prepare Paleontological Mitigation Plan	Prepare Materials Handouts	rispai s neuliusi i. sii ginseri y riss	Branzia Basisant Franciscant IIIa	Update Construction Schedule	THE STATE OF	Prepare Final Specification Special Provisions	Prepare 100% kdadway Quantines and Cost Estimate	Prepare 100% roadway plans	Final Roodway PS&E		Final PS&E	Confident Manager Laborated for Columnia	Envision Certification	Update Transportation Management Plan	Prepare Environmental Commitments Resord (ECR)	Update Storm Water Data Report	Prepare Construction Schedule	Prepare structural calculations	Update structures quantities and cost estimate	Prepare structure specification special provisions	tellusian tenta edissin & alivenimae tenega.	Nonstanderd Retaining Wall Plans	7th Street ped bridge plans	LA River Bike/Ped Structure Plans	Roundabout Structure Plans	Shoemaker Bridge Plans (I.A. River span)	Prepare Checked Structures Plans	Description
Certified Envision specialist to work with project team to incorporate Chydrigeted Envision elements into project design and PS&E package and propage Certification florumentation & Boom to renewarrantific.	Prepare contractor survey file in accordance with Caltrans requirements including roadway cross sections	Assist City in preparing bid documents	Prepare mitigation plan for contractor	Prepare materials handouts in accordance with Caltrans requirements	Licky at Int 114 de després de la constant de la co	Prename RE file in accordance with Cabrans requirements	Revise construction schedule to address City comments and						package and obtain concurrence on disposition -Update/revise Draft PS&E package to address comments received and finalize for approval	Prepare responses to agency comments on 95% submittal	design and PS&E package	Certified Envision specialist to work with project team to incorporate City-directed Envision elements into project	Update Draft TMP to address Caltrans comments and finalize for approval	Prepare ECR to confirm that EIR/EA mitigations have been incorporated into the project design.	Update Storm Water Data Report to address comments received from Caltrans on draft submittal	Prepare draft schedule for project construction	Compile structural design calculations completed as part of structures design development into binders in preparation for submittal to City and Calirans	Update quantities and Engineer's Estimate consistent with 95% design.	Prepare completed draft SSP s and NSSPs for elements identified as part of Task 3A.11		der kombenmen anden betreiten der eine der der der der der der der der der de					Update structures plans to address independent check comments and advance to completion	Description of Key Activities
Envison Certification Compliance Report	Survey file including roadway cross sections		Paleontological Mitigation Plan	Materials handouts	-Flash drive of project CADD files (1 flash drive)	Decident Business of the	Final construction schedule	Provisions, and Engineer's Estimate	Response to comments matrices (one per agency)	Provisions, and Engineer's Estimate	Response to comments matrices (one per agency)					Envision compliance audit documentation	Final TMP	Updated ECR, Environmental commitment tracking system, draft & final report on project compliance	Final Storm Water Data Report	Draft Construction Schedule		Updated structures quantity summaries and Engineer's Estimate for Construction	Draft Structures Specification Special Provisions							Completed structures plans with construction details	Deliverables
								-Bevarder roundsbout structure and LA fixer bridge are Ordinary Non- strandard bridges and podestrian bridges are Ordinary Standard bridges per Callarus SDC. Existing surfax are articipated to be improved for bridge foundation analysis/sesign. -Study/use or base isolation is not included.	Linal Design to be initiated immediately upon 95% PS&E submittal.	AND		- Company Comp												to review by the Engineer,	The best common and the property of the property of the contraction within				-Élevazed roundabout structure and LA River bridge are Ordinary Non- randard bridges and pedestrab bridge are Ordinary Sandard bridge per Caltrans SDC. Essing, solid are anticipated to be improved for bridge foundation analysis/design.	 -independent Check of elevated roundabout and LA River bridges and 95% Design to be initiated immediately upon 65% PS&E submittal. 	Notes/Assumptions
\$ 11,982	\$ 34,040		\$ 7,351	26,045	-	C 41 875	\$ 5,245	,	\$ 32,792					\$ 991,360	4 450 351 5	\$ 11,982	\$ 42,926	\$ 24,794	\$ 18,000	\$ 12,087	\$ 71,553	\$ 15,060	\$	\$ Sanation		79.626		\$ 1,327,873	5 1,799,138	\$ 3,403,452	Cost Cost

	3 6 3 6	38.3.6	38.3.5	38.3.4	3833	38,3.2	383.1	Ç Ç	90	38.2.10	38.2.9	382.8	38.27	38.2.6	38.2.5	38.2.4	36.2.3	38.2.1			36.2		0.0000000000000000000000000000000000000			WW. SERVICE STATES AND SERVICE S								38.7.11	20110			3817			5.1.86			3B,112	38.4.4	38.1		PS&E Package	No.	PS&E Task Li
Pump stotion	Unided in a Buttanasa	contour grading	Lighting & Electrical	Bike path/hardscape	Irrigation	Ländscaping	Drainage/Stormwater	Property Continues on Conjuners Section	Provide Completed and Engineer Commite	Pump station	Wayfinding & signage	Utilities	contour grading	Lighting & Electrical	Bike path/hardscape	iri zation	Landscaping	Seneral Provisions			Prepare Outline Specifications	Salidate press	COLITION	P&ID Plans	Electrical Plans	HVAC Plans	Cathodic Protection	Mechan at	Architectural plans	She Civil, Piping and Force Mains Plans and Details	Demoition Sheets	Seneral Sheets		Prepare Pump Station Plans	Program way finding / Lippang pilang	Sueld Aligh ausdaid	Prepare contour grading plans	Presare Lighting & Electrical Plans	Prepare Irrigation Plans	Prepare Landscaping Plans	Prepare LD Report			Prepare Drainage/Stormwater Plans	Cranya Canard Spiner End Distr	Proper 65% films	Access 1862 A see to make the mark the property than the property of the prope	lty 95&E Package for Pump Station, Landscaping, and Urban Design Work	Description	PS&E Task Listing and Responsibility Matrix (Revised January 2021) Task Task
								consistent with 65% design	Prepare a draft Engineer's Estimate for Construction											be needed to supplement the Green Book Standard Specs	Prepare outline general and technical specifications that will												based upon approved preliminary design prepared in Task 2.8	Prepare plans for proposed relocated SD-1 pump station							facilities are to be incorporated in design package.					Proper coassay pins and evelop quantities for project demants aling within Gry jurisdition in accordance with City plan formatting requirements based upon approved design concepts prepared as part of Tax 2.11.			Description of Key Activities	
								Estimate for Construction	Backup quantity summaries by discipline and Engineer's	- Jeconical Specifications but line capie Summary of reakings required to General Provisions											Draft Outline General and Technical Specifications																				Walt to report	Dept In Section				by value to construction area.			Deliverables	
									Cost estimate format will be agreed upon by City prior to initiating work.							specifications to be included in construction bid package.	-City will be responsible for the preparation of the overall project	edited by HDR to fit this project.	-City will provide boilerplate copy of general provisions to be reviewed and	Book Standard Specifications or special provisions to the Standard	-HDR is responsible for preparing supplemental specifications to the Green															HDR to prepare plans for all City owned utilities including sewer and water.			Hardscape plans assume no mechanical foundains or water features		Complete transfer and and an analysis of the complete analysis of the complete and an analysis of the complete analysis of the complete and an analysis of the complete and an analysis of the complete analysis of the complete analysis of the complete anal	Extraction.	elements only. All street drainage to be covered in other PSEE package. Assumes all runoff is to be conveyed to LB MUST facility or to SD-01 pump.	Includes design of storm drainage and water quality features for park			Station and park elements outside of Calirans jurisdiction	durations against a st salessed the guarantings against the salesses against a	Notes/Assumptions	
30,774	5 6,86	S 4,623		194			£859		5 62,430		51116	2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	, L	5 333	3,938	192	\$ 2,560	(S	9		3 86,580		3,834	a t	2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2		\$ 4,561	\$ 20,02	\$ 37,920	39.91	2 23/0/	\$ 12,114		\$ 209,211	5 47,922	- MONEY		\$ 20,090	34,54			\$ 68.073		\$ 42,787	3 337				Cost	Baseline
4	5	3	2			011111111111111111111111111111111111111	3		9					•			0) 11861 1081 1081 1081 1081				9	\$ 26,356					N CONTROL OF THE PARTY OF THE P	•						1 \$ 26,356	1	•	7							7			•	#ENE 5	Cost	Optional

8 of 11

. c 16677		Sexyet sugarustico automatico servicio de la companya de la compan		PS&R (95%) Submittal for Early Action Utility Relocations	**************************************
113,829	1 1			City PS&E Package for for Early Action Utility Relocations	City PS&E Package for
\$ 27,957		Envision Certification Compliance Report	Certified Envision specialist to work with project years to incorporate City-directed Envision elements into project design and PS&E package and prepare Certification Documentation Report to receive credits.	Evidion Cerdination	58.4 E
25,209	9	Updated/final structures quantity summaries and Engineer's Estimate for Construction	Update quantities and Engineer's Estimate consistent with 100% design.	Pregare final Quantities and Engineers Estimate	58.3 Pr
54,249		final front end and technical specifications	Revise specifications to address agency comments on draft submittal and advance to completion for City approval.	Prepare Final Specifications	
	5			Prepare Pump Station Plans	58.1.9
	3			epare contour grading plans	
				Prepare Lighting & Electrical Plans	
	2			epare: Bike Path/Hardscape Plans	
20,201				epare Landscapling Plans	58.1.3
	5			Prepare Drainage/Stormwater Plans	
			atvance to completion for City approval.	Propare preservitivos and plans:	
373,998 \$ 27,957 294,540	3	Eng (mans for annyma)	per delset Alig at streamed mores seeings at seein some	Final PS&E (100%) Submitted for Pump Station, Landscaping, and Urban Dosign Work	59 Fina
		Envision compliance audit documentation	Certified Envision specialist to work with project team to incorporate City-directed Envision elements into project design and PS&E package.	Emision Certification	
15,139	3			Fump station	
1.882	99			antour gracing	
100 1	5			Lighting & Electrical	
	\$			ike path//hardscape	
	5			andscaping.	4832
5 2,099		an in the second	Add weeds	Drainage/Stormwater	
		Updated quantity summaries and Engineer's Estimate for	Update quantities and Engineer's Estimate consistent with	Prepare Updated Quantitles and Engineers Estimate	
	5			ayrınding ex signage	
1589				confour grading.	
10,344				Ughting & Electrical	
11 440	sperintations to be included in construction and package.			igation	
7,740	City will be responsible for the preparation of the overall project			Landscaping	
11,289	edited by HDR to fit this project.			General/Front end Drainage/Stormwater	48.2.1 48.2.2
	Specifications as well as the bid list.		consistent with 93% design.		
\$ 106,669	HDR is responsible for preparing supplemental specifications to the Green Social Standard Specifications or special provisions to the Standard	Draft front end and technical specifications	Prepare draft front end General Provisions and technical	pare Draft Specifications	
				Prepare Pump Station Plans	48.110
				repare utilities plans	
	S			repare contour grading plans	
	S (The control of the			repaire Dienting & Electrical Plans	
	0 50			repare irrigation Plans	
	S			epare Landscaping Plans	8555
43/785	3	Will include Final LID Report with plans		Prepare General/Front End Plans Prepare Orashaee/Stormwater Plans	48.112
			comments and advance to 95% completion		
5 605,684 \$ 7,968	9,8	Completed plans with construction details	Modify roadway design elements to address review	Initial PS&E (95%) Submittal for Pump Station, Landscaping, and Urban Design Work. Prepare 95% Plans	48 I Init
\$,398 2,388		Envision compliance audit documentation	Certified Envision specialist to work with project team to incorporate City-directed Envision elements into project design and PS&E package.	Envision Certification	38,4
Cost	Notes/Assumptions	Deliverables	Description of Key Activities	Description	ō.

623		6.1,4	6.1.3												6.1.2	6.1,1	6	Ş	5C2.3	5C23	ı	\$012	\$611	£C3	56	\$C3	4C23	4C.Z.Z		Ď	4 C1.2	4011	4C1	No.
Right of Way Mapping Review	Right of Way Appraisal and Acquisition Services	Right of Way Design Support	Prepare ROW/Julilly Certification documents	Prepare Property Acquisition Documents	Prepare Right of Way Maps				Prepare Monument Perpérdation Surveys	Propare Jahol Met Mago "Delor's Condition" Record of Survey	Periori il lano net necovery ana riera (es.		Acoulte Title Reports	Perform Record Data Search	Document Right of Way Requirements	Review Edisting Right of Way Mapping and Suppliement as Necessary	Right of Way Services	Prepare Final Quantities and Engineers Estimate	United Communication of the Co	General/Front end Erosion control	PT-Charte i rinas of conferencies	Prepare utility pians	Prepare General/Front End Plans	Prepare 100% Plans	Final PS&E (190%) Submittal for Early Artion Utility Relocations	Prepare Quantities and Engineers Essimate	Utilities	Epsion control	Connectification and the second secon	Proper Draft Specifications	Prepare utility plans and the country of the countr	Prepare General/Front End Plans		Description
Review appraisal and right of way needs maps to understand		To support R/W requirements, prepare R/W exhibit for each impacted parcel showing R/W needs, cover letters that describe TCE needs, and coordinate with Caltrans on breatration of PD-26 packages for R/W appraisal maps.	To compile required information needed to convey to Caltrans that right of way being transferred to State is free of any encumberances.	Prepare Plats & Legal Descriptions for all right of way needs by parcel	Prepare maps documenting proposed Caltrans rights of way in post-project condition and submit to Caltrans for approval and filing	Setting replacement monuments after construction to effect said perpetuation	-Referencing threatened monuments with tie-outs for perpetuation through construction	-Preparation of lists of monuments threatened with destruction	Activity required by Professional Land Surveyors Act and involves:	Activity required by professional land ourseyors Accided involves production and filing of "Before Condition" Record of Survey.	describe, and tie-in controlling land survey monuments.	requirements.	Obtain title reports for all parcels impacted by proposed R/W	Search ownership of impacted properties, analyze ownership deeds, field notes, and survey maps contained in State,		A Minimum Market		Update quantities and Engineer's Estimate consistent with 100% design.			submittal and advance to completion for City approval.	Health de sanctiment voteste sanctiment de s		Revise plans to address agency comments on 95% design and advance to completion for City approval.		Update quantities and Engineer's Estimate for sewer and water relocations consistent with 95% design.			consistent with 95% design.	Prepare draft front end Seneral Provisions and technical specifications to supplement Green Book Standard Specs			Modify roadway and sewer relocations elements to address review comments and advance to 55% completion.	Description of Key Activities
		Right of way needs exhibits for impacted parcels, cover letters		Plats & Legal Descriptions	<u> </u>				-Ust of threatened existing monuments -Set replacement monuments	recurs of source.	Banny of Circles		Title Reports for impacted properties		-	Updated right of way base mapping	The state of the s	Updated/inst structures quantity summatites and engineers Estimate for Construction				Englisher and and technical coordinations		Final plans for approval		Draft quantity summaries and Engineer's Estimate for Construction				Draft front end and sechnical specifications			Completed plans with	Deliverables
			Right of way cert binder to be prepared in accordance with Caltrans requirements.		The state of the s				Activity assumed to be completed by contractor post- construction.				The second secon			ALLEGATION	- Landstonnest									Cost estimate format will be agreed upon by City prior to initiating work.	one will be responsible for the propagation on the precise project specifications to be included in construction bid package.	edited by HDR to fit this project.	Specifications as well as the bid list. City will provide bollerplate copy of general provisions to be reviewed and	HDR is responsible for preparing supplemental specifications to the Green Book Standard Specifications or special provisions to the Standard	motives y design of sewer and waste religiously divisive or several safety of 2015.		Plans will be formatted in accordance with City plan formatting standards:	Notes/Assumptions
	5 108,379	\$ 62,957							er e				\$ 22,044	20/200		\$ 52,802	\$ 532,807		\$ 3,934	5 648		S 19,140 S 8,998	\$ 7,751	26,890	\$ 36,332	5 232		S	5	5 694	30		IPPES \$	Cost Cost

10 of 11

Attachment 2
Shoemaker Bridge PS&E
PS&E Task Listing and Responsibility Matrix (Revised January 2021)

22,550,235	883,111 21,776,842 \$	Grand Total with Escalation \$				
773,393	264,185 20,893,731 \$	ODC Total S Grand Total S				
773,393	20,629,545 \$					
	22,069	\$	Bid adde⊓da	See task description	Prepare Bid Addenda	8.1.3
	44 046		White a reconnect		AKERIA FIE-DIO INVESSIX	813
	75,882				City Construction Contract	8.2
	19,571	\$	Bid addenda	See task description	Prepare Bid Addenda	8,1,3
	37,129	\$	Written responses		Respond to Bidder Inquiries	8.1.2
	5,491	in t		See task description	Attend Pre-Bid Meeting	8.1.1
	46.731	4		MIS APPOINT MAINS HATCH.	Caltrans Construction Contract	2
				bidding phase of the two construction contracts including		
	138,073	\$		Provide technical support services to the City during the	Bid Support Services	8
	29,954		Grant applications; cost/benefit analysis worksheets, summaries etc.	Assist the City in preparing grant applications to seek funding for construction.	Provide grant application preparation and cost/benefit analysis support services	7.9
	71,328	Assumes public outroach affort will be leafly City.	Meeting emilits, boards, etc.	Provide support to the city in conducting public cultreach services during final design including the use of social media platforms to provide public information and project updates.	Public Outreach and Social Media Support Services	
			Caltrans Encroachment Permit for Construction	L		
	27,569	-Required prior to any ground breaking activities -Application to occur prior to construction	-HDP Permit Application from Port of Long Beach -Construction Work Discharge Permit from the IA Sanitation -District of Los Angeles -Building permit for pump station	HDR will support City in obtaining necessary agreements and approvals from participating 3rd party agency for project construction.	Obtain public agency approvals and agreements for construction	7.7
				part of project either ahead of or as part of construction.		
	15,418	v		and party utility owners for the relocations of their facilities as	Option utility owner approvals and agreements for construction	7.6
	1000	2	Section 214 agreement	_		,
	17,200	\$	Permit requirements technical memorandum, exectured	y with mechanism to fund	Execute Section 214 agreement between City/Metro and USACE	7.5
	12,710	5	Executed cooperative agreement	HDR will support City with execution of cooperative agreement between City and Caltrans for both final design and construction phases of project.	Facilitate execution of cooperative agreement between City and Cultrans	7.4
	158,066	•	401, 404, 408, and 1802 Permit applications and Coastal Development Permit, CZMA Consistency Certification, CDP application for consistency determination		Prepare Environmental Regulatory Permits for Construction	7.3
	16,299	to.	Permit application and secured permit	Permit for discharge of waste and pollutants into surface waters, Issued to maintain quality of surface witers and check that projects to not impact water quality.	Prepare NPDES General Construction Activity Stormwater Permit	7.2
	9,678	W	Encroachment permit applications and executed permits	Allows for access into State right of way by project staff during PS&E phase to conduct field reviews etc.	Prepare Caltrans Encroachment Permit for PS&E phase	7.1
	358,218	9			Permitting Services and Other Support Services	7
	39,439	Assume 10 meetings attended by up to three (3) HDR staff as augmorphise 5		and the best start.	Property owner sportination meetings	628
	5,414			Provide support to City in securing legal possession of	Secura Legal Possession	£
	7,760			Provide support to City in coordinating with escrow company during property purchase process	Extrew Coordination State Control and Cont	625
	11,00%			process (if needed)	Crineminiation Support	0.65
	12.451	2 2		See task description	Frovide support to City in good faith negotiations	6.2.4
	5,414				Coordinate with City in review and approval of offer packages	
	10,202		Property offer packages (1 per property)	See task description	Prepare draft offer packages and submit to City	0
	3,880	9			HDR reviews original appraisal and intendent appraisal review	
	3,880				Appraisal Coordination - Independent Appraisal Review	
	12,001		Property annuals le	Conduct appraisals of impacted properties to determine acquisition costs	Conduct Property Approxisats Annotes Conditions - See Annotes	6.2.2
Cost	Cost	Notes/Assumptions	Deliverables	Description of Key Activities	Pescription Pescription	No.
					Loose lask risking and Responsionity International Asset	PAGE 185K

Exhibit "C-1"
City's Representative is Keith Hoey,
Assistant City Engineer,
562/570-6586
Keith.Hoey@LongBeach.Gov