OFFICE OF THE CITY ATTORNEY ROBERT E. SHANNON, City Attorney 333 West Ocean Boulevard, 11th Floor Long Beach, CA 90802-4664

1

2

3

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

22

23

24

25

26

27

28

RESOLUTION NO. HD- 2498

A RESOLUTION OF THE BOARD OF HARBOR COMMISSIONERS OF THE CITY OF LONG BEACH: CERTIFYING THE FINAL ENVIRONMENTAL REPORT FOR THE MIDDLE HARBOR REDEVELOPMENT PROJECT (SCH No. 2004091010); MAKING CERTAIN FINDINGS AND DETERMINATIONS RELATIVE THERETO: **STATEMENT ADOPTING** OF OVERRIDING **ADOPTING** CONSIDERATIONS: MITIGATION MONITORING AND REPORTING PROGRAM; APPROVING THE PROJECT; ADOPTING THE APPLICATION SUMMARY REPORT AND APPROVING A HARBOR DEVELOPMENT PERMIT

WHEREAS, the City of Long Beach, acting by and through its Board of Harbor Commissioners (Board) has authority over the City of Long Beach's Harbor District, commonly known as the Port of Long Beach; and

WHEREAS, on November 5, 2003, the Deputy Chief Harbor Engineer of the Long Beach Harbor Department submitted an application for a Harbor Development Permit (HDP) for the Port of Long Beach Middle Harbor Redevelopment Project (Project); and

WHEREAS, the Project concerns Piers D, E, and F and would rehabilitate or replace obsolete terminal facilities; provide deeper water at berths and in basins and channels; create new land; modernize marine terminal facilities; and implement environmental controls, including the Port's Green Port Policy and Clean Air Action Plan, expanding the existing 294-acre site, consisting of the Pier E terminal, the Pier F terminal, 18 acres of underutilized land north of the Gerald Desmond Bridge and Ocean Boulevard, and the Berth E24 subsided oil area, into a single, modern 345-acre terminal;

and

WHEREAS, in addition to the HDP, the Project would require the issuance of permits by the U.S. Army Corps of Engineers (USACE) authorizing work and structures in the navigable waters of the United States and the discharge of fill in those waters; and

WHEREAS, the Board is the lead agency for California Environmental Quality Act (CEQA) (Public Resources Code §§ 21,000 *et seq.*) compliance for the Project, and USACE is the federal lead agency for National Environmental Policy Act (NEPA) (42 USC §§ 4341 *et seq.*) compliance for the Project; and

WHEREAS, the Board determined that because the Project could have a significant effect on the environment, an Environmental Impact Report (EIR) should be prepared to assess the environmental impacts associated with the construction and operation of the Project; and

WHEREAS, USACE determined that an Environmental Impact Statement (EIS) should be prepared to assess the environmental impacts associated with the issuance of the federal permits authorizing work and structures in the navigable waters of the United States and the discharge of fill in those waters; and

WHEREAS, the Board and USACE jointly prepared a combined Draft EIS/EIR in the interest of efficiency and to avoid duplication of effort; and

WHEREAS, USACE will consider certification and approval of the EIS separate from the Board's consideration of the EIR; and

WHEREAS, a Notice of Preparation (NOP) of the Draft EIS/EIR was mailed to public agencies, organizations, and persons likely to be interested in the potential impacts of the proposed Project on December 19, 2005, and two public scoping meetings were thereafter held on January 30, 2006, and February 6, 2006, to gather public and agency comments concerning the preparation of the Draft EIS/EIR; and

WHEREAS, the Board and USACE thereafter jointly caused the Draft EIS/EIR to be prepared, which took into account the comments received on the NOP,

described the Project, the environmental impacts resulting therefrom, and the proposed mitigation measures; and

WHEREAS, on May 19, 2008, the Draft EIS/EIR was circulated for public and agency review and comment; and

WHEREAS, public hearings were held on the Draft EIS/EIR on June 11, 2008 and June 18, 2008, which hearings were noticed by publications in the Press-Telegram, a newspaper of general circulation, and by news releases in the Press Telegram, the Business Journal, and the Gazettes, as well as through letters, e-mail blasts, postings on the City's website, and contacts with over 100 organizations; and

WHEREAS, the public comment period, as extended, closed on August 8, 2008; and

WHEREAS, the comments received on the Draft EIS/EIR were reviewed, and full and complete responses thereto were prepared and distributed on April 2, 2009, in accordance with Public Resources Code section 21092.5; and

WHEREAS, the Final Environmental Impact Report (Final EIR) for the Project was presented to the Board, as the decision making body of the lead agency, for certification as having been completed in compliance with the provisions of CEQA and the State and local CEQA Guidelines; and

WHEREAS, the Board has carefully reviewed and considered all environmental documentation comprising the Final EIR, including the Draft EIS/EIR and the comments and the responses thereto, and has found that the Final EIR considers all potentially significant environmental impacts of the proposed project and is complete and adequate, and fully complies with all requirements of CEQA and the State and local CEQA Guidelines; and

WHEREAS, prior to action on this Project, the Board considered all significant impacts, mitigation measures, and Project alternatives identified in the Final EIR and found that all potentially significant impacts of the Project have been lessened or avoided to the extent feasible; and

7.

WHEREAS, CEQA and the CEQA Guidelines provide that no public agency shall approve or carry out a project for which an EIR has been completed that identifies one or more significant effects of the project unless the public agency makes certain written findings for each of the significant effects, accompanied by a statement of facts supporting each finding; and

WHEREAS, CEQA and the CEQA Guidelines require that where an agency approves a project that would allow the occurrence of significant environmental effects which are identified in an EIR, but are not mitigated to a level of insignificance, the agency state in writing the specific reasons supporting its action based on the Final EIR and/or other information in the record; and

WHEREAS, the Board has balanced the benefits of the Project against its unavoidable environmental risks in determining to approve the Project as necessary to serve the existing and future needs of the Port of Long Beach, and has determined that any remaining unavoidable significant impacts are outweighed by specific economic, legal, social, technological or other benefits of the Project.

NOW, THEREFORE, the Board of Harbor Commissioners of the City of Long Beach resolves as follows:

Section 1. <u>Certification</u>. Based on its review and consideration of the Final EIR and all written communications and oral testimony regarding the Project which have been submitted to, and received by, the Port, the Board certifies that the Final EIR for the Project has been completed in compliance with CEQA and the State and local CEQA Guidelines. The Board, having final approval authority over the Project, finds that the Final EIR reflects the Board's independent judgment and analysis as lead agency under CEQA, and hereby adopts and certifies the Final EIR as complete and adequate. The Board further certifies that the Final EIR was presented to the Board and that the Board reviewed and considered the information contained in it prior to approving the Project.

Section 2. <u>CEQA Findings and Statement of Facts</u>. Pursuant to Public

.2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

22

23

24

25

26

27

28

Resources Code section 21081 and CEQA Guidelines section 15091, the Board has reviewed, and hereby makes and adopts, the CEQA Findings of Fact for the Project, attached as and included in Exhibit "A," which is incorporated herein by reference as though set forth in full.

Statement of Overriding Considerations. Pursuant to Public Section 3. Resources Code section 21081 and CEQA Guidelines section 15093, the Board has reviewed and hereby makes and adopts the Statement of Overriding Considerations for the Project, attached as and included in Exhibit "A," which is incorporated herein by reference as though set forth in full.

Mitigation Plan Approval. Although the Final EIR identifies Section 4. certain significant environmental effects that would result from approval of the Project, most environmental effects can feasibly be avoided or mitigated and will be avoided or mitigated by imposition of mitigation measures included in the Final EIR and the Mitigation Monitoring and Reporting Program. Pursuant to Public Resources Code section 21081 and CEQA Guidelines section 15097, the Board hereby adopts and approves the Mitigation Monitoring and Reporting Program for the Project, attached hereto as Exhibit "B," which is incorporated herein by reference as though set forth in full. The Board further finds that the mitigation measures identified in the Final EIR are feasible, and specifically makes each mitigation measure a condition of Project approval.

No Significant New Information Added to Draft EIS/EIR. The Section 5. information provided in the various reports submitted in connection with the Project and in the responses to comments on the Draft EIS/EIR, the information added to the Final EIS/EIR, and the evidence presented in written and oral testimony at public hearings on the Project and the Draft EIS/EIR, do not constitute significant new information that would require recirculation of the Draft EIS/EIR pursuant to Public Resources Code section 21092.1 and CEQA Guidelines section 15088.5.

Section 6. Conformity with Port Master Plan. The Board finds on the basis of the whole record before it that the Project is in conformity with the Port Master

Plan and is consistent with the goals and objectives of the plan.

Section 7. Location and Custodian of Record of Proceedings. The Director of Environmental Planning of the Long Beach Harbor Department, whose office is located at 925 Harbor Plaza, Long Beach, California 90802, is hereby designated as the custodian of the documents and other materials which constitute the record of proceedings upon which the Board's decision is based, which documents and materials shall be available for public inspection and copying in accordance with the provisions of the California Public Records Act (Government Code §§ 6250 et seq.).

Section 8. <u>Notice of Determination</u>. The Director of Environmental Planning shall file a notice of determination with the County Clerk of the County of Los Angeles and with the state Office of Planning and Research within five (5) working days after this approval.

Section 9. <u>Approval of Project, Adoption of Application Summary Report and Approval of Harbor Development Permit.</u> The Board hereby approves the Project, adopts the Application Summary Report, and approves a Level III Harbor Development Permit pursuant to the California Coastal Act, the certified Port Master Plan, and Article XII, Section 1215 of the Long Beach City Charter.

Section 10. <u>Certification, Posting and Filing</u>. The Secretary of the Board shall certify the passage of this Resolution by the Board, shall cause the same to be posted in three (3) conspicuous places in the City of Long Beach, and shall cause a certified copy of this Resolution to be filed forthwith with the City Clerk, at which time it shall take effect.

24 | // 25 | //

I hereby certify that the foregoing Resolution was adopted by the Board of Harbor Commissioners of the City of Long Beach at its meeting of April 13, 2009 by the following vote: Commissioners: Ayes: Noes: Commissioners: Commissioners: Absent: Not Voting: Commissioners: Secretary BJM:arh 04/08/09 #A09-01088

> A09-01088 MIDDLE HARBOR [BJM]

Middle Harbor Redevelopment Project

Findings of Fact and Statement of Overriding Considerations

Prepared By



The Port of Long Beach 925 Harbor Plaza Long Beach, CA 90802


With Assistance From



Science Applications International Corporation 5464 Carpinteria Avenue, Suite K Carpinteria, CA 93013

April 2009






Middle Harbor Redevelopment Project

Findings of Fact and Statement of Overriding Considerations

Prepared by The Port of Long Beach 925 Harbor Plaza Long Beach, CA 90802

With assistance from Science Applications International Corporation 5464 Carpinteria Avenue, Suite K
Carpinteria, CA 93013

April 2009



MIDDLE HARBOR REDEVELOPMENT PROJECT FINDINGS OF FACT and STATEMENT OF OVERRIDING CONSIDERATIONS

1.0 INTRODUCTION

These Findings of Fact have been prepared by the City of Long Beach acting by and through its Board of Harbor Commissioners (POLB or Port) in its capacity as lead agency pursuant to the California Environmental Quality Act (CEQA) to support a decision on the Middle Harbor Redevelopment Project (Project or proposed Project). Section 21081 of the California Public Resources Code and Section 15091 of the CEQA Guidelines provide that no public agency shall approve or carry out a project for which an environmental impact report (EIR) has been certified which identifies one or more significant environmental effects of the project unless the public agency makes one or more written findings for each of those significant effects, accompanied by a brief explanation of the rationale for each finding. The possible findings are:

- 1. Changes or alterations have been required in, or incorporated into, the project, which avoid or substantially lessen the significant environmental effects as identified in the Final EIR.
- 2. Such changes or alterations are within the responsibility and jurisdiction of another public agency and not the agency making the finding. Such changes have been adopted by such other agency or can and should be adopted by such other agency.
- Specific economic, legal, social, technological, or other considerations, including provisions of employment opportunities for highly trained works, make infeasible the mitigation measures or project alternatives identified in the Final EIR.

Additionally, the lead agency must not approve a project that will have a significant effect on the environment unless it finds that specific overriding economic, legal, social, technological, or other benefits of the project outweigh the unavoidable adverse environmental effects. (Pub. Res. Code § 21081(b); 14 Cal. Code Regs. § 15093.) The Statement of Overriding Considerations set forth below identifies the specific overriding economic, legal, social, technological, or other benefits of the project that outweigh the significant environmental impacts identified in the Final EIR.

2.0 MIDDLE HARBOR REDEVELOPMENT PROJECT

2.1 Project Objectives

CEQA requires that an EIR state the objectives of a proposed project to explain the reasons for project development and why this particular solution is being recommended. Additionally, the project objectives are instrumental in determining which alternatives should be considered in the EIR.

The Port's overall goal for the proposed Project is to provide a portion of the facilities needed to accommodate the projected growth in volume of containerized cargo through the Port and to maximize the efficiency and capacity of terminals, while mitigating the impacts of projected growth on the local communities by implementing pollution control measures and all feasible mitigation measures. In order to accomplish these basic goals in a manner consistent with the Port's public trust responsibilities, the objectives of the proposed Project are to:

- 1. Consolidate common operations and wharves of two terminals (Piers E and F) into one terminal;
- 2. Rehabilitate and modernize existing primary Port facilities, including replacement of obsolete and deteriorated wharf structures with adequate, well-equipped wharf areas, along with channels and berths

_

The proposed Project includes project elements that will require federal permits from the U.S. Army Corps of Engineers (USACE). As such, an Environmental Impact Statement (EIS) was also prepared for the proposed Project. The USACE and POLB prepared a joint EIS/EIR in the interest of efficiency and to avoid duplication of effort. The USACE will consider the EIS separate from the Board of Harbor Commissioner's consideration of this EIR.

of sufficient width, length, and depth to allow access to the docks by existing and future cargo vessels, and provide for replacement of obsolete gantry cranes with new generation cranes that are able to reach across the new, larger vessels;

- 3. Implement the Green Port Policy and the San Pedro Bay Ports Clean Air Action Plan (CAAP);
- 4. Provide for efficient terminal traffic flow and cargo handling operations; and
- 5. Link new and improved dock and wharf operations to planned and existing on-dock intermodal railyard facilities and separate on-dock intermodal terminal lead track operations (i.e., loading/unloading and switching) from mainline track operations.

2.2 Project Overview

The Project would rehabilitate or replace deteriorated and obsolete terminal facilities; provide deeper water (-55 feet Mean Lower Low Water [MLLW]) at berths and in basins and channels; create new land; modernize marine terminal facilities; and implement environmental controls, including the Port's Green Port Policy and CAAP, to accommodate a portion of the predicted future increases in containerized cargo volume and the modern, larger cargo vessels that are expected to transport these goods to and from the Port. The existing 294-acre Project site would be increased to 345-acres, including 54.6 net acres of newly created land. The Project includes terminal consolidation, redevelopment, and expansion on areas of existing and newly created land, dredge and fill operations, wharf construction to create three deep water berths with -55 feet MLLW depths, and rail infrastructure improvements (e.g., mainline track realignment at Ocean Boulevard/Harbor Scenic Drive, Pier F Avenue storage yard and tracks, Pier F tail track, and expanding the existing Pier F intermodal railyard). The Project also would include construction of a 66kV substation (Pier E Substation) to provide power that would support Middle Harbor container terminal operations, including supplying shore-to-ship power, and future power needs for other Port facilities.

Project construction would occur in two phases, the first phase in five stages and the second in four stages, and would be scheduled for completion in 2019 (i.e., Project build-out year). However, the proposed Middle Harbor container terminal is forecasted to be fully optimized at maximum capacity by 2025.

When completed, the Project would consist of one consolidated container terminal that would be designed to load and unload containerized cargo to and from marine vessels. When optimized at maximum throughput capacity (by year 2025), the consolidated container terminal would be designed to accommodate approximately 3,320,000 TEUs per year. The proposed expanded Pier F intermodal railyard would handle approximately 26.3 percent (873,160 TEUs per year) of the terminal's expected throughput. Middle Harbor container terminal operations would result in a maximum of approximately 364 vessel calls per year. Truck trips to and from the Middle Harbor container terminal would increase from the 2005 baseline average of 6,528 trips per day to an average of approximately 10,112 trips per day in the year 2030. Approximately 2,098 annual train trips would be required at maximum capacity in 2025 to support Middle Harbor container terminal operations. The terminal would operate under a new lease between the terminal operator and the Port that would include environmental controls imposed pursuant to the Port's Green Port Policy and the CAAP. The proposed Project would include participation in the POLB/POLA Vessel Speed Reduction Program (VSRP) (CAAP measure OGV1) and compliance with applicable U.S. Environmental Protection Agency (EPA), California Air Resource Board (ARB), and South Coast Air Quality Management District (SCAQMD) regulations.

3.0 CEQA FINDINGS

The Findings of Fact are based on information contained in the Final EIS/EIR for the proposed Project, as well as information contained within the administrative record. The administrative record includes, but is not limited to, the Project application, Project staff reports, Project public hearing records, public notices, written comments on the Project, proposed decisions and findings on the Project, and all other documents relating to the agency decision on the Project. When making CEQA findings required by Public Resources Code Section 21081(a), a public agency shall specify the location and custodian of the documents or other material, which constitute the record of proceedings upon which its decision is based. The Director of Environmental Planning of the Long Beach Harbor Department, whose office is located at 925 Harbor Plaza, Long Beach, California 90802, is designated as the custodian of the documents and other materials which constitute the record of proceedings upon which the Board's decision is based, which documents and materials shall be available for

public inspection and copying in accordance with the provisions of the California Public Records Act (Government Code §§ 6250 et seq.).

The Draft EIS/EIR addresses the Project's potential effects on the environment, and was circulated for public review and comment pursuant to the CEQA Guidelines. Comments were received from a variety of public agencies, organizations, and individuals. The Final EIS/EIR contains copies of all comments and recommendations received on the Draft EIS/EIR, a list of persons, organizations and public agencies commenting on the Draft EIS/EIR, responses to comments received during the public review, and identifies changes to the Draft EIS/EIR. This section provides a summary of the environmental effects of the project that are discussed in the EIS/EIR, and provides written findings for each of the significant effects, which are accompanied by a brief explanation of the rationale for each finding.

3.1 Environmental Impacts of the Proposed Project

Less Than Significant Impacts

The EIS/EIR determined that some impacts in the following environmental resource areas would be less-thansignificant prior to mitigation if the proposed Project were implemented:

- 1. Geology, Groundwater, and Soils;
- 2. Air Quality;
- 3. Hydrology and Water Quality;
- 4. Biota and Habitats;
- Ground Transportation;
- Vessel Transportation;
- 7. Land Use:
- 8. Public Services/Health and Safety;
- 9. Noise;
- 10. Hazards and Hazardous Materials;
- 11. Recreation:
- 12. Socioeconomics:
- 13. Cultural Resources; and
- 14. Aesthetics/Visual Resources.

Significant Impacts That Will Be Mitigated

The EIS/EIR determined that some impacts in the following environmental resource areas would be significant but feasibly mitigated with adoption of mitigation measures if the proposed Project were implemented:

- 1. Air Quality;
- 2. Biota and Habitats:
- 3. Ground Transportation;
- Public Services/Health and Safety; and
- 5. Cultural Resources.

Significant and Unavoidable Impacts

The EIS/EIR determined that some impacts in the following environmental resource areas would be significant and unavoidable if the proposed Project were implemented:

- 1. Air Quality;
- 2. Biological Resources;
- 3. Ground Transportation; and
- 4. Noise.

3.2 Findings Regarding Environmental Impacts Determined to be Not Significant or Less Than Significant

The Board of Harbor Commissioners hereby finds that the following environmental impacts of the Project are less than significant. Under CEQA, no mitigation measures are required for impacts that are less than significant (14 Cal. Code Regs. §15126.4(a)(3)).

Resource Area	Impact	Board Finding
Geology, Groundwater, and Soils	GEO-1 : The Project would not substantially alter the topography beyond that resulting from natural erosion and depositional processes.	This impact will be less than significant because the topography in the vicinity of the Project site is flat and not subject to landslides or mudflows, and the Project would not result in alteration of the topography, beyond that resulting from natural erosion and depositional processes.
Geology, Groundwater, and Soils	GEO-2: The Project would not disturb or otherwise adversely affect unique geologic features (e.g., paleontological resources) or geologic features of unusual scientific value.	The Project area is relatively flat and paved, with no prominent geologic or topographic features. The Project would not result in any distinct and prominent geologic, paleontological, or topographic features being destroyed, permanently covered, or materially and adversely modified. Therefore, for the reasons described in Final EIS/EIR Section 3.1.2.3, impacts will be less than significant.
Geology, Groundwater, and Soils	GEO-3: The Project would not accelerate geologic processes, such as erosion.	This impact will be less than significant be- cause runoff of soil during Project construc- tion would be controlled by use of BMPs, as required by either the General Construction Activity Stormwater Permit or a site-spec
Geology, Groundwater, and Soils	GEO-4: The Project site is underlain by the Wilmington Oil Field.	Two oil production areas are present on existing Pier E. Although one of these areas would be abandoned during Project construction, the second area would remain active. Petroleum reserves beneath the site could be accessed from remote locations, using directional (or slant) drilling techniques. Therefore, for the reasons described in Final EIS/EIR Section 3.1.2.3, impacts will be less than significant.
Geology, Groundwater, and Soils	GEO-5: Construction activities may encounter toxic substances or other contaminants associated with historical uses of the Port, resulting in short-term exposure (duration of construction) to construction personnel.	This impact will be less than significant because the contractor would remediate and/or dispose undocumented oil field equipment and/or contaminated soil and groundwater encountered during construction in accordance with all federal, state, and local regulations.
Geology, Groundwater, and Soils	GEO-6: No active faults are located beneath the Project site.	No impact will occur because there are no known active or potentially active faults crossing the Project area that might result in ground rupture and attendant damage to structures, limiting their use due to safety considerations or physical condition.

Resource Area	Impact	Board Finding
Geology, Groundwater, and Soils	GEO-7: Seismic activity along numerous regional faults could produce seismic ground shaking, liquefaction, differential settlement, or other seismically induced ground failure that would expose people and structures to greater than normal risk.	This impact will be less than significant be- cause Project construction would be in ac- cordance with the City of Long Beach Build- ing Code requirements and State-mandated MOTEMS, which would limit the probability of occurrence and the severity of consequences from severe seismically induced ground movement during operations.
Geology, Groundwater, and Soils	GEO-8: Project construction and operation in the Middle Harbor area would not likely expose people and structures to greater than normal risk involving tsunamis or seiches.	Impacts due to seismically induced tsunamis and seiches are typical for the entire California coastline and would not be increased by construction of the proposed Project. However, because the Project elevation is located within 10 to 16 feet above MLLW, there is a risk of coastal flooding due to tsunamis and seiches. Regardless, the likelihood of such an occurrence is extremely low. Therefore, for the reasons described in Final EIS/EIR Section 3.1.2.3, impacts will be less than significant.
Air Quality	AQ-3: The proposed Project would result in operational emissions that exceed SCAQMD thresholds of significance.	Annual average daily emissions from operations of the proposed Project would be less than significant in all project years. The peak daily emissions from operations would be less than significant for all pollutants except NO_x in 2010, which is mitigated to be less than significant.
Air Quality	AQ-5: The proposed Project would not create objectionable odors to sensitive receptors.	This impact will be less than significant because in all future years, the operation of the proposed Project would produce lower diesel combustion products (mainly VOC and PM) and associated odors compared to the CEQA Baseline. Project operational activities would generate air pollutants from the combustion of diesel fuels.
Air Quality	AQ-6: The proposed Project would not expose receptors to significant levels of TACs.	The proposed Project would result in a reduction in cancer risk for all receptor types compared to the CEQA Baseline. While the proposed Project also would result in an increase in non-cancer chronic health effects at the maximum occupational receptor location, the increase would be less than significant. Therefore, for the reasons described in Final EIS/EIR Section 3.2.2.3, this impact will be less than significant.
Air Quality	AQ-7: The proposed Project would not conflict with or obstruct implementation of the applicable AQMP.	This impact will be less than significant because the proposed Project would comply with the 2007 AQMP emission reduction measures that are designed to bring the SCAB into attainment of the national and state ambient air quality standards. It would not conflict with or obstruct implementation of the SIP. See also the conformity analysis in Appendix A-4.
Hydrology and Water Quality	WQ-1.1: Wharf demolition, dredging, and excavation in Slip 3 and Berth F201, and fill in Slip 1 and the East Basin could result in violation of regulatory standards or guidelines.	This impact will be less than significant because in-water construction activities would not create pollution, contamination, a nuisance, or violate any water quality standards. All in-water work would be conducted in accordance with Project-specific permits that include measures to minimize impacts to water quality and monitoring to verify the performance of those measures. Therefore, for the reasons described in Final EIS/EIR Section 3.3.2.3, impacts will be less than significant.

Resource Area	Impact	Board Finding
Hydrology and Water Quality	WQ-1.2: Backland construction activities could result in violation of regulatory standards or guidelines.	This impact will be less than significant because implementation of BMPs (e.g., daily equipment inspection, designated/contained refueling areas, use of drip pans under stationary equipment, all drip pans would be covered during rainfall, and BMP monitoring to ensure compliance) to control runoff of soils and pollutants from general construction activities means that the proposed Project would have only short-term, localized impacts on water quality.
Hydrology and Water Quality	WQ-2: Construction activities would not substantially alter harbor water circulation.	Circulation patterns, tides, and wave action in the Middle to Inner Harbor would change very little as a result of the Project dredging and filling activities. Therefore, for the reasons described in Final EIS/EIR Section 3.3.2.3, impacts will be less than significant.
Hydrology and Water Quality	WQ-3.1: Project construction would not result in increased flooding that would have the potential to harm people or damage property or sensitive biological resources.	Project site elevations would remain generally the same as a result of Project construction, and runoff would be directed to storm drains. This impact will be less than significant because flooding would not be increased by Project construction.
Hydrology and Water Quality	WQ-4.1: Construction activities have the potential to accelerate natural processes of wind and water erosion and sedimentation, resulting in substantial soil runoff or deposition which could not be contained or controlled onsite.	Construction activities would generally not accelerate natural processes of wind and water erosion resulting in soil runoff or deposition that could not be contained or controlled onsite through implementation of BMPs to control runoff. This impact will be less than significant because runoff from general construction activities would have short-term, localized impacts on water quality.
Hydrology and Water Quality	WQ-1.3: Operation of Project facilities could result in violation of regulatory standards or guidelines.	Existing regulatory controls for runoff and storm drain discharges, as implemented by the Port's Stormwater Program, are designed to reduce impacts to water quality; the terminal operator would be required to implement pollution control measures in compliance with the Port's Stormwater Program.
		Potential runoff of pollutants from a large accidental spill to marine waters and sediments would be minimized through existing regulatory controls, which minimize the likelihood of a large spill reaching the marine waters and sediments. The Release Response Plan prepared in accordance with the Hazardous Material Release Response Plans and Inventory Law (California Health and Safety Code, Chapter 6.95), which is administered by the LBFD, also regulates hazardous material activities within the Port. These activities are conducted under the review of a number of agencies and regulations including the USCG, fire department, and state and federal departments of transportation (49 CFR Part 176).
		The small amount of pollutants in discharges from Project vessels would be controlled by existing regulations. Therefore, for the reasons described in Final EIS/EIR Section 3.3.2.3, impacts will be less than significant.

Resource Area	Impact	Board Finding
Hydrology and Water Quality	WQ-3.2: Operation of Project facilities would not result in increased flooding, which would have the potential to harm people or damage property or sensitive biological resources.	Impacts will be less than significant be- cause the likelihood of flooding would not be increased by operations at Project facili- ties.
Hydrology and Water Quality	WQ-4.2: Operations have a low potential to accelerate natural processes of wind and water erosion and sedimentation, resulting in substantial soil runoff or deposition which would not be contained or controlled onsite.	This impact will be less than significant because the reduction in unpaved surface area and the implementation of BMPs to control soil runoff as required by existing regulations would minimize erosion and soil runoff from the Project site.
Biota and Habitats	BIO-1.1: Construction activities would not substantially affect any rare, threatened, or endangered species or their habitat.	Construction activities would result in no loss of individuals or habitat for rare, threatened, or endangered species. Implementation of proposed environmental controls that would require construction contractors to use sound abatement techniques, implement a "soft start" technique, and biological monitoring in the vicinity of pile driving techniques would ensure that sound pressure waves from construction activities in the water would not injure marine mammals. Project-related vessel strikes of blue whales, gray whales, and sea turtles would be unlikely to occur. Therefore, for the reasons described in Final EIS/EIR Section 3.4.2.3, impacts will be less than significant.
Biota and Habitats	BIO-2.1: Construction activities would not interfere with wildlife movement/migration corridors.	No impact will occur because no wildlife movement or migration corridors would be affected by the Project.
Biota and Habitats	BIO-5.1: Dredging, filling, and wharf construction activities would not substantially disrupt local biological communities.	This impact will be less than significant because local benthic, fish, and plankton communities would not be substantially disrupted by the small change in the amount of hard substrate habitat present at the Project site relative to that in the harbor. Short duration turbidity in the water would not exceed water quality standards, and impacts to aquatic biota would be less than significant due to the short duration and small area likely to be affected.
		Runoff of pollutants from backland construction activities would have localized, short-term, and less than significant effects on marine organisms in the vicinity of drain outlets due to implementation of runoff control measures that are part of the Project. Accidental spills from equipment during dredging are unlikely to occur, and any small spills would be cleaned up immediately, resulting in only localized effects. Therefore, for the reasons described in Final EIS/EIR Section 3.4.2.3, impacts will be less than significant.
Biota and Habitats	BIO-1.2: Operations would not substantially affect any endangered, threatened, or rare species or their habitat.	This impact will be less than significant because operational activities would result in no loss of individuals or habitat for rare, threatened, or endangered species, and underwater sound from Project-related vessels would affect few, if any, marine mammals. Vessel collisions with whales or sea turtles in offshore waters are unlikely.

Resource Area	Impact	Board Finding
Biota and Habitats	BIO-2.2: Operations activities would not interfere with wildlife movement/migration corridors.	No impact will occur because no wildlife movement or migration corridors would be affected by the Project.
Biota and Habitats	BIO-3.2: Operation of Project facilities would not substantially reduce or alter marine habitat.	This impact will be less than significant because no marine habitat would be lost or substantially altered as a result of Project operations.
Biota and Habitats	BIO-4.2: Operations of Project facilities could substantially affect a natural habitat or plant community.	Increased vessel traffic and runoff from the terminal during operations would have less than significant impacts on EFH. Operations would have no impacts on natural communities such as kelp, eelgrass beds, salt marsh, and freshwater wetlands. Therefore, for the reasons described in Final EIS/EIR Section 3.4.2.3, impacts will be less than significant.
Biota and Habitats	BIO-5.2: Operation of Project facilities would not substantially disrupt local biological communities.	This impact will be less than significant because operations would not substantially disrupt local biological communities as a result of runoff of contaminants, increased vessel traffic, or lighting.
Ground Transportation	TRANS-3.1: Construction would not increase the demand for transit services.	The only public transit in the vicinity of the Project site is a tourist-oriented line that runs from downtown Long Beach to the Queen Mary. Due to the lack of available public transit options, impacts will be less than significant because use of public transit by construction workers would be negligible.
Ground Transportation	TRANS-4.1: Construction would not result in any increases in rail activity.	This impact will be less than significant because construction-related activities would not use rail services, including the two grade crossings in the Port vicinity. Because the contractor would be required to use construction truck routes that avoid the grade crossings in order to minimize delays (Mitigation Measure TRANS-1.1a), the additional traffic associated with construction would be negligible at the grade crossings.
Ground Transportation	TRANS-3.2: Project operations would not increase the demand for transit services.	This impact will be less than significant because the additional onsite employees would not affect public transit in the Project vicinity. The public does not travel to the Project site. The vehicle traffic generated by the Project will be largely truck traffic that would not involve public transit, and terminal operators currently operate shuttles to transport longshoremen to the terminals when ships arrive. This practice will continue and is part of the Clean Air Action Plan that the Port will continue to enforce through leases with the terminal operators.
Ground Transportation	TRANS-4.2: Project operations would not result in any significant rail impacts.	This impact will be less than significant because the Project-related increase in train trips can be easily accommodated by the Alameda Corridor and regional rail facilities without causing any significant impact. Also, the proposed Project would have a negligible impact on vehicular delays at the two grade crossings in the vicinity of the Project site and at grade crossings in the Inland Empire.

Resource Area	Impact	Board Finding
Vessel Transportation	VT-1.1: Project construction-related marine traffic would not interfere with normal navigational activities within and near the POLB.	This impact will be less than significant because all in-water construction vessel traffic would be subject to established regulatory conditions ensuring safety of users in Long Beach Harbor waters, and activities would be scheduled to avoid existing marine container terminal traffic.
Vessel Transportation	VT-1.2: Project operations would not result in a substantial increase in vessel traffic or a change in patterns of vessel movements that would impair the level of safety for vessels navigating in the Middle Harbor area and/or the precautionary areas.	This impact will be less than significant because the estimated number of Project-related vessel accidents would increase the overall annual average accident rate within the POLB and POLA by only 2.3 percent.
Land Use	LU-1.1: Project construction would be consistent with the adopted goals, objectives, and/or policies of applicable land use plans.	This impact will be less than significant because Project construction would be consistent with the adopted environmental goals and policies contained in the POLB Master Plan (PMP)/California Coastal Act (CCA) and the Coastal Zone Management Act (CZMA).
Land Use	LU-2.1: Project construction would be consistent with the adopted goals, objectives, and/or policies of applicable land use plans.	This impact will be less than significant because Project construction activities would be consistent with surrounding Portindustrial land uses.
Land Use	LU-1.2: Project operations would be consistent with the adopted goals, objectives, and/or policies of the PMP.	This impact will be less than significant because proposed Middle Harbor terminal activities would be consistent with the environmental goals and policies identified in the PMP and the CCA.
Land Use	LU-2.2: Proposed Middle Harbor container terminal activities would be consistent with surrounding Port-related industrial land uses.	This impact will be less than significant because proposed Middle Harbor terminal activities would be consistent with the permitted Port-related industrial land uses identified in the PMP and the CCA/CZMA.
Public Services/Health and Safety	PHS-1.1: Project construction activities would not sufficiently burden existing staff levels and facilities whereby the LBPD would not be able to maintain an adequate level of service.	Standard Maritime Transportation Security Act (MTSA) security measures would remain in place throughout the duration of Project construction, therefore minimizing the burden on Long Beach Police Department (LBPD) staff levels and facilities during proposed container terminal construction activities. Additionally, as the construction activities requiring roadway modifications would be conducted in accordance with the proposed Traffic Management Plan and subject to review and approval by the LBPD, the proposed Project would not impede law enforcement services in the Project area. Therefore, for the reasons described in Final EIS/EIR Section 3.8.2.3, impacts will be less than significant.
Public Services/Health and Safety	PHS-3.1: Project construction would not substantially increase demands on USCG staff levels and facilities.	This impact will be less than significant because the Project would implement standard existing safety precautions governing POLB navigation on all support vessels in the Project area. Proposed Project construction activities would be located within the same operating distance of other facilities served by the USCG and, therefore, would not increase emergency response times.

Resource Area	Impact	Board Finding
Public Services/Health and Safety	PHS-4.1: Project construction would not result in a substantially diminished level of public protection services provided by the SCCC.	This impact will be less than significant because standard security measures would be implemented during construction that would reduce the likelihood of an event occurring that would require Security Command and Control Center (SCCC) services. Implementation of the proposed Traffic Management Plan would ensure advanced coordination with LBPD and Long Beach Fire Department (LBFD) to establish alternative response routes, ensuring continuous access to surrounding areas.
Public Services/Health and Safety	PHS-5.1: Construction activities would not substantially interfere with an existing emergency response or evacuation plan, capable of increasing risk of injury or death.	Project contractors would be required to adhere to all LBFD emergency response and evacuation regulations, ensuring compliance with existing emergency response plans. Therefore, for the reasons described in Final EIS/EIR Section 3.8.2.3, impacts will be less than significant.
Public Services/Health and Safety	PHS-1.2: Project operations would not sufficiently burden existing staff levels and facilities such that the LBPD would not be able to maintain an adequate level of service.	This impact will be less than significant because provisions for security features including terminal security personnel, gated entrances, perimeter fencing, terminal and backlands lighting, camera systems, and additional security feature mandated by the MTSA would reduce the demand for law enforcement.
Public Services/Health and Safety	PHS-3.2: Project operations would not substantially increase demands on USCG staff levels and facilities such that the adequate service levels would be maintained.	This impact will be less than significant because the proposed Project would be located within the same operating distance of other facilities served by the USCG and, therefore, would not increase emergency response times.
Public Services/Health and Safety	PHS-4.2: Project operations would not result in a substantially diminished level of public protection services provided by the SCCC.	Standard security measures would be implemented during Project operation that would reduce the likelihood of an event occurring that would require SCCC services. As land based emergency response does not originate from the SCCC facility, the permanent relocation of site access would not affect SCCC emergency coordination services; all waterside access would be maintained during Project operations. Therefore, for the reasons described in Final EIS/EIR Section 3.8.2.3, impacts will be less than significant.
Public Services/Health and Safety	PHS-5.2: Project operations would not substantially interfere with any existing emergency response plans or emergency evacuation plans.	This impact will be less than significant because the terminal would continue to operate as a container terminal, proposed road improvements would provide additional emergency access, and Project operations would be subject to emergency response and evacuation systems implemented by the LBFD. Project operations would not interfere with any emergency response or emergency evacuation plans.
Noise	NOI-1.2: Project operations would not generate noise levels that would increase ambient noise levels by three dBA.	This impact will be less than significant because operational noise levels associated with the Project (not including contributions from non-Project related growth in traffic) would increase ambient noise levels by a maximum of 0.5 dBA.

Resource Area	Impact	Board Finding
Noise	NOI-2.2: Project operations would not exceed City of Long Beach Municipal Code maximum noise levels.	This impact will be less than significant because future increases in traffic noise levels would not be significantly influenced by the Project. Therefore, Project-related traffic would not result in noise levels that exceed the maximum thresholds allowed by the LBMC.
Noise	NOI-3.1: Project operations would not generate ground vibration levels that would exceed ANSI S3.29-1983 acceptability limits.	Vibration measurements at Site 3 did not indicate a significant difference between ambient ground vibration and ground vibration during train movements on the Port mainline tracks. Measured vibration levels are well below the acceptability curve prescribed by ANSI S3.29-1983. Train movements on the Port mainline tracks associated with Project operations would have a less than significant vibration impact on sensitive receptors at or near Cesar Chavez Park. Therefore, for the reasons described in Final EIS/EIR Section 3.9.2.3, impacts will be less than significant.
Noise	NOI-4.1: Project operations would not increase the number of vibration events that would exceed ANSI S3.29 acceptability limits.	Project operations would substantially increase rail traffic in and out of the Port. Measurements from Site 3 show that ground vibration levels in Cesar Chavez Park produced by each train movement would not exceed the limits prescribed by ANSI S3.29-1983. Therefore, train movements associated with Project operations on the Port mainline tracks would not generate substantial vibration impacts on sensitive receptors at or near Cesar Chavez Park. Therefore, for the reasons described in Final EIS/EIR Section 3.9.2.3, impacts will be less than significant.
Hazards and Hazardous Materials	HAZ-1: Construction activities would not result in an accidental release of hazardous materials from onshore facilities or from vessels that would adversely affect the health and safety of the general public or workers.	This impact will be less than significant because the Project would ensure implementation of standard BMPs, proper use and storage of hazardous materials and petroleum products, and proper removal of ACMs, lead-based paint, and PCBs, in accordance with applicable federal, state, and local regulations.
Hazards and Hazardous Materials	HAZ-2: The Project would not result in noncompliance with state guidelines associated with abandoned oil wells.	Associated oil field infrastructure, such as oil separation facilities, storage tanks, and pipelines (oil, gas, and water) continue to be used on Pier E to support oil and gas production. However, implementation of standard DOGGR measures would reduce adverse health and safety impacts to construction and operational personnel. Therefore, for the reasons described in Final EIS/EIR Section 3.10.2.3, impacts will be less than significant.
Hazards and Hazardous Materials	HAZ-3: Project operations would not substantially increase the probable frequency and severity of consequences to people or property as a result of accidental release of a petroleum product or hazardous substance.	This impact will be less than significant because compliance with applicable federal, state, and local laws and regulations governing the transport of hazardous materials and emergency response to hazardous material spills would minimize the potentials for adverse public health impacts. Therefore, proposed Project operations would not substantially increase the probable frequency and severity of consequences to people or property as a result of a potential accidental release or explosion of a hazardous substance.

Resource Area	Resource Area Impact	
Hazards and Hazardous Materials	HAZ-4: The Project would comply with Risk Management Program policies guiding development within the Port.	No impact will occur because liquid bulk storage facilities are not proposed as part of the Project.
Recreation	REC-1.1: Project construction would not result in a substantial loss or diminished quality of recreational, educational, or visitor-oriented opportunities, facilities, or resources.	This impact will be less than significant because Project construction would not remove or affect existing recreational facilities, including parks and marine recreational opportunities.
Recreation	REC-2.1: Project construction would not result in a demand for recreation and park services that exceeds the available resources.	This impact will be less than significant because no substantial influx of workers in the local communities is anticipated due to the existing sizable local and regional labor pool in the Long Beach area.
Recreation	REC-1.2: Project operation would not result in a substantial loss or diminished quality of recreational, educational, or visitororiented opportunities, facilities, or resources.	The Project site is located in an industrial area that is not generally used for recreational purposes, and the potential for interference with pleasure craft traffic located in the immediate Project area would be nominal. Therefore, for the reasons described in Final EIS/EIR Section 3.11.2.3, impacts will be less than significant.
Recreation	REC-2.2: Project operation would not result in a demand for recreation and park services that exceeds the available resources.	Indirect impacts from the Project on recreational resources resulting from increased employment and housing in the Gateway Cities subregion would be incrementally mitigated through the local housing project permitting process. Therefore, for the reasons described in Final EIS/EIR Section 3.11.2.3, impacts will be less than significant.
Socioeconomics	SOCIO-1.1: The Project would not increase employment in the five-county region by 0.5 percent or more.	This impact will be less than significant because construction-related employment associated with the Project would comprise between 0.003 percent and 0.005 percent of regional employment.
Socioeconomics	SOCIO-2.1: The Project would not increase population in the Gateway Cities subregion by 0.5 percent or more.	This impact will be less than significant because it is likely that most of the construction workers involved already reside in the Gateway Cities subregion and would not migrate to the area and increase the population.
Socioeconomics	SOCIO-3.1: The Project would not increase the demand for housing units in the Gateway Cities subregion by 0.5 percent or more.	This impact will be less than significant because the construction labor force in the region would be sufficient to complete the construction projects without workers migrating to the region. Therefore, no new housing units would be necessary and the construction spending would not impact housing demand.
Socioeconomics	SOCIO-1.2: The Project would not increase employment in the five-county region by 0.5 percent or more.	This impact will be less than significant because the share of employment generated by the Project would only range between zero percent and 0.25 percent.
Socioeconomics	SOCIO-2.2: The Project would not increase population in the Gateway Cities subregion by 0.5 percent or more.	This impact will be less than significant because the additional population through the Gateway Cities would comprise at most 0.3 percent of the total population in each individual city. Therefore, the additional population would not comprise 0.5 percent or more of the region's population,

Resource Area	Impact	Board Finding
Socioeconomics	SOCIO-3.2: The Project would not increase the demand for housing units in the Gateway Cities subregion by 0.5 percent or more.	This impact will be less than significant because the additional housing units that would be demanded in the Gateway Cities subregion would comprise between 0.1 percent in 2010 and 0.4 percent in 2020 and 2025 of the total number of housing units.
Utilities and Service Systems	UTIL-1.1: Project construction activities would result in the extension of new utility line connections to Project sites.	This impact will be less than significant because all demolition of existing utility infrastructure and construction of new infrastructure would be conducted in a manner designed to prevent service interruptions for adjacent tenants, and new construction would be in conformance with current design standards.
Utilities and Service Systems	UTIL-2.1: Proposed Project construction activities would not exceed existing water supply, wastewater, or landfill capacities.	This impact will be less than significant because the proposed Project would result in minimal demands on municipal utilities/service systems during construction activities, including water services, wastewater, and solid waste, that would not exceed existing capacities.
Utilities and Service Systems	UTIL-1.2: Project operations would result in the extension of new utility line connections to the Project site.	This impact will be less than significant because the number of new Project employees and increased terminal electrical demand would not be substantial relative to the existing and projected regional electrical supply.
Utilities and Service Systems	UTIL-2.2: Project operations would not exceed existing water supply, wastewater, or landfill capacities.	This impact will be less than significant because Project operations would represent minimal increases in demands on water supply, wastewater treatment, and solid waste disposal that would no exceed existing capacities.
Cultural Resources	CR-1.1: Project ground disturbances would not impact potentially significant archaeological resources.	Project construction would not reasonably be expected to disturb, damage, or degrade unknown, intact, potentially significant archaeological resources. As the potential for damaging unknown prehistoric remains is remote, potential impacts on ethnographic resources considered significant to contemporary Native Americans are also not reasonably expected. However, in the unlikely event that any archaeological material is discovered during construction, all work would be halted within the vicinity of the archaeological discovery until an assessment of the significance by a qualified archaeologist is completed (Mitigation Measure CR-1.1.1). Therefore, for the reasons described in Final EIS/EIR Section 3.14.2.3, impacts will be less than significant.
Cultural Resources	CR-2.1: The Project would not result in the permanent loss of or loss of access to a paleontological resource.	The artificial fill material within the upland portion of the Project area has no potential to contain intact vertebrate fossils. Similarly, the Middle Harbor in-water area has been historically dredged, and it is reasonable to assume that any intact vertebrate fossils within these dredged areas would have been removed or severely disturbed. Therefore, for the reasons described in Final EIS/EIR Section 3.14.2.3, impacts will be less than significant.

Resource Area	Impact	Board Finding
Cultural Resources	CR-1.3: Industrial reuse of the three potentially relocated historic properties would be consistent with their original Port-related function.	If the two historic properties (i.e., 1953 Smoke Houses/Offices) were relocated within the Port and reused for similar industrial activities, they would be consistent with their original function. If the structures were used for other interpretive purposes illustrating the development of the Port after WWII, this use would also be consistent with their historic significance. Therefore, for the reasons described in Final EIS/EIR Section 3.14.2.3, impacts will be less than significant.
Aesthetics/Visual Resources	VIS-1.1: Project construction activities would not substantially contrast with the existing industrial visual quality of the Project area.	This impact will be less than significant because no substantial contrast with the existing visual quality of the Project site and vicinity would occur during Project construction activities.
Aesthetics/Visual Resources	VIS-2.1: Project construction activities would not adversely impact the existing visual industrial character and quality of the Project site and its surroundings.	This impact will be less than significant because the presence of vessel and land-based equipment over the approximate 10-year construction period would be compatible with the existing industrial character and visual quality of the Project site and surroundings.
Aesthetics/Visual Resources	VIS-3.1: Project construction activities would not create a new source of substantial light or glare that would adversely affect day or nighttime views in the area.	Project construction activities would not occur during the evening hours. Additionally, construction equipment including vessels and land based vehicles would not have reflective surfaces capable of increasing sunlight glare. Therefore, for the reasons described in Final EIS/EIR Section 3.16.2.3, impacts will be less than significant.
Aesthetics/Visual Resources	VIS-1.2: Project development would not substantially contrast with the visual industrial quality of the Project area.	This impact will be less than significant because the change in visual industrial quality of background views from public vantage points would be minor relative to the existing highly industrialized inner Port complex perceived in distant background and closer foreground public views.
Aesthetics/Visual Resources	VIS-2.2: Project development would not substantially degrade the existing industrial character or quality of the site and its surroundings.	This impact will be less than significant because Project development would be consistent with the general industrial nature of the Port and would not introduce incompatible visual characteristics.
Aesthetics/Visual Resources	VIS-3.2: Project development would introduce new glare sources that would potentially degrade existing visual conditions.	The implementation of proposed Environmental Lighting Controls including photo cells/timers, low energy fixtures, and light-spillover reduction features into new terminal lighting would result in less than substantial increases in night light over the Project site and surrounding areas compared to existing levels. Any increase in potential daytime glare resulting from increased massing of terminal structures and containers on the Project site would be minimal. Therefore, for the reasons described in Final EIS/EIR Section 3.16.2.3, impacts will be less than significant.

3.3 Findings Regarding Environmental Impacts Determined to be Mitigated to Less Than Significant Levels

The EIS/EIR identified certain potentially significant effects that could result from the proposed Project. However, the Port finds for each of the significant or potentially significant impacts defined in this section, based upon substantial evidence in the record, that changes or alterations have been required or incorporated into the proposed Project that avoid or substantially lessen the significant effect as identified in the EIS/EIR. As a result, adoption of the mitigation measures set forth below would reduce the identified significant effects to a less than significant level.

3.3.1 Biota and Habitats

As discussed in Final EIS/EIR Section 3.4.2.3, there would be two significant impacts to biota and habitats that would be mitigated to less than significant levels as a result of mitigation measures that have been incorporated into the proposed Project. The impacts and mitigation measures are discussed below.

Impact BIO-3.1: Construction would result in a substantial loss or alteration of marine habitat through filling (in Slip 1, for the Berth E24 extension, and in a portion of the East Basin) and excavation (widening Slip 1 and at Berth F201) for a net loss of 54.6 acres.

Placement of fill would cause a loss of marine habitat, including water surface, water column, soft bottom, and hard substrate. Based on preliminary design, approximately 65.3 acres of marine habitat would be permanently lost (Table 3.3-1) due to fill placement in Slip 1 and the East Basin. Widening Slip 3 would create approximately 6.3 acres of marine habitat, and excavation at Berth F201 would create about 4.4 acres of marine habitat. The net loss of marine habitat would be an estimated 54.6 acres (Table 3.3-1). The exact amount of habitat gain and loss would be calculated by the Port and the agencies who are signatories to the Inter-Agency Bolsa Chica Memorandum of Agreement (MOA) after completion of the Project, on the basis of the "as-built" surveys. Those final figures would not be expected to vary from the above estimates by more than a few acres, so that the final loss of habitat could range from 50 to 60 acres. For this analysis, however, the estimates from the preliminary design are used.

Construction Phase	Location	Marine Habitat Loss/Gain ¹	Inner Harbor	Outer Harbor
1	Slip 1 fill	-25.6	-25.6	
2	East Basin fill	-34.3	-10.0	-24.3
1	Pier E Extension	-5.4		-5.4
Total Habitat Loss		65.3	-35.6	-29.7
1	Slip 3 widening	+6.3	+6.3	_
2	Berth F201 excavation	+4.4		+4.4
Total F	labitat Created	+10.7	+6.3	+4.4
Net Habitat Loss		-54.6	-29.3	-25.3
	oft bottom, and hard substrate. proximate. += gain and -= los			

The rocky dike constructed along Pier D and at Berths E23-E26 would create approximately 14.4 acres of new hard substrate that would partially offset the 16.1-acre loss from the fill placement in Slip 1 and East Basin for a net loss of 1.7 acres. Hard substrate habitat in the form of pilings associated with the wharves in Slip 1 (1,746 piles and fenders), in Slip 3 (805 piles and fenders), and along Pier F (1,071 piles and fenders) in East Basin would also be lost, but 2,707 new pilings would be installed for Berths E23-E26 with over half in the water. The vertical bulkhead in the water along Pier D and Pier E in Slip 3 and along Pier F in Slip 1 would also be removed or covered with fill (total of 5,897 linear feet), and 410 linear feet of bulkhead would be constructed in the water along Pier E. The net effect of these changes would be a loss of hard substrate habitat. The permanent net loss of 54.6 acres of marine habitat in Long Beach Harbor would be a potentially significant impact.

Finding

Unavoidable losses of marine habitat in the Long Beach/Los Angeles Harbor complex are mitigated by the use of habitat credits from mitigation banks created by the two ports. This policy was developed by the USACE, USFWS, NOAA Fisheries, and CDFG in consultation with the ports and has been applied to Port development projects for the past 20 years. The goal of the mitigation policy is "no net loss of in-kind habitat value," where in-kind refers to marine tidal water of value to fish and birds. Given the infeasibility of undertaking any substantial onsite mitigation and the public interest mandate of accommodating maritime cargo conferred upon the Port by the California Coastal Act, offsite mitigation is allowed between Pt. Conception and the Mexican border (area of ecological continuity). Implementation of mitigation measures shall occur prior to or concurrent with Project impact. The preferred mitigation is the restoration of coastal embayment habitat (i.e., tidal wetlands).

Accordingly, the two ports have undertaken several wetlands restoration projects (e.g., Anaheim Bay and Batiquitos Lagoon) that generated habitat mitigation credits. The most recent credits have been generated by funding a multi-agency project to restore tidal wetland habitats in the Bolsa Chica lowlands in Orange County. The credits were vested via the Inter-Agency Bola Chica MOA that was negotiated in 1996 and amended in 2003 to provide in-kind credits for Port fills. The parties to the MOA include NMFS, USFWS, CDFG, USACE, California Coastal Conservancy, Ports of Los Angeles and Long Beach, EPA, California Resources Agency, and CSLC; thus the MOA incorporates all applicable federal and state agencies and their associated mitigation policies.

Recognizing that the credits would be applied to a harbor complex in which habitat quality varies, the Inter-Agency Bolsa Chica MOA also defined how those credits were to be used. Under the MOA, areas of the harbor designated as "Inner Harbor" for habitat mitigation purposes require the application of 0.5 credit to offset each acre of lost habitat, whereas areas designated as "Outer Harbor" require the application of 1.0 credit per acre of loss. The delineation of Inner and Outer Harbor is contained in Exhibit C of the MOA (Figure 3.4-1).

For the proposed Project, habitat credits from restoration of Bolsa Chica would be used to offset the 54.6-acre loss of marine habitat in accordance with the MOA. The entire Slip 1 fill (25.6 acres) and 10.0 acres of the East Basin 34.3-acre fill would constitute Inner Harbor habitat (Table 3.3-2), while the remaining 24.3 acres of East Basin Fill and the 5.4-acre Pier E extension fill would constitute Outer Harbor habitat. Widening Slip 3 would result in the creation of 6.3 acres of Inner Harbor habitat leaving a net loss of 29.3 acres of Inner Harbor habitat. Excavation at Berth F201 would result in the creation of 4.4 acres of Outer Harbor habitat, leaving a net loss of 25.3 acres of Outer Harbor habitat.

Project	Credits ¹	Debits ²	Balance
Projects Prior to 1997	195.2	194.5	0.7
Release of Escrow (1997)	14.0		14.7
Bolsa Chica Initial (1997)	227.0		241.7
Bolsa Chica Subsequent (1997)	40.0		281.7
Slip 2 Pier E 29-acre Fill		14.5	267.2
Pier S/T Mole 22-acre Fill		22.0	245,2
Pier G/J Phase I 10.1-acre Fill		10.1	235.1
Pier T Navy Mole Fill		2.4	232.7
Bolsa Chica 3rh Agreement (2005)	38.0		270.7
Pier G/J Phase 2 39.8-acre fill		19.9 ³	250.8
Middle Harbor 54.6-acre fill		40.0	210.8
Pier S Wharf (dike cut)	9.2		220.0

- Notes:
 - Credits are estimated and may change based on as-built surveys.
 - 2. As of 1997, pursuant to Exhibit C of the Bolsa Chica Interagency MOA, mitigation credits utilized for harbor fills will be deducted at the ratio of 1.0 credit:1.0 acre of fill in the outer harbor, and at the rate of 0.5 credit:1.0 acre of fill in the inner harbor.
 - 3. Mitigated as Inner Harbor per Bolsa Chica MOA.

To mitigate these losses, Bolsa Chica credits would need to be applied as follows: 14.7 credits to mitigate 29.3 acres of Inner Harbor fill at a ratio of 0.5 credit:1 acre of fill and 25.3 credits to mitigate the Outer Harbor fill at a ratio of 1:1, for a total of 40.0 credits. As noted above, the completed Project could result in the use of more or fewer credits, but the difference would only be four or five credits at most, meaning that actual mitigation credits needed would be between 35 and 45. Currently, the Port has approximately 270 Bolsa Chica credits remaining in its account (Table 3.3-2). Therefore, sufficient credits remain in the Port's account to mitigate the marine habitat lost due to construction of the Project even if the as-built survey results show the need for as many as 45 credits.

Changes or alterations have been incorporated into the Project that avoid or substantially lessen the significant environmental effect as identified in the Final EIS/EIR. These changes are set forth in **Mitigation Measure BIO-3** below.

Mitigation Measure BIO-3: The Port would apply approximately 40 credits available in the Bolsa Chica bank to compensate for loss of fish and wildlife habitat due to construction of fill in Slip 1 and East Basin. Implementation of this mitigation measure would occur upon completion of construction of the Project, although permits to begin construction would normally not be issued until the permitting agencies (USACE and POLB for this Project) have received assurance that sufficient mitigation is or will be available. The Final EIS/EIR constitutes that assurance.

Rationale for Finding

Implementation of **Mitigation Measure BIO-3** would fully mitigate the significant loss of marine habitat for aquatic species by replacing the lost habitat. Therefore, impacts to biota and habitats would be less than significant.

Impact BIO-4.1: Construction activities would substantially affect a natural habitat or plant community.

The Project could have effects on Fishery Management Plan (FMP) species that are rare or uncommon, such as California skate, big skate, California scorpionfish, and black rockfish (MEC Analytical Systems, Inc. 2002), although few if any individuals would likely be in the disturbance area. The net loss of marine habitat due to placement of fill and excavation (54.6 acres), however, would result in a substantial loss of habitat for the FMP species that use Middle Harbor, including water column and benthic habitats. Both habitats provide food sources for FMP species occurring in the Project region. Dredging, pile removal, and wharf construction/reconstruction at Berths E23-E27 along with excavation at Berths D29-D31 and F201 also could affect FMP species through habitat disturbance; turbidity and resuspension of contaminants from sediments; and vibration from pile and sheetpile driving and stone column installation. These effects would be temporary and would occur at intervals throughout the construction period, with a return to baseline conditions following construction. Therefore, no permanent loss of habitat would occur from the wharf work, and few, if any, individual fish would be lost because most individuals could avoid the work area.

Construction activities on land would have no direct effects on EFH, which is located in the water. Runoff of sediments from such construction, however, could enter harbor waters. As discussed in Final EIS/EIR Section 3.3.2.3, Hydrology and Water Quality, implementation of sediment control measures would avoid or minimize such runoff.

No kelp, eelgrass beds, salt marsh, or freshwater wetlands are present in the Project area, and those in other parts of the harbor would not be affected by construction activities in the Middle Harbor Project area due to their distance from Middle Harbor and the localized effects of sediment suspended during dredging and filling (Section 3.3). No designated Significant Ecological Areas (SEA), including the least tern nesting site on Pier 400, would be affected by the Project.

Filling of Slip 1 and part of East Basin would result in a permanent loss of EFH in Middle Harbor, a significant impact

Finding

Mitigation Measure BIO-3 would apply to this impact. Mitigation of the fill impacts would be by the use of approximately 40 existing mitigation credits. This mitigation measure would fully offset Project impacts to sustainable fisheries.

Rationale for Finding

Implementation of **Mitigation Measure BIO-3** would fully mitigate the significant loss of EFH by replacing the lost habitat. Therefore, impacts to biota and habitats would be less than significant.

3.3.2 Ground Transportation

As discussed in Final EIS/EIR Section 3.4.2.3, there would be one significant impact to ground transportation that would be mitigated to a less than significant level as a result of mitigation measures that have been incorporated into the proposed Project. The impacts and mitigation measures are discussed below.

Impact TRANS-1.1: Construction would result in short-term, temporary increases in auto and truck traffic at certain study intersections.

Construction would have significant impacts at the following study intersections:

- Pico Avenue/Pier G Avenue and Harbor Plaza (2010);
- Pico Avenue and Pier E Street/Ocean Blvd. EB On- and Off-Ramps (2020); and
- Pico Avenue and Pier D Street (2020)

Finding

Changes or alterations have been incorporated into the Project that avoid or substantially lessen the significant environmental effect as identified in the Final EIS/EIR. These changes are set forth in **Mitigation Measure TRANS-1.1a** through **TRANS-1.1e** below. Implementation of **Mitigation Measure TRANS-1.1a** further refines the environmental control identified in Final EIS/EIR Section 1.7.3.

Mitigation Measure TRANS-1.1a: Prior to beginning construction, the construction contractor shall prepare a detailed traffic management plan, which in addition to work shift start/end times, shall include the following: detour plans, coordination with emergency services, coordination with adjacent property owners and tenants, advanced notice of temporary parking loss, identification of temporary parking replacement or alternative adjacent parking within a reasonable walking distance, use of designated haul routes, use of truck staging areas, observance of hours of operations restrictions and appropriate signing for construction activities. The traffic management plan shall be submitted to Port of Long Beach for approval before beginning construction.

Mitigation Measure TRANS-1.1b: Consistent with City of Long Beach Public Works Department practice, the construction-related traffic to/from the Project site shall be restricted during morning and afternoon peak commute hours. Furthermore, no closure of major road corridors shall be permitted as a result of construction activities.

Mitigation Measure TRANS-1.1c: The Port shall install a signal at the intersection of Pico Avenue and Pier E Street/Ocean Blvd EB On- and Off-Ramps.

Mitigation Measure TRANS-1.1d: The Port shall install a signal at the intersection of Pico Avenue and Pier D Street.

Mitigation Measure TRANS-1.1e: The Port shall install a signal at the intersection of Pico Avenue/Pier G Avenue and Harbor Plaza.

Because **Mitigation Measures TRANS-1.1c** and **TRANS-1.1e** are local measures, construction work related to these improvements could be completed primarily during the off-peak hours. Therefore, there would not be any secondary impacts associated with the construction of these mitigation measures.

Rationale for Finding

Implementation of **Mitigation Measures TRANS-1.1a through TRANS-1.1e** would fully mitigate significant impacts on intersections. Therefore, impacts would be less than significant.

Impact TRANS-1.2: Additional traffic generated by the Project would have significant impacts at certain study area intersections.

The proposed Project would have significant impacts at the following four study area intersections:

- Pico Avenue/Pier G Avenue and Harbor Plaza;
- Pico Avenue and Pier E Street/Ocean Blvd EB On- and Off-Ramps;
- Pico Avenue/Ocean Blvd WB Off-Ramp; and
- Pico Avenue and Pier D Street.

Finding

Changes or alterations have been incorporated into the Project that avoid or substantially lessen the significant environmental effect as identified in the Final EIS/EIR. These changes are set forth in **Mitigation Measure TRANS-1.1a** through **TRANS-1.1e** below. Implementation of **Mitigation Measure TRANS-1.1a** further refines the environmental control identified in Final EIS/EIR Section 1.7.3.

Mitigation MeasureTRANS-1.1a: Prior to beginning construction, the construction contractor shall prepare a detailed traffic management plan, which in addition to work shift start/end times, shall include the following: detour plans, coordination with emergency services, coordination with adjacent property owners and tenants, advanced notice of temporary parking loss, identification of temporary parking replacement or alternative adjacent parking within a reasonable walking distance, use of designated haul routes, use of truck staging areas, observance of hours of operations restrictions and appropriate signing for construction activities. The traffic management plan shall be submitted to Port of Long Beach for approval before beginning construction.

Mitigation MeasureTRANS-1.1b: Consistent with City of Long Beach Public Works Department practice, the construction-related traffic to/from the Project site shall be restricted during morning and afternoon peak commute hours. Furthermore, no closure of major road corridors shall be permitted as a result of construction activities.

Mitigation MeasureTRANS-1.1c: The Port shall install a signal at the intersection of Pico Avenue and Pier E Street/Ocean Blvd EB On- and Off-Ramps.

Mitigation MeasureTRANS-1.1d: The Port shall install a signal at the intersection of Pico Avenue and Pier D Street.

Mitigation MeasureTRANS-1.1e: The Port shall install a signal at the intersection of Pico Avenue/Pier G Avenue and Harbor Plaza.

Because **Mitigation Measures TRANS-1.1c**, **TRANS-1.1d**, **and TRANS-1.1e** are local measures, construction work related to these improvements could be completed primarily during the off-peak hours. Therefore, there would not be any secondary impacts associated with the construction of these mitigation measures.

Rationale for Finding

Implementation of **Mitigation Measures TRANS-1.1a through TRANS-1.1e** would fully mitigation significant impacts on intersections. Therefore, impacts would be less than significant.

3.3.3 Public Services/Health and Safety

As discussed in Final EIS/EIR Section 3.8.2.3, there would be two significant impacts to public services/health and safety that would be mitigated to less than significant levels as a result of mitigation measures that have been incorporated into the proposed Project. The impacts and mitigation measures are discussed below.

Impact PHS-2.1: Project construction activities would require upgrades to existing antiquated fire protection facilities to maintain acceptable emergency response times.

Development of the proposed Project would not substantially increase the occurrence or risk of fire or other emergencies. It would, however, require the removal and relocation of fire hydrants and water supply trunk lines and distribution mains in the Project area. This would have the potential to temporarily interrupt fire water supplies in the Project area. However, utility relocations frequently occur during POLB terminal developments; these activities are typically conducted with minimal, if any, disruptions in service. Prior to Project construction, removal and relocation of fire hydrants and water supply trunk lines and distribution mains would be subject to review and approval by the LBFD and/or jurisdictional agencies to ensure that adequate fire flow water supplies within the Project vicinity would be provided. The LBFD would be notified in advance and afforded the opportunity to review and comment on Project features affecting fire suppression infrastructure. In addition, the Project would be designed and constructed according to all applicable state and local codes and ordinances to ensure adequate fire protection. The LBFD would conduct a fire-life-safety review during the design review process to assess the required fire flow for the Project. However, as the existing antiquated facilities at Stations 15 and 20 affect LBFD's ability to provide acceptable emergency response times, Project construction activities would further exacerbate inadequate fire service response times.

Proposed roadway modifications would restrict and/or temporarily remove access to roadways in the Project vicinity. These roadway modifications would include realignment of Harbor Scenic Drive, construction of mainline track under Ocean Boulevard, modification to Pier F Avenue, and construction of a loop road around the track on Pier F. The proposed Pier F loop road would provide an alternate vehicular emergency access route. However, proposed construction activities requiring roadway modifications would potentially result in the temporary interruption and/or delays for fire emergency response services.

The Port would prepare a Traffic Management Plan (Final EIS/EIR Section 1.7.3) as part of the proposed Project. This plan would ensure advanced coordination with LBFD to establish alternative fire and emergency response access routes, ensuring continuous access to surrounding areas. Although construction activities requiring roadway modifications would not substantially burden LBFD, proposed construction activities would further exacerbate existing inadequate emergency response times. Therefore, impacts on fire services would be potentially significant.

Finding

Changes or alterations have been incorporated into the Project that avoid or substantially lessen the significant environmental effect as identified in the Final EIS/EIR. These changes are set forth in **Mitigation Measure PHS-2.1** below.

Mitigation Measure PHS-2.1: The Port shall enter into a mitigation agreement to upgrade existing facilities at Stations 15 and 20. The Port shall submit proof to the City of Long Beach that an agreement has been executed prior to commencement of construction activities.

Rationale for Finding

Implementation of **Mitigation Measure PHS-2.1** would ensure upgrades to existing LBFD facilities that would be required to ensure acceptable LBFD emergency response times. Accordingly, construction activities would not substantially burden the LBFD, and adequate emergency response services would occur during construction. Therefore, impacts would be less than significant.

Impact PHS-2.2: Project operations would require upgrades to existing antiquated fire protection facilities to maintain acceptable emergency response times.

Proposed Project fire infrastructure would be designed in accordance with applicable City of Long Beach Fire Codes and state codes. Fire protection features (e.g., fire hydrants and water supply trunk lines) would be incorporated into the design process of the proposed terminal, Project operations would not substantially increase the demand for fire protection services. Furthermore, construction of the Pier F tail track would result in a loop road that extends around the track on Pier F. This roadway would provide an alternate vehicular emergency access route, therefore improving fire and emergency access during Project operation. However, the existing antiquated facilities at Stations 15 and 20 would affect LBFD's ability to provide acceptable emergency response times. Although the proposed Project would not result in substantial operational demands on fire protection services, Middle Harbor container terminal operations would further exacerbate inadequate emergency response times in the Project area. Therefore, impacts would be potentially significant.

LBFD would be notified in advance and afforded the opportunity to review and comment on proposed Project design plans to ensure adequate provisions for emergency circulation throughout Middle Harbor, including roadway width, turning radii, and staging areas for emergency equipment.

Finding

Mitigation Measure PHS-2.1 would apply to this impact.

Rationale for Finding

Implementation of **Mitigation Measure PHS-2.1** would ensure upgrades to existing LBFD facilities that would be required to ensure acceptable LBFD emergency response times. Accordingly, Middle Harbor container terminal activities would not substantially burden the LBFD, and adequate emergency response services would occur during Project operations. Therefore, impacts would be less than significant.

3.3.3 Cultural Resources

As discussed in Final EIS/EIR Section 3.14.2.3, there would be one significant impact to cultural resources that would be mitigated to a less than significant level as a result of a mitigation measure that has been incorporated into the proposed Project. The impact and mitigation measure is discussed below.

Impact CR-1.2: Construction activities would adversely impact potentially significant historic architectural resources.

Two potentially significant historic architectural resources, including the two 1953 Smoke Houses/Offices, are located within the proposed terminal area. Both resources would be relocated during Project construction. This would be a significant impact on historic resources.

Finding

Changes or alterations have been incorporated into the Project that avoid or substantially lessen the significant environmental effect as identified in the Final EIS/EIR. These changes are set forth in **Mitigation Measure CR-1.2.1** below.

Mitigation Measure CR-1.2.1: The two historic architectural resources shall be temporarily moved during construction and then relocated to another suitable location within the Project area subsequent to construction under the direction of a qualified Architectural Historian. A survey shall be conducted after the relocation to document, identify, and describe any internal and external cracking, condition of walls, and other elements as a result of their movement. The survey shall be undertaken under the direction of a qualified Architectural Historian and shall be in accordance with accepted standard methods. A written report documenting conditions after Project completion shall be prepared under the supervision and approval of a qualified Architectural Historian. The report shall provide any necessary measures to address stabilization and repair of areas that have been disturbed during relocation, including photo-documentation. The repairs shall be undertaken by the Port in a timely manner.

Rationale for Finding

The two Smoke Houses were designed to be moved as needed, so relocating them within the Project area would not result in a loss of their historical context. Therefore, impacts on historic architectural structures would be less than significant with implementation of **Mitigation Measure CR-1.2.1**.

3.3.4 Air Quality

As discussed in Final EIS/EIR Section 3.2.2.3, there would be one significant impact to air quality that would be mitigated to less than significance as a result of mitigation measures that have been incorporated into the proposed Project. The impact and mitigation measures are discussed below.

Impact AQ-3: The proposed Project would result in operational emissions that exceed SCAQMD thresholds of significance.

On a peak day, operation of the proposed Project prior to mitigation would result in NO_x emissions in 2010 (although not in subsequent years) that exceed SCAQMD thresholds. As a result, the unmitigated Project would produce significant peak daily NO_x emissions in 2010.

Finding

Mitigations have been incorporated into the Project that avoid or substantially lessen its significant environmental effect as identified in the Final EIS/EIR. These changes are set forth in **Mitigation Measures AQ-4**, AQ-5, AQ-6, AQ-7, AQ-7a, AQ-8, AQ-9, AQ-10, AQ-11, AQ-25, and AQ-26 below.

Mitigation Measure AQ-4: Expanded VSRP. All OGV that call at the Middle Harbor container terminal shall comply with the expanded VSRP of 12 knots from 40 nm, that is, from Point Fermin to the Precautionary Area. This measure equates to CAAP measure OGV1.

Mitigation Measure AQ-5: Shore-to-Ship Power ("Cold Ironing"). OGV that call at the Middle Harbor container terminal shall utilize shore-to-ship power while at berth. Lease stipulations shall include consideration of alternative technologies that achieve 90 100 percent of the emission reductions of cold-ironing. Three new berths with the capacity to cold-iron OGV would become available according to the following Project construction schedule: (1) December 2009; (2) March 2012; and (3) December 2014. This measure is consistent with CAAP measure OGV2.

Mitigation Measure AQ-6: Low-sulfur Fuels in OGV. All OGV shall use 0.2 percent or lower sulfur MGO fuel in vessel auxiliary and main engines at berth and out to a distance of 40 nm from Point Fermin, or implement equivalent emission reductions. This measure equates to CAAP measures OGV3 and OGV4.

Mitigation Measure AQ-7: Container Handling Equipment. All Project CHE shall meet the following performance standards. This measure equates to CAAP measures CHE1: By the end of 2010, all yard tractors shall meet, at a minimum, the EPA non-road Tier 4 engine standards;

- By the end of 2012, all pre-2007 on-road or pre-Tier 4 non-road top picks, forklifts, reach stackers, RTGs, and straddle carriers less than 750 Hp shall meet, at a minimum, the EPA non-road Tier 4 engine standards; and
- By the end of 2014, all CHE with engines greater than 750 Hp shall meet, at a minimum, the EPA Tier 4 non-road engine standards. Starting in 2009 (until equipment is replaced with Tier 4), all CHE with engines greater than 750 Hp shall install the cleanest available VDEC, as established by the ARB.

Mitigation Measure AQ-7a: High Efficiency Rail Mounted Gantry (RMG) Cranes. The Project terminal operator shall replace all diesel-powered RTGs with electric-powered RMGs, as soon as feasible, but no later than the completion of construction in 2020. Each RMG shall include high efficiency, regenerative drive systems.

Mitigation Measure AQ-8: Heavy-Duty Trucks. Container trucks that call at the Middle Harbor container terminal shall comply with the following replacement schedule as part of the POLB Clean Truck Program tariff. This measure goes beyond the ARB's requirements for reducing truck emissions. It is similar to CAAP measure HDV1 (Clean Trucks Program), however it is more stringent and would result in the following:

- Ban pre-1989 trucks by 10/1/2008;
- Ban 1989-1993 trucks by 1/1/2010;
- Ban un-retrofitted 1994-2003 trucks by 1/1/2010; and
- Ban all trucks that do not meet the EPA 2007 Heavy-Duty Highway Rule emission standards by 1/1/2012.

Under **Mitigation Measure AQ-8**, the truck emission reductions were analyzed assuming all engines would continue to burn diesel. This is conservative as the CTP proposed has a goal that 50 percent of the trucks funded through the CTP be alternative-fueled trucks,, which would result in lower emissions for the mitigated Project than analyzed.

Although not quantified in the analysis of the mitigated Project operational emissions, the following would result in reductions in criteria pollutant emissions from Project operations.

Mitigation Measure AQ-9: Clean Rail yard Standards. The expanded Pier F intermodal rail yard shall incorporate the cleanest locomotive technologies into its operations. Technologies that reduce fuel consumption or use alternative fuels would reduce criteria pollutant emissions. These include diesel-electric hybrids, multiple engine generator sets, use of alternative fuels, and idling shut-off devices. Because some of these systems are not yet available, but are expected to be available within the next few years, this measure has not been quantified. However, implementation of this measure would reduce the Project's criteria pollutant emissions by less than 0.1 percent.

Mitigation Measure AQ-10: Truck Idling Reduction Measures. The Middle Harbor container terminal operator shall minimize on-terminal truck idling and emissions. Potential methods to reduce idling include, but are not limited to (1) maximize the durations when the main gates are left open, including during off-peak hours, and (2) implement a container tracking and appointment-based truck delivery and pick-up system to minimize fuel consumption and resulting criteria pollutant emissions. The estimate of unmitigated on-terminal trucking emissions considered the efficiencies of movement designed into the proposed Middle Harbor container terminal and, therefore, assumed a low rate of onterminal idling. Nevertheless, additional design measures proposed in Mitigation Measure AQ-10 would further reduce on-terminal truck activities and associated criteria pollutant emissions. However, this measure was not quantified.

Mitigation Measure AQ-11: Slide Valves on OGV Main Engines. OGVs that call at the Project container terminal shall have slide fuel valves installed on their main engines, or implement an equivalent emission reduction technology. This retrofit is most applicable to OGVs with MAN B&W engines. This technology would reduce emissions of VOC, NO_x , and DPM from OGV main engines.

Mitigation Measure AQ-25: Periodic Technology Review. To promote new emission control technologies, the tenant shall implement in 2015 and every 5 years following the effective date of the lease agreement, a review of new air quality technological advancements, subject to mutual agreement on operational feasibility, technical feasibility, and cost-effectiveness and financial feasibility, which agreement shall not be unreasonably withheld. If a technology is determined to be feasible in terms of cost, technical and operational feasibility, the tenant shall work with the Port to implement such technology.

Mitigation Measure AQ-26: Cargo Throughput Monitoring. Every five years, the Port shall compare actual cargo throughput that occurred at the terminal to the cargo assumptions used to develop the Final EIS/EIR. The years used in this analysis shall include 2015, 2020, 2025, and 2030. The Port shall calculate annual air emissions associated with these throughput levels (for OGVs, assist tugs,

locomotives, cargo handling equipment, and trucks) and compare them to the annual air emissions presented in the Final EIS/EIR. If actual emissions exceed those presented in the Final EIS/EIR, then new/additional mitigations would be applied through Mitigation Measure AQ-25.

Rationale for Finding

Implementation of **Mitigation Measures AQ-4 through AQ-8** would reduce the emissions from proposed Project operations from unmitigated levels. Although not quantified in the analysis, **Mitigation Measures AQ-7a, AQ-9 through AQ-11, AQ-25, and AQ-26** would further reduce combustive emissions. With these mitigation measures, peak daily Project operations would produce less than significant emissions of NO_x in 2010. Thus, there would be no significant impacts from operations.

3.4 Findings Regarding Significant Environmental Impacts that Cannot be Mitigated to a Less Than Significant Level

The EIS/EIR identified certain potentially significant effects that could result from the proposed Project. The Port finds for each of the significant impacts identified in this section, based upon substantial evidence in the record, that changes or alterations have been required or incorporated into the proposed Project that substantially lessen the significant effects as identified in the Final EIS/EIR. However, even with adoption of the mitigation measures set forth below, Project impacts are not reduced below a level of significance.

Attachment A contains a list of comments received on the Draft EIS/EIR that contain suggested mitigation measures and/or alternatives suggested to reduce significant and unavoidable impacts. The discussion below refers to Attachment A and indicates whether the proposed mitigation measures and/or alternatives have been added to the Final EIS/EIR and/or incorporated into the Project. It has determined that certain proposed mitigation measures and/or alternatives are infeasible in light of specific economic, legal, social, technological, and other considerations and, therefore, have not been incorporated into the Project. The evidence of such infeasibility is explained in Attachment A.

3.4.1 Air Quality

As discussed in Final EIS/EIR Section 3.2, there would be four significant impacts to air quality as a result of the proposed Project during construction and operation that would remain significant and unavoidable.

Impact AQ-1: Proposed Project construction would produce emissions that exceed SCAQMD emission significance thresholds.

During a peak day of activity, Project construction would produce levels of VOC, CO, NO_x , PM_{10} , and $PM_{2.5}$ emissions that exceed SCAQMD daily emission thresholds. These levels would represent significant air quality impacts.

Finding

The Board of Harbor Commissioners hereby finds that changes or alterations have been incorporated into the project that avoid or substantially lessen the significant environmental effect identified in the Final EIS/EIR. These changes are set forth in **Mitigation Measures AQ-1**, **AQ-2**, **AQ-2a**, **AQ-2b**, **AQ-3**, and **AQ-3a** below.

Mitigation Measure AQ-1: **Additional Fugitive Dust Controls.** The calculation of unmitigated fugitive dust emissions from Project earth-moving activities is based on Project compliance with SCAQMD Rule 403, which is assumed to produce a 75 percent reduction in PM $_{10}$ emissions from uncontrolled levels to simulate rigorous watering of the site and use of other measures. To provide a 90 percent reduction of fugitive dust emissions from uncontrolled levels, the Project construction contractor shall develop and implement dust control methods that shall achieve this control level in a SCAQMD Rule 403 dust control plan; and designate personnel to monitor the dust control program and order increased watering, as necessary, to ensure a 90 percent control level. Their duties shall include holiday and weekend periods when work may not be in progress.

Additional control measures to reduce fugitive dust shall include, but are not limited to, the following:

- Apply approved non-toxic chemical soil stabilizers according to manufacturers' specifications
 to all inactive construction areas or replace groundcover in disturbed areas;
- Provide temporary wind fencing around sites being graded or cleared;
- Cover truck loads that haul dirt, sand, or gravel or maintain at least two feet of freeboard in accordance with Section 23114 of the California Vehicle Code;
- Install wheel washers where vehicles enter and exit unpaved roads onto paved roads, or wash off tires of vehicles and any equipment leaving the construction site;
- Suspend all soil disturbance activities when winds exceed 25 mph as instantaneous gusts or when visible dust plumes emanate from the site, and stabilize all disturbed areas;
- Appoint a construction relations officer to act as a community liaison concerning on-site construction activity including resolution of issues related to PM₁₀ generation;
- Sweep all streets at least once a day using SCAQMD Rule 1186.1 certified street sweepers
 or roadway washing trucks if visible soil materials are carried to adjacent streets (recommend
 water sweepers with reclaimed water);
- Apply water three times daily, or non-toxic soil stabilizers according to manufacturers' specifications, to all unpaved parking or staging areas or unpaved road surfaces;
- Pave road and road shoulders; and
- Apply water three times daily or as needed to areas where soil is disturbed.

Mitigation Measure AQ-2: **Emission Controls for Non-road Construction Equipment**. Although not quantified in the analysis, to reduce combustive emissions, construction equipment shall meet the EPA Tier 4 non-road engine standards, where feasible. The Tier 4 standards become available starting in year 2012.

Mitigation Measure AQ-2a: Best Management Practices (BMPs) for Construction Equipment. The construction contractor shall implement the following BMPs on construction equipment, where feasible, to further reduce emissions from these sources:

- Use of diesel oxidation catalysts and/or catalyzed diesel particulate traps, as feasible;
- Maintain equipment according to manufacturer specifications;
- Restrict idling of equipment and trucks to a maximum of 5 minutes (per ARB regulation);
- Use of high-pressure fuel injectors on diesel-powered equipment; and
- Use of electricity from power poles rather than temporary diesel- or gasoline-powered generators.

Mitigation Measure AQ-2b: **Construction Traffic Emission Reductions**. The construction contractor shall implement the following measures to further reduce emissions from construction:

- Trucks used for construction (a) prior to 2015 shall use engines certified to no less than 2007 NO_x emissions levels and (b) in 2015 and beyond shall meet USEPA 2010 emission standards;
- Provide temporary traffic control such as flag person, during all phases of construction to maintain smooth traffic flow;
- Schedule construction activities that affect traffic flow on arterial systems to off-peak hour where possible;
- Re-route construction trucks away from congested streets or sensitive receptor areas;
- Provide dedicated turn lanes for movement of construction trucks and equipment on- and offsite;

- Configure construction parking to minimize traffic interference;
- Improve traffic flow by signal synchronization;
- All vehicle and equipment will be properly tuned and maintained according to manufacturer specification; and
- Reduce traffic speeds on all unpaved roads to 15 miles per hour or less.

Mitigation Measure AQ-3: **Emission Controls for Construction Tugboats**. The unmitigated Project analysis assumes partial implementation of Tier 2 engine standards on construction tug boats. Although not quantified in the analysis, to reduce combustive emissions, all tug boats used in construction shall meet the EPA Tier 2 marine engine standards, and if feasible use construction tugs that meet the EPA Tier 3 marine engine standards. The Tier 3 standards become available starting in year 2009.

Mitigation Measure AQ-3a (Added to Final EIS/EIR): Construction Tugboat Home Fleeting. The construction contractor shall require all construction tug boats that home fleet in the San Pedro Bay Ports to (a) shut down their main engines and (b) refrain from using auxiliary engines while they are at docked or to use electrical shore power, if need be.

Although not calculated, **Mitigation Measures AQ-2**, **AQ-2a**, **AQ-2b**, **AQ-3**, **and AQ-3a** would reduce combustive emissions and their resulting ambient impacts from Project construction. Incorporation of these mitigation measures, however, would not reduce impacts to air quality below significance. Specific legal, economical and technological considerations make additional mitigation measures infeasible, as explained below.

Rationale for Finding

The analysis assumes as part of the Project description that all construction off-road equipment would meet EPA Tier 3 standards. No feasible mitigation measures are available to further reduce combustive emissions from proposed sources. Construction equipment that meets EPA Tier 4 standards will become available starting in year 2012. Mitigation Measure AQ-2 requires construction equipment to meet EPA Tier 4 non-road engine standards, where feasible. It will not be feasible to require compliance with that standard in 2012. Due to the slow penetration of Tier 4 engines into the construction fleet, it would be impractical and economically infeasible to require these engines on all proposed construction equipment until several years after the rule effective date. The USEPA assumes that 100% compliance by the national equipment fleet with these standards will not occur until 2030, based on estimated fleet turn over rates. A 5% annual turnover rate means that it will take a number of years before there will be a meaningful penetration of the new equipment into southern California, thereby making it infeasible to require as part of a Project's bid specifications. In spite of this expected penetration rate, Final EIS/EIR Mitigation Measure AQ-2 requires Tier 4 standard engines in construction equipment, whenever feasible. An assessment of feasibility will need to be made at the time the construction project is bid.

A number of mitigation measures related to Project construction were provided during the comment period of the Draft EIS/EIR. The mitigation matrix included as Attachment A of this report identifies those mitigation measures that were incorporated into the Final EIS/EIR, and it presents the rationale for rejecting other mitigation measures, based upon their infeasibility.

Impact AQ-2: Proposed Project construction would result in offsite ambient air pollutant concentrations that exceed a SCAQMD threshold of significance.

For a peak day of Project construction, emissions from fugitive dust and onsite construction equipment and haul trucks would result in maximum ambient offsite concentrations of 24-hour PM_{10} of 40.4 $\mu g/m^3$ that would exceed the SCAQMD significance threshold of 10.4 $\mu g/m^3$. The maximum ambient offsite concentration of all other pollutants would be less than significant prior to mitigation.

Finding

The Board of Harbor Commissioners hereby finds that changes or alterations have been incorporated into the project that avoid or substantially lessen the significant environmental effect identified in the Final EIS/EIR. Implementation of **Mitigation Measure AQ-1** would reduce emissions of fugitive dust (PM₁₀/PM_{2.5}) during Project construction. Although not assessed, **Mitigation Measures AQ-2**, **AQ-2a**, **AQ-2b**, **AQ-3**, and **AQ-3a** would reduce combustive emissions and their resulting ambient impacts from proposed construction. These mitigation measures are described above (listed in the discussion of **Impact AQ-1**).

With all feasible mitigation measures, the maximum mitigated offsite concentrations of 24-hour PM $_{10}$ would be 17.1 μ g/m 3 . This would still exceed the SCAQMD threshold of 10.4 μ g/m 3 . As a result, Project construction would remain significant for 24-hour PM $_{10}$ ambient concentration impact.

Rationale for Finding

As described above under Impact AQ-1, no additional feasible mitigation measures are available to further reduce PM_{10} emissions, either from fugitive dust or combustive emissions from construction sources. The analysis assumes as part of the Project description that all construction off-road equipment would meet Tier 3 standards, although it is expected that some equipment would meet Tier 4 standards during the later years of Project construction. Additionally, **Mitigation Measure AQ-2a** (BMPs for Construction Equipment) was added in the Final EIS/EIR (but its effects were not quantified) and is expected to future reduce construction equipment emissions.

As discussed above under **Impact AQ-1**, a number of mitigation measures related to Project construction were provided during the comment period of the Draft EIS/EIR. The mitigation matrix, included as Attachment A of this report, identifies those mitigation measures that were incorporated into the Final EIS/EIR, and it presents the rationale for rejecting other mitigation measures, based upon their infeasibility.

Impact AQ-4: Proposed Project operations would result in offsite ambient air pollutant concentrations that exceed a SCAQMD threshold of significance.

Proposed Project operational emissions would result in maximum ambient offsite concentrations of 1-hour and annual NO_2 that would exceed the SCAQMD significance thresholds. The maximum ambient offsite concentration of all other pollutants would be less than significant prior to mitigation.

Finding

The Board of Harbor Commissioners hereby finds that changes or alterations have been incorporated into the project that lessen the significant environmental effect identified in the Final EIS/EIR. Implementation of **Mitigation Measures AQ-4 through AQ-8** would reduce the Project's contribution to ambient pollutant concentrations from unmitigated levels. Although not quantified in the analysis, **Mitigation Measures AQ-7a**, **AQ-9 through AQ-11**, **AQ-25**, and **AQ-26** would further reduce operational emissions and their ambient concentrations. These mitigation measures are described in Section 3.3.4 of this document and they represent all feasible means to reduce air emissions and ambient pollutant impacts from Project operations.

With all feasible mitigation measures, maximum mitigated offsite 1-hour and annual NO_2 concentrations would remain in excess of SCAQMD thresholds (refer to discussions on pages 3.2-38 and 3.2-39 of the Final EIS/EIR). As a result, Project operations would have significant and unavoidable impacts on 1-hour and annual NO_2 ambient concentrations.

Rationale for Finding

Ship Emissions

With regard to ship emissions, Project shippers must comply with the IMO MARPOL Annex VI NOx limits that took effect in 2005 and the new standards approved in October 2008 that limit fuel sulfur content and NOx emissions. These requirements include (1) global standards and (2) tighter standards for ships that operate in

areas with air quality problems, designated as Emission Control Areas (ECAs). The engine standards include the following:

- 1. The ECA engine emission standards are Tier 3 for new engines and equate to 80 percent NOx reduction starting January 2016 (based on the use of advanced catalytic after treatment systems). EPA is in the process of preparing an application for ECA status for U.S. coastal waters. The Port is working with the EPA to develop a West Coast ECA and they fully support the establishment of the West Coast as an ECA.
- 2. The global engine emission standards are (1) Tier 2 for new engines (20 percent NOx reduction starting January 2011) and (2) Tier 1 for existing engines, or equal to those adopted by EPA in 2003 and the current IMO Annex VI standards (15-20 percent NOx reduction from current uncontrolled levels).

The unmitigated Project scenarios would operate according to the ARB Fuel Sulfur Regulation for OGVs, meaning use of 1.5/0.1 percent sulfur fuel in Project year 1/year 2012. The mitigated Project scenarios would implement Mitigation Measure AQ-6 at the commencement of the lease (Project year 1), which requires the use of 0.2 percent sulfur diesel in OGV auxiliary generators and main engines. Additionally, the new International Maritime Organization (IMO) regulations recently adopted do not require 0.1 percent sulfur until January 2015 and only for the Emission Control Areas. Beginning in year 2012, the mitigated Project scenarios would use 0.1 percent sulfur diesel in auxiliary generators, main engines, and boilers and consistent with the requirements of the ARB Regulation. For the years prior to 2012, the mitigation measure is more stringent than the ARB Fuel Sulfur Regulation. For years prior to 2015, the mitigation measure is more stringent than the IMO Fuel Sulfur limits for ECAs. It is expected that with the implementation of Project Mitigation Measure AQ-11 (slide valves), Mitigation Measure AQ-6 (low sulfur fuels in OGVs), and introduction of IMO-compliant OGVs, the Project OGV fleet would achieve significant reductions in fleet average NOx and PM emissions. Additionally, emission controls in new OGV engines is a topic of research by the CAAP TAP process. Additional emission controls on new OGV builds will be implemented as they become required by regulations or are deemed feasible through the TAP process. Final EIS/EIR Mitigation Measure AQ-25 requires the terminal tenant in 2015 and every 5 years afterwards to review new air quality technological advancements for the purpose of implementing new feasible mitigations.

Three new berths with the capacity to cold-iron OGV would become available according to the following Project construction schedule: (1) December 2009; (1) March 2012; and (3) December 2014. As each of these berths become available, they would cold-iron one-third of the total annual ship visits at the Middle Harbor container terminal. Therefore, by December 2014, 100 percent of the Project's ship visits would cold-iron. Given the magnitude and scale of proposed construction, this is the earliest that the Project could provide cold-iron capable berths. This schedule complies with the CAAP and exceeds requirements of the ARB AtBerth Ocean-Going Vessels Regulation. Essentially, any Project OGV that is retrofitted to cold-iron would moor at a berth with cold-ironing capabilities unless it is already in use. This requirement would be part of the new lease for the terminal facility.

A number of mitigation measures related to Project ship operations were provided during the comment period of the Draft EIS/EIR. The mitigation matrix included as Attachment A of this report identifies those mitigation measures that were incorporated into the Final EIS/EIR, and it presents the rationale for rejecting other mitigation measures, based upon their infeasibility.

Truck Emissions

With regard to truck emissions, the Port of Long Beach adopted a port-wide approach to dealing with drayage trucks rather than a project by project approach due to a number of complicating factors. As a result, the Port has taken an approach that spreads fleet modernization costs over an accelerated five-year schedule that covers all terminals on port-owned property in the Ports of Long Beach and Los Angeles. Through this approach, the Board of Harbor Commissioners also adopted, as part of the CTP, Clean Truck Fee exemptions that encourage the purchase of alternatively-fueled trucks by industry and adopted a goal that 50% of the CTP-funded trucks be liquefied natural gas (LNG). It is important to note that emissions benefits achieved through the use of LNG-fueled trucks would only provide marginal emissions benefits. Currently, most of the diesel trucks being funded through the CTP program have lower particulate matter emissions than LNG

trucks. While LNG trucks do currently have lower emissions of nitrogen oxides, by 2010 new diesel and new LNG trucks will have the same emission rates for nitrogen oxides.

A number of mitigation measures related to Project truck operations were provided during the comment period of the Draft EIS/EIR. The mitigation matrix included as Attachment A of this report identifies those mitigation measures that were incorporated into the Final EIS/EIR, and it presents the rationale for rejecting other mitigation measures, based upon their infeasibility.

Rail Emissions

On March 14, 2008, the EPA adopted Tier 3 and Tier 4 emission standards for diesel line-haul and switcher locomotives. Conversion of the national line haul locomotive fleet to these standards will substantially reduce emissions from these sources as compared to the fleet with only Tier 2 standards. With regard to train emissions, the Final EIS/EIR has been revised to assume that, based on EPA-estimated remanufacturing rates and new purchases, the fleet of locomotives serving the proposed Project and SCAB region would have the equivalent of Tier 3 emissions beginning in 2025. Since locomotive engines with Tier 4 standards will not be available until 2015, it is infeasible to assume the entire fleet could comply with this requirement. Thus, additional emissions reduction which were not quantified in the Final EIS/EIR would be further reduce Project operational emissions.

A number of mitigation measures related to Project rail operations were provided during the comment period of the Draft EIS/EIR. The mitigation matrix included as Attachment A of this report identifies those mitigation measures that were incorporated into the Final EIS/EIR, and it presents the rationale for rejecting other mitigation measures, based upon their infeasibility.

Cargo Handling Equipment

With regard to implementing zero- or near-zero emission transport technologies such as rail electrification. the Alameda Corridor Use and Operating Agreement specifically prohibits the Ports from unilaterally mandating rail electrification. The Port is in the process of reviewing possible zero- or near-zero emission transport technologies as envisioned in the CAAP. In 2007, Cambridge Systematics prepared the Alternative Container Technology Evaluation and Comparison assessment for the Ports of Long Beach and Los Angeles. The Port is exploring feasible technologies and in 2009 will release a Request for Proposals for the design of a zero- or low-emission container movement demonstration project between one marine terminal and a near-dock rail facility. The demonstration project will address certain key issues that will help determine whether this technology can be feasibly employed in Port operations, including the functionality of the system, the availability of rights-of-way to accommodate the system, the capital costs for the construction of the system and the costs of operations and maintenance, and the needed interface between the terminals and the rail yards. Should the Port's demonstration project establish that a zero- or near-zero emission transport technology is operationally and financially feasible, the Port will investigate expanding the system to include the Middle Harbor operations. At this point, the Board finds that t is not financially or operationally feasible to include a zero- or near-zero emission transport technology as a mitigation measure for the Project. However, the Final EIS/EIR includes a new Mitigation Measure AQ-25 that requires the terminal tenant in 2015 and every 5 years thereafter, to review new air quality technological advancements for the purpose of implementing new feasible mitigations.

The unmitigated Project scenarios include CAAP measures that are Port-wide and would occur regardless of terminal lease agreements. In addition, as part of the Port's commitment to promote the POLB Green Port Policy and implement the CAAP, the mitigated operational activities associated with Alternative 1 include all applicable CAAP control measures and additional clean air technologies. Due to this high level of emission control, few feasible mitigation measures are available to further reduce proposed Project emissions and air quality impacts. As discussed under Impact AQ-3 in Final EIS/EIR Section 3.2.2.3, the unmitigated and mitigated Project would produce lower operational emissions compared to CEQA Baseline levels in 2005. This is the case since due to currently adopted regulations (Table 3.2-11) most unmitigated Project vehicle fleets would turn over to substantially lower emission standards with time, compared to 2005 existing conditions. These lower emission rates would offset throughput increases and activities associated with the Project. Unmitigated scenarios include emission reductions that are associated with the implementation of Port-wide CAAP measures (see Final EIS/EIR Table 3.2-11). However, **Mitigation Measures AQ-4 through AQ-11** that are proposed in the Final EIS/EIR are attributed to implementation of the Project, as these control meas-

ures (e.g., Mitigation Measure AQ-5, Shore-to-Ship Power) could not be put in place unless the terminal is redeveloped and new lease is established that includes these mitigation measures.

With regard to Cargo Handling Equipment (CHE), the most feasible and economical way to comply with **Mitigation Measure AQ-7** is to replace current CHE with new equipment that achieve the USEPA nonroad Tier 4 standards. This infusion of new, more fuel efficient engines would minimize emissions from the proposed CHE fleet. Additionally, the Final EIS/EIR includes a new **Mitigation Measure AQ-7a** that would replace all diesel-powered Rubber-tired Gantry (RTG) Cranes with electrified rail-mounted gantry cranes (RMGs) with high efficiency, regenerative drive systems by the end of proposed construction, or year 2020 at the latest. This time lag is needed, as it would be necessary to wait until near completion of Project construction to efficiently install the associated rail system throughout the terminal. However, electrification of other CHE is deemed economically infeasible at this time. Nevertheless, to promote an ongoing evaluation of future air emission control technologies, Final EIS/EIR **Mitigation Measure AQ-25** requires the terminal tenant in 2015 and every 5 years afterwards to review such advancements for the purpose of implementing new feasible mitigations.

A number of mitigation measures related to Project CHE operations were provided during the comment period of the Draft EIS/EIR. The mitigation matrix included as Attachment A of this report identifies those mitigation measures that were incorporated into the Final EIS/EIR, and it presents the rationale for rejecting other mitigation measures, based upon their infeasibility.

No additional feasible measures are available for consideration at this time to reduce ship, train, truck, rail, or CHE emissions.

Impact AQ-8: The proposed Project would produce GHG emissions that would exceed the CEQA threshold.

An individual project does not generate by itself enough GHG emissions to significantly influence global climate change (AEP 2007). Thus, the issue of global climate change is a cumulative impact, such that an appreciable impact on global climate change would only occur when GHG emissions from a project combine with GHG emissions from other man-made activities on a global scale. Nevertheless, for the purposes of this EIS/EIR, the Port has chosen to assess GHG emissions as a project-level impact, as project GHG emissions would incrementally contribute to global effects.

The Project GHG significance criterion states that any increase in GHG emissions above CEQA Baseline levels is significant. The proposed Project would generate GHG emissions during each future year of construction and operation that would exceed CEQA Baseline levels. Therefore, GHG emissions from Project construction and operation would produce a significant impact to global climate change.

Finding

The Board of Harbor Commissioners hereby finds that changes or alterations have been incorporated into the project that would substantially lessen the significant environmental effect identified in the Final EIS/EIR. These changes include implementation of **Mitigation Measures AQ-2 through AQ-11, AQ-25, and AQ-26**, as described in Section 3.3.4 of this document, which would reduce Project contributions of both criteria pollutants and GHG emissions from unmitigated levels. The Middle Harbor Redevelopment Project Draft EIS/EIR proposed additional mitigation measures that would reduce operational GHG emissions. They include the following:

Mitigation Measure AQ-12: **Expanded VSRP for GHG**. All OGV that call at the Middle Harbor container terminal shall comply with the expanded VSRP of 12 knots from the California overwater border to the Precautionary Area.

Mitigation Measure AQ-13: **Low-sulfur Fuels in OGV for GHG**. All OGV shall use 0.2 percent or lower sulfur MGO fuel in vessel auxiliary and main engines at berth and within California State Waters, or implement equivalent emission reductions.

Mitigation Measure AQ-14: LEED. The main terminal building shall obtain the LEED gold certification level.

Mitigation Measure AQ-15: **Compact Fluorescent Light Bulbs**. All interior terminal building lighting shall use compact fluorescent light bulbs. Fluorescent light bulbs produce less waste heat and use substantially less electricity than incandescent light bulbs.

Mitigation Measure AQ-16: **Energy Audit**. The Middle Harbor Terminal tenant shall conduct a third party energy audit every five years and install innovative power saving technologies where feasible, such as power factor correction systems and lighting power regulators. Such systems help to maximize usable electric current and eliminate wasted electricity, thereby lowering overall electricity use.

Mitigation Measure AQ-17: **Solar Panels**. The applicant shall install solar panels on the main terminal building.

Mitigation Measure AQ-18: **Recycling**. The terminal buildings shall achieve a minimum of 40 percent recycling by 2012 and 60 percent recycling by 2015. Recycled materials shall include:

- White and colored paper;
- Post-it notes:
- Magazines;
- Newspaper;
- File folders;
- All envelopes including those with plastic windows;
- All cardboard boxes and cartons;
- · All metal and aluminum cans;
- · Glass bottles and jars; and
- · All plastic bottles.

Mitigation Measure AQ-19: **Tree Planting**. The Port shall plant shade trees around the main terminal building. Trees act as insulators from weather, thereby decreasing energy requirements. Onsite trees also provide carbon storage (AEP 2007).

Subsequent to publication of the Draft EIS/EIR, the Port conducted a rigorous evaluation to identify feasible measures that could further mitigate GHG emissions from the Project. This included a thorough review of regulatory measures proposed or adopted by state, federal and international governments to reduce GHG emissions, measures being considered by goods movement industry organizations for voluntary implementation, measures adopted by other public agencies in environmental impact statements or reports, master plans, climate action plans, or other environmental programs, and measures requested in public comments on the Project Draft EIS/EIR. In addition, the Port considered other technologies that may not have been used in a maritime port setting but could be transferred to goods movement activities and applied to the Project. The evaluation process to determine the feasibility of measures to reduce GHG emissions from the Project is documented in Final EIS/EIR Section 10, responses to air quality comments (in particular, response to comment DOJ-5) and the mitigation matrix included as Attachment A of this document.

The findings of the GHG mitigation evaluation determined that the following additional measures could feasibly mitigate GHG emissions from the Project, as proposed in the Final EIS/EIR.

Mitigation Measure AQ-17a: **Solar Carports**. The applicant will install carport-mounted PV solar panels over the employee and visitor parking areas to the maximum extent feasible.

Mitigation Measure AQ-19a: **Tree Planting – Transportation Corridors**. The Port shall plant new shade trees on Port-controlled lands adjacent to the roads into the Middle Harbor terminal to the extent practicable given safety and other land use considerations.

Mitigation Measure AQ-20: **Cool Roofs**. Buildings on the Middle Harbor terminal will incorporate cool roofing systems to the extent feasible. Building rooftop areas which are covered with solar panels in accordance with Mitigation Measure AQ-17 shall be exempt from this measure.

Mitigation Measure AQ-21: Energy Efficient Boom Flood Lights. The Port shall install boom flood lights with energy efficient features on existing and new dock cranes to the extent feasible. Such features may include, but are not limited to, use of photo cells/timers, low energy fixtures, and light-spillover reduction features, electronic ballasts, use of double filaments, and applying auto-switch-off controls when the crane boom is up.

Mitigation Measure AQ-22: **Reefer Lighting**. The terminal tenant shall downsize light fittings and associated electrical power usage at reefer platforms to the extent feasible.

Mitigation Measure AQ-23: **Employee Carpooling**. The construction contractor and terminal tenant shall encourage construction and terminal employees to carpool or to use public transportation. These employers shall provide incentives to promote the measure, include preferential parking for carpoolers, vanpool subsidies, and they shall provide information to employees regarding the benefits of alternative transportation methods.

Mitigation Measure AQ-24: Mitigation for Indirect GHG Emissions. The terminal tenant shall be required to use green commodities, such as those available from the California Climate Action Registry's Climate Action Reserve, to offset carbon emissions associated with terminal's electricity consumption subject to the limitation specified below. This measure applies to all electricity consumed at the terminal, including shore-to-ship power usage ("cold ironing"). The terminal-related carbon emissions from electricity consumption will be calculated each year based on the local utility's carbon intensity for that year as recognized by the State of California. The tenant may adjust the carbon intensity value to wholly reflect any carbon offsets provided by the electricity deliverer (i.e., point of generation or point of importation) under applicable California and/or Federal cap-and-trade regulations (i.e., no double offsetting). The maximum expenditure for purchased offsets required under this measure shall not exceed 15 percent of the terminal electricity costs for any given year (i.e., cost of offsets shall not exceed 15 percent of terminal electricity costs (US\$ basis).

Mitigation Measure AQ-27: **Electrical Regenerative Systems on Dock Cranes**. Port will require that the terminal operator to have electric regenerative systems on all Project dock cranes in Project year 1.

The Port is developing a Climate Change/Greenhouse Gas (CC/GHG) Strategic Plan (CC/GHG Plan), whose goal is to reduce the cumulative impact of GHG emissions from Port operations. One element of the CC/GHG Plan is the Greenhouse Gas Emission Reduction Program Guidelines (GHG Guidelines). These Guidelines describe a procedure that the Port will use to select GHG emission reduction programs that meet the CC/GHG Plan reduction goals. Since the Project would produce significant levels of GHG emissions, the GHG Guidelines are included as the following mitigation measure to further reduce Project GHG emissions:

Mitigation Measure AQ-28: Greenhouse Gas Emission Reduction Program Guidelines (GHG Program). To partially address the cumulative GHG impacts of the Middle Harbor Project, the Port will require this Project to provide funding for the GHG Program in the amount of \$5 million. This money will be used to pay for measures pursuant to the GHG Emission Reduction Program Guidelines, and include, but are not limited to, generation of green power from renewable energy sources, ship electrification, goods movement efficiency measures, cool roofs to reduce building cooling loads and the urban heat island effect, building upgrades for operational efficiency, tree planting for biological sequestration of CO₂, energy-saving lighting, and purchase of renewable energy certificates (RECs).

Implementation of **Mitigation Measures AQ-5**, **AQ-7a**, **AQ-12**, and **AQ-13** would reduce Project emissions of CO₂e by 16 to 18 percent from unmitigated levels, depending on the Project year. Although not quantified in this analysis, implementation of **Mitigation Measures AQ-8 through AQ-11 and AQ-14 through AQ-28** would further reduce Project GHG emissions. Specific legal, economic, and technical considerations, as identified in Final EIS/EIR Section 10 and Attachment A of this document, make additional mitigation measures infeasible. As such, GHG emissions from the Project would remain significant after consideration of all feasible mitigation measures.

Rationale for Finding

The Final EIS/EIR has thoroughly disclosed the potential GHG emissions associated with the Project and it has expended considerable effort to identify all feasible measures to mitigate proposed GHG emissions. It would be technologically and economically infeasible and outside of the control of the Port or Project terminal tenant to implement any additional measures beyond those described above. Therefore, after mitigation, Project impacts to global climate change would be significant and unavoidable.

In the future, the Port will continue to pursue additional GHG mitigation measures under the CC/GHG Plan. This will result in additional reductions in GHG emissions beyond those that would be achieved through the direct project mitigation measures described above. Future Port-wide greenhouse gas emission reductions are also anticipated through AB 32 rule promulgation. However, the methods of such reductions have not been identified, and the associated reductions have not yet been quantified, as AB 32 implementation is still under development by the ARB. Although the State has yet to formalize GHG regulations for the goods movement sector, the Port has already begun work in this area. In September 2008, the Port's Board of Harbor Commissioners adopted a resolution establishing a framework for reducing GHG emissions. The framework outlined efforts that are already underway at the Port toward addressing the issue of climate change. These efforts include:

- 1. The Port collaborated with other City departments to produce the City's first voluntary GHG emissions inventory (calendar year 2007) which was submitted to the California Climate Action Registry (CCAR).
- 2. The Port joined other City departments in preparing a plan to increase energy efficiency in City-owned facilities, in turn reducing indirect GHG emissions from energy generation. This initiative is known as the Southern California Edison 2009-2011 Local Government Partnership.
- 3. The Port participates in tree planting and urban forest renewal efforts through its support of the City of Long Beach's Urban Forest Master Plan.
- 4. Port staff consulted with the Long Beach Gas and Oil Department (LBGO) and Tidelands Oil Production Company (Tidelands) to evaluate potential opportunities for capturing carbon dioxide produced by oil operations in the Harbor District and re-injecting (sequestration) it through wells at the Port back into the subsurface formations.
- 5. Beginning with the 2006 POLB air emissions inventory, GHG emissions from ocean-going vessels, heavy-duty trucks, cargo-handling equipment, harbor craft, and locomotives are quantified to enable the establishment of GHG reduction goals.
- 6. The Port's Renewable Energy Working Group is developing strategies to expand renewable energy at the Port. Criteria for emerging technologies will be established so that the technologies can be evaluated in a manner similar to the existing CAAP Technology Advancement Program (TAP).
- 7. The Port's Renewable Energy Working Group recently finalized a Solar Energy Technology and Siting Study ("Solar Siting Study") that reviewed available solar technologies and the estimated solar energy generation potential for the entire Harbor District. The study determined that there are many sites within the Harbor District where solar energy generating technologies could be developed on building rooftops and at ground-level.

8. Based on the Solar Siting Study, Port staff are developing a program to provide incentive funding to Port tenants for the installation of solar panels on tenant-controlled facilities.

A number of mitigation measures related to Project GHG emissions were provided during the comment period of the Draft EIS/EIR. The mitigation matrix included as Attachment A of this report and Final EIS/EIR Section 10 responses to air quality comments (in particular, response to comment DOJ-5) identifies those mitigation measures that were incorporated into the Final EIS/EIR and they present the rationale for rejecting other mitigation measures, based upon their infeasibility.

3.4.2 Biota and Habitats

As discussed in Final EIS/EIR Section 3.4, there would be one significant impact on biota and habitat as a result of the proposed Project during construction and operation. This impact would remain significant and unavoidable.

Impact BIO-5.3: Project operations could disrupt local biological communities through introduction of non-native species.

The amount of ballast water discharged into East Basin and, thus, the potential for introduction of invasive exotic species could increase since more and larger container ships would use the Port as a result of the Project. Because these vessels would come primarily from outside the Economic Exclusion Zone (EEZ), they would be subject to regulations to minimize the introduction of non-native species in ballast water, such as discharging to approved receivers and not exchanging ballast water within ports. Vessels unloading cargo would need to take on ballast water, while those loading cargo would need to discharge ballast water. Most container vessels entering the Port would be unloading cargo and, thus, not discharging ballast water.

Non-native algal species and invertebrates can also be spread via vessel hulls and external machinery (Final EIS/EIR Section 3.4.1.2). Algal species such as *Undaria pinnatifida*, discovered in Long Beach/Los Angeles Harbor in 2000 (MEC Analytical Systems, Inc. 2002), and *Sargassum filicinum* could be transported to the harbor via vessels traveling between ports within the EEZ. The new facilities in the Middle Harbor would result in a small increase (approximately 3.4 percent) in vessel traffic compared to the total number of vessels entering the harbor. Considering this small increment and the ballast water regulations currently in effect, the potential for introduction of additional exotic species via ballast water would be low from vessels entering from or going outside the EEZ. For these reasons, the Project has a low potential to increase the introduction of non-native algal and invertebrate species into the harbor. The potential for introduction or spread of the invasive alga, *Caulerpa taxifolia*, as a result of Project operations is very low because the species is most likely introduced from disposal of aquarium plants and water, and is spread by fragmentation rather than from ship hulls or ballast water.

Operation of the Project facilities has the potential, even though of low probability, to result in the introduction of non-native species into the harbor via ballast water or vessel hulls, thereby substantially disrupting local biological communities. Impacts would, therefore, be significant.

Finding

Ballast water discharges are now regulated, which has significantly reduced the potential for introduction of invasive exotic species. The potential for introduction of exotic species via vessel hulls has been reduced by using antifouling paints and periodic cleaning of hulls to minimize frictional drag from growth of organisms. However, due to the lack of a proven technology, no feasible mitigation measures are available to prevent introduction of invasive species via ballast water and/or vessel hulls. The Board hereby finds that specific technological considerations make additional mitigation measures infeasible that would reduce these impacts to less than significant levels.

Rationale for Finding

Although regulations are currently being developed by the state to address ballast water discharges, no feasible mitigation is currently available to totally prevent introduction of invasive species via vessel hulls or even ballast water, due to the lack of a proven technology. New technologies are being explored, and if methods

become available in the future, they would be implemented as appropriate at that time. Therefore, impacts on biota and habitats would be significant and unavoidable.

3.4.3 Ground Transportation

As discussed in Final EIS/EIR Section 3.5, there would be two significant impacts to ground transportation as a result of the proposed Project during construction and operation. These impacts would remain significant and unavoidable.

Impact TRANS-2.1: Additional traffic generated by construction activities would have short-term significant impacts on certain highway locations in the study area.

The proposed Project's construction traffic would have short-term significant impacts on study highway segments up to the horizon year 2020. To be conservative, the same highway segments identified under the operational analysis are assumed to be impacted by the increase in construction-related traffic. The proposed Project would have significant impacts on the following study highway segments:

- I-405 n/o I-710, both Directions (starting 2010);
- I-405 s/o I-710, both directions (starting 2010);
- I-710 between Willow Street and Pacific Coast Highway, both directions (starting 2010);
- SR-91 e/o I-710, both directions (starting 2010); and
- SR-91 w/o I-710, both directions (starting 2015).

Finding

The Board of Harbor Commissioners hereby finds that changes or alterations have been incorporated into the Project that avoid or substantially lessen the significant environmental effect identified in the Final EIS/EIR. Incorporation of **Mitigation Measure TRANS-2.1**, however, would not reduce impacts to ground transportation below significance. Specific legal, economical, and technological considerations make additional mitigation measures infeasible, as explained below.

The Port does not own, control, or maintain any of the impacted highway segments. These segments fall under the jurisdiction of Caltrans. Therefore, the Port does not have authority to unilaterally implement any mitigation measures on the highway segments. However, implementation of the following measure would minimize impacts on highway segments.

Mitigation MeasureTRANS-2.1: If Caltrans either (a) adopts a fair share based program to collect funds for actual mitigation that Caltrans commits itself to implement, or (b) otherwise obtains the balance of funding needed to improve the impacted study highway segments in a manner that will improve the segments level of operation, POLB shall pay its fair share into that program.

If Caltrans does not implement either of these steps, the impact on these freeway segments would remain significant and unavoidable.

In addition, it should be noted that the POLB is currently participating in the following on-going regional transportation programs, which are intended to address future regional traffic growth and resulting congestion on area freeways.

I-710 Corridor EIS/EIR 2008. The Port is presently working with Caltrans, Metro, SCAG, and Gateway Cities Council of Governments (COG) (of which the Port and City of Long Beach are member agencies) on the I-710 Corridor EIR/EIS and Caltrans Project Report. POLB has committed \$5 million to this \$34-million, 42-month study, which was commenced in early 2008. This project entails analyzing potential impacts and advancing preliminary engineering of the Locally Preferred Strategy (LPS) adopted by the communities and participating agencies in 2004/2005. The LPS consists of dedicated truck lanes commencing at Ocean Boulevard, additional mixed flows on I-710 between Ocean Boulevard and Washington Street, and numerous freeway to

freeway and arterial street interchange improvements. The POLB, City of Long Beach, and Gateway Cities COG are aggressively seeking federal, state, and Metro funds for the I-710 Corridor.

Advanced Transportation Management, Information and Security (ATMIS). The POLB/POLA will also be implementing an Intelligent Transportation Systems (ITS) project by 2009. This \$11-million program will provide real-time information to travelers in the Port vicinity and on adjacent regional transportation facilities. The ATMIS System will monitor vehicle traffic conditions through the use of closed circuit television cameras and vehicle detection devices at the terminal gates. The ATMIS System will distribute the traffic information to truck drivers, motorists, other agencies, and intermodal industry information systems through the use of strategically placed changeable message signs, internet video, and appropriate data sharing means. While the ATMIS system will assist in addressing recurring daily congestion, its major benefit will be providing information to inform drivers, including trucks exiting the Port gates, of non-recurring incidents and congestion and to allow them to choose, if possible, alternative routes to avoid congested areas.

The ATMIS System will be a major component in an overall ITS program for the I-710 Corridor/Gerald Desmond Bridge Gateway Program. This planned project will help to mitigate the I-710 impacts of the Project.

SR-91 Corridor Study. The Gateway Cities COG has initiated a SR-91 Corridor Study to explore options that will improve traffic conditions on this freeway. POLB continues to work in cooperation with the COG, Caltrans, and other agencies to find solutions to improving operating conditions on SR-91.

No additional feasible mitigation measures are available at this time.

Rationale for Finding

It can be assumed that until Caltrans implements improvements on the I-710, I-405, and SR-91 highway segments, the Project would have significant impacts at these locations. Therefore, impacts on highway segments would be significant and unavoidable.

Impact TRANS-2.2: Additional traffic generated by operation of the Project would have significant impacts on certain highway locations in the study area.

The operation of the proposed Project would have significant impacts on the following study highway segments:

- I-405 Freeway n/o I-710 Freeway, both Directions (starting 2010, max fair share of one percent in 2020);
- I-405 Freeway s/o I-710 Freeway, both directions (starting 2010, max fair of 5 percent in 2010):
- I-710 Freeway between Willow Street and Pacific Coast Highway, both directions (starting 2010, max fair share of four percent in 2020);
- I-110 Freeway n/o C-Street, northbound (2030, max fair share of 1.5 percent in 2030);
- SR-91 Freeway e/o I-710 Freeway, both directions (starting 2010, max fair share of four percent in 2030); and
- SR-91 Freeway w/o I-710 Freeway, both directions (starting 2015, max fair share of 3.5 percent in 2030).

The Project would cause an impact on more highway segments under this scenario because the CEQA Baseline (2005) traffic levels are compared to future traffic levels that include not only Project traffic, but also all forecasted future traffic on these highway segments resulting from regional growth and other area projects and activities unrelated to this Project. Although total highway traffic would increase substantially in the future, this Project contributes only a small portion of the anticipated future traffic. The Project's maximum share of the future traffic on each individual link ranges from approximately one to five percent.

Finding

The Board of Harbor Commissioners hereby finds that changes or alterations have been incorporated into the Project that avoid or substantially lessen the significant environmental effect identified in the Final EIS/EIR. Incorporation of **Mitigation Measure TRANS-2.1**, however, would not reduce impacts to ground transportation below significance. Specific legal, economical, and technological considerations make additional mitigation measures infeasible, as explained below.

The Port does not own, control, or maintain any of the impacted highway segments. These segments fall under the jurisdiction of Caltrans. Therefore, the Port does not have authority to unilaterally implement any mitigation measures on the highway segments. However, implementation of **Mitigation Measure TRANS-2.1** would minimize impacts on highway segments.

If Caltrans does not implement either of the steps identified in **Mitigation Measure TRANS-2.1**, including adopting a fair share based program to collect funds for actual mitigation that Caltrans commits itself to implement, or obtaining the balance of funding needed to improve the impacted study highway segments in a manner that will improve the segments level of operation, the impact on these freeway segments would remain significant and unavoidable.

In addition, it should be noted that the Port is currently participating in the on-going regional transportation programs, as described above, which are intended to address future regional traffic growth and resulting congestion on area freeways.

No additional feasible mitigation measures are available at this time.

Rationale for Finding

It can be assumed that until Caltrans implements improvements on the I-710, I-405, and SR-91 highway segments, the Project would have significant impacts at these locations. Therefore, impacts on highway segments would be significant and unavoidable.

Comment CBD-69 suggested increased public transit as a way to mitigate impacts to freeway segments. However, increased public transit would not take Project trips off the road. It is not a technically or economically feasible mitigation measure. The public does not travel to the Project site. The vehicle traffic generated by the Project will be largely truck traffic that would not involve public transit. Terminal operators currently operate shuttles to transport longshoremen to the terminals when ships arrive. This practice will continue and is part of the Clean Air Action Plan that the Port will continue to enforce through leases with the terminal operators. Therefore, increased transit service would not address Project traffic issues.

Comment CBD-70 suggested employee-model truck programs to reduce trips to the Project site. However, employee-model truck programs have not yet been proven to improve truck efficiency and reduce truck traffic. There have not been any comprehensive studies supporting a finding that the employee-model reduces commute-only truck trips. Nor have there been documented findings on efficiency differential since an owner-operated truck could also be used for multiple shifts. In fact, under the POLA concession more personal trips by truck drivers will likely occur as they commute to and from work site for their shifts. Such increase in personal trips would simply shift traffic congestion from one region to another and yield no environmental benefit. The employee-model truck program is not technically, legally, or socially a viable mitigation measure.

Comment SCAQMD-7 and CBD-20 proposed increasing the amount of cargo that moves from the Project by on-dock rail. Increased use of on-dock rail above and beyond the Project is not a technically feasible mitigation measure. Every effort was made from the design and operation perspective to maximize the rail yard capacity, taking into account the need for the additional container yard capacity necessary to accommodate projected demand. Even were there a legitimate need for more on-dock rail capacity, which there is not, the planned on-dock rail yard could not be expanded into the planned container yard because overall terminal capacity would be reduced, thus creating a less efficient terminal. In light of the physical constraints of the site and the need to provide sufficient container yard capacity to handle the projected cargo throughput, the proposed Project maximizes on-dock rail capacity. The proposed re-use of this site has been carefully planned to ensure adequate space for operations, storage, and trackage that will result in an increase of 613,160 TEUs

between the 2030 No Project and 2030 Project alternatives (the only difference in throughput being the design of the site). Moreover, a sizeable amount of the Project throughput will be made up of low-volume destination cargo that must be assembled at the near- and off-dock rail yards throughout the region. Specifically, low-volume-destination containers (i.e. non-Chicago-bound containers) oftentimes cannot wait for a unit train to be built on-dock. Rather, these boxes are assembled off-dock from multiple terminals in order to achieve the appropriate volumes to generate a single train in a timely fashion. Therefore, some direct intermodal containers will always need to be drayed to the Intermodal Container Transfer Facility, Hobart Yards, and other rail yards throughout the region regardless of the size of the on-dock rail yard at Middle Harbor.

Comments SCAQMD-27, CBD-20, CBD-21, CBD-71, CBD-100, CSE(A)-3, CSE(A)-4, CSE(B)-3, and JW-3 suggested Maglev or electrified rail. CBD-71 and CSE(B)-3 also suggested the construction of an intermodal facility on Port property, such as the import car lot off Anaheim Street, as ways to reduce truck trips. However, Magley and an intermodal facility at the import car lot are not feasible mitigation measures. The Port is in the process of reviewing possible zero- or near-zero emission transport technologies as envisioned in the CAAP. In 2007, Cambridge Systematics prepared the Alternative Container Technology Evaluation and Comparison assessment for the Ports of Long Beach and Los Angeles. The Port is exploring feasible technologies and in 2009 will release a Request for Proposals for the design of a zero- or low-emission container movement demonstration project between one marine terminal and a near-dock rail facility. The demonstration project will address certain key issues that will help determine whether this technology can be feasibly employed in Port operations, including the functionality of the system, the availability of rights-of-way to accommodate the system, the capital costs for the construction of the system and the costs of operations and maintenance, and the needed interface between the terminals and the rail yards. Should the Port's demonstration project establish that a zero- or near-zero emission transport technology is operationally and financially feasible, the Port will investigate expanding the system to include the Middle Harbor operations. At this point, the Board finds that t is not financially or operationally feasible to include a zero- or near-zero emission transport technology as a mitigation measure for the Project. However, the Final EIS/EIR includes a new Mitigation Measure AQ-25 that requires the terminal tenant in 2015 and every 5 years thereafter, to review new air quality technological advancements for the purpose of implementing new feasible mitigations. Electrification of the rail corridors is well outside of the scope of the Project. Electrifying the Alameda Corridor has been studied fully and is not being pursued for several reasons, including operational feasibility during loading/unloading of trains and environmental and fiscal impacts of constructing a new power plant that could supply a sufficient source of power. The Southern California Association of Governments conducted a study on electrifying the Southern California rail system in the 1990s and concluded it was prohibitively expensive to do so, and thus infeasible at that time. Electrifying the region's rail system is still being evaluated to address air quality attainment objectives. The cost to electrify rail in Southern California was estimated to be in excess of \$6 billion, thus it is an economically infeasible mitigation measure. Regarding construction of a parking structure to free up space for a Maglev system, the cost per parking space for a parking structure ranges from \$20,000 to \$25,000. Constructing a 4 or 5-story parking structure on Pier B, which is leased terminal space, would greatly limit future lease options and could significantly constrain the future use on this terminal. Not only is Maglev not yet a proven alternative, but

No additional traffic mitigation measures have been identified at this time. Unless Caltrans implements a mechanism to assess a fair share contribution, the Project's traffic impacts will be significant and unavoidable.

the cost of constructing a parking structure for a limited period of time is economically infeasible.

3.4.4 Noise

As discussed in Final EIS/EIR Section 3.9, there would be two significant impacts to noise as a result of the proposed Project during construction and operation. These impacts would remain significant and unavoidable.

Impact NOI-1.1: Project construction activities would increase ambient noise levels by three dBA.

The minimum ambient daytime hourly Leq noise level recorded at the closest sensitive receptor site (i.e., Site 1) was 61 dBA. During Project pile driving activities, calculated hourly Leq noise levels at Site 1 would range between 64 – 66 dBA, which would exceed a three dB increase. Pile-driving activities mostly would occur during Construction Phase 1, but also during part of Phase 2. The longest scheduled period of pile-driving would occur for 12 months during Construction Phase 1/Stage 1 for the new Berth E24 extension and redevelopment of the existing berth at Berth E24. Project construction activities would cause ambient noise levels to be in-

creased by more than three dBA at nearby sensitive receptors (i.e., Site 1), resulting in significant short-term impacts. Pile-driving activities would also occur during Construction Phase 1/ Stage 2, Construction Phase 1/Stage 3, and Construction Phase 2/Stage 2 in-water activities associated with new wharf construction at Berth E23 and wharf redevelopment/ improvements at Berths E25, E26, and E27.

At receiver Site 2, levels of existing daytime ambient noise are significantly higher than those at Site 1. Calculated construction noise levels at this location would not exceed the existing daytime ambient noise level by three dBA.

At receiver Sites 3 through 7, increased distance from the Project and the shielding effects of intervening structures and topography would reduce construction noise levels to below the existing ambient level.

Finding

The Project includes the following standard construction noise controls described in Final EIS/EIR Section 1.7.3.

- 1. Construction Equipment All construction equipment powered by internal combustion engines would be properly muffled and maintained.
- 2. *Idling Prohibitions* The idling of internal combustion engines near noise-sensitive areas would be prohibited during Project construction.
- 3. Equipment Location All stationary noise-generating construction equipment, such as air compressors and portable power generators, would be located as far as practical from existing noise-sensitive land uses.
- 4. Quiet Equipment Selection Quiet construction equipment would be used during Project construction to the extent feasible.
- 5. Notification The Port would publish notices in the Press Telegram and all property managers adjacent to the Project site would be notified in advance of the construction schedule. The Port would coordinate with schools and other affected agencies to ensure construction activities would not substantially interfere with facility operations.

The Board of Harbor Commissioners hereby finds that changes or alterations have been incorporated into the Project that avoid or substantially lessen the significant environmental effect identified in the Final EIS/EIR. These changes are set forth in **Mitigation Measures NOI-1.1a and NOI-1.1b**, set forth below.

Mitigation Measure NOI-1.1a: Temporary noise barriers shall be located between noise-generating construction activities (e.g., pile driving) and hotel/residential buildings and Cesar Chavez School to the east.

Mitigation Measure NOI-1.1b: Pile-driving activities shall be limited to the hours of 7:00 am to 7:00 pm on weekdays, between 9:00 am and 6:00 pm on Saturdays, and prohibited anytime on Sundays and holidays as prescribed by Section 8.80.202 of the LBMC.

Incorporation of these mitigation measures will not reduce construction noise impacts to less than significant.

Rationale for Finding

Due to the difficulty of effectively mitigating substantial noise-generating activities, adherence to standard controls and construction of temporary noise barriers would not be sufficient to reduce projected increases in ambient noise levels to the point where it would no longer cause a substantial increase. Therefore, impacts would remain significant after mitigation.

Comment LBUSD-20 suggested limiting construction activities during school hours of operation and testing periods to reduce this significant unavoidable impact. This recommendation has been incorporated into the Project's construction noise controls as a notification requirement. Furthermore, Final EIS/EIR **Mitigation**

Measure NOI-1.1a has been modified to require installation of temporary noise barriers between pile driving activities and Cesar Chavez School.

Impact NOI-2.1: Construction activities would exceed City of Long Beach Municipal Code maximum noise levels.

Receiver Site 1 is in the City of Long Beach General Plan Land Use District (LUD) Three, for which the maximum noise level allowed by the Long Beach Municipal Code (LBMC) is 65 dBA (Leq, one-hour) (Final EIS/EIR Table 3.9-6). However, many of the construction activities would invoke the five dBA penalty for impulsive/tonal noise character, which would reduce the maximum allowable noise level in this location to 60 dBA. Calculated hourly average construction noise levels would intermittently exceed 60 dBA at receiver Site 1 until the end of Construction Phase 2.

Receiver Site 2 is in LUD One (Final EIS/EIR Table 3.9-6). Taking existing ambient noise levels into account, as well as the impulsive/tonal noise penalty, the maximum daytime noise level allowed in this location under the LBMC would be 65 dBA (Leq, one-hour). Calculated hourly average construction noise levels at Site 2 would exceed 65 dBA during the noisiest periods of construction.

At receiver Sites 3 through 7, increased distance from the Project site and the shielding effects of intervening structures and topography would reduce construction noise to levels below the maximum allowed by the LBMC.

Project construction activities would cause ambient noise levels to exceed LBMC maximum noise levels at Sites 1 and 2; therefore, significant short-term impacts would occur.

Finding

The Board of Harbor Commissioners hereby finds that changes or alterations have been incorporated into the Project that avoid or substantially lessen the significant environmental effect identified in the Final EIS/EIR. These changes are set forth in **Mitigation Measures NOI-1.1a** and **NOI-1.1b**, set forth above. Incorporation of these mitigation measures will not reduce construction noise impacts to less than significant.

Rationale for Finding

Due to the difficulty of effectively mitigating substantial noise-generating activities, adherence to standard controls and construction of temporary noise barriers would not be sufficient to reduce projected increases in ambient noise levels to the point where it would no longer cause a substantial increase. Therefore, impacts would remain significant after mitigation.

3.5 Cumulatively Considerable Impacts

CEQA Guidelines (Section 15130) require an analysis of the Project's contribution to significant and unavoidable cumulative impacts. Cumulative impacts include "two or more individual effects which, when considered together, are considerable or which compound or increase other environmental impacts" (CEQA Guidelines, Section 15355).

The discussion below identifies cumulatively significant and unavoidable impacts. The Board of Harbor Commissioners has determined that certain proposed mitigation measures and/or alternatives that may reduce these impacts below significance are infeasible in light of specific economic, legal, social, technological, and other considerations and, therefore, have not been incorporated into the Project. The evidence of such infeasibility is explained below.

3.5.1 Air Quality

Cumulative Criteria Pollutants Impacts

This impact represents the potential of the proposed Project to contribute, in conjunction with other cumulative projects, to significant mass emissions or ambient offsite concentrations of criteria pollutants.

Finding

With regard to Impacts AQ-1 and AQ-2, peak daily Project construction activities, with implementation of Mitigation Measures AQ-1, AQ-2, AQ-2a, AQ-2b, AQ-3, and AQ-3a, would produce mitigated emissions that would exceed the SCAQMD peak daily emission thresholds for VOC, CO, NO_x, PM₁₀, and PM_{2.5}, and the 24-hour PM₁₀ ambient thresholds. This Project-specific significant impact would also represent a cumulatively considerable contribution to a significant cumulative impact. No additional mitigation measures beyond those identified in the Final EIS/EIR for project-specific impacts are available to mitigate these significant cumulative impacts, as identified in Attachment A of this document.

With regard to Impact AQ-4, Project operations, with implementation of Mitigation Measures AQ-4 through AQ-8, AQ-9 through AQ-11, AQ-25, and AQ-26, would produce ambient impacts that would exceed the SCAQMD one-hour and annual NO₂ ambient thresholds. As a result, mitigated Project operations, in combination with existing and future related projects, would produce cumulatively considerable and unavoidable contributions to ambient NO₂ levels. However, these impacts represent lower cumulative NO₂ impacts compared to those produced from existing terminal operations in 2005. No additional mitigation measures beyond those identified in the Final EIS/EIR for project-specific impacts are available to mitigate these significant cumulative impacts, as identified in Attachment A of this document.

The Board hereby finds that changes or alterations have been incorporated into the Project that minimize the significant cumulative environmental effect identified in the Final EIS/EIR. Incorporation of all feasible mitigation measures and adherence to proposed environmental controls, however, would not reduce criteria pollutant cumulative impacts to below significance. Specific legal, economical, and technological considerations make additional mitigation measures infeasible.

Rationale for Finding

Due to its large population, substantial numbers of emission sources, and geographical/ meteorological conditions that inhibit atmospheric dispersion, the SCAB experiences degraded air quality. As stated in Section 3.2, the region presently does not attain the national and/or state ambient air quality standards for O_3 , PM_{10} , and $PM_{2.5}$. These pollutant nonattainment conditions within the Project region are considered to be cumulatively significant. However, the 2007 AQMP predicts attainment of all NAAQS within the SCAB, including $PM_{2.5}$ by 2014 and O_3 by 2024, although these predictions are speculative.

Construction activities resulting from some of the cumulative and related projects (e.g., Pier G & J Terminal Redevelopment Project; Berths 97-109 Container Terminal Project, West Basin; Channel Deepening Project; Berths 136-147 Marine Terminal; Berth 206-209 Interim Container Terminal Reuse Project; Pacific Los Angeles Marine Terminal; Port of Los Angeles Charter School and Port Police Headquarters Project; and San Pedro Waterfront Enhancement Project) would add to the emission levels and ambient concentrations around the Ports due to their construction schedules, which overlap with that of this proposed Project.

Any activity that occurs concurrently in the vicinity of proposed Project terminal operations would add to the significant ambient concentration impact of air pollutants from Project operations. As a result, impacts from mitigated Project operations would produce cumulatively considerable and unavoidable impacts to 1-hour and annual NO₂ levels. Operational activities resulting from projects such as the Pier G & J Terminal Redevelopment Project; Berths 97-109 Container Terminal Project, West Basin; Channel Deepening Project; Berths 136-147 Marine Terminal; Berth 206-209 Interim Container Terminal Reuse Project; Pacific Los Angeles Marine Terminal; Port of Los Angeles Charter School and Port Police Headquarters Project; and San Pedro Waterfront Enhancement Project) would add to the ambient concentrations around the Ports due to their overlapping construction and operation schedules, which overlap with the operation of the proposed Project.

The San Pedro Bay Standards (described below) will be a valuable tool for long-term air quality planning, aiding the Ports of Long Beach and Los Angeles and air agencies to achieve substantial reductions in long-term cumulative air quality impacts of emissions from ongoing and future Port operations in conjunction with implementation of CAAP measures and existing regulations.

The Final EIS/EIR has thoroughly disclosed potential criteria pollutant emissions and associated cumulative impacts due to the Project and it has expended considerable effort to identify all feasible measures to mitigate

these impacts. It would be technologically and economically infeasible and outside of the control of the Port or Project terminal tenant to implement any additional measures beyond those described above. Therefore, after mitigation, Project cumulative impacts to criteria pollutant levels would be significant and unavoidable.

In the future, the Project lease agreement would include a condition requiring that every 5 years the Project lease would be re-opened to consider implementation of new feasible mitigations in accordance with Final EIS/EIR **Mitigation Measure AQ-25**. This and Final EIS/EIR **Mitigation Measure AQ-29** (presented below) would mitigate Project cumulative air quality impacts in addition to those presented in the Final EIS/EIR.

Cumulative Toxic Air Contaminants Impacts

This impact represents the potential of the proposed Project to contribute, in conjunction with other cumulative projects, to a significant cancer risk or non-cancer chronic or acute health effects on residential, offsite occupational, or sensitive receptors.

Finding

With regard to Impact AQ-6, emissions of TACs from Project construction and operation, with implementation of Mitigation Measures AQ-2 through AQ-12, AQ-25, and AQ-26, would reduce cancer risks to all receptor types within the Project region compared to the CEQA Baseline. As a result, the mitigated Project would produce less than cumulatively considerable contributions to cancer effects under CEQA. The mitigated Project would increase chronic non-cancer effects at the maximum occupational receptor locations, but all other receptors in the Project region would have chronic non-cancer impacts which are less than those identified at the maximum occupational receptor location. This increase would represent cumulatively considerable contributions of air-borne non-cancer effects to occupational receptors.

Since the Project would produce significant cumulative health impacts, the Final EIS/EIR proposes the following mitigation measure to further reduce the effects of this impact on the community. Details of the cumulative guidelines are presented in the Rationale for Finding section below:

Mitigation Measure AQ-29: Cumulative Air Quality Impact Reduction Program. To help reduce cumulative air quality impacts of the Middle Harbor Redevelopment Project, the Port will require the Project to provide funding in support of the Schools and Related Sites Guidelines for the Port of Long Beach Grant Programs and Healthcare and Seniors Facility Program Guidelines for the Port of Long Beach Grant Programs in the amount of \$5 million each. The distribution of these funds to potential applicants and projects will be determined through a public evaluation process and by approval of the Board of Harbor Commissioners.

The timing of the payments pursuant to **Mitigation Measure AQ-29** shall be made by the later of the following two dates: (1) the date that the Port issues a Notice to Proceed or otherwise authorizes the commencement of construction on the Phase 1 Construction Contract or (2) the date that the Middle Harbor Final EIR is conclusively determined to be valid, either by operation of Public Resources Code Section 21167.2 or by final judgment or final adjudication.

The Board hereby finds that changes or alterations have been incorporated into the Project that minimize the significant cumulative environmental effect identified in the Final EIS/EIR. Specific legal, economic, and technical considerations, as identified in Attachment A of this document, make additional mitigation measures infeasible. As such, cumulative non-cancer effects from the Project would remain significant after consideration of all feasible mitigation measures.

Rationale for Finding

The SCAQMD in their MATES-II and MATES-III (current draft) reports and the ARB in their *Diesel Particulate Matter Exposure Assessment Study for the Ports of Los Angeles and Long Beach* estimated that elevated levels of cancer risks due to operational emissions from the POLB and POLA occur within and in proximity to the two Ports (SCAQMD 2000 and 2008; ARB 2006). Regarding non-cancer effects, the ARB identifies that elevated levels of air pollution that can occur within the Ports region are associated with adverse health effects, including asthma, bronchitis, reduced lung function, and increased mortality and morbidity (ARB 2006d).

Based on this information, the existing and future baseline airborne cancer and non-cancer conditions within the Project region are cumulatively significant.

Emissions of TACs from construction and operation of the mitigated Project would reduce cancer risks to all receptor types within the Project region. As a result, the mitigated Project would produce less than cumulatively considerable contributions to cancer effects.

Emissions of TACs from construction and operation of the mitigated Project would reduce non-cancer health effects to all receptor types within the Project region, except for chronic non-cancer effects to occupational receptors. As a result, the mitigated Project would produce less than cumulatively considerable contributions to non-cancer effects, except for chronic non-cancer effects to occupational receptors. The maximum Project chronic non-cancer effects to occupational receptors would not exceed the 1.0 hazard index significance criterion. However, since the mitigated Project would increase chronic non-cancer effects in the Project region, it would produce a cumulatively considerable and unavoidable contribution of airborne non-cancer effects to occupational receptors.

In developing the San Pedro Bay Ports CAAP, the Ports of Long Beach and Los Angeles established a series of principles and goals designed to reduce air emissions and related health impacts while allowing Ports development to continue. The CAAP committed the Ports, with the assistance of their agency partners (the technical working group or TWG, comprised of representatives from ARB, SCAQMD, and the USEPA) to establish San Pedro Bay Standards (SPBS) to define targets for reduction of Ports-related air impacts, specifically air quality and health risk impacts. The SPBS address the Ports' primary air quality goals of reducing health risks to local communities from Ports' operations and reducing emissions to allow the region to reach attainment with the health-based ambient air quality standards. The Ports have been actively engaged in discussions with the TWG to reach agreement on the Standards since the CAAP was adopted in November 2006. The development of the Standards has been challenging, as no precedent existed that could be used as a framework. The Ports recently completed the Draft SPBS, which is currently under review by the other members of the SPBS working group, including the SCAQMD. The Ports anticipate that agreement between the TWG and the Ports on the SPBS will be achieved shortly, and at that time the Standards will be available for public review.

The primary purpose of the San Pedro Bay Standards will be to provide a valuable tool for long-term air quality planning, aiding the Ports and the agencies to achieve substantial reductions in the long-term cumulative air quality impacts of emissions from ongoing and future ports operations over time in conjunction with implementation of CAAP measures and existing regulations. In developing the San Pedro Bay Standards the Ports recognize the importance of ensuring that new projects are designed to be consistent with the CAAP, as well as with other applicable regulations, and that implementation of the project will allow the Ports to meet their longterm health risk and emission reduction goals. The forecasting used for developing the Health Risk Reduction and Emission Reduction components of the San Pedro Bay Standards was based on implementation of the CAAP through the specified implementation mechanisms, such as CEQA mitigations and terminal leases, and implementation of existing regulations. As long as a project meets the assumptions used to develop the San Pedro Bay Standards, including all then-applicable CAAP measures and regulatory requirements, as well as any new emissions control measures determined to be feasible, available and effective at reducing emissions covered under the Standards, then it will be consistent with the San Pedro Bay Standards. The Port of Long Beach has worked to ensure that the Middle Harbor Project fully meets these criteria; the proposed Project is consistent with the Draft San Pedro Bay Standards as it includes all applicable CAAP measures, existing regulations, and, in some areas exceeds compliance with applicable CAAP measures.

The Port has developed two programs with corresponding guidelines in an effort to mitigate potential cumulative air quality and noise impacts of projects in the San Pedro Bay Ports' area (including marine terminal expansions/modernizations for the Ports of Long Beach and Los Angeles and related transportation projects). In particular, the programs are designed to (1) reduce emissions (e.g., school bus diesel particulate matter (DPM) filters) and/or (2) exposure to air emissions and noise impacts directly (e.g., high-efficiency particulate air (HEPA) filters, noise berms, etc.) or though prevention, education, and outreach programs. The programs are specifically aimed at sensitive populations (i.e., school-age children, senior citizens, and persons with specific respiratory illnesses), which have been identified by state and local air agencies as particularly sensitive to air pollutants. One program is focused on school-age children; the Port has prepared *Schools and Related*

Sites Guidelines for the Port of Long Beach Grant Programs that identify eligible applicants as schools, preschools, and daycare centers where children spend a significant portion of their waking hours. The other program is focused on specific prevention, education, and outreach programs, as well as direct mitigation projects for hospitals, healthcare facilities, retirement homes, senior centers, and convalescent homes. The Port has prepared Healthcare and Seniors Facility Program Guidelines for the Port of Long Beach Grant Programs, which includes funding opportunities for prevention/education/outreach programs to help sensitive receptors which include children, senior citizens, and people with respiratory illnesses in areas determined to be most affected by cumulative air impacts near the ports as well as direct mitigation projects for certain facilities described previously. Mitigation Measure AQ-29.

The Port will fund mitigation projects and prevention programs for people sensitive to air pollutants, as well as certain noise mitigation projects. Projects/programs would be submitted to the Board of Harbor Commissioners by applicants for review and approval. The Grant Guidelines, adopted on March 23, 2009, establish: (1) the eligibility criteria for applicants and projects/ programs; (2) the ranking criteria for proposed projects/programs if proposal requests exceed available funding; and (3) review and approval procedures. Funding established by the approval of the Middle Harbor Project would enable the expeditious implementation of many cumulative impact mitigation projects and health-related prevention programs in the areas most directly affected by port area sources. These measures are designed to supplement source-reduction measures in the near term when cumulative impacts are predicted to be highest.

The Final EIS/EIR has thoroughly disclosed potential TACs emissions and associated cumulative impacts due to the Project and it has expended considerable effort to identify all feasible measures to mitigate these impacts. It would be technologically and economically infeasible and outside of the control of the Port or Project terminal tenant to implement any additional measures beyond those described above. Therefore, after mitigation, Project cumulative impacts to non-cancer levels would be significant and unavoidable.

Cumulative GHG Impacts

This impact represents the potential of proposed Project construction and operation in conjunction with other cumulative projects to cause a substantial increase in GHG emissions and contribute to climate change.

Finding

As described above (Section 3.4.1), the proposed Project in combination with related and cumulative projects would generate GHG emissions that would contribute to climate change. The Board hereby finds that changes or alterations have been incorporated into the Project that minimize the significant cumulative environmental effect identified in the Final EIS/EIR. Incorporation of **Mitigation Measures AQ-5**, **AQ-7a**, **AQ-9 through AQ-28**, however, would not reduce cumulative impacts below significance. Specific legal, economic, and technical considerations, as identified in Final EIS/EIR Section 10 and Attachment A of this document, make additional mitigation measures infeasible.

Rationale for Finding

Any concurrent emissions-generating activity that occurs worldwide would add additional air emission burdens to the GHG emission levels associated with the Project. It is unclear whether GHG emissions from the Project would make a significant contribution to the impact of global climate change when considered with GHG emissions generated by all natural and human activities. However, the Project GHG significance criterion states that any increase in GHG emissions is significant. Therefore, emissions of GHG from construction and operation of the mitigated Project would produce cumulatively considerable and unavoidable contributions to global climate change.

The Port is now in the process of developing a Climate Change/Greenhouse Gas (CC/GHG) Strategic Plan (CC/GHG Plan). This plan, which will be comprehensive in nature, will examine GHG impacts for all activities within the Harbor District, and will identify strategies for reducing the overall carbon footprint of those activities. Similar to the CAAP, the Port's GHG/CC Plan will identify strategies for activities under direct Port control and those that are the controlled by third parties, such as tenants. This Plan will outline the overall approach for mitigating potential project-specific and/or cumulative GHG impacts of projects through the modernization and/or upgrading of marine terminals and other facilities in the Long Beach Harbor District.

One element of the Port's CC/GHG Plan is the Greenhouse Gas Emission Reduction Program Guidelines (Guidelines). The Guidelines describe a procedure for the evaluation and prioritization of GHG emission reduction projects and practices that the Port may fund consistent with the Port's overall CC/GHG reduction goals. The Port has conducted an exhaustive search for additional measures that could feasibly mitigate GHG emissions from the proposed Middle Harbor Redevelopment Project. This included a thorough review of regulatory measures proposed or adopted by state, federal and international governments to reduce GHG emissions, measures being considered by goods movement industry organizations for voluntary implementation, and measures adopted by other public agencies in environmental impact statements or reports, master plans, climate action plans, or other environmental programs. In addition, the Port considered other technologies that may not have been used in a maritime port setting but could be transferred to the goods movement activities and applied to the Project. As discussed, under the Project-specific impacts under Impact AQ-8, new mitigation measures have been implemented in the Project to mitigate project-specific and cumulative GHG impacts from the Project.

The Final EIS/EIR has thoroughly disclosed potential GHG emissions and associated cumulative impacts due to the Project and it has expended considerable effort to identify all feasible measures to mitigate these impacts. It would be technologically and economically infeasible and outside of the control of the Port or Project terminal tenant to implement any additional measures beyond those described above. Therefore, after mitigation, Project cumulative impacts to global climate change would be significant and unavoidable.

3.5.2 Biota and Habitats

Cumulative Impact BIO-1: Special Status Species

This impact represents the potential of the proposed Project in conjunction with other cumulative projects to cause a substantial increase in vessel activity and corresponding potential for vessel strikes with blue whales within the cumulative region of influence.

Finding

The potential for a Project-related support vessel collision with a blue whale while in transit within the Long Beach Breakwater and Outer Harbor would be unlikely due to the infrequent presence of these mammals. Furthermore, all vessels would be required to slow to 12 knots when within 40 nm of Point Fermin as part of the VSRP (**Mitigation Measure AQ-4**). Normal swimming speeds of blue whales are 22 km/hr, which is approximately 10 knots; however, blue whales can swim up to 48 km/hr when alarmed (Wilson and Ruff 1999). Therefore, it is very unlikely that Project-related vessels traveling at 12 knots would increase the potential for whale strikes. No feasible measures are currently available to reduce whale strikes in the open ocean at greater than 40 nm from the harbor. However, in the event that a Project-related vessel strike with a blue whale did occur, it would make a cumulative contribution to significant and unavoidable impacts associated with vessel strikes to that species. The small increase in vessel traffic in the harbor (3.4 percent) caused by the Project would add to that cumulative potential, resulting in a significant cumulative impact.

The Board hereby finds that changes or alterations have been incorporated into the Project that minimize the significant environmental effect identified in the Final EIS/EIR. Incorporation of this mitigation measure and adherence to proposed environmental controls, however, would not reduce cumulative impacts below significance. Specific legal, economical, and technological considerations make additional mitigation measures infeasible.

Rationale for Finding

The list of related and cumulative projects was reviewed to determine if construction and operation activities associated with any of these projects could, in combination with the proposed Project, cause a cumulative increase in vessel activity and associated increase in potential vessel strikes to blue whales, a federally listed endangered species. Mortality of blue whales is a particular concern, and cumulative impacts would be significant and unavoidable for this species.

Cumulative marine terminal projects (e.g., Piers G & J (#2), Pier A East (#5), Pier S (#3) San Pedro Waterfront (#22), Channel Deepening (#15), Evergreen Redevelopment (#13), Pier 400 Oil Marine Terminal (#17),

Ultramar (#19), China Shipping (#14), Berths 171-181 (#16) would increase vessel transportation activity in the Long Beach Breakwater and Outer Harbor. The increase in vessel traffic, particularly large vessels travelling at greater than 10 knots, would increase the potential for vessel strikes of whales. Mortality of blue whales is a particular concern, and cumulative impacts would be significant and unavoidable for this species. It is reasonable to assume that cumulative projects would be required to adhere to VSRP regulations requiring vessels to slow to 12 knots within 40 nm of Point Fermin (CAAP Measure OGV1). As blue whales can swim up to 48 km/hr when alarmed (Wilson and Ruff 1999), it is very unlikely that vessels traveling at 12 knots would increase the potential for whale strikes. Although vessel strikes to blue whales would be unlikely to occur, any that did occur would make a cumulatively considerable contribution to significant and unavoidable cumulative impacts associated with vessel strikes to that species. No feasible measures are currently available to reduce whale strikes in the open ocean at greater than 40 nm from the harbor.

Comments USEPA(B)-12 and -34 suggested a sound alarm system be required to warn of the existence of whales. Because whale strikes by Project-related vessels could occur a considerable distance from the harbor, a warning system in nearshore waters would not prevent those strikes. Furthermore, the vessel traffic lanes along the coast are used by vessels that are not travelling to or from the harbor, and the ports have no authority to request those vessels to slow down when whales are present. Based on the reference cited in the comment, the warning system technology is still in the preliminary design stages. Because the location and species of whales (and their behaviors) are different, testing in the vicinity of the Long Beach — Los Angeles Harbor would need to be conducted to determine if this technology would be feasible and effective before it could be installed. Based on currently available information, this technology is not feasible for this Project at this time.

Cumulative Impact BIO-5: Disruption of Local Biological Communities

This impact represents the potential of the proposed Project in conjunction with other cumulative projects to cause a cumulatively substantial disruption of local biological communities (e.g., from the introduction invasive species).

Finding

The Project-related increase in vessel traffic in the harbor (3.4 percent) would add to the cumulative potential of introducing invasive species in the harbor, resulting in a cumulatively considerable effect. Ballast water discharges are now regulated, which has significantly reduced the potential for introduction of invasive exotic species. The potential for introduction of exotic species via vessel hulls has been reduced by using antifouling paints and periodic cleaning of hulls to minimize frictional drag from growth of organisms. However, due to the lack of a proven technology, no feasible mitigation measures are available to prevent introduction of invasive species via ballast water and/or vessel hulls. The Board hereby finds that specific technological considerations make additional mitigation measures infeasible that would reduce these impacts to less than significant levels.

Rationale for Finding

Cumulative marine terminal projects (e.g., Piers G & J (#2), Pier A East (#5), Pier S (#3) San Pedro Waterfront (#22), Channel Deepening (#15), Evergreen Redevelopment (#13), Pier 400 Oil Marine Terminal (#17), Ultramar (#19), China Shipping (#14), Berths 171-181 (#16)) that involve vessel transport of cargo into and out of the harbor would increase vessel traffic in harbor waters. Past, present, and reasonably foreseeable vessel traffic has introduced invasive exotic species into the harbor through ballast water discharges and via their hulls. Ballast water discharges are now regulated, which has significantly reduced the potential for introduction of invasive exotic species. The potential for introduction of exotic species via vessel hulls has been reduced by using antifouling paints and periodic cleaning of hulls to minimize frictional drag from growth of organisms. While exotic species are present in the harbor, there is no evidence that these species have disrupted the biological communities in the harbor. Biological baseline studies conducted in the harbor continue to show the existence of diverse and abundant biological communities. However, absent the ability to eliminate the introduction of new species through ballast water or on vessel hulls, it is possible that additional invasive exotic species could become established in the harbor, even with these control measures.

3.5.3 Ground Transportation

Cumulative Impact TRANS-2: Increase the Demand to Capacity Ratio at Study Area Highway Segments

This impact represents the potential of proposed Project construction and operations activities in conjunction with other cumulative projects to substantially impact the existing level of service on highway segments within the cumulative region of influence.

Finding

The Project when considered cumulatively would have significant impacts at certain study highway segments. Additional traffic generated by the Project to the cumulative background traffic conditions would deteriorate existing LOS at certain highway locations in the study area. Therefore, the Project would have a significant cumulative contribution to highway segment impacts.

The Port does not own, control, or maintain any of the impacted highway segments. These segments fall under the jurisdiction of Caltrans. Therefore, the Port does not have authority to unilaterally implement any mitigation measures on the highway segments. Accordingly, the Project's contribution to cumulative impacts during construction and operation would remain significant and unavoidable, even with implementation of **Mitigation Measure TRANS-2.1**, requiring the Project's fair-share contribution to Caltrans highway improvement programs. The Board hereby finds that changes or alterations have been incorporated into the Project that minimize the significant environmental effects identified in the Final EIS/EIR. If Caltrans does not adopt a fair share based program to collect funds for actual mitigation that Caltrans commits itself to implement, or obtain the balance of funding needed to improve the impacted study highway segments in a manner that will improve the segments level of operation, the Project's contribution to regional cumulative impacts on these freeway segments would remain significant and unavoidable. Specific legal, economical, and technological considerations make additional mitigation measures infeasible.

It should be noted that the Port is currently participating in on-going regional transportation programs, which are intended to address future regional traffic growth and resulting congestion on area freeways.

Rationale for Finding

The list of related and cumulative projects was reviewed to determine if construction and operation activities associated with any of these projects could, in combination with the proposed Project, cause cumulative impacts on highway segments in the cumulative region of influence. The Future Year Baseline model used in this analysis includes traffic from the related projects identified in Table 2.1-1 and Regional Transportation Plan projects to be in place as assumed in the SCAG's base model. The San Pedro Bay Ports growth is not an integral part of the SCAG model, but is added on top of the SCAG regional base model. The Ports model was also refined to provide more accurate assignment of special generator trips such as those in downtown Long Beach, San Pedro, and other projects in the Port vicinity. These reasonably foreseeable cumulative projects were incorporated in the Ports model to assess the cumulative background traffic growth in the study area.

A cumulative impact analysis was conducted to determine if Project-specific impacts on highway segments would together with the effects of other related projects, result in cumulatively significant impacts. The comparison of the Project and alternatives to the Future Year Baseline conditions primarily constitutes the cumulative impact analysis and is presented in Final EIS/EIR Sections 3.5.2.3. Both construction and operation of the Project would contribute to the cumulative significant traffic impacts at certain highway locations.

It can be assumed that until Caltrans implements improvements on the I-710, I-405, and SR-91 highway segments, the Project would have significant impacts at these locations. Therefore, impacts on highway segments would be significant and unavoidable.

Comment CBD-69 suggested increased public transit as a way to mitigate impacts to freeway segments. However, increased public transit would not take Project trips off the road. It is not a technically or economically feasible mitigation measure. The public does not travel to the Project site. The vehicle traffic generated

by the Project will be largely truck traffic that would not involve public transit. Terminal operators currently operate shuttles to transport longshoremen to the terminals when ships arrive. This practice will continue and is part of the Clean Air Action Plan that the Port will continue to enforce through leases with the terminal operators. Therefore, increased transit service would not address Project traffic issues.

Comment CBD-70 suggested employee-model truck programs to reduce trips to the Project site. However, employee-model truck programs have not yet been proven to improve truck efficiency and reduce truck traffic. There have not been any comprehensive studies supporting a finding that the employee-model reduces commute-only truck trips. Nor have there been documented findings on efficiency differential since an owner-operated truck could also be used for multiple shifts. In fact, under the POLA concession more personal trips by truck drivers will likely occur as they commute to and from work site for their shifts. Such increase in personal trips would simply shift traffic congestion from one region to another and yield no environmental benefit. The employee-model truck program is not technically, legally, or socially a viable mitigation measure.

Comment SCAQMD-7 and CBD-20 proposed increasing the amount of cargo that moves from the Project by on-dock rail. Increased use of on-dock rail above and beyond the Project is not a technically feasible mitigation measure. Every effort was made from the design and operation perspective to maximize the rail yard capacity, taking into account the need for the additional container yard capacity necessary to accommodate projected demand. Even were there a legitimate need for more on-dock rail capacity, which there is not, the planned on-dock rail yard could not be expanded into the planned container yard because overall terminal capacity would be reduced, thus creating a less efficient terminal. In light of the physical constraints of the site and the need to provide sufficient container yard capacity to handle the projected cargo throughput, the proposed Project maximizes on-dock rail capacity. The proposed re-use of this site has been carefully planned to ensure adequate space for operations, storage, and trackage that will result in an increase of 613,160 TEUs between the 2030 No Project and 2030 Project alternatives (the only difference in throughput being the design of the site). Moreover, a sizeable amount of the Project throughput will be made up of low-volume destination cargo that must be assembled at the near- and off-dock rail yards throughout the region. Specifically, lowvolume-destination containers (i.e. non-Chicago-bound containers) oftentimes cannot wait for a unit train to be built on-dock. Rather, these boxes are assembled off-dock from multiple terminals in order to achieve the appropriate volumes to generate a single train in a timely fashion. Therefore, some direct intermodal containers will always need to be drayed to the Intermodal Container Transfer Facility, Hobart Yards, and other rail yards throughout the region regardless of the size of the on-dock rail yard at Middle Harbor.

Comments SCAQMD-27, CBD-20, CBD-21, CBD-71, CBD-100, CSE(A)-3, CSE(A)-4, CSE(B)-3, and JW-3 suggested Maglev or electrified rail. CBD-71 and CSE(B)-3 also suggested the construction of an intermodal facility on Port property, such as the import car lot off Anaheim Street, as ways to reduce truck trips. However, Maglev and an intermodal facility at the import car lot are not feasible mitigation measures. The Port is in the process of reviewing possible zero- or near-zero emission transport technologies as envisioned in the CAAP. In 2007, Cambridge Systematics prepared the Alternative Container Technology Evaluation and Comparison assessment for the Ports of Long Beach and Los Angeles. The Port is exploring feasible technologies and in 2009 will release a Request for Proposals for the design of a zero- or low-emission container movement demonstration project between one marine terminal and a near-dock rail facility. The demonstration project will address certain key issues that will help determine whether this technology can be feasibly employed in Port operations, including the functionality of the system, the availability of rights-of-way to accommodate the system, the capital costs for the construction of the system and the costs of operations and maintenance, and the needed interface between the terminals and the rail yards. Should the Port's demonstration project establish that a zero- or near-zero emission transport technology is operationally and financially feasible, the Port will investigate expanding the system to include the Middle Harbor operations. At this point, the Board finds that t is not financially or operationally feasible to include a zero- or near-zero emission transport technology as a mitigation measure for the Project. However, the Final EIS/EIR includes a new Mitigation Measure AQ-25 that requires the terminal tenant in 2015 and every 5 years thereafter, to review new air quality technological advancements for the purpose of implementing new feasible mitigations. Electrification of the rail corridors is well outside of the scope of the Project. Electrifying the Alameda Corridor has been studied fully and is not being pursued for several reasons, including operational feasibility during loading/unloading of trains and environmental and fiscal impacts of constructing a new power plant that could supply a sufficient source of power. The Southern California Association of Governments conducted a study on electrifying the Southern California rail system in the 1990s and concluded it was prohibitively expensive to do so, and thus infeasible at that time. Electrifying the region's rail system is still being evaluated to address air quality attainment objectives. The cost to electrify rail in Southern California was estimated to be in excess of \$6 billion, thus it is an economically infeasible mitigation measure. Regarding construction of a parking structure to free up space for a Maglev system, the cost per parking space for a parking structure ranges from \$20,000 to \$25,000. Constructing a 4 or 5-story parking structure on Pier B, which is leased terminal space, would greatly limit future lease options and could significantly constrain the future use on this terminal. Not only is Maglev not yet a proven alternative, but the cost of constructing a parking structure for a limited period of time is economically infeasible.

Comment SCAQMD-7 proposed adding unsorted trains as an operational feature of the Project. However, this suggestion would not enhance on-dock rail capacity or mitigate any traffic impact o the Project. It should be understood that Parson's rail yard capacity model assumes that trains are fed constantly with containers, in essence mimicking the effect of building unsorted trains. Consequently, the capacity numbers would not be increased by including unsorted trains as an alternative operating procedure. Further, the Class-1 railroads (UP and BNSF) already have the ability to sort unsorted trains inland, and the railroads will do so if, and when, it makes business and operating sense. This decision involves a change in business operations, and it is not within the control of the Port to unilaterally impose such a condition, especially since the feasibility of such a condition has not yet been established. The Port is currently undertaking a feasibility study to explore other opportunities for inland port operations (not to be confused with maximizing on-dock rail capacity) that would minimize truck trips.

No additional traffic mitigation measures have been identified at this time. Unless Caltrans implements a mechanism to assess a fair share contribution, the Project's traffic impacts will be significant and unavoidable.

3.5.4 Noise

Cumulative Construction Noise Impacts

This impact represents the potential of proposed Project construction activities in conjunction with other cumulative projects to cause a substantial increase in ambient noise levels at sensitive receptors within the cumulative region of influence.

Finding

All of the projects listed in Final EIS/EIR Table 2.1-1 would have some potential for construction noise impacts, with the exception of the projects that do not involve construction activities (i.e., Berths 206-209 Interim Container Terminal Reuse Project and Ultramar Lease Renewal Project). Where project construction schedules overlap, there is the potential for cumulative construction noise impacts because multiple sources could jointly contribute to increases in ambient noise at one or more locations.

Due to the difficulty of effectively mitigating substantial noise-generating activities, adherence to standard controls and construction of temporary noise barriers would not be sufficient to reduce projected increases in ambient noise levels to the point where it would no longer cause a substantial increase. Therefore, during construction, the Project's contribution to cumulative impacts would remain significant and unavoidable, even with implementation of **Mitigation Measures NOI-1.1a and NOI-1.1b**, and adherence to modern construction engineering and safety standards.

To help address the significant cumulative construction noise impacts of the Project, the Port will require this Project to fund the Schools and Related Sites Program that was adopted by the Board of Harbor Commissioners on March 23, 2009, as required by **Mitigation Measure AQ-29**. The funding will be used for eligible noise mitigation projects as specified in the Schools and Related Sites Program Guidelines. The guidelines: (1) establish eligibility criteria for potential applicants based on facility type and proximity to the San Pedro Bay Ports; (2) provide metrics that will be used to assess a proposed project's noise impact mitigation potential based on established regulatory mitigation programs and recent scientific information on noise impacts, and (3) explains how the Port of Long Beach Harbor Commissioners will choose among eligible proposals and approve funding.

The Board hereby finds that changes or alterations have been incorporated into the Project that minimize the significant environmental effect identified in the Final EIS/EIR. Incorporation of these mitigation measures,

however, would not reduce cumulative noise impacts below significance. Specific legal, economical, and technological considerations make additional mitigation measures infeasible.

Rationale for Finding

The list of related and cumulative projects was reviewed to determine if construction activities associated with any of these projects could, in combination with the proposed Project, cause a cumulative construction noise impact.

The Chemoil Marine Terminal Tank Installation Project (#6) would be located immediately adjacent to Pier F container terminal improvements element of the proposed Project. It is likely that construction activities associated with the Chemoil Marine Terminal Tank Installation Project would be concurrent with construction activities necessary for the proposed Pier F improvements, or would occur in about the same timeframe, extending the period of elevated noise levels. While a detailed assessment of construction noise levels that could result from this related project has not been completed, it is likely that construction activities and associated noise levels would be similar to those expected from the proposed Project. There are other projects in the related and cumulative project list that could also affect sensitive receptors within the cumulative region of influence. The Administration Building Replacement Project (#8) that was approved in 2008 is located in close proximity to sensitive receptors at the West Coast Long Beach Hotel. The I-710 Major Corridor Study (#36), which is in the conceptual planning stages, is located adjacent to sensitive receptors along the I-710 corridor. The City of Long Beach Shoreline Gateway Project (#11) that would include a mixed-use development north of Ocean Boulevard, between Atlanta Avenue and Alamitos Avenue, would be located east of sensitive receptors at the Long Beach Hilton.

One comment was received during the public review period that suggested mitigation to reduce this significant unavoidable impact (Comment LBUSD-20). The comment proposed limiting construction activities during school hours of operation and testing periods, which has been incorporated into the Project's construction noise controls as a notification requirement. Furthermore, Final EIS/EIR **Mitigation Measure NOI-1.1a** has been modified to require installation of temporary noise barriers between pile driving activities and Cesar Chavez School.

3.6 Finding Regarding Responses to Comments on the Draft EIS/EIR

The Board of Harbor Commissioners finds that information added to the EIS/EIR after public notice of the availability of the Draft EIS/EIR for public review, but before certification merely clarifies or makes minor modification to an adequate EIS/EIR and does not require recirculation.

Recirculation is required only when "significant" new information is added to an EIR after public review and comment on the draft EIR but before certification. (PRC § 21092.1) Not all new information added to an EIR is "significant." According to the CEQA Guidelines, new information added to an EIR is significant only if "the EIR is changed in a way that deprives the public of a meaningful opportunity to comment upon a substantial adverse environmental effect of the project or a feasible way to mitigate or avoid such effect (including a feasible project alternative) that the project's proponents have declined to implement." (14 C.C.R. § 15088.5). Examples of significant new information include: (1) a new significant impact of the project or from a new mitigation measure proposed to be implemented; (2) a substantial increase in the severity of an environmental impact for which no mitigation measures are added which reduce the impact to a level of insignificance; or (3) a feasible project alternative or mitigation measure considerably different from others previously analyzed would clearly lessen the environmental impacts of the project, but the project proponent declines to adopt it. Based on these standards, there is no reason to recirculate the Draft EIS/EIR. Although some new information has been added to the Final EIS/EIR in response to comments, none of the information is significant. No new impacts have been identified, the severity of the impacts identified in the Draft EIS/EIR are not substantially increased over what is described in the document, and no feasible alternatives or mitigation measures were identified which would clearly lessen the environmental impacts of the Project.

4.0 ALTERNATIVES TO THE PROPOSED PROJECT

CEQA Guidelines Section 15126.6 requires that an EIR examine alternatives to a project in order to explore a reasonable range of alternatives that meet most of the basic project objectives, while reducing the severity of potentially significant environmental impacts. CEQA Guidelines Section 15126.6(a) states:

An EIR shall describe a range of reasonable alternatives to the project, or to the location of the project, which would feasibly attain most of the basic objectives of the project but would avoid or substantially lessen any of the significant effects of the project, and evaluate the comparative merits of the alternatives. An EIR need not consider every conceivable alternative to a project. Rather it must consider a reasonable range of potentially feasible alternatives that will foster informed decision making and public participation. The lead agency is responsible for selecting a range of project alternatives for examination and must publicly disclose its reasoning for selecting those alternatives. There is no ironclad rule governing the nature or scope of the alternatives to be discussed other than the rule of reason.

The alternatives were also assessed in accordance with CEQA Guidelines Section 15126.6(f) which states:

The range of alternatives required in an EIR is governed by a "rule of reason" that requires the EIR to set forth only those alternatives necessary to permit a reasoned choice. The alternatives shall be limited to ones that would avoid or substantially lessen any of the significant effects of the Project. Of those alternatives, the EIR need examine in detail only the ones that the lead agency determines could feasibly attain most of the basic objectives of the project.

Ten alternatives were considered during preparation of this EIS/EIR, including alternative terminal configurations and locations. However, only four alternatives meet most of the proposed Project's objectives and have been selected to be carried forward for detailed analysis (Section 4.2). Alternatives considered but not carried forward are addressed in Section 4.1.

4.1 Alternatives Considered but Not Carried Forward for Analysis

The screening process used in the EIS/EIR to evaluate a reasonable range of alternatives was based on the Project's objectives (Section 2.1). Screening criteria were also used to determine feasibility in accordance with the Port's legal mandates under the state Tidelands Trust and the Long Beach City Charter. The Port is one of only five locations in the State identified in the California Coastal Act (CCA) for the purposes of international maritime commerce. These mandates identify the Port and its facilities as an essential element of the national maritime industry. Port activities should be water dependent and give highest priority to navigation, shipping, and necessary support facilities to accommodate the demands of foreign and domestic waterborne commerce. Based on existing capacity limitations on industrial Port uses, the majority of industrial facilities adjacent to deep water are required to accommodate forecasted increases in containerized cargo.

Alternatives that are remote or speculative, or the effects of which cannot be reasonably predicted, need not be considered (CEQA Guidelines, Section 15126[f][2]). Alternatives may be eliminated from detailed consideration in an EIR if they fail to meet most of the project objectives, are infeasible, or do not avoid any significant environmental effects (CEQA Guidelines, Section 15126.6[c]). The following alternatives were considered but eliminated from further discussion in the EIS/EIR. Additional details regarding the rationale for decisions to eliminate alternatives from detailed analysis are included in Final EIS/EIR Section 1.6.2. Those alternatives are:

- Construction of a new near-dock intermodal container railyard to serve multiple marine terminals;
- Use of other North American ports (i.e., those located on the West, East, and Gulf Coasts) to accommodate the Port's forecasted increases in container cargo;
- Expansion of marine terminals within southern California but outside of the Long Beach Harbor;
- Inland port (an intermodal facility for exclusive handling of international cargo);
- Marine terminal automation; and

• Offsite backlands facility alternative (i.e., using underdeveloped land outside the Port as a container storage and handling facility).

An additional alternative was identified by the U.S. Environmental Protection Agency (EPA) during the Draft EIS/EIR public review period. The proposed alternative would not include any fill activities, but would provide deeper water (-55 feet MLLW) at berths and in basins and channels to accommodate the current and expected future generations of cargo vessels. However, under this alternative the existing terminal areas would remain insufficient to support the activities and modern equipment necessary to efficiently and safely handle the anticipated containerized cargo volumes. Furthermore, Slips 1 and 3 would remain too narrow (395 feet and 364 feet, respectively) for the current larger vessels that require a width of approximately 480 feet to maneuver safely up to and away from the existing berths; and Pier E docks and adjacent backland areas would be separated from the intermodal rail facilities on Pier F, resulting in an existing Pier E terminal that would be inadequately connected to the essential infrastructure required to handle intermodal containerized cargo. Also, as dredged material would not be reused under this alternative, the Port would need to locate new disposal locations and conduct additional sediment characterization. Therefore, this alternative was eliminated from further consideration in the Final EIS/EIR and is considered infeasible.

4.2 Alternatives Analyzed in the Draft EIS/EIR

Four alternatives meet most of the proposed Project's objectives and were selected to be carried forward for detailed analysis in the EIS/EIR. The alternatives carried forward for detailed analysis include:

- Alternative 1 345-Acre Alternative (the Project);
- Alternative 2 315-Acre Alternative;
- Alternative 3 Landside Improvements Alternative; and
- Alternative 4 No Project Alternative.

Final EIS/EIR Chapter 4 presents a comparison of the proposed Project to the alternatives that were considered during preparation of the Final EIS/EIR. The four alternatives are summarized in Table 4.2-1. Table 4.2-2 summarizes the results of the impact analysis for the proposed Project and alternatives.

Table 4.2-1. Summary of Proposed Project and Alternatives at Full Buildout						
	Alternative 1: 345-Acre Alternative (the Project)	Alternative 2: 315-Acre Alternative	Alternative 3: Landside Improvements Alternative	Alternative 4: No Project Alternative		
Project Site Gross Acreage	345	315	294	294		
Total Container Terminal Acreage	322	292	267	244		
Total TEUs ²	3,320,000	2,870,000	2,910,000	2,600,000		
Annual Vessel Calls	364	364	416	312		
Average Daily Truck Trips	10,112	8,026	9,830	9,594		
Annual Trains ³	2,098	2,095	1,380	786		
Total Container Berth Length (LF)4	4,250	4,250	4,480	4,480		
Joint Terminal Intermodal Yard Acreage	47	47	25	05		

Notes.

- The total container yard acreage is assumed to be slightly smaller than the Project site area due to other uses on the site (e.g., breakbulk cargo). The container yard is defined as the area dedicated to container activities, wharves, and spaces related to buildings and personal vehicles.
- TEUs = Twenty-foot Equivalent Units. The TEU-per-acre estimates are based on the approximate size of the container yard projected for year 2025.
- 3. Estimate assumes 25 rail cars per train.
- 4. All Pier D berths and E-12-13 are break-bulk berths and are not included in container berth length. The total container berth lengths include both Pier E and Pier F berths.
- 5. Assumes the existing LBCT nine acre intermodal railyard would remain operational.

Sources: Moffatt & Nichol. 2006b. Middle Harbor Container Terminal EIS/EIR Documents Backup, February 16.

Table 4.2-2. Summary of CEQA Significance Analysis by Alternative						
Environmental Resource Area	Alternative 1: 345 Acre Alternative	Alternative 2: 315 Acre Alternative	Alternative 3: Landside Improvements Alternative	Alternative 4: No Project Alternative		
Geology, Groundwater, and Soils	III	III	111	111		
Air Quality and Health Risk	1	1	l	111		
Hydrology and Water Quality	III		III]]]		
Biota and Habitats	1		l	l l		
Ground Transportation	i i		l	1		
Vessel Transportation	ill	III	III	III		
Land Use	111	III	III	III		
Public Services/Health and Safety	11	II	ll l	111		
Noise	i	ı	l	IV		
Hazards and Hazardous Materials	III	III	111	111		
Recreation	III	III	111	IV		
Socioeconomics	III	III	III	III		
Utilities and Service Systems	III		III	ill		
Cultural Resources	II .	11	11	IV		
Environmental Justice	I	I	III			
Aesthetics/Visual Resources	III	111	III	III		

Notes:

I = Unavoidable significant impact

II = Significant but mitigable impact

III = Less than significant impact (not significant)

IV = No impact

4.3 Findings for Alternatives Analyzed

Project Purpose

The purpose of the Project is to increase and optimize the cargo handling efficiency and capacity of the Port, by constructing sufficient berthing and infrastructure capacity to accommodate a proportional share of foreseeable increases in containerized cargo. Additional Project purposes include improving marine terminal operational efficiency that would expand the use of existing waterways for international maritime commerce, and upgrading utility infrastructure to support the implementation of environmental controls necessary to reduce pollution and conserve energy.

The Port is operated under legal mandates of the Tidelands Trust, which identify the Port and its facilities as a primary economic/coastal resource of the State and an essential element of the national maritime industry for promotion of commerce, navigation, fisheries, and harbor operations. According to the Tidelands Trust, Port-related activities should be water dependent and should give highest priority to navigation, shipping, and necessary support and access facilities to accommodate the demands of foreign and domestic waterborne commerce.

Project Objectives

The objectives of the Middle Harbor Redevelopment Project are to:

- 1. Consolidate common operations and wharves of two terminals (Piers E and F) into one terminal;
- 2. Rehabilitate and modernize existing primary Port facilities, including replacement of obsolete and deteriorated wharf structures with adequate, well-equipped wharf areas, along with channels and berths of sufficient width, length, and depth to allow access to the docks by existing and future cargo vessels, and provide for replacement of obsolete gantry cranes with new generation cranes that are able to reach across the new, larger vessels;
- 3. Implement the Green Port Policy (Section 1.7.1) and the CAAP (Section 1.7.2);
- 4. Provide for efficient terminal traffic flow and cargo handling operations; and

 Link new and improved dock and wharf operations to planned and existing on-dock intermodal railyard facilities and separate on-dock intermodal terminal lead track operations (i.e., loading/unloading and switching) from mainline track operations.

4.3.1 Alternative 1 – 345-Acre Alternative (the Project)

The Project would rehabilitate or replace deteriorated and obsolete terminal facilities; provide deeper water (-55 feet Mean Lower Low Water [MLLW]) at berths and in basins and channels; create new land; modernize marine terminal facilities; and implement environmental controls, including the Port's Green Port Policy and CAAP, to accommodate a portion of the predicted future increases in containerized cargo volume and the modern, larger cargo vessels that are expected to transport these goods to and from the Port. The existing 294-acre Project site would be increased to 345-acres, including 54.6 net acres of newly created land. The Project includes terminal consolidation, redevelopment, and expansion on areas of existing and newly created land, dredge and fill operations, wharf construction to create three deep water berths with -55 feet MLLW depths, and rail infrastructure improvements (e.g., mainline track realignment at Ocean Boulevard/Harbor Scenic Drive, Pier F Avenue storage yard and tracks, Pier F tail track, and expanding the existing Pier F intermodal railyard). The Project would include construction of a 66kV substation (Pier E Substation) to provide power that would support Middle Harbor container terminal operations, including supplying shore-to-ship power, and future power needs for other Port facilities.

Project construction would occur in two phases, the first phase in five stages and the second in four stages, and would be scheduled for completion in 2019 (i.e., Project build-out year). However, the proposed Middle Harbor container terminal is forecasted to be fully optimized at maximum capacity by 2025. Detailed construction elements of the Project are presented in Final EIS/EIR Section 1.6.3.1.

When completed, the Project would consist of one consolidated container terminal that would be designed to load and unload containerized cargo to and from marine vessels. When optimized at maximum throughput capacity (by year 2025), the consolidated container terminal would be designed to accommodate approximately 3,320,000 TEUs per year. The proposed expanded Pier F intermodal railyard would handle approximately 26.3 percent (873,160 TEUs per year) of the terminal's expected throughput. Middle Harbor container terminal operations would result in a maximum of approximately 364 vessel calls per year. Truck trips to and from the Middle Harbor container terminal would increase from the 2005 baseline average of 6,528 trips per day to an average of approximately 10,112 trips per day in the year 2030. Approximately 2,098 annual train trips would be required at maximum capacity in 2025 to support Middle Harbor container terminal operations. The terminal would operate under a new lease between the terminal operator and the Port that would include environmental controls imposed pursuant to the Port's Green Port Policy and the CAAP. This EIS/EIR assumes the proposed Project includes participation in the POLB/POLA Vessel Speed Reduction Program (VSRP) (CAAP measure OGV1) and compliance with applicable U.S. Environmental Protection Agency (EPA), California Air Resource Board (ARB), and South Coast Air Quality Management District (SCAQMD) regulations.

Finding

The Board hereby finds that the proposed Project is the only feasible alternative that best meets the Project objectives of maximizing the cargo handling efficiency and capacity of the Port, and for the reasons set forth in the Statement of Overriding Considerations (Section 5.0), the benefits of the proposed Project justify its approval.

Facts in Support of Finding

The Project would rehabilitate or replace deteriorated and obsolete terminal facilities; provide deeper water (-55 feet MLLW) at berths and in basins and channels; create new land; modernize marine terminal facilities; provide rail infrastructure improvements (e.g., mainline track realignment at Ocean Boulevard/Harbor Scenic Drive, Pier F Avenue storage yard and tracks, Pier F tail track, and expansion of the existing Pier F intermodal railyard); construct a 66kV substation to support Middle Harbor container terminal operations, including shore-to-ship power; and implement environmental controls, including the Port's Green Port Policy and CAAP, to accommodate a portion of the predicted future increases in containerized cargo volume and the modern, larger cargo vessels that are expected to transport these goods to and from the Port. Project throughput volumes (3,320,000 TEUs) would adequately accommodate forecasted container throughput growth at the Port. This

approach is consistent with the CZMA and the CCA that encourage modernization of existing facilities within existing Port boundaries.

4.3.2 Alternative 2 - 315-Acre Alternative

The 315-Acre Alternative would add 24.7 net acres of newly created land to the existing 294-acre Project site by filling Slip 1 between Piers E and F (Berths E12-E14 and F1-F4). This alternative would include terminal expansion on adjacent areas of existing and newly created land, dredge and fill operations, and new wharf construction. Under the 315-Acre Alternative, a new wharf would be constructed to handle increased cargo throughput and accommodate deep-draft container ships, and to replace existing, insufficient wharves. The new 2,900-foot wharf would consist of two deep water berths with -55 feet MLLW depth. Buildout under this alternative would include the rail improvements identified for the Project (e.g., mainline track realignment at Ocean Boulevard/Harbor Scenic Drive, Pier F Avenue storage yard and tracks, Pier F tail track, and expanding the existing Pier F intermodal railyard). The proposed 66kV Pier E Substation would also be constructed, as described for Alternative 1.

When completed, the 315-Acre Alternative would consist of one consolidated container terminal that would be designed to load and offload containerized cargo from marine vessels. When optimized at maximum throughput capacity (anticipated by approximately 2025), the consolidated container terminal would be designed to accommodate approximately 2,870,000 TEUs per year. The proposed expanded Pier F intermodal railyard would handle approximately 30.4 percent (872,480 TEUs per year) of the terminal's expected throughput. Under this alternative, Middle Harbor container terminal operations would result in approximately 364 maximum vessel calls per year. Truck trips to and from the Middle Harbor container terminal would increase from the 2005 baseline average of 6,528 trips per day to an average of approximately 8,026 trips per day in 2030. Approximately 2,095 trips annual train trips would be required at maximum capacity in 2025 to support Middle Harbor container terminal operations.

The terminal would operate under a new lease between the terminal operator and the Port that would include environmental controls imposed pursuant to the Port's Green Port Policy and the CAAP. Similar to the Project, this EIS/EIR assumes Alternative 2 would include participation in the POLB/POLA VSRP (CAAP measure OGV1) and compliance with applicable EPA, ARB, and SCAQMD regulations.

Finding

The Board hereby finds that Alternative 2 (315-Acre Alternative) would not meet the overall Project purpose and need of increasing container terminal efficiency to accommodate a portion of the predicted future containerized cargo throughput volumes. Therefore, the Board finds that Alternative 2 is infeasible relative to fulfilling the overall Project purpose and need and will not be adopted in lieu of the proposed Project.

Facts in Support of Finding

Alternative 2 would be similar to the proposed Project except that the 34.3-acre East Basin area would not be filled and the Berth E23 wharf would not be constructed. The elimination of the East Basin fill and Berth E23 wharf would decrease container movement efficiency compared to the Project. Alternative 2 would result in the consolidation of common operations and wharves of the existing two terminals on Piers E and F into one terminal, as would occur under the proposed Project. However, under this design the available area along the expanded Pier F intermodal railyard would be substantially limited in width and, consequently, would not support efficient access by trucks transporting containerized cargo. Therefore, under Alternative 2 the proposed terminal areas would not support the activities and modern equipment necessary to efficiently and safely handle the anticipated containerized cargo volumes. Overall, Alternative 2 would be less environmentally damaging than the Project; however, it would not meet the overall Project purpose and need of increasing container terminal efficiency to accommodate a portion of the predicted future containerized cargo throughput volumes.

4.3.3 Alternative 3 – Landside Improvements Alternative

The Landside Improvements Alternative would redevelop existing terminal areas on Piers E and F and convert underutilized land north of the Gerald Desmond Bridge and Ocean Boulevard within the Project site to a container yard (Final EIS/EIR Figure 1.6-10). The alternative would include construction of the following upland

site improvements: redevelopment and backland expansion on existing lands within the Project site (the Berth E23 oil area would be abandoned and redeveloped as container yard area); construction of a new 66 kV Pier E Substation; and construction of shore-to-ship infrastructure at Piers E and F to cold-iron vessels while at berth. This alternative would also include construction of a mainline track realignment at Ocean Boulevard/Harbor Scenic Drive and the Pier F storage yard and tracks. The alternative would expand the existing Pier F intermodal railyard to six tracks.

When completed, the Landside Improvements Alternative would consist of a consolidated container terminal that would be operated by one terminal operator. The terminal would be operated under a new lease between the terminal operator and the Port that would include environmental controls imposed pursuant to the Port's Green Port Policy and the CAAP. In addition to compliance with applicable EPA, ARB, and SCAQMD regulations assumed for the Project, Alternative 3 would implement all applicable CAAP measures and regulations, including emission standards for terminal equipment (CAAP measure CHE1), the VSRP (CAAP measure OGV1), low-sulfur fuel requirements for vessels (CAAP measures OGV3 and OGV4), OGV cold-ironing (CAAP measure OGV2), and the POLA/POLB Clean Trucks Program (CAAP measure HDV1).

When optimized at maximum throughput capacity (anticipated by approximately 2025), the terminals would be designed to accommodate a combined total of about 2,910,000 TEUs per year. Approximately 416 vessel calls per year would be expected by 2025. This alternative would result in 9,830 average daily truck trips to and from Middle Harbor terminals in 2030. Approximately 1,380 train trips per year would be required to support Middle Harbor container terminal operations at maximum capacity in 2025.

Under this alternative, there would be no in-water activities (e.g., dredging, filling Slip 1 and the East Basin, new wharf construction) as proposed for the Project, no wharf upgrades would occur (except the provisions for shore-to-ship power), and channel and berth deepening would not occur.

Finding

The Board hereby finds that while Alternative 3 (Landside Improvements Alternative) would not meet the overall Project purpose of increasing and optimizing the cargo handling efficiency and capacity of the Port, by constructing sufficient berthing and infrastructure capacity to accommodate a proportional share of foreseeable increases in containerized cargo. Alternative 3 would not allow for improving marine terminal operational efficiencies that would expand the use of existing waterways for international maritime commerce. Therefore, the Board finds that Alternative 3 is infeasible and will not be adopted in lieu of the proposed Project.

Facts in Support of Finding

Under Alternative 3, there would be no in-water activities (e.g., dredging, filling Slip 1 and the East Basin, new wharf construction) as proposed for the Project, no wharf upgrades would occur (except the provisions for shore-to-ship power), and channel and berth deepening would not occur. Accordingly, this alternative would not meet the Project objectives associated with constructing sufficient berthing and infrastructure capacity to accommodate the modern cargo vessels that would transport goods to and from the Port. Furthermore, Alternative 3 would not best optimize the use of existing waterways consistent with the Port's overall use of available shoreline, accommodate foreseeable containerized cargo volumes through the Port, increase container handling efficiency including on/offloading of container ships in a safe and efficient manner, and improve or construct container ship berthing and infrastructure capacity where necessary to accommodate projected containerized cargo volumes through the Port. Because of the lack of waterside improvements, this alternative does not maximize use of the larger modern ships and would result in limited cargo capacity due to berth constraints.

4.3.4 Alternative 4 - No Project Alternative

This alternative considers what would reasonably be expected to occur on the site if the Port did not implement the proposed Project. The Port would take no further action to construct additional backlands or redevelop the 294 acres that currently exist. The USACE would not issue permits for dredge and fill or wharf construction activities. This alternative would not allow implementation of the proposed Project or other physical improvements at Middle Harbor. The No Project Alternative would maintain the current CUT and LBCT con-

tainer terminals at a combined size of 294 acres and in their current configuration. Forecasted increases in cargo would still occur as greater operational efficiencies are implemented.

Under this alternative no construction and, consequently, no construction-related impacts would occur. However, the two terminals would continue to generate operational impacts: cargo ships that currently berth and load/unload at the terminal would continue to do so; terminal equipment would continue to handle cargo containers; and trucks would continue to transport containers to outlying distribution facilities. Because no rail improvements would be constructed under this alternative, the majority of the intermodal cargo to and from the two terminals would continue to be hauled by truck. In addition, the Pier E Substation would not be constructed, which would eliminate the potential for vessels to cold-iron under this alternative. However, in addition to environmental controls imposed by federal, state, and local regulatory agencies, the terminal would implement the POLB/POLA VSRP (CAAP measure OGV1) under this alternative. No other CAAP measures would be implemented under this alternative.

The No Project Alternative would result in a maximum throughput of approximately 2,600,000 TEUs per year. Approximately 312 vessel calls per year would be expected by 2025. As the existing Pier F intermodal railyard would remain operational, proposed terminal operations would result in approximately 786 annual train trips. This alternative would result in approximately 9,594 average daily truck trips to and from Middle Harbor terminals in 2030.

Finding

The Board hereby finds that the No Project Alternative is infeasible and will not achieve the majority of the overall Project objectives. Therefore, this alternative will not be adopted in lieu of the proposed Project.

Facts in Support of Finding

If the No Project Alternative were implemented, the Port would not be able to accommodate the projected increased in containerized cargo throughput volumes and the modern cargo vessels that transport those goods to and from the Port. Under this alternative, existing site conditions would constrain the ability of Middle Harbor to function as modern and efficient primary Port facilities. The lack of waterside and upland improvements would mean that the current inefficiency of cargo movement through the site's existing marine terminals would continue. As Pier E has minimal rail capability (i.e., Slip 1 separates Pier E docks and backlands from existing intermodal rail facilities) and the existing intermodal Pier F railyard is too small to accommodate regular service of modern intermodal trains, the No Project Alternative would not provide sufficient rail infrastructure to handle intermodal containerized cargo. Additionally, without the necessary dredging to deepen the channels and berths in the Middle Harbor to the planned -55-foot MLLW depth, the existing marine terminals would be limited in their ability to service modern, large, deep-draft cargo ships.

5.0 STATEMENT OF OVERRIDING CONSIDERATIONS

CEQA requires a public agency to balance the benefits of a proposed project against its unavoidable, adverse environmental impacts in determining whether to approve the project.

Section 15093 of the State CEQA Guidelines provides the following:

- (a) CEQA requires the decision-making agency to balance, as applicable, the economic, legal, social, technological, or other benefits of a proposed project against its unavoidable environmental risks when determining whether to approve the project. If the specific economic, legal, social, technological, or other benefits of a proposed project outweigh the unavoidable adverse environmental effects, the adverse environmental effects may be considered "acceptable."
- (b) When the lead agency approves a project which will result in the occurrence of significant effects which are identified in the Final Environmental Impact Report (Final EIR) but are not avoided or substantially lessened, the agency shall state in writing the specific reasons to support its action based on the Final EIR and/or other information in the record. The statement of overriding considerations shall be supported by substantial evidence in the record.

(c) If an agency makes a statement of overriding considerations, the statement should be included in the record of the project approval and should be mentioned in the notice of determination. This statement does not substitute for, and shall be in addition to, finding required pursuant to Section 15091.

5.1 PROJECT SIGNIFICANT IMPACTS

The proposed Project would result in significant unavoidable impacts related to air quality, biota and habitats, ground transportation, and noise.

5.1.1 Air Quality

During a peak day of activity, Project construction would produce levels of VOC, CO, NO_x , PM_{10} , and $PM_{2.5}$ emissions that exceed SCAQMD daily emission thresholds. In addition, for a peak day of Project construction, emissions from fugitive dust and onsite construction equipment and haul trucks would result in maximum ambient offsite concentrations of 24-hour PM_{10} that would exceed the SCAQMD significance threshold. Even with application of all feasible mitigations, these peak daily construction emissions and 24-hour PM_{10} concentrations would remain in excess of SCAQMD thresholds, and would represent Project-specific and cumulative significant air quality impacts.

Proposed Project operational emissions would result in maximum ambient offsite concentrations of 1-hour and annual NO₂ that would exceed the SCAQMD significance thresholds. This impact would represent a Project-specific and a significant cumulative impact.

The mitigated Project would increase chronic non-cancer effects on occupational receptors in the Project region. Although not significant for the Project individually, this increase would represent a cumulatively considerable and unavoidable contribution of airborne non-cancer effects to occupational receptors. These increased non-cancer effects could include asthma, bronchitis, reduced lung function, and increased mortality and morbidity.

An individual project does not generate by itself enough GHG emissions to significantly influence global climate change (AEP 2007). Thus, the issue of global climate change is a cumulative impact, such that an appreciable impact on global climate change would only occur when GHG emissions from a project combine with GHG emissions from other man-made activities on a global scale. Nevertheless, for the purposes of this EIS/EIR, the Port has chosen to assess GHG emissions as a project-level impact, as project GHG emissions would incrementally contribute to global effects. Construction and operation of the proposed Project would generate GHG emissions in each Project construction phase/stage and future year of operation. The Project GHG significance criterion states that any increase in GHG emissions is significant; therefore, these increases would produce a significant impact.

5.1.2 Biota and Habitats

The potential for a Project-related support vessel collision with a blue whale while in transit within the Long Beach Breakwater and Outer Harbor would be unlikely due to the infrequent presence of these mammals. Furthermore, all vessels would be required to slow to 12 knots when within 40 nm of Point Fermin as part of the VSRP (**Mitigation Measure AQ-4**). Normal swimming speeds of blue whales are 22 km/hr, which is approximately 10 knots; however, blue whales can swim up to 48 km/hr when alarmed (Wilson and Ruff 1999). Therefore, it is very unlikely that Project-related vessels traveling at 12 knots would increase the potential for whale strikes. No feasible measures are currently available to reduce whale strikes in the open ocean at greater than 40 nm from the harbor. Although vessel strikes to blue whales would be unlikely to occur, any that did occur would make a cumulatively considerable contribution to significant and unavoidable cumulative impacts associated with vessel strikes to that species. Therefore, as provided in the findings above for Cumulative Impact BIO-4, the small increase in Project-related vessel traffic in the harbor (3.4 percent) would add to that cumulative potential, resulting in a significant cumulative impact.

The amount of ballast water discharged into the harbor and, thus, the potential for introduction of invasive exotic species could increase because more and larger container ships would use the Port as a result of related and cumulative projects. In addition, it is also possible that exotic species could enter harbor waters on the ship hulls, anchors, and anchor chains. These vessels would come primarily from outside the Economic Exclusion Zone (EEZ) and would be subject to regulations to minimize the introduction of non-native species in

ballast water as described in Draft EIS/EIR Section 3.4.3. Most ships also utilize bottom paint that is resistant to accumulation of fouling organisms. In addition, container ships coming into the Port loaded would be taking on local water while unloading and discharging this water when reloading. This would also diminish the opportunity for discharge of non-native species. Thus, ballast water discharges during cargo transfers in the Port would be unlikely to contain non-native species but is still a possibility, as is the potential introduction of non-native species on ship hulls. No feasible mitigation is currently available to totally prevent introduction of invasive species via ballast water or vessel hulls, due to the lack of a proven technology. New technologies are being explored, and if methods become available in the future, they would be implemented as required at that time through federal and state regulations. Therefore, as provided in the findings above for Cumulative Impact BIO-5, the introduction of invasive species in ballast water or on the hulls of ships are significant, unavoidable impacts.

5.1.3 Ground Transportation

Additional traffic generated by Project construction and operational activities would have significant impacts on certain highway locations in the Project area. The proposed Project's construction traffic would have short-term significant impacts on the following highway segments up to the horizon year 2020:

- I-405 n/o I-710, both Directions (starting 2010);
- I-405 s/o I-710, both directions (starting 2010);
- I-710 between Willow Street and Pacific Coast Highway, both directions (starting 2010);
- SR-91 e/o I-710, both directions (starting 2010); and
- SR-91 w/o I-710, both directions (starting 2015).

The proposed Project would have significant impacts on the following study highway segments during operations:

- I-405 Freeway n/o I-710 Freeway, both Directions (starting 2010, max fair share of one percent in 2020);
- I-405 Freeway s/o I-710 Freeway, both directions (starting 2010, max fair of 5 percent in 2010);
- I-710 Freeway between Willow Street and Pacific Coast Highway, both directions (starting 2010, max fair share of four percent in 2020);
- I-110 Freeway n/o C-Street, northbound (2030, max fair share of 1.5 percent in 2030);
- SR-91 Freeway e/o I-710 Freeway, both directions (starting 2010, max fair share of four percent in 2030); and
- SR-91 Freeway w/o I-710 Freeway, both directions (starting 2015, max fair share of 3.5 percent in 2030).

When considered cumulatively, the Project would have significant impacts at certain study highway segments. Additional traffic generated by the Project to the cumulative background traffic conditions would deteriorate the existing LOS at certain highway locations in the study area.

The Port does not own, control, or maintain any of the impacted highway segments. These segments fall under the jurisdiction of Caltrans. Therefore, the Port does not have authority to unilaterally implement any mitigation measures on the highway segments. Accordingly, the Project's contribution to cumulative impacts during construction and operation would remain significant and unavoidable, even with implementation of **Mitigation Measure TRANS-2.1**, requiring the Project's fair-share contribution to Caltrans highway improvement programs. If Caltrans does not adopt a fair share based program to collect funds for actual mitigation that Caltrans commits itself to implement, or obtain the balance of funding needed to improve the impacted study highway segments in a manner that will improve the segments level of operation, the Project's contribution to regional cumulative impacts on these freeway segments would remain significant and unavoidable. Specific legal, economical, and technological considerations make additional mitigation measures infeasible. There-

fore, as provided in the findings above for Impact TRANS-1.1, Impact TRANS-2.1, and Cumulative Impact TRANS-2, impacts on certain highway segments in the Project area would be significant and unavoidable.

5.1.4 Noise

Project construction activities would increase ambient noise levels by three dBA at the West Coast Long Beach Hotel sensitive receptor site (Site 1), and would exceed LBMC maximum noise levels at Site 1 and the Long Beach Hilton Hotel sensitive receiver site (Site 2).

The minimum ambient daytime hourly Leq noise level recorded at the closest sensitive receptor site (i.e., Site 1) was 61 dBA. During Project pile driving activities, calculated hourly Leq noise levels at Site 1 would range between 64 – 66 dBA, which would exceed a three dB increase. The longest scheduled period of pile-driving would occur for 12 months in Construction Phase 1/Stage 1 during construction of the new Berth E24 extension and redevelopment of the existing berth at Berth E24. Project construction activities would cause ambient noise levels to be increased by more than three dBA at nearby sensitive receptors (i.e., Site 1), resulting in significant short-term impacts.

Receiver Site 1 is in the City of Long Beach General Plan LUD Three, for which the maximum noise level allowed by the LBMC is 65 dBA (Leq, one-hour). However, many of the construction activities would invoke the five dBA penalty for impulsive/tonal noise character, which would reduce the maximum allowable noise level in this location to 60 dBA. Calculated hourly average construction noise levels would intermittently exceed 60 dBA at receiver Site 1 until the end of Construction Phase 2. Receiver Site 2 is in LUD One. Taking existing ambient noise levels into account, as well as the impulsive/tonal noise penalty, the maximum daytime noise level allowed in this location under the LBMC would be 65 dBA (Leq, one-hour). Calculated hourly average construction noise levels at Site 2 would exceed 65 dBA during the noisiest periods of construction. Project construction activities would cause ambient noise levels to exceed LBMC maximum noise levels at Sites 1 and 2; therefore, significant short-term impacts would occur.

In addition to the standard construction noise controls described in Final EIS/EIR Section 1.7.3, **Mitigation Measures NOI-1.1a and NOI-1.1b** would apply to this impact. Due to the difficulty of effectively mitigating substantial noise-generating activities, adherence to standard controls and construction of temporary noise barriers would not be sufficient to reduce projected increases in ambient noise levels to the point where it would no longer cause a substantial increase. Therefore, as provided in the findings above for Impact NOI-1.1, Impact NOI-1.2, and Cumulative Construction Noise Impact, noise impacts during Project construction would be significant and unavoidable.

To help address the significant cumulative construction noise impacts of the Project, the Port will require this Project to fund the Schools and Related Sites Program that was adopted by the Board of Harbor Commissioners on March 23, 2009, as required by **Mitigation Measure AQ-29**. The funding will be used for eligible noise mitigation projects as specified in the Schools and Related Sites Program Guidelines. The guidelines: (1) establish eligibility criteria for potential applicants based on facility type and proximity to the San Pedro Bay Ports; (2) provide metrics that will be used to assess a proposed project's noise impact mitigation potential based on established regulatory mitigation programs and recent scientific information on noise impacts, and (3) explains how the Port of Long Beach Harbor Commissioners will choose among eligible proposals and approve funding.

5.2 OVERRIDING CONSIDERATIONS

The proposed Project offers numerous benefits that outweigh the unavoidable adverse environmental effects of the Project. The Board recognizes that significant and unavoidable impacts will result from implementation of the Project, as discussed above. Having (1) adopted all feasible mitigation measures, (2) recognized all significant, unavoidable impacts, and (3) balanced the benefits of the Project against the Project's significant and unavoidable impacts, the Board finds that there are specific overriding economic, legal, social, technological, or other benefits of the proposed Project that outweigh those impacts and provide sufficient reasons for approving the proposed Project. These overriding considerations justify adoption of the Project and certification of the Final EIS/EIR. Those reasons are as follows:

Fulfills Port legal mandates and objectives. The proposed Project would fulfill the Port's Tidelands Trust to promote and develop commerce, navigation and fisheries, and other uses of statewide interest and benefit including industrial, and transportation uses. The Coastal Act identifies the Port as an essential element of the national maritime industry and obligates the Port to modernize and construct necessary facilities to accommodate deep-draft vessels and the demands of foreign and domestic waterborne commerce in order to preclude the necessity for developing new ports elsewhere in the state. Furthermore, the Coastal Act provides that the Port should give highest priority to the use of existing land space within harbors for Port purposes, including, but not limited to navigational facilities, shipping industries and necessary ancillary and access facilities. The proposed Project meets these requirements by modernizing the channels, wharves and backlands at Middle Harbor to accommodate anticipated growth in water dependent maritime cargo. The Project also modernizes existing backlands by providing facilitated support and access facilities such as truck gates, road improvements and on-dock rail to allow for the effective import and export of maritime cargo.

Diverts containers from truck to intermodal railyard. The existing Middle Harbor container terminal has limited rail capability and the existing Pier F railyard is insufficient to accommodate regular service of modern intermodal trains. A portion of the current and future cargo would be diverted from trucks to the expanded Pier F intermodal railyard, avoiding the drayage to near-dock railyards or downtown facilities.

The Project includes an intermodal railyard to promote the direct transfer of cargo between ship and rail. The Project terminal operator shall replace all diesel-powered RTGs with electric-powered RMGs, as soon as feasible, but no later than the completion of construction in 2020. **Mitigation Measure AQ-9** requires that the expanded Pier F intermodal railyard incorporate the cleanest locomotive technologies into its operations. Technologies that reduce fuel consumption or use alternative fuels would reduce criteria pollutant emissions. These include diesel-electric hybrids, multiple engine generator sets, use of alternative fuels, and idling shutoff devices. Because some of these systems are not yet available, but are expected to be available within the next few years, this measure has not been quantified. However, implementation of this measure would reduce the Project's criteria pollutant emissions by less than 0.1 percent.

The proposed Pier F intermodal railyard is beneficial because it lowers the number of trucks that would otherwise be required to transport discretionary cargo to near-dock and downtown railyards. This will reduce roadway congestion in the Port vicinity and the emissions associated with these truck operations. Utilization of electric RMGs reduces emissions of criteria pollutants and GHGs.

Includes energy efficiency in building/construction/operation. The proposed Project includes construction of a Leadership in Energy and Environmental Design (LEED) certified "Gold" main terminal building and other efficiency measures including: use of compact fluorescent light bulbs, conducting third-party energy audits, use of solar panels on the main terminal building, use of carport-mounted PV solar panels over the employee and visitor parking areas, implementing recycling and planting trees around the main building and on Port-controlled lands adjacent to the roads into the Middle Harbor terminal.

Implements the San Pedro Bay Clean Air Action Plan (CAAP). In developing the San Pedro Bay Ports CAAP, the Ports established a series of principles and goals designed to reduce air emissions and related health impacts while allowing Ports development to continue. The CAAP committed the Ports, with the assistance of their agency partners (the technical working group or TWG, comprised of representatives from ARB, SCAQMD, and the USEPA) to establish San Pedro Bay Standards to define targets for reduction of Ports-related air impacts, specifically air quality and health risk impacts. The Port has worked to ensure that the Project includes all applicable CAAP measures, existing regulations, and, in some areas, exceeds compliance with applicable CAAP measures. In fact, implementation of the Project provides a mechanism for implementing new control measures identified through TAP and that are implemented in updates to th CAAP. This would be accomplished through the lease reopener mechanism included in the Project.

Reduces criteria pollutants from terminal operations. Emission reductions for unmitigated scenarios that would occur due to CAAP measures that are part of the Project lease agreement are attributed to the Project (Final EIS/EIR Table 3.2-11). All feasible mitigation measures have been included in the Project and those measures are consistent with or go beyond the CAAP requirements applicable to each source type. A number of mitigation measure would be implemented if the project is approved that will reduce current emissions from existing terminal operations. They include:

Mitigation Measures AQ-4 (Expanded VSRP), which expands VSP of 12 knots from 40 nm, i.e., from Point Fermin to the Precautionary Area;

AQ-5 (Shore-to-Ship Power ["Cold Ironing"]), requiring 100 percent of OGV to "cold iron" or use alternative technology that can achieve 90% reduction in emissions by 2014;

AQ-6 (Low-sulfur Fuels in OGV), which requires all OGV to use 0.2 percent or lower sulfur MGO fuel in vessel auxiliary and main engines at berth and out to a distance of 40 nm from Point Fermin, or implement equivalent emission reductions (equal to CAAP measures OGV3 and OGV4);

AQ-7 (Container Handling Equipment), which implements aggressive control measure over a set schedule (equates to CAAP measure CHE1);

AQ-7a (High Efficiency Rail Mounted Gantry (RMG) Cranes), which requires the terminal operator to replace all diesel-powered RTGs with electric-powered RMGs, as soon as feasible, but no later than the completion of construction in 2020;

AQ-8 (Heavy-Duty Trucks), a measure that goes beyond the ARB's requirements for reducing truck emissions, similar to CAAP measure HDV1 (CTP);

AQ-9 (Clean Railyard Standards), which requires the expanded Pier F intermodal railyard to incorporate the cleanest locomotive technologies into its operations;

AQ-10 (Truck Idling Reduction Measures), which requires the container terminal operator to minimize on-terminal truck idling and emissions. Additional design measures proposed in this mitigation measure would further reduce on-terminal truck activities and associated criteria pollutant emissions;

AQ-11 (Slide Valves on OGV Main Engines), which requires OGV that call at the Project container terminal to have slide fuel valves installed on their main engines, or implement an equivalent emission reduction technology; and

AQ-25 (Periodic Technology Review), which requires the tenant to periodically review new air quality technological advancements, and if any of the technologies is determined to be feasible in terms of cost, technical and operational feasibility, to work with the Port to implement such technology.

Many of these mitigation measures would not feasible or could not be enforced if the Project is not implemented as the Port would not a mechanism to enforce them. Final EIS/FEIR Section 3.2.4 (MMRP) identifies enforcement mechanisms for each mitigation measure. All of the identified measures will be implemented, regardless of changes or delays in the implementation of the CAAP. It is expected that a future CAAP measure for a given source category would be at least as stringent as the current measure, and therefore implementation of future CAAP measures would result in higher emission reductions. The Project lease agreement would include a condition requiring that every 5 years the Project lease would be re-opened to consider implementation of new feasible mitigations in accordance with **Mitigation Measure AQ-25**.

The Port has worked to ensure that the Project is consistent with the draft San Pedro Bay Standards as it includes all applicable CAAP measures, existing regulations, and, in some areas, exceeds compliance with applicable CAAP measures.

Reduces estimated health risk from terminal operation. The proposed Project would result in a reduction in cancer and acute health risks for all receptor types. While the proposed Project would result in an increase in non-cancer chronic health effects at the maximum occupational receptor location, the increase would be less than significant. Additionally, all other receptors in the Project region would have chronic non-cancer impacts that are less than those identified at the at the maximum occupational receptor location. Implementation of the proposed operational mitigation measures described above would result in significant reductions in diesel particulate matter (DPM) emissions from current CEQA baseline conditions and a corresponding reductions in health risks. Therefore, the Board finds that for the reasons described in Final EIS/EIR Section 3.2.2.3, this impact will be less than significant.

Provides new jobs during the life of the project. Net changes in employment attributable to terminal operations under the proposed Project could reach 2,961 jobs annually by the year 2030 (refer to Final EIS/EIR Section 1.6.3.1 and Table 1.6-1 for a comparison of alternatives). Absent construction contract and lease approvals associated with this Project, the Project would not be implemented, and therefore there would be no additional jobs or wages.

Efficient accommodation of increased throughput. In accordance with Project objectives, the proposed Project provides for improved efficiencies in the accommodation of containerized cargo in the following ways: improved gate facilities to facilitate truck ingress and egress from the facility; expanded Pier F intermodal railyard; new electric container cranes to allow for efficient unloading of the larger container ships; and more berth capacity and deeper berths to maximize the use of the deep channel of the Port by larger container ships. It would not be possible to achieve these efficiencies or to reach maximum terminal capacity absent implementation of these improvements through Project approval.

The Port finds that there are specific considerations associated with the proposed Project that serve to override and outweigh the Project's significant environmental impacts. The Project will allow the Port to meet its legal mandates to accommodate growing international commerce, while reducing Port air emissions, and provide jobs to the local economy. The Board hereby finds that the benefits of the proposed project outweigh the significant and unavoidable environmental impacts of the Project, which are therefore considered acceptable.

Upgrades critical fire fighting/safety facilities. The proposed Project would result in significant upgrades to Long Beach Fire Stations 15 and 20 within the POLB. Stations 15 and 20, which are fireboat stations that are critically important first responders in the harbor area, are antiquated and inadequate to support current operations. Mitigation Measure PHS-2.1 requires an executed mitigation agreement to upgrade these existing fire facilities prior to the commencement of Project construction in order to ensure adequate emergency response time in the area. Without the Project, these upgrades, which benefit the harbor area as well as the surrounding region, would not occur.

This page intentionally left blank.

Middle Harbor Redevelopment Project

Mitigation Monitoring and Reporting Program

Prepared for



The Port of Long Beach 925 Harbor Plaza Long Beach, CA 90802

Prepared by



Science Applications International Corporation 5464 Carpinteria Avenue, Suite K Carpinteria, CA 93013

April 2009



Middle Harbor Redevelopment Project

Mitigation Monitoring and Reporting Program

Prepared for

The Port of Long Beach 925 Harbor Plaza Long Beach, CA 90802

Prepared by

Science Applications International Corporation 5464 Carpinteria Avenue, Suite K Carpinteria, CA 93013

April 2009

MIDDLE HARBOR REDEVELOPMENT PROJECT MITIGATION MONITORING AND REPORTING PROGRAM

INTRODUCTION

This Mitigation Monitoring and Reporting Program (MMRP) fulfills the requirements of California Public Resources Code Section 21081.6 and CEQA Guidelines Section 15097. As stated in Public Resources Code Section 21081.6(a)(1):

The public agency shall adopt a reporting or monitoring program for the changes made to the project, or conditions of approval, adopted in order to mitigate or avoid significant effects on the environment.

The Port of Long Beach (POLB or Port) is the lead agency for the proposed Middle Harbor Redevelopment Project (Project) under CEQA and, therefore, responsible for administrating and implementing the MMRP. The U.S. Army Corps of Engineers (USACE) is the federal lead agency for the proposed Project under the National Environmental Policy Act (NEPA), and responsible for ensuring implementation of mitigation measures within areas under federal jurisdiction.

The primary purpose of the MMRP is to ensure that the mitigation measures identified in the Final Environmental Impact Statement/Environmental Impact Report (EIS/EIR) are implemented to reduce or avoid identified environmental effects and to appropriately assign the mitigation responsibilities for implementing the proposed Project. The mitigation measures listed in the MMRP will be adopted by the POLB Board of Harbor Commissioners as a condition of the primary Project approval.

PROJECT OVERVIEW

The USACE and the City of Long Beach, acting by and through its Board of Harbor Commissioners, is proposing to redevelop, expand, and modernize existing terminal facilities and waterfront property within the Port to accommodate a portion of the forecasted increases in containerized cargo throughput volumes.

The Project would consolidate and expand the existing 294-acre Project site, consisting of the Pier E terminal (170 acres), the Pier F terminal (101 acres), 18 acres of underutilized land north of the Gerald Desmond Bridge and Ocean Boulevard, and the Berth E24 subsided oil area (five acres), into a single, modern, 345-acre

container terminal. The Project would include a berth depth of -55 feet mean lower low water level (MLLW) to accommodate the current and expected future generations of cargo vessels and to support modernized operations. The Project would incorporate environmental practices and equipment pursuant to the Port's Green Port Policy and the San Pedro Bay Ports (SPBP) Clean Air Action Plan (CAAP).

The Project would rehabilitate old terminal facilities; provide deeper water at berths; improve and expand rail infrastructure; create new land: modernize marine terminal facilities; implement environmental controls, including the Port's Green Port Policy and CAAP. The Project would include construction of a 66kV substation (Pier E Substation) to provide power to support Middle Harbor container terminal operations, including supplying shore-to-ship power, and future power needs for other Port facilities. The existing 294-acre Project site would be increased to 345 acres, by creating approximately 54.6 net acres of new land (the net acreage estimate takes into account proposed fill areas, new wharf construction to create three deep water berths with -55 feet MLLW depths, and the demolition of existing wharves and land that would not be replaced).

Project construction would occur in two phases, the first phase in five stages and the second phase in four stages, and is scheduled to be completed in 2019 (i.e., Project build-out year); however, the proposed Middle Harbor container terminal is forecasted to be fully optimized at maximum capacity by 2025. Specific construction elements of the Project, as well as operation of the Project, are described below.

Dredging, excavation, and fill would be required during a number of the construction stages. Approximately 10.7 acres of existing land would be cut away and converted to water area. The Project would generate approximately 680,000 cubic yards (cy) of dredged material and approximately 1,290,000 cy of excavated material. All dredged and excavated materials generated by the Project would be reused onsite as fill and/or surcharge (surcharge is soil/fill material that is placed on top of the fill area to promote settling and compression of the new fill area to the desired density). Approximately 65.3 acres of water area would be filled. Import fill would be required in addition to

Project generated materials to create the landfill. Approximately 6,730,000 cy of additional imported fill material from sources inside (including material dredged/excavated for the Project) and outside the Harbor District would also be required. The net result of these construction activities would be the creation of approximately 54.6 acres of new land which, when added to the existing Project site, would total approximately 345 acres of land.

When completed, the Project would consist of one consolidated container terminal that would load and unload containerized cargo to and from marine vessels.

When optimized at maximum throughput capacity (by year 2025), the terminal would accommodate approximately 3,320,000 twenty-foot equivalent units (TEUs) per year. The proposed expanded Pier F intermodal railyard would handle approximately 26.3 percent (873,160 TEUs per year) of the terminal's expected throughput.

Construction

Construction - Phase 1

Phase 1 construction would redevelop the existing Piers D/E container terminal area in five stages. It is anticipated that Phase 1 construction would begin in 2009 and continue until 2017.

Stage 1: Stage 1 construction activities would widen and deepen Slip 3 by removing portions of Pier D (Berths D29-D31) and Pier E (Berths E23-E24); include demolition of existing wharf structures, backland areas, and existing facilities; and dredge portions of Slip 3 to elevation -55 MLLW. Approximately four acres on the southwest portion of Pier E (existing subsided Tideland oil area) would be raised approximately four feet to elevation +15 MLLW, and approximately 5.4 acres of new land would be created to extend the Berth E24 wharf. Stage 1 activities would also include filling the 25.6acre Slip 1 and surcharging 10 acres at the northern end of the fill, realigning the mainline track at Ocean Boulevard/Harbor Scenic Drive, constructing the Pier F storage yard and tracks, and constructing a 66kV electrical substation (Pier E Substation) north of Ocean Boulevard. Stage 1 would begin in 2009 and continue through 2010, assuming all permits are secured.

Stage 2: Stage 2 construction activities would include development of Slip 1 for container yard use, and redevelopment of Berth E25. Stage 2 would begin in approximately 2010 and continue through 2012.

Stage 3: Stage 3 construction activities would include wharf development at Berth E26 and Berth E27. Stage 3 would begin in 2012 and continue through 2014.

Stage 4: Stage 4 construction activities would include redevelopment of the Seaside Railyard area on Pier E and construction of new terminal buildings. Stage 4 would begin in 2015 and continue through 2017.

Stage 5: Stage 5 construction activities would redevelop 18 acres north of the Gerald Desmond Bridge and Ocean Boulevard. Stage 5 would begin in 2015 and continue through 2017.

Construction - Phase 2

Proposed Phase 2 improvements would fill the East Basin to connect the existing Pier E terminal to the existing Pier F container terminal, develop this newly created land for container terminal use, and extend the wharf constructed in Phase 1 by 1,350 linear feet (LF).

It is anticipated that Phase 2 construction activities would begin in 2011 and continue through 2019, and would consist of four stages.

Stage 1: Stage 1 construction yard activities would involve developing the remaining 12 acres of the Slip 1 fill as container yard, filling in 12 acres of the East Basin area, and constructing an expanded intermodal railyard. This stage would begin in 2011 and continue through 2014.

Stage 2: Stage 2 construction activities would demolish the remaining Berths F6-F10 wharf structures, fill the remaining 21 acres of the East Basin between Piers E and F, and construct a new connecting wharf (Berth E23). Stage 2 would begin in 2014 and continue through 2018.

Stage 3: Stage 3 construction activities would redevelop the existing Pier F container yard. Stage 3 would begin in 2016 and continue through 2018.

Stage 4: Stage 4 construction would build a tail track and a loop road around the track on Pier F. Stage 4 would begin in 2018.

Operations

When completed, the Project would consist of one consolidated container terminal that would load and offload containerized cargo from marine vessels.

Terminal Security

Containers would be screened and protected by a number of safety and security features including, but not necessarily limited to:

Radiation Portal Monitors (RPM) — The Project site would incorporate RPM equipment at the exit gate area for the initial automated inspection of the contents of containers prior to exiting the marine terminal.

Customs Radiation Inspection Facility — A secondary RPM facility inside the marine terminal would be installed and used for detailed inspection of container contents where radiation was detected in the initial RPM inspection. U.S. Customs Border Patrol would operate this facility and provide the inspection service.

Project Site Fencing — Existing fencing would be modified to provide adequate security for the marine terminal as required by U.S. Customs Border Patrol.

Terminal Operations

At full operation (anticipated in approximately year 2025), the proposed container terminal would operate approximately 21 hours per day, 365 days per year, and would accommodate approximately 3,320,000 TEUs per year. The new combined terminal would operate under a new lease between the terminal operator and the Port that would include environmental controls imposed pursuant to the Port's Green Port Policy and the CAAP. This EIS/EIR assumes the proposed Project includes participation in the POLB/POLA Vessel Speed Reduction Program (VSRP) (CAAP measure OGV1) and compliance with applicable U.S. Environmental Protection Agency (EPA), California Air Resource Board (ARB), and South Coast Air Quality Management District (SCAQMD) regulations.

Middle Harbor container terminal operations would include stevedoring (loading/unloading ships), container storage activities, intermodal railyard operations, and trucking to offsite locations such as warehouses and railyards. Once containers have been off-loaded from the ship or received through the gates on trucks and trains, they would be stored and moved around the container terminal storage yard using one of three systems:

1) a grounded or "stacked" system (where containers are stacked); 2) a chassis or "wheeled" system (where the containers are stored on a

single, wheeled chassis and are not stacked); or 3) a combination grounded/chassis system.

Electric gantry cranes would load and unload cargo containers between vessels and the terminal. Yard tractors would transport the cargo containers to and from the container storage areas within the terminal and to and from railcars at the intermodal railyard. Offloaded (import) containers would either be stored temporarily in the container terminal storage yard or immediately shipped out of the terminal via truck or rail. Loaded (export) cargo would be imported to the Middle Harbor container terminal by truck or rail; export cargo shipped via rail would either arrive directly at the proposed expanded Pier F intermodal railyard or would arrive at another local railyard and then be trucked to the terminal gate for receiving. Export cargo containers would be transferred by "toppick" or Rubber Tired Gantry (RTG) cranes from the rail cars to chassis hauled by yard tractors, and the tractors would then transport the cargo to the container terminal storage yard where the cargo would be lifted to grounded locations by toppicks or RTG cranes.

Vessel Operations

The proposed Middle Harbor container terminal operations would result in a maximum of approximately 364 vessel calls per year. All vessel unloading/loading activities associated with the Project would occur at proposed Berths E23-E27 and F6-F10. Due to scheduling constraints and U.S. Coast Guard (USCG) Captain of the Port (COTP) regulations, the schedules used to estimate future berth activity/capacity predict that a maximum of four vessels could be berthed at one time.

Vessels accessing the Middle Harbor container terminal would be required to use a Port Pilot for transit in and out of San Pedro Bay (except for U.S. vessels that have a federally licensed pilot onboard), and have tug assistance within the POLB harbor. Vessels calling at the new terminal would be required to slow to 12 knots within 40 nautical miles (nm) of Point Fermin. Once at berth, the offloading/loading process begins; the vessels typically "hotel" or stay at the terminal for approximately 36 hours (1.5 days), but the largest ships may stay as long as three days. While at berth, all vessels would be required to utilize shore-to-ship power to provide electrical power for vessel functions. In addition, all vessels calling at the Middle Harbor container terminal would be required to use 0.2 percent or lower sulfur Marine Gas Oil (MGO) fuel in auxiliary and main engines at berth and out to a distance of 40 nm from Point Fermin.

Truck Operations

Preliminary estimates indicate that the total number of truck trips to and from the Middle Harbor container terminal would increase from the 2005 baseline average of 6,528 trips per day to an average of approximately 10,112 trips per day in the year 2025 as a result of increased import and export of containerized cargo. At maximum terminal capacity in 2025, approximately 2,446,840 TEUs would be moved to and from the terminal via truck. About 10 percent of those truck movements would transport containers to and from off-dock and near-dock railyards. The remaining truckhauled containers would be transported to and from warehouses and distribution centers in the Los Angeles Basin, southern California, and nearby western states. Middle Harbor container terminal operations include use of an automated appointment system that would enable trucks to reschedule their trips to avoid peak hour traffic and congestion.

Rail Operations

When the Project terminal is fully optimized at maximum throughput capacity in 2025, the railyard would operate approximately 21 hours per day, 365 days per year, and handle approximately 873,160 TEUs per year, which would represent approximately 26.3 percent of the terminal's expected throughput. Preliminary estimates indicate that annual train trips would increase from the 2005 baseline average of 138 trips per year to an average of approximately 2,098 trips per year at maximum capacity in 2025. Rail operations assume three line haul locomotives per train for each inbound/outbound trip and one switch locomotive in operation within the expanded Pier F intermodal railyard for each inbound/outbound trip. Intermodal export cargo would arrive either directly at the expanded Pier F intermodal railyard or at another local railyard (e.g., the Intermodal Container Transfer Facility [ICTF] in Carson, BNSF's yards at Hobart and City of Industry, or UP's East L.A. and Los Angeles Transportation Center [LATC] yards) and then be trucked to the terminal gate for receiving.

IMPACTS REQUIRING MITIGATION

Impacts of the proposed Project that require mitigation include:

 Emissions from construction activities that exceed SCAQMD emission significance thresholds:

- Offsite ambient air pollutant concentrations during construction that exceed a SCAQMD threshold of significance;
- Offsite impacts during operations that exceed SCAQMD ambient thresholds of significance for one-hour and annual NO;
- GHG emissions during construction and operation that would exceed the CEQA threshold;
- Substantial loss or alteration of marine habitat through filling (in Slip 1, for the Berth E24 extension, and in a portion of the East Basin) and excavation (widening Slip 1 and at Berth F201) for a net loss of 54.6 acres:
- Substantial effects on Essential Fish Habitat (EFH) and temporary disturbances to habitat for Fishery Management Plan (FMP) species;
- Short-term, temporary increases in auto and truck traffic at certain study area intersections during Project construction;
- Short-term impacts on highway locations in the study area during Project construction;
- Increases in auto and truck traffic at certain study intersections during operations;
- Impacts on highway locations in the study area during operations;
- Exacerbation of existing inadequate Long Beach Fire Department emergency response times during Project construction and operations;
- Increase in noise levels by more than three dBA at nearby sensitive receptors during Project construction (i.e., pile driving);
- Increase in noise levels such that the Long Beach Municipal Code (LBMC) maximum noise levels would be exceeded at two sensitive receptor sites (i.e., West Coast Long Beach Hotel and Long Beach Hilton Hotel) during Project construction;
- Potentially significant impacts to archaeological resources during ground disturbing activities; and
- Adverse impacts to historic architectural resources, including two 1953 Smoke Houses/Offices during Project construction.

CEQA GUIDELINES

CEQA Guidelines Section 15097 explains the requirements of Public Resources Code Section 21081.6(a) regarding mitigation monitoring and reporting. Mitigation is defined in CEQA Guidelines Section 15370 as a measure that:

- Avoids the impact altogether by not taking a certain action or parts of an action;
- Minimizes impacts by limiting the degree or magnitude of the action and its implementation;
- Rectifies the impact by repairing, rehabilitating, or restoring the impacted environment;
- Reduces or eliminates the impact over time by preservation and maintenance activities during the life of the project; and
- Compensates for the impacts by replacing or providing substitute resources or environments.

Mitigation measures provided in this MMRP were identified in Final EIS/EIR Chapter 3 (Environmental Setting and Project Impacts), as feasible and effective in mitigating Project-related environmental impacts.

POLB MMRP APPROACH

For each adopted mitigation measure, the MMRP identifies the following:

- · Required action;
- · When the action is required to be taken;
- · Agency responsible for action;
- · Agency responsible for tracking;
- · Submittal date;
- · Person verifying implementation;
- Attachments required to verify implementation; and
- Comments made by verifying personnel.

The POLB maintains the primary responsibility for ensuring that the mitigation measures are implemented. When Project work is undertaken by the Port's contractors, the pertinent mitigation measures will be included in the terms and conditions of the contracts. Port construction inspectors will undertake regular inspections of the job site to ensure that contractors are

implementing the mitigation measures and complying with their contract. The Port's project manager will be responsible for ensuring that mitigation measures which are the responsibility of the Port are carried out.

MITIGATION MONITORING AND REPORTING PROGRAM PROCEDURES

The POLB's designated environmental monitor will track and document compliance with mitigation measures, note any problems that may result, and take appropriate action to remedy problems. Specific responsibilities of the POLB are listed below.

- Coordination of all mitigation monitoring activities;
- Management of the preparation, approval, and filing of monitoring or permit compliance reports;
- Maintenance of records concerning the status of all approved mitigation measures;
- Quality control assurance of field monitoring personnel;
- Coordination with other agencies regarding compliance with mitigation or permit requirements;
- Reviewing and recommending acceptance and certification of implementation documentation; and
- Acting as a contact for interested parties or surrounding property owners who wish to register complaints; and
- Documenting observations of unsafe conditions or environmental violations, and developing any necessary corrective actions.

MITIGATION AND MONITORING REPORTING PLAN CHECKLIST

The MMRP is organized in a checklist format, with each mitigation measure on a separate page. A summary of all mitigation measures is provided on the cover page to the checklist. The agency responsible for taking the action (POLB Real Estate and/or POLB Engineering Division) will submit the appropriate attachment to the agency responsible for tracking the action (POLB Planning Division). By his or her signature, the POLB Planning Division representative verifies that the mitigation measure has been implemented.

MIDDLE HARBOR REDEVELOPMENT PROJECT MITIGATION MONITORING AND REPORT PLAN CHECKLIST

Summary of Mitigation Measures

AIR QUALITY

Mitigation Measure AQ-1: Additional Fugitive Dust Controls. The Project construction contractor shall develop and implement dust control methods that shall achieve this control level in a SCAQMD Rule 403 dust control plan; and designate personnel to monitor the dust control program and order increased watering, as necessary, to ensure a 90 percent control level.

Mitigation Measure AQ-2: Emission Controls for Non-road Construction Equipment. Construction equipment shall meet the EPA Tier 4 non-road engine standards, where feasible. The Tier 4 standards become available starting in year 2011. Until Tier 4 equipment is feasible, Tier 3 construction equipment shall be required.

Mitigation Measure AQ-2a: Best Management Practices (BMPs) for Construction Equipment. The construction contractor shall implement additional BMPs on construction equipment, where feasible, to further reduce emissions from emissions sources.

Mitigation Measure AQ-2b: Construction Traffic Emission Reductions. The construction contractor shall implement measures to further reduce emissions from construction traffic.

Mitigation Measure AQ-3: Emission Controls for Construction Tugboats. All tugboats used in construction shall meet the EPA Tier 2 marine engine standards, and if feasible use construction tugs that meet the EPA Tier 3 marine engine standards.

Mitigation Measure AQ-3a: Construction Tugboat Home Fleeting. The construction contractor shall require all construction tugboats that home fleet in the SPBP to (a) shut down their main engines and (b) refrain from using auxiliary engines at dock or to use electrical shore power.

Mitigation Measure AQ-4: Expanded VSRP. All OGV that call at the Middle Harbor container terminal shall comply with the expanded VSRP of 12 knots from 40 nm from Point Fermin to the Precautionary Area.

Mitigation Measure AQ-5: Shore-to-Ship Power ("Cold Ironing"). All OGV that call at the Middle Harbor container terminal shall utilize shore-to-ship power while at berth.

Mitigation Measure AQ-6: Low-sulfur Fuels in OGV. All OGV that call at the Middle Harbor container terminal shall use 0.2 percent or lower sulfur MGO fuel in vessel auxiliary and main engines at berth and out to a distance of 40 nm from Point Fermin.

Mitigation Measure AQ-7: Container Handling Equipment. All Project CHE shall meet the requirements of CAAP measure CHE-1.

Mitigation Measure AQ-7a: High Efficiency Rail Mounted Gantry (RMG) Cranes. The Project terminal operator shall replace all diesel-powered RTGs with electric-powered RMGs, as soon as feasible, but no later than the completion of

Mitigation Measure AQ-8: Heavy-Duty Trucks. Container trucks that call at the Middle Harbor container terminal shall comply with the replacement schedule as part of the POLB CTP tariff.

Mitigation Measure AQ-9: Clean Railyard Standards. The expanded Pier F intermodal railyard shall incorporate the cleanest locomotive technologies into its operations.

Mitigation Measure AQ-10: Truck Idling Reduction Measures. The Middle Harbor container terminal operator shall minimize on-terminal truck idling and emissions.

Mitigation Measure AQ-11: Slide Valves on OGV Main Engines. All OGV that call at the Project container terminal shall have slide fuel valves installed on their main engines, or implement an equivalent emission reduction technology.

Mitigation Measure AQ-12: Expanded VSRP for GHG. All OGV that call at the Middle Harbor container terminal shall comply with the expanded VSRP of 12 knots from the California overwater border to the Precautionary Area.

Mitigation Measure AQ-13: Low-sulfur Fuels in OGV for GHG. All OGV that call at the Project container terminal shall use 0.2 percent or lower sulfur MGO fuel in vessel auxiliary and main engines at berth and within California State Waters. Mitigation Measure AQ-14: LEED. The main terminal building shall obtain the LEED gold certification level

Mitigation Measure AQ-15: Compact Fluorescent Light Bulbs. All interior terminal building lighting shall use compact

fluorescent light bulbs. Mitigation Measure AQ-16: Energy Audit. The Middle Harbor container terminal tenant shall conduct a third party energy

audit every five years and install innovative power saving technologies where feasible.

Mitigation Measure AQ-17: Solar Panels. The applicant shall install solar panels on the main terminal building.

Mitigation Measure AQ-17a: Solar Carports. The applicant will install carport-mounted PV solar panels over the employee and visitor parking areas to the maximum extent feasible.

Summary of Mitigation Measures (continued)

AIR QUALITY (CONTINUED)

Mitigation Measure AQ-18: Recycling. The terminal buildings shall achieve a minimum of 40 percent recycling by 2012 and 60 percent recycling by 2015.

Mitigation Measure AQ-19: Tree Planting. The Port shall plant shade trees around the main terminal building.

Mitigation Measure AQ-19a: Tree Planting – Transportation Corridors. The Port shall plant new shade trees on Port-controlled lands adjacent to the roads into the Middle Harbor container terminal to the extent practicable given safety and other land use considerations.

Mitigation Measure AQ-20: Cool Roofs. Buildings on the Middle Harbor container terminal will incorporate cool roofing systems to the extent feasible.

Mitigation Measure AQ-21: Energy Efficient Boom Flood Lights. The Port shall install boom flood lights with energy efficient features on existing and new dock cranes to the extent feasible.

Mitigation Measure AQ-22: Reefer Lighting. The terminal tenant shall downsize light fittings and associated electrical power usage at reefer platforms to the extent feasible.

Mitigation Measure AQ-23: Employee Carpooling. The construction contractor and terminal tenant shall encourage construction and terminal employees to carpool or to use public transportation.

Mitigation Measure AQ-24: Mitigation for Indirect GHG Emissions. The terminal tenant shall be required to use green commodities, such as those available from the California Climate Action Registry's Climate Action Reserve, to offset carbon emissions associated with terminal's electricity consumption. This measure applies to all electricity consumed at the terminal, including shore-to-ship power usage ("cold ironing"), with costs not to exceed 15% of annual terminal electricity costs.

Mitigation Measure AQ-25: Periodic Technology Review. To promote new emission control technologies, the tenant shall implement in 2015 and every five years following the effective date of the lease agreement, a review of new air quality technological advancements, subject to mutual agreement on operational feasibility, technical feasibility, and cost-effectiveness and financial feasibility, which shall not be unreasonably withheld.

Mitigation Measure AQ-26: Cargo Throughput Monitoring: Every five years, the Port shall compare actual cargo throughput that occurred at the terminal to the cargo assumptions used to develop the Final EIS/EIR.

Mitigation Measure AQ-27: Electrical Regenerative Systems on Dock Cranes. Port will require the terminal operator to have electric regenerative systems on all Project dock cranes in Project year 1.

Mitigation Measure AQ-28: Greenhouse Gas Emission Reduction Program Guidelines (GHG Program). To partially address the cumulative GHG impacts of the Middle Harbor Redevelopment Project, the Port will require this Project to provide funding for the GHG Emission Reduction Program in the amount of \$5 million. This money will be used to pay for measures pursuant to the GHG Emission Reduction Program Guidelines, including but not limited to generation of green power from renewable energy sources, ship electrification, goods movement efficiency measures, cool roofs to reduce building cooling loads and the urban heat island effect, building upgrades for operational efficiency, tree planting for biological sequestration of CO₂, energy-saving lighting, and purchase of renewable energy certificates (RECs).

Mitigation Measure AQ-29: Cumulative Air Quality Impact Reduction Program. To help reduce cumulative air quality impacts of the Middle Harbor Redevelopment Project, the Port will require the Project to provide funding in support of the Schools and Related Sites Guidelines for the Port of Long Beach Grant Programs and Healthcare and Seniors Facility Program Guidelines for the Port of Long Beach Grant Programs in the amount of \$5 million each. The distribution of these funds to potential applicants and projects will be determined through a public evaluation process and by approval of the Board of Harbor Commissioners.

Mitigation Measure AQ-30: Investigation of Marine Vessel Main Engine Technology. The Port and terminal tenant will expeditiously contact marine vessel engine manufacturers to identify the maximum technically achievable NOX and PM emission reduction strategies that can be implemented no later than 2014 for main engines on the specific vessels (or on the vessel engine types) that will call on the Project terminal. The Port and terminal tenant will work with the California Air Resources Board and the South Coast Air Quality Management District, with public input, to develop an expeditious schedule to implement such strategies.

BIOTA AND HABITATS

Mitigation Measure BIO-3: Compensation for Loss of Marine Habitat. Compensate for loss of marine habitat in Slip 1 and the East basin through use of existing mitigation bank credits.

GROUND TRANSPORTATION

Mitigation Measure TRANS-1.1a: Traffic Management Plan. Prior to beginning construction, the construction contractor shall prepare a detailed traffic management plan, which in addition to work shift start/end times, shall include the following: detour plans, coordination with emergency services, coordination with adjacent property owners and tenants, advanced notice of temporary parking loss, identification of temporary parking replacement or alternative adjacent parking within a reasonable walking distance, use of designated haul routes, use of truck staging areas, observance of hours of operations restrictions, and use of appropriate signing for construction activities. The traffic management plan shall be submitted to Port of Long Beach for approval before beginning construction.

Summary of Mitigation Measures (continued)

GROUND TRANSPORTATION (CONTINUED)

Mitigation Measure TRANS-1.1b: Restricted Construction-Related Traffic Hours. Consistent with City of Long Beach Public Works Department practice, the construction-related traffic to/from the Project site shall be restricted during morning and afternoon peak commute hours. Furthermore, no closure of major road corridors shall be permitted as a result of construction activities.

Mitigation Measure TRANS-1.1c: Signal Installation. The Port shall install a signal at the intersection of Pico Avenue and Pier E Street/Ocean Blvd EB On- and Off-Ramps.

Mitigation Measure TRANS-1.1d: Signal Installation. The Port shall install a signal at the intersection of Pico Avenue and Pier D Street.

Mitigation Measure TRANS-1.1e: Signal Installation. The Port shall install a signal at the intersection of Pico Avenue/Pier G Avenue and Harbor Plaza.

Mitigation Measure TRANS-1.2: Signal Installation. The Port shall install a signal at the intersection of Pico Avenue and Ocean Blvd WB Off-Ramp.

Mitigation Measure TRANS-2.1: Fair Share Based Program. If Caltrans either a) adopts a fair share based program to collect funds for actual mitigation that Caltrans commits itself to implement, or b) otherwise obtains the balance of funding needed to improve the impacted study highway segments in a manner that will improve the segments level of operation, POLB shall pay its fair share into that program.

PUBLIC SERVICES/HEALTH AND SAFETY

Mitigation Measure PHS-2.1: Mitigation Agreement. The Port shall enter into a mitigation agreement to upgrade existing facilities at Stations 15 and 20. The Port shall submit proof to the City of Long Beach that an agreement has been executed prior to commencement of construction activities.

Noise

Mitigation Measure NOI-1.1a: Temporary Noise Barriers. Temporary noise barriers shall be located between noise-generating construction activities (e.g., pile driving) and hotel/residential buildings and Cesar Chavez School to the east.

Mitigation Measures NOI-1.1b: Restricted Hours for Pile-driving Activities. Pile-driving activities shall be limited to the hours of 7:00 am to 7:00 pm on weekdays, between 9:00 am and 6:00 pm on Saturdays, and prohibited anytime on Sundays and holidays as prescribed by Section 8.80.202 of the LBMC.

CULTURAL RESOURCES

Mitigation Measure CR-1.1.1: Archaeological Material Discovery Plan. In the unlikely event that any archaeological material is discovered during construction, all work must be halted within the vicinity of the archaeological discovery until an assessment of the significance by a qualified archaeologist is completed. If the resources are found to be significant, they shall be avoided or shall be mitigated consistent with SHPO Guidelines. Treatment plans must be developed in consultation with the County, SHPO, and local Native Americans. If human remains are encountered, the Los Angeles County Coroner shall be contacted immediately. If the remains appear to be Native American, the coroner shall contact the Native American Heritage Commission who will appoint the Most Likely Descendent. Additionally, if the human remains are determined to be Native American, a plan will be developed regarding the treatment of human remains and associated burial objects, and the plan will be implemented under the direction of the Most Likely Descendent.

Mitigation Measures CR-1.2.1: Relocation of Historic Architectural Resources. The two historic architectural resources shall be temporarily moved during construction and then relocated to another suitable location within the Project area subsequent to construction under the direction of a qualified Architectural Historian. A survey shall be conducted after their relocation to document, identify, and describe any internal and external cracking, condition of walls, and other elements as a result of their movement. The survey shall be undertaken under the direction of a qualified Architectural Historian and shall be in accordance with accepted standard methods. A written report documenting conditions after Project completion shall be prepared under the supervision and approval of a qualified Architectural Historian. The report shall provide any necessary measures to address stabilization and repair of areas that have been disturbed during relocation, including photo-documentation. The repairs shall be undertaken by the Port in a timely manner.

Mitigation Measure AQ-1: Additional Fugitive Dust Controls

Required Action: Mitigation Measure AQ-1: Additional Fugitive Dust Controls. The Project construction contractor shall develop and implement dust control methods that shall achieve this control level in a SCAQMD Rule 403 dust control plan; and designate personnel to monitor the dust control program and order increased watering, as necessary, to ensure a 90 percent control level. Their duties shall include holiday and weekend periods when work may not be in progress. Additional control measures to reduce fugitive dust shall include, but are not limited to, the following:

- Apply approved non-toxic chemical soil stabilizers according to manufacturers' specifications to all inactive construction areas or replace groundcover in disturbed areas;
- Provide temporary wind fencing around sites being graded or cleared;
- Cover truck loads that haul dirt, sand, or gravel or maintain at least two feet of freeboard in accordance with Section 23114 of the California Vehicle Code;
- Install wheel washers where vehicles enter and exit unpaved roads onto paved roads, or wash off tires of vehicles and any equipment leaving the construction site;
- Suspend all soil disturbance activities when winds exceed 25 mph as instantaneous gusts or when visible
 dust plumes emanate from the site and stabilize all disturbed areas;
- Appoint a construction relations officer to act as a community liaison concerning on-site construction activity including resolution of issues related to PM₁₀ generation;
- Sweep all streets at least once a day using SCAQMD Rule 1186, 1186.1 certified street sweepers or roadway washing trucks if visible soil materials are carried to adjacent streets (recommend water sweepers with reclaimed water);
- Apply water three times daily, or non-toxic soil stabilizers according to manufacturers' specifications, to all
 unpaved parking or staging areas or unpaved road surfaces;
- Pave road and road shoulders; and
- Apply water three times daily or as needed to areas where soil is disturbed.

When Required: Daily during all construction activities.

Agency Responsible for Action: POLB Engineering Division.

Agency Responsible for Tracking: POLB Environmental Planning Division.

Action (i): Engineering Division to include requirements in Project construction specifications and bid process.

Action (ii): Construction Management Division to verify that the dust control program is monitored; non-toxic chemical soil stabilizers are applied; wind fencing is provided; trucks hauling dirt, sand, or gravel are either covered or maintain at least two feet of freeboard; wheel washers are installed or tires are washed prior to leaving construction site; and soil disturbance activities are suspended when winds exceed 25 mph or when dust plumes are visible.

Subilitial Date.		
Verified By:	Title:	
Attachments:		
Comments:		

0 1 '44 - 1 D - 4 - -

Mitigation Measure AQ-2: Emission Controls for Non-road Construction Equipment		
Required Action: Mitigation Measure AQ-2: Emission Controls for Non-road Construction Equipment. Construction equipment shall meet the EPA Tier 4 non-road engine standards, where feasible. The Tier 4 standards become available starting in year 2011. Until Tier 4 equipment is feasible, Tier 3 construction equipment shall be required.		
When Required: During all construction activities		
Agency Responsible for Action: POLB Engineering	Division.	
Agency Responsible for Tracking: POLB Environm	ental Planning Division.	
Action (i): Engineering Division to include requirement	s in Project construction specifications and bid process.	
Action (ii): Construction Management Division to veri engines, as feasible, are being used.	fy that Tier 3 non-road engines and/or Tier 4 non-road	
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure AQ-2a: Best Management Practices (BMPs) for Construction Equipment

Required Action: <u>Mitigation Measure AQ-2a: Best Management Practices (BMPs) for Construction Equipment.</u> The construction contractor shall implement the following BMPs on construction equipment, where feasible, to further reduce emissions from these sources.

- Use of diesel oxidation catalysts and/or catalyzed diesel particulate traps, as feasible.
- Maintain equipment according to manufacturer specifications.
- Restrict idling of equipment and trucks to a maximum of five minutes (per ARB regulation).
- Use of high-pressure fuel injectors on diesel-powered equipment.
- Use of electricity from power poles rather than temporary diesel- or gasoline-powered generators.

When Required: Daily during all construction activities.

Agency Responsible for Action: POLB Engineering Division.

Agency Responsible for Tracking: POLB Environmental Planning Division.

Action (i): Engineering Division to include requirements in Project construction specifications and bid process.

catalyst, maintaining equipment accordin	Division to verify that construction BMPs including diesel oxidation by to manufacturers specifications, restrict idling of equipment and of high-pressure fuel injectors on diesel-powered equipment, and used.	d
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure AQ-2b: Mitigation Measure AQ-2b: Construction Traffic Emission Reductions

Required Action: <u>Mitigation Measure AQ-2b: Construction Traffic Emission Reductions</u>. The construction contractor shall implement the following measures to further reduce emissions from construction.

- Trucks used for construction (a) prior to 2015 shall use engines certified to no less than 2007 NOx emissions standards and (b) in 2015 and beyond shall meet EPA 2010 emission standards.
- Provide temporary traffic control such as a flag person, during all phases of construction to maintain smooth traffic flow.
- Schedule construction activities that affect traffic flow on arterial systems to off-peak hour where possible.
- Re-route construction trucks away from congested streets or sensitive receptor areas.
- Provide dedicated turn lanes for movement of construction trucks and equipment on- and off-site.
- Configure construction parking to minimize traffic interference.
- Improve traffic flow by signal synchronization.
- All vehicle and equipment will be properly tuned and maintained according to manufacturer specification.

Reduce traffic speeds on all unpaved roads to 15 mph or less.
 When Required: During all construction activities; per the specified schedule for truck emission standards, and daily for traffic measures.
 Agency Responsible for Action: POLB Engineering Division.
 Agency Responsible for Tracking: POLB Environmental Planning Division.
 Action (i): Engineering Division to include requirements in Project construction specifications and bid process.
 Action (ii): Construction Management Division to verify that contractor is implementing emission reduction measures.
 Submittal Date:
 Verified By: Title:
 Attachments:

Mitigation Measure AQ-3: Emission Controls for Construction Tugboats		
Required Action: Mitigation Measure AQ-3: Emission Controls for Construction Tugboats. All tugboats used in construction shall meet the EPA Tier 2 marine engine standards, and if feasible use construction tugs that meet the EPA Tier 3 marine engine standards. The Tier 3 standards become available starting in year 2009.		
When Required: During all construction activities inv	•	
Agency Responsible for Action: POLB Engineering	g Division.	
Agency Responsible for Tracking: POLB Environn	nental Planning Division.	
Action (i): Engineering Division to include requiremen	ts in Project construction specifications and bid process.	
Action (ii): Construction Management Division to ve engines.	erify that all tugboats use a minimum of Tier 2 marine	
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure AQ-3a: Construction Tugboat Home Fleeting		
Required Action: Mitigation Measure AQ-3a: Construction Tugboat Home Fleeting. The construction contractor shall require all construction tugboats that home fleet in the SPBP to (a) shut down their main engines and (b) refrain from using auxiliary engines at dock or to use electrical shore power, if need be.		
When Required: Daily during all construction activities	es	
Agency Responsible for Action: POLB Engineering	Division.	
Agency Responsible for Tracking: POLB Environm	ental Planning Division.	
Action (i): Engineering Division to include requirement	ts in Project construction specifications and bid process.	
Action (ii): Construction Management Division to ver engines and (b) refrain from using auxiliary engines a	ify that construction tugboats (a) shut down their main t dock or to use electrical shore power.	
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure AQ-4: Mitigation Measure AQ-4: Expanded VSRP		
Required Action: Mitigation Measure AQ-4: Expanded VSRP. All OGV that call at the Middle Harbor container terminal shall comply with the expanded VSRP of 12 knots from 40 nm from Point Fermin to the Precautionary Area.		
When Required: Daily at the commencement of a fu	illy executed lease.	
Agency Responsible for Action: POLB Real Estate	e Division.	
Agency Responsible for Tracking: POLB Environn	nental Planning Division.	
Action (i): Real Estate Division shall include requirements in Project lease agreement.		
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Middle Harbor container terminal shall utilize shore-to-ship power while at berth according to the following schedule: (1) 33 percent of all OGV by December 2009 (2) 66 percent of all OGV by March 2012, and (3) 100 percent of all OGV by December 2014. Lease stipulations shall include consideration of alternative	Mitigation Measure AQ-5: Shore-to-Ship Power ("Cold Ironing")		
Agency Responsible for Action: POLB Real Estate Division. Agency Responsible for Tracking: POLB Environmental Planning Division. Action (i): Real Estate Division to include requirements in Project lease agreement. Submittal Date: Verified By: Attachments:	Required Action: Mitigation Measure AQ-5: Shore-to-Ship Power ("Cold Ironing"). All OGV that call at the Middle Harbor container terminal shall utilize shore-to-ship power while at berth according to the following schedule: (1) 33 percent of all OGV by December 2009 (2) 66 percent of all OGV by March 2012, and (3) 100 percent of all OGV by December 2014. Lease stipulations shall include consideration of alternative technologies that achieve 90-100 percent of the emission reductions of cold-ironing.		
Agency Responsible for Tracking: POLB Environmental Planning Division. Action (i): Real Estate Division to include requirements in Project lease agreement. Submittal Date: Verified By: Attachments:			
Action (i): Real Estate Division to include requirements in Project lease agreement. Submittal Date: Verified By: Attachments:	Agency Responsible for Action: POLB Real Estate	Division.	
Submittal Date: Verified By: Attachments:	Agency Responsible for Tracking: POLB Environm	nental Planning Division.	
Verified By: Title: Attachments:	Action (i): Real Estate Division to include requirement	nts in Project lease agreement.	
Attachments:	Submittal Date:		
	Verified By:	Title:	
Comments:	Attachments:		
	Comments:		

Mitigation Measure AQ-6: Low-sulfur Fuels in OGV		
Required Action: <u>Mitigation Measure AQ-6: Low-sulfur Fuels in OGV.</u> All OGV that call at the Middle Harbor container terminal shall use 0.2 percent or lower sulfur MGO fuel in vessel auxiliary and main engines at berth and out to a distance of 40 nm from Point Fermin, or implement equivalent emission reductions.		
When Required: Daily at the commencement of a fu		
Agency Responsible for Action: POLB Real Estate	Division.	
Agency Responsible for Tracking: POLB Environm	nental Planning Division.	
Action (i): Real Estate Division to include requirements in Project lease agreement.		
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure AQ-7: Container Handling Equipment

Required Action: <u>Mitigation Measure AQ-7:</u> <u>Container Handling Equipment.</u> All Project CHE shall meet the following performance standards.

- By the end of 2010, all yard tractors shall meet, at a minimum, the EPA non-road Tier 4 engine standards;
- By the end of 2012, all pre-2007 on-road or pre-Tier 4 non-road top picks, forklifts, reach stackers, RTGs, and straddle carriers less than 750 Hp shall meet, at a minimum, the EPA non-road Tier 4 engine standards; and

standards; and	
	nan 750 Hp shall meet, at a minimum, the EPA Tier 4 ipment is replaced with Tier 4), all CHE with engines VDEC, as established by the ARB.
When Required: Daily according to the operational s	
Agency Responsible for Action: POLB Real Estate	Division.
Agency Responsible for Tracking: POLB Environm	ental Planning Division.
Action (i): Real Estate Division to include requiremen	nts in Project lease agreement.
Submittal Date:	
Verified By:	Title:
Attachments:	
Comments:	
	•
I	

Mitigation Measure AQ-7a: High Efficiency Rail Mounted Gantry (RMG) Cranes

Required Action: <u>Mitigation Measure AQ-7a: High Efficiency Rail Mounted Gantry (RMG) Cranes.</u> The Project terminal operator shall replace all diesel-powered RTGs with electric-powered RMGs, as soon as feasible, but no later than the completion of construction in 2020. Each RMG shall include high efficiency, regenerative drive systems.

When Required: Daily, as soon as possible, but no later than 2020.		
Agency Responsible for Action: POLB Engineering Division and Real Estate Division.		
Agency Responsible for Tracking: POLB Environm	nental Planning Division.	
Action (i): Engineering Division shall construct the n support the use of RMGs.	ecessary infrastructure during Project construction to	
Action (ii): Real Estate Division to include requiremen to RTGs.	ts in Project lease agreement to use RMGs, as opposed	
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure AQ-8: Heavy-Duty Trucks

Required Action: Mitigation Measure AQ-8: Heavy-Duty Trucks. Container trucks that call at the Middle Harbor container terminal shall comply with the following replacement schedule as part of the POLB Clean Truck Program (CTP) Tariff No. 4. This measure goes beyond the ARB's requirements for reducing truck emissions. However, it is more stringent and would result in the following:

- Ban pre-1989 trucks by 10/1/2008;
- Ban 1989-1993 trucks by 1/1/2010;
- Ban un-retrofitted 1994-2003 trucks by 1/1/2010; and
- Ban all trucks that do not meet the EPA 2007 Heavy-Duty Highway Rule emission standards by 1/1/2012.

1/1/2012.	
When Required: At the commencement of a fully executed lease and daily according to the operational schedule in POLB Tariff No. 4.	
Agency Responsible for Action: POLB Real Estate	Division.
Agency Responsible for Tracking: POLB Environm	ental Planning Division.
Action (i): Real Estate Division to include requirement comply with POLB Tariff No. 4, which contains the red	ts in the Project lease agreement that the tenant must quirements of the Clean Trucks Program.
Submittal Date:	
Verified By:	Title:
Attachments:	
Comments:	

Mitigation Measure AQ-9: Clean Railyard Standards		
Required Action: Mitigation Measure AQ-9: Clean Railyard Standards. The expanded Pier F intermodal railyard shall incorporate the cleanest locomotive technologies into its operations.		
When Required: Daily at the commencement of a fu	lly executed lease.	
Agency Responsible for Action: POLB Real Estate	Division.	
Agency Responsible for Tracking: POLB Environm	nental Planning Division.	
Action (i): Real Estate Division shall include requiren	nents in Project lease agreement.	
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure AQ-10: Truck Idling Reduction Measures		
Required Action: Mitigation Measure AQ-10: Truck Idling Reduction Measures. The Middle Harbor container terminal operator shall minimize on-terminal truck idling and emissions. Potential methods to reduce idling include, but are not limited to (1) maximize the durations when the main gates are left open, including during off-peak hours, and (2) implement a container tracking and appointment-based truck delivery and pick-up system to minimize fuel consumption and resulting criteria pollutant emissions.		
When Required: Daily at the commencement of a fully executed lease.		
Agency Responsible for Action: POLB Real Estate Division.		
Agency Responsible for Tracking: POLB Environmental Planning Division.		
Action (i): Real Estate Division to include requirements in Project lease agreement.		
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure AQ-11: Slide Valves on OGV Main Engines	
Required Action: Mitigation Measure AQ-11: Slide Valves on OGV Main Engines. All OGV that call at the Project container terminal shall have slide fuel valves installed on their main engines, or implement an equivalent emission reduction technology. This retrofit is most applicable to OGV with MAN B&W engines.	
When Required: Daily at the commencement of a fully executed lease.	
Agency Responsible for Action: POLB Real Estate	Division.
Agency Responsible for Tracking: POLB Environmental Planning Division.	
Action (i): Real Estate Division to include requirements in Project lease agreement.	
Submittal Date:	
Verified By:	Title:
Attachments:	
Comments:	

Mitigation Measure AQ-12: Expanded VSRP for GHG	
Required Action: Mitigation Measure AQ-12: Expanded VSRP for GHG. All OGV that call at the Middle Harbor container terminal shall comply with the expanded VSRP of 12 knots from the California overwater border to the Precautionary Area.	
When Required: Daily at the commencement of a fully executed lease.	
Agency Responsible for Action: POLB Real Estate	e Division.
Agency Responsible for Tracking: POLB Environmental Planning Division.	
Action (i): Real Estate Division to include requirements in Project lease agreement.	
Submittal Date:	
Verified By:	Title:
Attachments:	
Comments:	
	ļ

Required Action: Mitigation Measure AQ-13: Low-sulfur Fuels in OGV for GHG. All OGV that call at the Project container terminal shall use 0.2 percent or lower sulfur MGO fuel in vessel auxiliary and main engines at berth and within California State Waters, or implement equivalent emission reductions. When Required: Daily at the commencement of a fully executed lease. Agency Responsible for Action: POLB Real Estate Division. Agency Responsible for Tracking: POLB Environmental Planning Division. Action (i): Real Estate Division to include requirements in Project lease agreement. Submittal Date: Verified By: Title:	
When Required: Daily at the commencement of a fully executed lease. Agency Responsible for Action: POLB Real Estate Division. Agency Responsible for Tracking: POLB Environmental Planning Division. Action (i): Real Estate Division to include requirements in Project lease agreement. Submittal Date:	
Agency Responsible for Tracking: POLB Environmental Planning Division. Action (i): Real Estate Division to include requirements in Project lease agreement. Submittal Date:	
Action (i): Real Estate Division to include requirements in Project lease agreement. Submittal Date:	
Submittal Date:	
Verified By: Title:	
-	
Attachments:	
Comments:	_
	İ

Mitigation Measure AQ-14: LEED		
Required Action: Mitigation Measure AQ-14: LEED. The main terminal building shall obtain the LEED gold certification level.		
When Required: Upon completion of Project constru	uction of main terminal building.	
Agency Responsible for Action: POLB Engineering	g Division.	
Agency Responsible for Tracking: POLB Environm	nental Planning Division.	
Action (i): Engineering Division to include requirement	ts in Project construction specifications and bid process.	
Action (ii): Construction Management Division to veri certification level.	fy that the main terminal building meets the LEED gold	
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure AQ-15: Compact Fluorescent Light Bulbs		
Required Action: Mitigation Measure AQ-15: Compact Fluorescent Light Bulbs. All interior terminal building lighting shall use compact fluorescent light bulbs.		
When Required: Daily at the commencement of a fully executed lease.		
Agency Responsible for Action: POLB Real Estate [Division.	
Agency Responsible for Tracking: POLB Environme	ntal Planning Division.	
Action (i): Real Estate Division shall include requirements in Project lease agreement.		
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		
	i i	
•		

APRIL 2009

Mitigation Measure AQ-16: Energy Audit		
Required Action: Mitigation Measure AQ-16: Energy Audit. The Middle Harbor container terminal tenant shall conduct a third party energy audit every five years and install innovative power saving technologies where feasible, such as power factor correction systems and lighting power regulators.		
When Required: At the commencement of a fully executed lease and every five years during Project operations.		
Agency Responsible for Action: POLB Real Estate Division.		
Agency Responsible for Tracking: POLB Environmental Planning Division.		
Action (i): Real Estate Division to include requirements in Project lease agreement.		
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure AQ-17: Solar Panels		
Required Action: Mitigation Measure AQ-17: Solar Panels. The Port shall install solar panels on the main terminal building.		
When Required: By completion of Project construction	on of the main terminal building.	
Agency Responsible for Action: POLB Engineering	g Division.	
Agency Responsible for Tracking: POLB Environm	nental Planning Division.	
Action (i): Engineering Division to include requirements in Project construction specifications and bid process.		
Action (ii): Construction Management Division to verify that solar panels are installed on the main terminal building.		
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure AQ-17a: Solar Carports		
Required Action: Mitigation Measure AQ-17a: Solar Carports. The Port shall install carport-mounted PV solar panels over the employee and visitor parking areas to the maximum extent feasible.		
When Required: By completion of Project construction.		
Agency Responsible for Action: POLB Engineering	Division.	
Agency Responsible for Tracking: POLB Environmental Planning Division.		
Action (i): Engineering Division to include requirements in Project construction specifications and bid process.		
Action (ii): Construction Management Division to verify that carport-mounted PV solar panels are installed over the employee and visitor parking area to the maximum extent feasible.		
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		
	,	

Mitigation Measure AQ-18: Recycling

Required Action: <u>Mitigation Measure AQ-18: Recycling</u>. The terminal buildings shall achieve a minimum of 40 percent recycling by 2012 and 60 percent recycling by 2015. Recycled materials shall include:

- White and colored paper;
- Post-it notes;
- Magazines;
- Newspaper;
- File folders;
- · All envelopes including those with plastic windows;
- All cardboard boxes and cartons;
- All metal and aluminum cans;
- · Glass bottles and jars; and
- All plastic bottles.

When Required: Daily according to operational schedule in measure.

Agency Responsible for Action: POLB Real Estate Division.		
Agency Responsible for Tracking	: POLB Environmental Planning Division.	
Action (i): Real Estate Division to in	nclude requirements in Project lease agreement.	
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure	AQ-19: Tree Planting	
Required Action: Mitigation Measure AQ-19: Tree Planting. The Port shall plant shade trees around the main terminal building.		
When Required: By completion of Project construction	on.	
Agency Responsible for Action: POLB Engineering	g Division.	
Agency Responsible for Tracking: POLB Environm	nental Planning Division.	
Action (i): Engineering Division to include requirement	ts in Project construction specifications and bid process.	
Action (ii): Construction Management Division to verify that shade trees are planted around the main terminal building.		
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure AQ-19a: Tree Planting - Transportation Corridors

Required Action: Mitigation Measure AQ-19a: Tree Planting – Transportation Corridors. The Port shall plant new shade trees on Port-controlled lands adjacent to the roads into the Middle Harbor container terminal to the extent practicable given safety and other land use considerations. The terminal will incorporate cool roofing systems to the extent feasible. Building rooftop areas which are covered with solar panels in accordance with Mitigation Measure AQ-17 shall be exempt from this measure.

panels in accordance with Mitigation Measure AQ-17 shall be exempt from this measure.		
When Required: By completion of Project construction		
Agency Responsible for Action: POLB Engineering	g Division.	
Agency Responsible for Tracking: POLB Environm	nental Planning Division.	
Action (i): Engineering Division shall include requirements in Project construction specifications and bid process		
Action (ii): Construction Management Division to veri adjacent to roads into the terminal to the extent practi	fy that shade trees are planted on Port-controlled land icable.	
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure AQ-20: Cool Roofs Required Action: Mitigation Measure AQ-20: Cool Roofs. Buildings on the Middle Harbor container terminal will incorporate cool roofing systems to the extent feasible. Building rooftop areas which are covered with solar panels in accordance with Mitigation Measure AQ-17 shall be exempt from this measure. When Required: By completion of Project construction. Agency Responsible for Action: POLB Engineering Division. Agency Responsible for Tracking: POLB Environmental Planning Division. Action (i): Engineering Division to include requirements in Project construction specifications and bid process. Action (ii): Construction Management Division to verify that cool roofing systems are incorporated into building design for buildings without solar panels. **Submittal Date:** Title: Verified By: Attachments: Comments:

Mitigation Measure AQ-21: Energy Efficient Boom Flood Lights

Required Action: Mitigation Measure AQ-21: Energy Efficient Boom Flood Lights. The Port shall install boom flood lights with energy efficient features on existing and new dock cranes to the extent feasible. Such features may include, but are not limited to, use of photo cells/timers, low energy fixtures, and light-spillover reduction features, electronic ballasts, use of double filaments, and applying auto-switch-off controls when the crane boom is up.

Agency Responsible for Action: POLB Engineering Division. Agency Responsible for Tracking: POLB Environmental Planning Division. Action (i): Engineering Division to include requirements in Project construction specifications and bid process. Action (ii): Construction Management Division to verify that boom flood lights with energy efficient features are installed on existing and new dock cranes to the extent feasible. Submittal Date: Verified By: Attachments: Comments:	
Action (i): Engineering Division to include requirements in Project construction specifications and bid process. Action (ii): Construction Management Division to verify that boom flood lights with energy efficient features are installed on existing and new dock cranes to the extent feasible. Submittal Date: Verified By: Attachments:	
Action (ii): Construction Management Division to verify that boom flood lights with energy efficient features are installed on existing and new dock cranes to the extent feasible. Submittal Date: Verified By: Attachments:	
Submittal Date: Verified By: Attachments:	
Verified By: Title: Attachments:	
Attachments:	
Comments:	

Mitigation Measure AQ-22: Reefer Lighting		
Required Action: Mitigation Measure AQ-22: Reefer Lighting. The Port shall downsize light fittings and associated electrical power usage at reefer platforms to the extent feasible.		
When Required: Daily at the commencement of a fu	lly executed lease.	
Agency Responsible for Action: POLB Engineering	Division.	
Agency Responsible for Tracking: POLB Environm	nental Planning Division.	
Action (i): Real Estate Division to include requirements in Project lease agreement.		
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure AQ-23: Employee Carpooling

Required Action: <u>Mitigation Measure AQ-23:</u> <u>Employee Carpooling.</u> The construction contractor and terminal tenant shall encourage construction and terminal employees to carpool or to use public transportation. These employers shall provide incentives to promote the measure, include preferential parking for carpoolers, vanpool subsidies, and they shall provide information to employees regarding the benefits of alternative transportation methods.

parking for carpoolers, vanpool subsidies, and they shall provide information to employees regarding the benefits of alternative transportation methods.		
When Required: Daily during Project construction an	nd at the commencement of a fully executed lease.	
Agency Responsible for Action: POLB Engineering	Division.	
Agency Responsible for Tracking: POLB Environm	nental Planning Division.	
Action (i): Engineering Division to include requirement	nts in Project construction specifications.	
Action (i): Real Estate Division to include requirements in the Project lease agreement.		
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure AQ-24: Mitigation for Indirect GHG Emissions

Required Action: Mitigation Measure AQ-24: Mitigation for Indirect GHG Emissions. The terminal tenant shall be required to use green commodities, such as those available from the California Climate Action Registry's Climate Action Reserve, to offset carbon emissions associated with terminal's electricity consumption subject to the limitation specified below. This measure applies to all electricity consumed at the terminal, including shore-to-ship power usage ("cold ironing"). The terminal-related carbon emissions from electricity consumption will be calculated each year based on the local utility's carbon intensity for that year as recognized by the State of California. The tenant may adjust the carbon intensity value to wholly reflect any carbon offsets provided by the electricity deliverer (i.e., point of generation or point of importation) under applicable California and/or federal cap-and-trade regulations (i.e., no double offsetting). The Port is limiting the potential cost of this measure. The maximum expenditure for purchased offsets required under this measure shall not exceed 15 percent of the terminal electricity costs for any given year (i.e., cost of offsets shall not exceed 15 percent of terminal electricity costs (US\$ basis)).

reflect any carbon offsets provided by the electricity de	eliverer (i.e., point of generation or point of
importation) under applicable California and/or federal The Port is limiting the potential cost of this measure.	cap-and-trade regulations (i.e., no double offsetting). The maximum expenditure for purchased offsets
required under this measure shall not exceed 15 perceive., cost of offsets shall not exceed 15 percent of terri	ent of the terminal electricity costs for any given year
When Required: Annually during Project operations	
Agency Responsible for Action: POLB Real Estate	Division.
Agency Responsible for Tracking: POLB Environm	nental Planning Division.
Action (i): Real Estate Division to include requirement	nts in Project lease agreement.
Submittal Date:	
Verified By:	Title:
Attachments:	
Comments:	

Mitigation Measure AQ-25: Periodic Technology Review

Required Action: Mitigation Measure AQ-25: Periodic Technology Review. To promote new emission control technologies, the tenant shall implement in 2015 and every five years following the effective date of the lease agreement, a review of new air quality technological advancements, subject to mutual agreement on

operational feasibility, technical feasibility, and cost-effectiveness and financial feasibility, which shall not be unreasonably withheld. If a technology is determined to be feasible in terms of cost, technical and operational feasibility, the tenant shall work with the Port to implement such technology. When Required: Every five years during Project operations after the commencement of a fully executed lease. Agency Responsible for Action: POLB Real Estate Division. Agency Responsible for Tracking: POLB Environmental Planning Division. Action (i): Real Estate Division shall include requirements in Project lease agreement. Submittal Date: Title: Verified By: Attachments: Comments:

Mitigation Measure AQ-26: Cargo Throughput Monitoring

Required Action: Mitigation Measure AQ-26: Cargo Throughput Monitoring. Every five years, the Port shall compare actual cargo throughput that occurred at the terminal to the cargo assumptions used to develop the Final EIS/EIR. The years used in this analysis shall include 2015, 2020, 2025, and 2030. The Port shall calculate annual air emissions associated with these throughput levels (for OGV, assist tugs, locomotives, cargo handling equipment, and trucks) and compare them to the annual air emissions presented in the Final EIS/EIR. If actual emissions exceed those presented in the Final EIS/EIR, then new/additional mitigations would be applied through Mitigation Measure AQ-25.

EIS/EIR. If actual emissions exceed those presented in the Final EIS/EIR, then new/additional mitigations would be applied through Mitigation Measure AQ-25.		
When Required: Every five years during Project opelease.	rations after the commencement of a fully executed	
Agency Responsible for Action: POLB Real Estate	Division.	
Agency Responsible for Tracking: POLB Environm	ental Planning Division.	
Action (i): Real Estate Division to include requiremen	nts in Project lease agreement.	
Action (ii): Environmental Planning Division will cond mitigation is necessary, and, if so, the nature of the m	luct the analysis every 5 years, determine if additional itigation.	
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure AQ-27: Electrical Regenerative Systems on Dock Cranes		
Required Action: Mitigation Measure AQ-27: Electrical Regenerative Systems on Dock Cranes. Port will require that the terminal operator to have electric regenerative systems on all Project dock cranes in Project year 1.		
When Required: One year after commencement of a	a fully executed lease.	
Agency Responsible for Action: POLB Real Estate	Division.	
Agency Responsible for Tracking: POLB Environm	nental Planning Division.	
Action (i): Real Estate Division to include requirement	nts in Project lease agreement.	
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		
·		

Mitigation Measure AQ-28: Greenhouse Gas Emission Reduction Program Guidelines (GHG Program)

Required Action: Mitigation Measure AQ-28: Greenhouse Gas Emission Reduction Program Guidelines (GHG Program). To partially address the cumulative GHG impacts of the Middle Harbor Redevelopment Project, the Port will require this Project to provide funding for the GHG Program in the amount of \$5 million. This money will be used to pay for measures pursuant to the GHG Emission Reduction Program Guidelines, include, but are not limited to, generation of green power from renewable energy sources, ship electrification, goods movement efficiency measures, cool roofs to reduce building cooling loads and the urban heat island effect, building upgrades for operational efficiency, tree planting for biological sequestration of CO₂, energy-saving lighting, and purchase of renewable energy certificates (RECs).

The timing of the payments pursuant to this mitigation measure shall be made by the later of the following two dates: (1) the date that the Port issues a Notice to Proceed or otherwise authorizes the commencement of construction on the Phase 1 Construction Contract; or (2) the date that the Middle Harbor Final EIS/EIR is conclusively determined to be valid, either by operation of PRC Section 21167.2 or by final judgment or final adjudication.

When Required: Following allocation of funding by the Board, the timing of the payments pursuant to Mitigation Measures AQ-28 shall be made by the later of the following two dates: (1) the date that the Port issues a Notice to Proceed or otherwise authorizes the commencement of construction on the Phase 1 Construction Contract; or (2) the date that the Middle Harbor Final EIR is conclusively determined to be valid, either by operation of Public Resources Code Section 21167.2 or by final judgment or final adjudication.

Cities by operation of the second of the sec	
Agency Responsible for Action: Board of Harbor C	Commissioners
Agency Responsible for Tracking: POLB Environn	nental Planning Division.
Action (i): Board of Harbor Commissioners allocates	s funding.
Action (ii): Environmental Planning Division shall impfunding.	olement the GHG Program Guidelines after allocation of
Submittal Date:	
Verified By:	Title:
Attachments:	
Comments:	

Mitigation Measure AQ-29: Cumulative Air Quality Impact Reduction Program

Required Action: Mitigation Measure AQ-29: Cumulative Air Quality Impact Reduction Program. To help reduce cumulative air quality impacts of the Middle Harbor Redevelopment Project, the Port will require the Project to provide funding in support of the Schools and Related Sites Guidelines for the Port of Long Beach Grant Programs and Healthcare and Seniors Facility Program Guidelines for the Port of Long Beach Grant Programs in the amount of \$5 million each. The distribution of these funds to potential applicants and projects will be determined through a public evaluation process and by approval of the Board of Harbor Commissioners.

The timing of the payments pursuant to this mitigation measure shall be made by the later of the following two dates: (1) the date that the Port issues a Notice to Proceed or otherwise authorizes the commencement of construction on the Phase 1 Construction Contract; or (2) the date that the Middle Harbor Final EIS/EIR is conclusively determined to be valid, either by operation of PRC Section 21167.2 or by final judgment or final adjudication.

When Required: Following allocation of funding by the Board, the timing of the payments pursuant to Mitigation Measures AQ-29 shall be made by the later of the following two dates: (1) the date that the Port issues a Notice to Proceed or otherwise authorizes the commencement of construction on the Phase 1 Construction Contract; or (2) the date that the Middle Harbor Final EIR is conclusively determined to be valid, either by operation of Public Resources Code Section 21167.2 or by final judgment or final adjudication.

Agency Responsible for Action: Board of Harbor Commissioners.

Agency Responsible for Tracking: POLB Environmental Planning Division.

Action (i): Board of Harbor Commissioners allocates funding.

Action (ii): Environmental Planning shall implement the Schools and Related Sites and Heathcare and Seniors Facility Guidelines after allocation of funding.

Seniors Facility Guidelines after a	llocation of funding.	
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure AQ-30: Investigation of Marine Vessel Main Engine Technology

Required Action: Mitigation Measure AQ-30. The Port and terminal tenant will expeditiously contact marine vessel engine manufacturers to identify the maximum technically achievable NOX and PM emission reduction strategies that can be implemented no later than 2014 for main engines on the specific vessels (or on the vessel engine types) that will call on the Project terminal. The Port and terminal tenant will work with the California Air Resources Board and the South Coast Air Quality Management District, with public input, to develop an expeditious schedule to implement such strategies.

When Required: Contacts to begin no later than the commencement of construction.

Agency Responsible for Action: POLB Planning.

Agency Responsible for Action: FOLD Flamming.	
Agency Responsible for Tracking: POLB Planning	-
Action (i): Initiate contact with marine vessel engine	manufacturers.
Action (ii): Coordinate with the California Air Resource District.	es Board and the South Coast Air Quality Management
Submittal Date:	
Verified By:	Title:
Attachments:	
<u>Comments:</u>	

Mitigation Measure BIO-3: Compensation for Loss of Marine Habitat

Required Action: Mitigation Measure BIO-3: Compensation for Loss of Marine Habitat. The Port shall apply approximately 40 credits available in the Bolsa Chica bank to compensate for loss of fish and wildlife habitat due to construction of fill in Slip 1 and East Basin. Implementation of this mitigation measure would occur upon completion of construction of the Project, although permits to begin construction would normally not be issued until the permitting agencies (USACE and POLB for this Project) have received assurance that sufficient mitigation is or will be available. This document constitutes that assurance.

mitigation is or will be available. This document constitutes that assurance.		
When Required: Upon completion of Project constru		
Agency Responsible for Action: POLB Engineering	Division.	
Agency Responsible for Tracking: POLB Planning	Division.	
Action (i): Engineering Division shall provide as-builts	upon completion of construction of the Project landfills	
Action (ii): Planning Division shall submit a final report, with as-builts, to the resource agencies for final approval		
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure TRANS-1.1a: Traffic Management Plan

Required Action: <u>Mitigation Measure TRANS-1.1a</u>: <u>Traffic Management Plan.</u> Prior to beginning construction, the construction contractor shall prepare a detailed traffic management plan, which in addition to work shift start/end times, shall include the following: detour plans, coordination with emergency services, coordination

temporary parking replacement or alternative adjacen designated haul routes, use of truck staging areas,	ed notice of temporary parking loss, identification of t parking within a reasonable walking distance, use of observance of hours of operations restrictions and ic management plan shall be submitted to Port of Long
When Required: Prior to commencement of constru	ction activities.
Agency Responsible for Action: POLB Engineering	g Division.
Agency Responsible for Tracking: POLB Environm	nental Planning Division.
Action (i): Engineering Division to include requirement	ts in Project construction specifications and bid process.
Action (ii): Construction Management Division to ver	ify that the traffic management plan is implemented.
Submittal Date:	
Verified By:	Title:
Attachments:	
Comments:	

Mitigation Measure TRANS-1.1b: Restricted Construction-Related Traffic Hours		
Required Action: Mitigation Measure TRANS-1.1b: Restricted Construction-Related Traffic Hours. Consistent with City of Long Beach Public Works Department practice, the construction-related traffic to/from the Project site shall be restricted during morning and afternoon peak commute hours. Furthermore, no closure of major road corridors shall be permitted as a result of construction activities.		
When Required: Prior to commencement of constru	ction activities.	
Agency Responsible for Action: POLB Engineering	g Division.	
Agency Responsible for Tracking: POLB Environn	nental Planning Division.	
Action (i): Engineering Division to include requirement	ents in Project construction sp	ecifications.
Action (ii): Construction Management Division to ve	rify that restrictions are imple	mented.
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		
		·

Mitigation Measure TRANS-1.1c: Signal Installation		
Required Action: Mitigation Measure <u>TRANS-1.1c</u> : <u>Signal Installation</u> . The Port shall install a signal at the intersection of Pico Avenue and Pier E Street/Ocean Blvd EB On- and Off-Ramps.		
When Required: Prior to commencement of Project	terminal construction.	
Agency Responsible for Action: POLB Engineering	Division.	
Agency Responsible for Tracking: POLB Environm	ental Planning Division.	
Action (i): Engineering Division to include requirement	s in Project construction specifications and bid process.	
Action (ii): Construction Management Division to verify that traffic signal is installed.		
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure TRANS-1.1d: Signal Installation		
Required Action: Mitigation Measure <u>TRANS-1.1d: Signal Installation.</u> The Port shall install a signal at the intersection of Pico Avenue and Pier D Street.		
When Required: Prior to commencement of Project	terminal construction.	
Agency Responsible for Action: POLB Engineering	Division.	
Agency Responsible for Tracking: POLB Environm	ental Planning Division.	
Action (i): Engineering Division to include requirements in Project construction specifications and bid process.		
Action (ii): Construction Management Division to ver	ify that traffic signal is installed.	
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Required Action: Mitigation Measure TRANS-1.1e: Signal Installation. The Port shall install a signal at the intersection of Pico Avenue/Pier G Avenue and Harbor Plaza. When Required: Prior to commencement of Project terminal construction. Agency Responsible for Action: POLB Engineering Division. Agency Responsible for Tracking: POLB Environmental Planning Division. Action (i): Engineering Division to include requirements in Project construction specifications and bid process. Action (ii): Construction Management Division to verify that traffic signal is installed. Submittal Date: Verified By: Attachments: Comments:	Mitigation Measure TRANS-1.1e: Signal Installation		
Agency Responsible for Action: POLB Engineering Division. Agency Responsible for Tracking: POLB Environmental Planning Division. Action (i): Engineering Division to include requirements in Project construction specifications and bid process. Action (ii): Construction Management Division to verify that traffic signal is installed. Submittal Date: Verified By: Attachments:	Required Action: Mitigation Measure TRANS-1.1e: Signal Installation. The Port shall install a signal at the		
Agency Responsible for Tracking: POLB Environmental Planning Division. Action (i): Engineering Division to include requirements in Project construction specifications and bid process. Action (ii): Construction Management Division to verify that traffic signal is installed. Submittal Date: Verified By: Attachments:	When Required: Prior to commencement of Project terminal constru	uction.	
Action (i): Engineering Division to include requirements in Project construction specifications and bid process. Action (ii): Construction Management Division to verify that traffic signal is installed. Submittal Date: Verified By: Attachments:	Agency Responsible for Action: POLB Engineering Division.		
Action (ii): Construction Management Division to verify that traffic signal is installed. Submittal Date: Verified By: Attachments:	Agency Responsible for Tracking: POLB Environmental Planning	Division.	
Submittal Date: Verified By: Title: Attachments:			
Verified By: Title: Attachments:	Action (ii): Construction Management Division to verify that traffic signal is installed.		
Attachments:			
Comments:	Attachments:		
	Comments:		

Mitigation Measure TRANS-1.2: Signal Installation		
Required Action: Mitigation MeasureTRANS-1.2: Signal Installation. The Port shall install a signal at the intersection of Pico Avenue and Ocean Blvd WB Off-Ramp.		
When Required: Prior to commencement of Project	terminal construction.	
Agency Responsible for Action: POLB Engineering	Division.	
Agency Responsible for Tracking: POLB Environm	ental Planning Division.	
Action (i): Engineering Division to include requirements in Project construction specifications and bid process.		
Action (ii): Construction Management Division to verify that traffic signal is installed.		
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		
	,	

Mitigation Measure TRANS-2.1: Fair Share Based Program		
Required Action: Mitigation MeasureTRANS-2.1: Fair Share Based Program. If Caltrans either: a) adopts a fair share based program to collect funds for actual mitigation that Caltrans commits itself to implement; or b) otherwise obtains the balance of funding needed to improve the impacted study highway segments in a manner that will improve the segments level of operation, POLB shall pay its fair share into that program.		
When Required: Undetermined at this time.		
Agency Responsible for Action: Caltrans.		
Agency Responsible for Tracking: POLB Environmental Planning Division.		
Action (i): POLB Transportation Planning Division to coordinate annually with Caltrans.		
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		
·		

Mitigation Measure PHS-2.1: Mitigation Agreement		
Required Action: Mitigation Measure PHS-2.1: Mitigation Agreement. The Port shall enter into a mitigation agreement to upgrade existing facilities at Stations 15 and 20. The Port shall submit proof to the City of Long Beach that an agreement has been executed prior to commencement of construction activities.		
When Required: Prior to commencement of construction	ction activities on fire stations.	
Agency Responsible for Action: POLB Real Estate	Division.	
Agency Responsible for Tracking: POLB Environm	nental Planning Division.	
Action (i): Real Estate Division to enter into an agreement with the City of Long Beach.		
Action (ii): Construction Management Division to ver	ify that fire station facilities are upgraded.	
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure NOI-1.1a: Temporary Noise Barriers		
Required Action: <u>Mitigation Measure NOI-1.1a</u> : <u>Temporary Noise Barriers</u> . Temporary noise barriers shall be located between noise-generating construction activities (e.g., pile driving) and hotel/residential buildings and Cesar Chavez School to the east.		
When Required: During pile-driving activity.		
Agency Responsible for Action: POLB Engineering	g Division.	
Agency Responsible for Tracking: POLB Environm	nental Planning Division.	
Action (i): Engineering Division to include requiremen	nts in Project construction specification and bid process.	
Action (ii): Construction Management Division to ver	ify that temporary noise barriers are used.	
Submittal Date:	·	
Verified By:	Title:	
Attachments:		
Comments:		
	}	

Mitigation Measure NOI-1.1b: Restricted Hours for Pile-driving Activities		
Required Action: <u>Mitigation Measure NOI-1.1b</u> : <u>Restricted Hours for Pile-Driving Activities</u> . Pile-driving activities shall be limited to the hours of 7:00 am to 7:00 pm on weekdays, between 9:00 am and 6:00 pm on Saturdays, and prohibited anytime on Sundays and holidays as prescribed by Section 8.80.202 of the LBMC.		
When Required: During pile-driving activity.		
Agency Responsible for Action: POLB Engineering	g Division.	
Agency Responsible for Tracking: POLB Environm	nental Planning Division.	
Action (i): Engineering Division to include requireme	nts in Project construction specification.	
Action (ii): Construction Management Division to verify that pile-driving activities occur only during specified hours.		
Submittal Date:		
Verified By:	Title:	
Attachments:		
Comments:		

Mitigation Measure CR-1.1.1: Archaeological Material Discovery Plan

Required Action: Mitigation Measure CR-1.1.1: Archaeological Material Discovery Plan. In the unlikely event that any archaeological material is discovered during construction, all work must be halted within the vicinity of the archaeological discovery until an assessment of the significance by a qualified archaeologist is completed. If the resources are found to be significant, they shall be avoided or shall be mitigated consistent with SHPO Guidelines. Treatment plans must be developed in consultation with the County, SHPO, and local Native Americans. If human remains are encountered, the Los Angeles County Coroner shall be contacted immediately. If the remains appear to be Native American, the coroner shall contact the Native American Heritage Commission who will appoint the Most Likely Descendent. Additionally, if the human remains are determined to be Native American, a plan will be developed regarding the treatment of human remains and associated burial objects, and the plan will be implemented under the direction of the Most Likely Descendent.

Americans. If human remains are encountered, the Los Angeles County Coroner shall be contacted immediately. If the remains appear to be Native American, the coroner shall contact the Native American Heritage Commission who will appoint the Most Likely Descendent. Additionally, if the human remains are determined to be Native American, a plan will be developed regarding the treatment of human remains and associated burial objects, and the plan will be implemented under the direction of the Most Likely Descendent.		
When Required: Daily during Project construction.		
Agency Responsible for Action: POLB Engineering Di	ivision.	
Agency Responsible for Tracking: POLB Environment	tal Planning Division.	
Action (i): Engineering Division to include requirements in	n Project construction specifications and bid process.	
Action (ii): Construction Management Division to verify work has stopped and the proper authorities notified.	that upon discovery of archaeological material that	
Submittal Date:		
Verified By:	itle:	
Attachments:		
Comments:		

Mitigation Measure CR-1.2.1: Relocation of Historic Architectural Resources

Required Action: CR-1.2.1: Relocation of Historic Architectural Resources. The two historic architectural resources shall be temporarily moved during construction and then relocated to another suitable location within the Project area subsequent to construction under the direction of a qualified Architectural Historian. A survey shall be conducted after their relocation to document, identify, and describe any internal and external cracking, condition of walls, and other elements as a result of their movement. The survey shall be undertaken under the direction of a qualified Architectural Historian and shall be in accordance with accepted standard methods. A written report documenting conditions after Project completion shall be prepared under the supervision and approval of a qualified Architectural Historian. The report shall provide any necessary measures to address stabilization and repair of areas that have been disturbed during relocation, including photo-documentation. The repairs shall be undertaken by the Port in a timely manner.

supervision and approval of a qualified Architectura measures to address stabilization and repair of areas photo-documentation. The repairs shall be undertake	al Historian. The report shall provide any necessary that have been disturbed during relocation, including
When Required: Prior to proposed Project construct	
Agency Responsible for Action: POLB Engineering	g Division.
Agency Responsible for Tracking: POLB Environm	nental Planning Division.
Action (i): Engineering Division to include requireme	nts in Project construction specification.
Action (ii): Construction Management Division to ve resources.	rify the relocation of the existing historic architectural
Submittal Date:	
Verified By:	Title:
Attachments:	
Comments:	

PORT OF LONG BEACH	 MITIGATION MONITORING AND REPORTING PROGRAM

This page intentionally left blank.