

Appendix D Noise Worksheets

Golden Shore Master Plan Project Draft EIR

Noise Worksheets

Provided by PCR Services Corporation

September 2009

- D-1 Ambient Noise Data
- D-2 Construction Noise Calculations
- D-3 Off-Site Traffic Noise Calculations

Appendix D-1

• Ambient Noise Data



Project:Golden Shore Master PlanLocation:R1 - North Property LineSources:Ambient

Date: November 20, 2008







Project:Golden Shore Master PlanLocation:R1 - North Property LineSources:Ambient

Date: November 21, 2008







Project:Golden Shore Master PlanLocation:R1 - North Property LineSources:Ambient

Date: November 22, 2008







Project:Golden Shore Master PlanLocation:R1 - North Property LineSources:Ambient

Date: November 23, 2008







Project:Golden Shore Master PlanLocation:R2 - Southwest Property LineSources:Ambient

Date: November 20, 2008







Project:Golden Shore Master PlanLocation:R2 - Southwest Property LineSources:Ambient

Date: November 21, 2008







Project:Golden Shore Master PlanLocation:R2 - Southwest Property LineSources:Ambient

Date: November 22, 2008







Project:Golden Shore Master PlanLocation:R2 - Southwest Property LineSources:Ambient

Date: November 23, 2008





Appendix D-2

• Construction Noise Calculations



Construction Phase: Phase 1 Demolition

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Concrete Saw	1	90	20%	200	0
Cranes	1	81	40%	200	0
Compressors	1	78	50%	200	0
Other Equipment	1	85	50%	200	0
Tractor/Loader/Backhoe	1	80	50%	200	0
Receptor:	R2				

Results:

Hourly Leq:

75



Construction Phase: Phase 1 Site Grading

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Water Trucks	1	80	10%	400	0
Excavator	1	81	40%	400	0
Graders	1	85	40%	400	0
Other Equipment	1	85	50%	400	0
Rubber Tired Loader	1	79	50%	400	0
Tractor/Loader/Backhoe	1	80	40%	400	0

Receptor:

R2

Results:

Hourly Leq:

68



Construction Phase: Phase 1 Foundation

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Tractor/Loader/Backhoe	1	80	40%	400	0
Pumps	1	81	50%	400	0
Concrete Mixer Trucks	1	79	40%	400	0
Water Trucks	1	80	10%	400	0
Pile Driver (Sonic)	1	96	20%	400	0
Other Equipment	1	85	50%	400	0

Receptor:

R2

Results:

Hourly Leq:

72



Construction Phase: Phase 1 Building Construction

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Cement and Mortar Mixers	1	79	40%	400	0
Forklift	1	75	10%	400	0
Generator Sets	1	81	50%	400	0
Other Equipment	1	85	50%	400	0
Cranes	1	81	40%	400	0
Welders	1	74	40%	400	0
_					
Decenter	D7				

Receptor:

R2

Results:

Hourly Leq:

67



Construction Phase: Phase 1 Demolition

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Concrete Saw	1	90	20%	1500	10
Cranes	1	81	40%	1500	10
Compressors	1	78	50%	1500	10
Other Equipment	1	85	50%	1500	10
Tractor/Loader/Backhoe	1	80	50%	1500	10
Receptor:	R4				

Results:

Hourly Leq:

47



Construction Phase: Phase 1 Site Grading

Equipment

ft, Acoustical Distance to Estimated Noise
Usage Factor Receptor, ft Shielding, dBA
10% 1500 10
40% 1500 10
40% 1500 10
50% 1500 10
50% 1500 10
40% 1500 10

Receptor:

Results:

R4

Hourly Leq:

47



Construction Phase: Phase 1 Foundation

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Tractor/Loader/Backhoe	1	80	40%	1500	10
Pumps	1	81	50%	1500	10
Concrete Mixer Trucks	1	79	40%	1500	10
Water Trucks	1	80	10%	1500	10
Pile Driver (Sonic)	1	96	20%	1500	10
Other Equipment	1	85	50%	1500	10
Pagantari					

Receptor:

R4

Results:

Hourly Leq:

51



Construction Phase: Phase 1 Building Construction

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Cement and Mortar Mixers	1	79	40%	1500	10
Forklift	1	75	10%	1500	10
Generator Sets	1	81	50%	1500	10
Other Equipment	1	85	50%	1500	10
Cranes	1	81	40%	1500	10
Welders	1	74	40%	1500	10
Decenter					
Receptor:	K4				

Results:

Hourly Leq:

45



Construction Phase: Phase 1 Demolition

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Concrete Saw	1	90	20%	800	5
Cranes	1	81	40%	800	5
Compressors	1	78	50%	800	5
Other Equipment	1	85	50%	800	5
Tractor/Loader/Backhoe	1	80	50%	800	5
Receptor:	R5				

Results:

Hourly Leq:

58



Construction Phase: Phase 1 Site Grading

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Water Trucks	1	80	10%	800	5
Excavator	1	81	40%	800	5
Graders	1	85	40%	800	5
Other Equipment	1	85	50%	800	5
Rubber Tired Loader	1	79	50%	800	5
Tractor/Loader/Backhoe	1	80	40%	800	5
_					

Receptor:

R5

Results:

Hourly Leq:

57



Construction Phase: Phase 1 Foundation

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Tractor/Loader/Backhoe	1	80	40%	800	5
Pumps	1	81	50%	800	5
Concrete Mixer Trucks	1	79	40%	800	5
Water Trucks	1	80	10%	800	5
Pile Driver (Sonic)	1	96	20%	800	5
Other Equipment	1	85	50%	800	5
Receptor:	R5				

Results:

Hourly Leq:

61



Construction Phase: Phase 1 Building Construction

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Cement and Mortar Mixers	1	79	40%	800	5
Forklift	1	75	10%	800	5
Generator Sets	1	81	50%	800	5
Other Equipment	1	85	50%	800	5
Cranes	1	81	40%	800	5
Welders	1	74	40%	800	5
Receptor:	R5				

Results:

Hourly Leq:

56



Construction Phase: Phase 1 Demolition

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Concrete Saw	1	90	20%	150	0
Cranes	1	81	40%	150	0
Compressors	1	78	50%	150	0
Other Equipment	1	85	50%	150	0
Tractor/Loader/Backhoe	1	80	50%	150	0
Receptor:	R6				

Results:

Hourly Leq:

77



Construction Phase: Phase 1 Site Grading

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Water Trucks	1	80	10%	150	0
Excavator	1	81	40%	150	0
Graders	1	85	40%	150	0
Other Equipment	1	85	50%	150	0
Rubber Tired Loader	1	79	50%	150	0
Tractor/Loader/Backhoe	1	80	40%	150	0
_					

Receptor:

R6

Results:

Hourly Leq:

77



Construction Phase: Phase 1 Foundation

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Tractor/Loader/Backhoe	1	80	40%	150	0
Pumps	1	81	50%	150	0
Concrete Mixer Trucks	1	79	40%	150	0
Water Trucks	1	80	10%	150	0
Pile Driver (Sonic)	1	96	20%	150	0
Other Equipment	1	85	50%	150	0
Receptor:	R6				

Results:

Hourly Leq:

81



Construction Phase: Phase 1 Building Construction

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Cement and Mortar Mixers	1	79	40%	200	0
Forklift	1	75	10%	200	0
Generator Sets	1	81	50%	200	0
Other Equipment	1	85	50%	200	0
Cranes	1	81	40%	200	0
Welders	1	74	40%	200	0
Decenter	DC				
Receptor:	K0				

Results:

Hourly Leq:

73



Construction Phase: Phase 2 Site Grading

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Water Trucks	1	80	10%	200	0
Excavator	1	81	40%	200	0
Graders	1	85	40%	200	0
Other Equipment	1	85	50%	200	0
Rubber Tired Loader	1	79	50%	200	0
Tractor/Loader/Backhoe	1	80	40%	200	0

Receptor:

R2

Results:

Hourly Leq:

74



Construction Phase: Phase 2 Foundation

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Tractor/Loader/Backhoe	1	80	40%	200	0
Pumps	1	81	50%	200	0
Concrete Mixer Trucks	1	79	40%	200	0
Water Trucks	1	80	10%	200	0
Pile Driver (Sonic)	1	96	20%	200	0
Other Equipment	1	85	50%	200	0
Receptor:	R2				

Results:

Hourly Leq:

78



Construction Phase: Phase 2 Building Construction

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Cement and Mortar Mixers	1	79	40%	200	0
Forklift	1	75	10%	200	0
Generator Sets	1	81	50%	200	0
Other Equipment	1	85	50%	200	0
Cranes	1	81	40%	200	0
Welders	1	74	40%	200	0
-					

Receptor:

R2

Results:

Hourly Leq:

73



Construction Phase: Phase 2 Site Grading

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Water Trucks	1	80	10%	1500	10
Excavator	1	81	40%	1500	10
Graders	1	85	40%	1500	10
Other Equipment	1	85	50%	1500	10
Rubber Tired Loader	1	79	50%	1500	10
Tractor/Loader/Backhoe	1	80	40%	1500	10

Receptor:

Results:

R4

Hourly Leq:

47



Construction Phase: Phase 2 Foundation

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Tractor/Loader/Backhoe	1	80	40%	1500	10
Pumps	1	81	50%	1500	10
Concrete Mixer Trucks	1	79	40%	1500	10
Water Trucks	1	80	10%	1500	10
Pile Driver (Sonic)	1	96	20%	1500	10
Other Equipment	1	85	50%	1500	10
Pocontor:	D/				

Receptor:

R4

Results:

Hourly Leq:

51



Construction Phase: Phase 2 Building Construction

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Cement and Mortar Mixers	1	79	40%	1500	10
Forklift	1	75	10%	1500	10
Generator Sets	1	81	50%	1500	10
Other Equipment	1	85	50%	1500	10
Cranes	1	81	40%	1500	10
Welders	1	74	40%	1500	10
	-				

Receptor:

R4

Results:

Hourly Leq:

45



Construction Phase: Phase 2 Site Grading

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Water Trucks	1	80	10%	1000	5
Excavator	1	81	40%	1000	5
Graders	1	85	40%	1000	5
Other Equipment	1	85	50%	1000	5
Rubber Tired Loader	1	79	50%	1000	5
Tractor/Loader/Backhoe	1	80	40%	1000	5

Receptor:

R5

Results:

Hourly Leq:

55



Construction Phase: Phase 2 Foundation

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Tractor/Loader/Backhoe	1	80	40%	1000	5
Pumps	1	81	50%	1000	5
Concrete Mixer Trucks	1	79	40%	1000	5
Water Trucks	1	80	10%	1000	5
Pile Driver (Sonic)	1	96	20%	1000	5
Other Equipment	1	85	50%	1000	5
-					
Receptor:	R5				

Results:

Hourly Leq:

59



Construction Phase: Phase 2 Building Construction

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Cement and Mortar Mixers	1	79	40%	1000	5
Forklift	1	75	10%	1000	5
Generator Sets	1	81	50%	1000	5
Other Equipment	1	85	50%	1000	5
Cranes	1	81	40%	1000	5
Welders	1	74	40%	1000	5
-					
Receptor:	R5				

Results:

Hourly Leq:

54



Construction Phase: Phase 2 Site Grading

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Water Trucks	1	80	10%	400	5
Excavator	1	81	40%	400	5
Graders	1	85	40%	400	5
Other Equipment	1	85	50%	400	5
Rubber Tired Loader	1	79	50%	400	5
Tractor/Loader/Backhoe	1	80	40%	400	5
_					
Receptor:	R6				

Results:

Hourly Leq:

63



Construction Phase: Phase 2 Foundation

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Tractor/Loader/Backhoe	1	80	40%	400	5
Pumps	1	81	50%	400	5
Concrete Mixer Trucks	1	79	40%	400	5
Water Trucks	1	80	10%	400	5
Pile Driver (Sonic)	1	96	20%	400	5
Other Equipment	1	85	50%	400	5
Receptor:	R6				

Results:

Hourly Leq:

67



Construction Phase: Phase 2 Building Construction

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Cement and Mortar Mixers	1	79	40%	400	5
Forklift	1	75	10%	400	5
Generator Sets	1	81	50%	400	5
Other Equipment	1	85	50%	400	5
Cranes	1	81	40%	400	5
Welders	1	74	40%	400	5
	D 2				
Receptor:	K0				
Receptor:	R6				

Hourly Leq:

Results:

62



Construction Phase: Phase 3 Demolition

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Concrete Saw	1	90	20%	350	5
Rubber Tired Loader	1	79	50%	350	5
Compressors	1	78	50%	350	5
Other Equipment	1	85	50%	350	5
Tractor/Loader/Backhoe	1	80	50%	350	5
Receptor:	R2				

Results:

Hourly Leq:

65



Construction Phase: Phase 3 Site Grading

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Water Trucks	1	80	10%	350	5
Excavator	1	81	40%	350	5
Graders	1	85	40%	350	5
Other Equipment	1	85	50%	350	5
Rubber Tired Loader	1	79	50%	350	5
Tractor/Loader/Backhoe	1	80	40%	350	5

Receptor:

R2

Results:

Hourly Leq:

64



Construction Phase: Phase 3 Foundation

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Tractor/Loader/Backhoe	1	80	40%	350	5
Pumps	1	81	50%	350	5
Concrete Mixer Trucks	1	79	40%	350	5
Water Trucks	1	80	10%	350	5
Pile Driver (Sonic)	1	96	20%	350	5
Other Equipment	1	85	50%	350	5
Receptor:	R2				

Results:

Hourly Leq:

69



Construction Phase: Phase 3 Building Construction

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Cement and Mortar Mixers	1	79	40%	350	5
Forklift	1	75	10%	350	5
Generator Sets	1	81	50%	350	5
Other Equipment	1	85	50%	350	5
Cranes	1	81	40%	350	5
Welders	1	74	40%	350	5
_					
Receptor:	R2				

Results:

Hourly Leq:

63



Construction Phase: Phase 3 Demolition

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Concrete Saw	1	90	20%	1200	10
Rubber Tired Loader	1	79	50%	1200	10
Compressors	1	78	50%	1200	10
Other Equipment	1	85	50%	1200	10
Tractor/Loader/Backhoe	1	80	50%	1200	10
Receptor:	R4				

Results:

Hourly Leq:

49



Construction Phase: Phase 3 Site Grading

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Water Trucks	1	80	10%	1200	10
Excavator	1	81	40%	1200	10
Graders	1	85	40%	1200	10
Other Equipment	1	85	50%	1200	10
Rubber Tired Loader	1	79	50%	1200	10
Tractor/Loader/Backhoe	1	80	40%	1200	10

Receptor:

Results:

R4

Hourly Leq:

49



Construction Phase: Phase 3 Foundation

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Tractor/Loader/Backhoe	1	80	40%	1200	10
Pumps	1	81	50%	1200	10
Concrete Mixer Trucks	1	79	40%	1200	10
Water Trucks	1	80	10%	1200	10
Pile Driver (Sonic)	1	96	20%	1200	10
Other Equipment	1	85	50%	1200	10
Receptor:	R4				

Results:

Hourly Leq:

53



Construction Phase: Phase 3 Building Construction

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Cement and Mortar Mixers	1	79	40%	1200	10
Forklift	1	75	10%	1200	10
Generator Sets	1	81	50%	1200	10
Other Equipment	1	85	50%	1200	10
Cranes	1	81	40%	1200	10
Welders	1	74	40%	1200	10
	- 1				

Receptor:

R4

Results:

Hourly Leq:

47



Construction Phase: Phase 3 Demolition

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Estimated Noise		
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Concrete Saw	1	90	20%	800	10
Rubber Tired Loader	1	79	50%	800	10
Compressors	1	78	50%	800	10
Other Equipment	1	85	50%	800	10
Tractor/Loader/Backhoe	1	80	50%	800	10
Receptor:	R5				

Results:

Hourly Leq:

53



Construction Phase: Phase 3 Site Grading

Equipment

		Reference Noise			
	No. of	Level at 50ft,	evel at 50ft, Acoustical Distance to		Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Water Trucks	1	80	10%	800	10
Excavator	1	81	40%	800	10
Graders	1	85	40%	800	10
Other Equipment	1	85	50%	800	10
Rubber Tired Loader	1	79	50%	800	10
Tractor/Loader/Backhoe	1	80	40%	800	10

Receptor:

R5

Results:

Hourly Leq:

52



Construction Phase: Phase 3 Foundation

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Tractor/Loader/Backhoe	1	80	40%	900	10
Pumps	1	81	50%	900	10
Concrete Mixer Trucks	1	79	40%	900	10
Water Trucks	1	80	10%	900	10
Pile Driver (Sonic)	1	96	20%	900	10
Other Equipment	1	85	50%	900	10
Receptor:	R5				

Results:

Hourly Leq:

55



Construction Phase: Phase 3 Building Construction

Equipment

		Reference Noise			
	No. of	Level at 50ft, Acoustical Distance to E Lmax Usage Factor Receptor, ft			Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Cement and Mortar Mixers	1	79	40%	900	10
Forklift	1	75	10%	900	10
Generator Sets	1	Reference NoiseLevel at 50ft, LmaxAcoustical Usage FactorDistance to Receptor, ftEstim 		10	
Other Equipment	1	85	50%	900	10
Cranes	1	81	40%	900	10
Welders	1	74	40%	900	10
Receptor:	R5				

Results:

Hourly Leq:

50



Construction Phase: Phase 3 Demolition

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Estimated Noise		
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Concrete Saw	1	90	20%	180	0
Rubber Tired Loader	1	79	50%	180	0
Compressors	1	78	50%	180	0
Other Equipment	1	85	50%	180	0
Tractor/Loader/Backhoe	1	80	50%	180	0
Receptor:	R6				

Results:

Hourly Leq:

76



Construction Phase: Phase 3 Site Grading

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Estimated Noise		
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Water Trucks	1	80	10%	150	0
Excavator	1	81	40%	150	0
Graders	1	85	40%	150	0
Other Equipment	1	85	50%	150	0
Rubber Tired Loader	1	79	50%	150	0
Tractor/Loader/Backhoe	1	80	40%	150	0
_					
Receptor:	R6				

Results:

Hourly Leq:

77



Construction Phase: Phase 3 Foundation

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Tractor/Loader/Backhoe	1	80	40%	200	0
Pumps	1	81	50%	200	0
Concrete Mixer Trucks	1	79	40%	200	0
Water Trucks	1	80	10%	200	0
Pile Driver (Sonic)	1	96	20%	200	0
Other Equipment	1	85	50%	200	0
Receptor:	R6				

Results:

Hourly Leq:

78



Construction Phase: Phase 3 Building Construction

Equipment

		Reference Noise			
	No. of	Level at 50ft,	Estimated Noise		
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Cement and Mortar Mixers	1	79	40%	200	0
Forklift	1	75	10%	200	0
Generator Sets	1	81	50%	200	0
Other Equipment	1	85	50%	200	0
Cranes	1	81	40%	200	0
Welders	1	74	40%	200	0
Desenter	DC				
Receptor:	K0				

Results:

Hourly Leq:

73

Appendix D-3

• Off-Site Traffic Noise Calculations



Existing										
	Speed		Traffic Volume	s		Leq			CNEL	
Roadway/Segment	MPH	AM	PM	ADT	ROW	25 Feet	50 Feet	ROW	25 Feet	50 Feet
Golden Ave./Golden Shore n/o Ocean Blvd.	30	780	1039	0	66.4	63.4	61.6	67.6	64.6	62.8
Golden Shore between Ocean Blvd. and Seaside Way	30	454	858	0	65.5	62.6	60.8	66.8	63.8	62.0
Golden Shore between Seaside Way and I-710 SB Off-Ramp	30	563	497	0	63.7	60.7	59.0	64.9	61.9	60.2
Golden Shore between I-710 SB Off-Ramp and EB Shoreline Dr. 0	30	509	510	0	63.3	60.3	58.5	64.5	61.5	59.8
0	0			0	-	-	-	-	-	-
Future No Project		•	•	•						
	Speed		Traffic Volume	s		Leq		CNEL		
Roadway/Segment	MPH	AM	PM	ADT	ROW	25 Feet	50 Feet	ROW	25 Feet	50 Feet
Golden Ave./Golden Shore n/o Ocean Blvd.	30	1058	1292	0	67.3	64.3	62.6	68.5	65.5	63.8
Golden Shore between Ocean Blvd. and Seaside Way	30	536	1002	0	66.2	63.2	61.5	67.4	64.4	62.7
Golden Shore between Seaside Way and I-710 SB Off-Ramp	30	655	576	0	64.4	61.4	59.6	65.6	62.6	60.8
Golden Shore between I-710 SB Off-Ramp and EB Shoreline Dr.	30	570	570	0	63.8	60.8	59.0	65.0	62.0	60.2
0	0			0	-	-	-	-	-	-
Future With Project										
	Speed		Traffic Volume	s		Leq			CNEL	
Roadway/Segment	MPH	AM	PM	ADT	ROW	25 Feet	50 Feet	ROW	25 Feet	50 Feet
Golden Ave./Golden Shore n/o Ocean Blvd.	30	1205	1397	0	67.7	64.7	62.9	68.9	65.9	64.1
Golden Shore between Ocean Blvd. and Seaside Way	30	820	1244	0	67.2	64.2	62.4	68.4	65.4	63.6
Golden Shore between Seaside Way and I-710 SB Off-Ramp	30	796	783	0	65.2	62.2	60.5	66.4	63.4	61.7
Golden Shore between I-710 SB Off-Ramp and EB Shoreline Dr. 0	30	630	640	0	64.3	61.3	59.5	65.5	62.5	60.7
0	0			0	-	-	-	-	-	-

		CNEL			
Summary	25 ft. fro	m ROW	At ROW		
	Project	Cumulative	Project	Cumulative	
Roadway/Segment	Increment	Increment	Increment	Increment	
Golden Ave./Golden Shore n/o Ocean Blvd.	0.4	1.3	0.4	1.3	
Golden Shore between Ocean Blvd. and Seaside Way	1.0	1.6	1.0	1.6	
Golden Shore between Seaside Way and I-710 SB Off-Ramp	0.8	1.5	0.8	1.5	
Golden Shore between I-710 SB Off-Ramp and EB Shoreline Dr.	0.5	1.0	0.5	1.0	
0	-	-	-	-	

	% of ADT								
Vehicle Type	Day	Eve	Night	Sub total					
Auto	77.60%	9.70%	9.70%	97.00%					
Medium Truck	1.60%	0.20%	0.20%	2.00%					
Heavy Truck	0.80%	0.10%	0.10%	1.00%					
	80.00%	10.00%	10.00%	100.00%					



Existing										
	Speed		Traffic Volume	es		Leq			CNEL	
Roadway/Segment	MPH	AM	PM	ADT	ROW	25 Feet	50 Feet	ROW	25 Feet	50 Feet
Ocean Blvd. w/o Golden Shore	45	2437	3016	0	72.4	70.4	69.0	73.6	71.6	70.2
Ocean Blvd. between Golden Shore and Magnolia Ave.	30	3080	3489	0	69.4	67.4	66.0	70.6	68.6	67.2
Ocean Blvd. between Magnolia Ave. and Chestnut Pl.	30	2885	3450	0	69.4	67.3	66.0	70.6	68.6	67.2
Ocean Blvd. between Chestnut PI. and Pacific Ave.	30	2942	3508	0	69.4	67.4	66.0	70.7	68.6	67.3
0	0			0	-	-	-	-	-	-
Future No Project	•									
	Speed		Traffic Volume	es		Leq		CNEL		
Roadway/Segment	MPH	AM	PM	ADT	ROW	25 Feet	50 Feet	ROW	25 Feet	50 Feet
Ocean Blvd. w/o Golden Shore	45	2738	3389	0	72.9	70.9	69.5	74.2	72.1	70.8
Ocean Blvd. between Golden Shore and Magnolia Ave.	30	3643	4047	0	70.1	68.0	66.7	71.3	69.2	67.9
Ocean Blvd. between Magnolia Ave. and Chestnut Pl.	30	3502	4150	0	70.2	68.1	66.8	71.4	69.4	68.0
Ocean Blvd. between Chestnut PI. and Pacific Ave.	30	3546	4190	0	70.2	68.2	66.8	71.4	69.4	68.0
0	0			0	-	-	-	-	-	-
Future With Project										
	Speed		Traffic Volume	es		Leq			CNEL	
Roadway/Segment	MPH	AM	PM	ADT	ROW	25 Feet	50 Feet	ROW	25 Feet	50 Feet
Ocean Blvd. w/o Golden Shore	45	2823	3477	0	73.1	71.0	69.7	74.3	72.2	70.9
Ocean Blvd. between Golden Shore and Magnolia Ave.	30	3813	4231	0	70.3	68.2	66.9	71.5	69.4	68.1
Ocean Blvd. between Magnolia Ave. and Chestnut Pl.	30	3553	4208	0	70.2	68.2	66.8	71.4	69.4	68.0
Ocean Blvd. between Chestnut Pl. and Pacific Ave.	30	3678	4327	0	70.3	68.3	66.9	71.6	69.5	68.2
0	0			0	-	-	-	-	-	-

			CNEL			
Summary		25 ft. fro	m ROW	At ROW		
		Project	Cumulative	Project	Cumulative	
Roadway/Segment		Increment	Increment	Increment	Increment	
Ocean Blvd. w/o Golden Shore		0.1	0.6	0.1	0.7	
Ocean Blvd. between Golden Shore and Magnolia Ave.		0.2	0.8	0.2	0.9	
Ocean Blvd. between Magnolia Ave. and Chestnut Pl.		0.0	0.8	0.0	0.8	
Ocean Blvd. between Chestnut Pl. and Pacific Ave.		0.1	0.9	0.2	0.9	
	0	-	-	-	-	

	% of ADT								
Vehicle Type	Day	Eve	Night	Sub total					
Auto	77.60%	9.70%	9.70%	97.00%					
Medium Truck	1.60%	0.20%	0.20%	2.00%					
Heavy Truck	0.80%	0.10%	0.10%	1.00%					
	80.00%	10.00%	10.00%	100.00%					



Existing										
	Speed		Traffic Volume	es		Leq			CNEL	
Roadway/Segment	MPH	AM	PM	ADT	ROW	25 Feet	50 Feet	ROW	25 Feet	50 Feet
Magnolia Blvd. between 3rd St. and 5th St.	25	660	739	0	63.3	60.3	58.6	64.5	61.5	59.8
Magnolia Blvd. between 5th St. and 6th St.	25	679	815	0	63.7	60.7	59.0	64.9	62.0	60.2
Magnolia Blvd. n/o 6th St.	25	730	859	0	63.9	61.0	59.2	65.2	62.2	60.4
Chestnut PI. between Seaside Wy. and Ocean Blvd.	25	198	203	0	59.7	55.6	53.5	60.9	56.8	54.7
Seaside Way w/o Chestnut Pl.	25	241	330	0	59.8	56.8	55.1	61.0	58.0	56.3
Future No Project										
	Speed		Traffic Volume	es		Leq		CNEL		
Roadway/Segment	MPH	AM	PM	ADT	ROW	25 Feet	50 Feet	ROW	25 Feet	50 Feet
Magnolia Blvd. between 3rd St. and 5th St.	25	860	966	0	64.5	61.5	59.7	65.7	62.7	60.9
Magnolia Blvd. between 5th St. and 6th St.	25	886	1062	0	64.9	61.9	60.1	66.1	63.1	61.4
Magnolia Blvd. n/o 6th St.	25	943	1108	0	65.1	62.1	60.3	66.3	63.3	61.5
Chestnut PI. between Seaside Wy. and Ocean Blvd.	25	264	274	0	61.0	56.9	54.8	62.2	58.1	56.0
Seaside Way w/o Chestnut Pl.	25	270	370	0	60.3	57.3	55.6	61.5	58.5	56.8
Future With Project										
	Speed	Traffic Volumes		Leq		CNEL				
Roadway/Segment	MPH	AM	PM	ADT	ROW	25 Feet	50 Feet	ROW	25 Feet	50 Feet
Magnolia Blvd. between 3rd St. and 5th St.	25	977	1090	0	65.0	62.0	60.3	66.2	63.2	61.5
Magnolia Blvd. between 5th St. and 6th St.	25	1002	1185	0	65.3	62.4	60.6	66.6	63.6	61.8
Magnolia Blvd. n/o 6th St.	25	1013	1191	0	65.4	62.4	60.6	66.6	63.6	61.9
Chestnut PI. between Seaside Wy. and Ocean Blvd.	25	346	353	0	62.1	58.0	55.9	63.3	59.2	57.2
Seaside Way w/o Chestnut Pl.	25	460	558	0	62.1	59.1	57.4	63.3	60.3	58.6

		CNEL			
Summary	25 ft. fro	m ROW	At ROW		
	Project	Cumulative	Project	Cumulative	
Roadway/Segment	Increment	Increment	Increment	Increment	
Magnolia Blvd. between 3rd St. and 5th St.	0.5	1.7	0.5	1.7	
Magnolia Blvd. between 5th St. and 6th St.	0.5	1.6	0.5	1.7	
Magnolia Blvd. n/o 6th St.	0.3	1.4	0.3	1.4	
Chestnut PI. between Seaside Wy. and Ocean Blvd.	1.1	2.4	1.1	2.4	
Seaside Way w/o Chestnut Pl.	1.8	2.3	1.8	2.3	

	% of ADT								
Vehicle Type	Day	Eve	Night	Sub total					
Auto	77.60%	9.70%	9.70%	97.00%					
Medium Truck	1.60%	0.20%	0.20%	2.00%					
Heavy Truck	0.80%	0.10%	0.10%	1.00%					
	80.00%	10.00%	10.00%	100.00%					



Existing										
	Speed		Traffic Volume	S		Leq			CNEL	
Roadway/Segment	MPH	AM	PM	ADT	ROW	25 Feet	50 Feet	ROW	25 Feet	50 Feet
Alamitos Ave. between Ocean Blvd. and Broadway	30	1243	1407	0	66.5	64.1	62.5	67.7	65.3	63.7
Alamitos Ave. between Broadway and 4th St.	30	1417	1878	0	67.8	65.3	63.8	69.0	66.5	65.0
Alamitos Ave. n/o 4th St.	30	1418	1760	0	67.5	65.0	63.5	68.7	66.3	64.7
0	0			0	-	-	-	-	-	-
0	0			0	-	-	-	-	-	-
Future No Project										
	Speed		Traffic Volume	S		Leq		CNEL		
Roadway/Segment	MPH	AM	PM	ADT	ROW	25 Feet	50 Feet	ROW	25 Feet	50 Feet
Alamitos Ave. between Ocean Blvd. and Broadway	30	1450	1411	0	66.6	64.2	62.6	67.9	65.4	63.9
Alamitos Ave. between Broadway and 4th St.	30	1657	1510	0	67.2	64.8	63.2	68.4	66.0	64.4
Alamitos Ave. n/o 4th St.	30	1681	2083	0	68.2	65.8	64.2	69.4	67.0	65.4
0	0			0	-	-	-	-	-	-
0	0			0	-	-	-	-	-	-
Future With Project										
	Speed		Traffic Volume	S		Leq			CNEL	
Roadway/Segment	MPH	AM	PM	ADT	ROW	25 Feet	50 Feet	ROW	25 Feet	50 Feet
Alamitos Ave. between Ocean Blvd. and Broadway	30	1599	1815	0	67.6	65.2	63.6	68.8	66.4	64.8
Alamitos Ave. between Broadway and 4th St.	30	1806	2341	0	68.7	66.3	64.7	69.9	67.5	65.9
Alamitos Ave. n/o 4th St.	30	1829	2238	0	68.5	66.1	64.5	69.7	67.3	65.7
0	0			0	-	-	-	-	-	-
0	0			0	-	-	-	-	-	-

			CNEL			
Summary		25 ft. fro	m ROW	At ROW		
		Project	Cumulative	Project	Cumulative	
Roadway/Segment		Increment	Increment	Increment	Increment	
Alamitos Ave. between Ocean Blvd. and Broadway		1.0	1.1	0.9	1.1	
Alamitos Ave. between Broadway and 4th St.		1.5	1.0	1.5	0.9	
Alamitos Ave. n/o 4th St.		0.3	1.0	0.3	1.0	
	0	-	-	-	-	
	0	-	-	-	-	

	% of ADT								
Vehicle Type	Day	Eve	Night	Sub total					
Auto	77.60%	9.70%	9.70%	97.00%					
Medium Truck	1.60%	0.20%	0.20%	2.00%					
Heavy Truck	0.80%	0.10%	0.10%	1.00%					
	80.00%	10.00%	10.00%	100.00%					