

Public Service

2nd Street Recommendations

R&R = remove and replace w/ = with a/c = asphalt concrete

Location	Issue	Recommendation	Emp	Total Hrs	Cost	Material	Total
E/B 2nd @ Park	10' dropped curb	R&R, Concrete curb and asphalt	3	40	\$1,800.00	\$200.00	\$2,000.00
E/B 2nd @ St.Joseph	Chipped curb	Dri tamp	1	2	\$90.00	\$15.00	\$105.00
4918 E. 2nd St.	Raised concrete	R&R raised colored stamped concrete 2x40	3	36	\$1,620.00	\$275.00	\$1,895.00
5000 E. 2nd St.	Sunken area w/signal boxes	R&R raised concrete, raise signal boxes 5X15	3	36	\$1,620.00	\$275.00	\$1,895.00
5110 E. 2nd St	Raised concrete	R&R raised concrete 2X40	3	36	\$1,620.00	\$275.00	\$1,895.00
E/B 2nd @ Corona	Sunken Curb	R&R 12' sunken curb and asphalt street	3	40	\$1,800.00	\$200.00	\$2,000.00
5236 E. 2nd St	Raised concrete	R&R raised concrete 2X50	3	36	\$1,620.00	\$300.00	\$1,920.00
E/B 2nd @ Pomona	Chipped curb	Dri-tamp curb	1	2	\$90.00	\$15.00	\$105.00
5368 E. 2nd St	Raised curb	R&R 10' raised curb, asphalt, install forms	3	40	\$1,800.00	\$200.00	\$2,000.00
5305 E. 2nd St	Raised concrete	Remove only 5X25 area of concrete and level off	3	18	\$810.00	\$275.00	\$1,085.00
5295 E. 2nd St	Raised concrete	R&R raised concrete 2X20	3	36	\$1,620.00	\$200.00	\$1,820.00
5287 E. 2nd St.	Raised concrete	R&R raised concrete 2X30	3	36	\$1,620.00	\$225.00	\$1,845.00
5269 E. 2nd St	Chipped curb	Dri Tamp	1	2	\$90.00	\$15.00	\$105.00
W/B 2nd @ Corona	Cracked/raised curb	Grind down the offset	1	2	\$90.00		\$90.00
5101 E. 2nd St	Raised concrete	R&R raised concrete 2X20 and 5X30	3	50	\$2,250.00	\$500.00	\$2,750.00
4911 E. 2nd St	Chipped curb	Dri-tamp	1	2	\$90.00	\$15.00	\$105.00
4817 E. 2nd St	Raised concrete	R&R raised concrete 5X25 and 2X30	3	50	\$2,250.00	\$475.00	\$2,725.00
4709 E. 2nd St.	Raised concrete	R&R raised concrete 2X50 and 4X10	3	50	\$2,250.00	\$350.00	\$2,600.00
4601 E. 2nd St.	Raised concrete	R&R raised concrete 2X20	3	36	\$1,620.00	\$200.00	\$1,820.00
					TOTAL ESTIMATE		\$28,760.00

I recommend also painting the tips of all the islands in both directions. I do not have the costs associated with this item.

Price estimates include all necessary posting, lane closures, material dumping costs, marking for USA, pre-warning signage, barricading off, forming for a/c, etc.