



1 to and incorporated in this Agreement, for an amount not to exceed \$1,102,526.25,  
2 including tax, with a ten percent contingency for the purchase of additional equipment and  
3 vehicles to be ordered in the City's sole discretion provided, however, that the "not to  
4 exceed" amount shall be reduced to \$960,486.01 if the City receives grant funding from  
5 UASI for these vehicles. To the extent that the Los Angeles Purchase Order and this  
6 Agreement are inconsistent, the following priority shall govern: (1) this Agreement and (2)  
7 the Los Angeles Purchase Order.

8 c. Payment for the vehicles and equipment purchased from Contractor by  
9 City shall be made by the City on delivery to and acceptance of the equipment by the City  
10 and submittal of an invoice to the City. Payment is due thirty (30) days after the date of the  
11 invoice.

12 d. All warranties shall accrue to the City of Long Beach.

13 e. The parties may, by mutual agreement, amend this Agreement with the  
14 approval of the City's City Council.

15 2. Neither this Agreement nor any money that becomes due to Contractor  
16 under this Agreement may be assigned by Contractor without the prior written consent of  
17 the City Manager or his designee.

18 3. Any notice given under this Agreement shall be in writing and personally  
19 delivered or deposited in the U.S. Postal Service, return receipt, and shall be delivered or  
20 mailed to Contractor at the relevant address first stated above, and to the City at 333 West  
21 Ocean Boulevard, Long Beach, California 90802 Attn: City Manager. Notice shall be  
22 deemed given three days after deposit in the mail.

23 4. The terms appearing on Los Angeles' Purchase Order are incorporated  
24 in this Agreement except to the extent that they are inconsistent with the City's Purchase  
25 Order or this Agreement.

26 5. Contractor shall cooperate with the City in all matters relating to  
27 self-accrual of use tax. Contractor shall contact the City Treasurer for additional  
28 information regarding self-accrual.

Robert E. Shannon  
City Attorney of Long Beach  
333 West Ocean Boulevard  
Long Beach, California 90802-4664  
Telephone (562) 570-2200


1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28

6. This Agreement and all documents which are incorporated by reference in this Agreement constitute the entire understanding between the parties and supersede all other agreements, oral or written, with respect to the subject matter of this Agreement. If there is any legal proceeding between the parties to enforce or interpret this Agreement, or to protect or establish any rights or remedies, the prevailing party shall be entitled to its costs and expenses, including reasonable attorney's fees.


IN WITNESS WHEREOF, the parties have caused this document to be duly executed with all formalities required by law as of the date first stated above.

WHEELED COACH INDUSTRIES, INC., a ~~California corporation~~

09/08, 2006

By   
President  
Robert Collins  
(Type or Print Name)

9/18, 2006

By   
Secretary  
Cletus Glasener, VP Finance/Treasurer/  
(Type or Print Name) Secretary

"Contractor"

CITY OF LONG BEACH, a municipal corporation

9.25, 2006

By   
City Manager

"City"

This Agreement is approved as to form on 9/21, 2006.

ROBERT E. SHANNON, City Attorney

By   
Senior Deputy

EXHIBIT "A"



**Long Beach Fire Department**

August 21, 2006

<u>DESCRIPTION</u>	<u>Per Unit</u>	<u>Extended</u>
(7) 2006 Ford E450, 158" WB, 14,050 lbs GVW, Type III Custom Ambulance Price per unit as quoted on June 20, 2006 (includes all Wheeled Coach discounts and FORD Concessions)	\$103,321.00	\$723,247.00
<b>Additions &amp; Deletions</b>		
Upgrade to LED Lighting (Lightbar, 9 Series, 7 Series)	\$3,582.00	\$25,074.00
Add Radio & Install at 911 Vehicles, Inc.	\$16,130.00	\$112,910.00
Add Lettering - SignCo, Inc.	\$2,297.00	\$16,079.00
Add Electric Locks, four (4), for total of eight (8)	\$500.00	\$3,500.00
Add Safari Land Level III Body Armor, two (2) @ \$595 each	\$1,190.00	\$8,330.00
Add Clear Coat to Interior Surface of All Exterior Compartments	\$225.00	\$1,575.00
Add OEM Locks Keyed Alike to Previous Units	\$160.00	\$1,120.00
Add Additional Cost for (1) Person to Inspection Trips	\$200.00	\$1,400.00
Delete Shelves in Compartments D, B, E	-\$400.00	-\$2,800.00
Delete 4" Pinstripe from Wheeled Coach Work Order	-\$450.00	-\$3,150.00
<b>Subtotal</b>	<b>\$126,755.00</b>	<b>\$887,285.00</b>
<b>Sales Tax @ 8.25%</b>	<b>\$10,457.29</b>	<b>\$73,201.01</b>
<b>TOTAL</b>	<b>\$137,212.29</b>	<b>\$960,486.01</b>

Payment Terms: 30 Days Net  
 FOB: Long Beach Fire Department, Long Beach, CA  
 Delivery: 60 - 90 Days After Confirmation of Order

Alan Try  
 Regional Sales Manager  
 (877) 503-9521

# Long Beach FD

# Wheeled Coach Industries, Inc.

City of Long Beach Fire Department  
 Seven (7) Units  
 Craig Crandall (562) 570-3355

Wheeled Coach - Southern CA  
 Geoff Maze/Alan Try

Rev. Date: 06/20/2006  
 Quote No: Quote-2007

T3 - 163: 0991017 Ford, 2006, E450, 158"WB, 163" Module  
 T3 - 163: 200030 Type 3 - 163" Module - Custom Series

06/20/2006 WO#: Page 1

PART NO	S	DESCRIPTION	QTY	ID
00-06-0050	X	(7) Units All Built Alike - City of Long Beach Fire Dept. CHASSIS:	1	WC
00-30-5061	< >	Ford, 2006, E450, Cutaway, 158", Custom, 165" Module 165X95 Autothrottle OEM Ford Alternators OEM Ford	1	WC
		CHASSIS ADD-ONS:	1	WC
1A-10-0100	< >	Lettering, By Outside Vendor Location:  Sign Co. Anaheim, CA Estimate # 21935	1	WC
1A-10-0A00	< >	Radio Add-ons, Outside Vendor Done by:  911Vehicle Anaheim, CA Quotation # 6106-01	1	WC
		CHASSIS ADD ONS, MISC	1	WC
2F-76-7A00	<	Bumper Guard, Gem, Bolt On, 2000,E450 set just outside of airhorn trumpets on front bumper	1	WC
		HEATING/AIR CONDITIONING:	1	WC
5U-12-5000		Hoses, Heater, Nomex to Rear, STD	1	WC
5U-12-9000	<	Heat/AC, F3, Combo, Hoseline, w/Ext Cond, Bottom Mnt, ILOS  with thermostat in action area, external condenser mounted under unit, curbside.  *****USE Bracket # B230079 for mounting of condensor for maximum ground clearance.	1	WC
		WHEELCOVERS INSTALLED:	1	WC

PART NO	S	DESCRIPTION	QTY	ID
X5-10-3000		Wheel Covers, Phoenix, F3, #NF9, Installed	1	WC
		MODULE BODIES:	1	WC
35-10-0100		> 10 Inch Extended Cab, 13" seat travel	1	WC
35-10-0900		> Headroom, 72 in. Type 3 - 165" module	1	WC
37-00-0130		Type 3 - 163" Module - Custom Series	1	WC
37-00-0300		< Compartments, Zolotone Finish (1) per compt	6	WC
		Battery, B1, B2, D, E, F		
37-00-0500		< > Compartments, Std, Floor 3" Drop Down from Door Opening	4	WC
		compts B1,B2,D,& E are STD drop down floor		
37-00-0600		< > Compartments, Sweepout	2	WC
		compt "A" & "F" are std sweep out		
37-00-0700		< Seamless Doors, Pan Doors, with Exposed Jambs	1	WC
		Magnetic door switches, STD, per ECN 1516		
37-00-0800		< Extruded Doors	1	WC
		*****		
		DO NOT USE THIS OPTION		
		PAN DOOR CONSTRUCTION		
		*****		
38-00-0000		< Type 3 - 163 Module, 10" Cab Extension	1	WC
		With double doors on compt E		
38-A0-01SR	X	< Body,Custom,Per Long Beach	1	
		Custom Body listed under (SO-A-233320) and (SO-F-233320)		
		(SO-BODY-233320)		
38-A0-0472		A, Compt, Split, Hoseline, 165" Module, 72" H.R.	1	WC
38-B1-0150		B1, Compt, Std, 165" Module, 72" H.R.	1	WC
38-B2-0172		B2, Compt, Std, 165" Module, 72"H.R.	1	WC
38-D0-0150		D, Compt, Std, 165" Module, 72" H.R.	1	WC
38-E0-0100		< E, Compt, Std, 165" Module	1	WC
		With Double Doors		
38-F0-0150		F, Compt, 3/4, 165" Module, 72" H.R	1	WC
		FUEL FILL HOUSING:	1	WC
3A-10-4000		Housing, Fuel Fill, Cast, F3 and CM+	1	WC
		EXTERIOR DIVIDERS:	1	WC
3F-10-0500		< > Divider, Vertical, (1), Mounted:	2	WC
		B2, F		
		SHELF- COMPARTMENT "A"/RF CABINET:	1	WC
3F-20-1000		< Shelf, Adjustable,(1), RF Cab Custom	1	WC
		install with shelf lips "down", rubber matting on top side.		

PART NO	S	DESCRIPTION	QTY	ID
3F-20-1500	<	Shelf, Additional, Adjustable, (1), RF Cab Custom install with shelf lips "down", rubber matting on top side.	1	WC
		SHELF- COMPARTMENT "B"/"B1":	1	WC
3F-30-1000	<	Shelf, Custom, Adj, Cmpt "B", (1) These small shelves(apx. 8" wide) run from the vertical divider to wall # 3. From ceiling: Place first shelf down 10", then space the remaining (4) shelves at 10" intervals.	1	WC
3F-30-1500		Shelf, Custom, Adj, Cmpt "B", (1), Additional SHELF- COMPARTMENT "D":	4	WC
3F-40-2000		Shelf, Adjustable, (1), Cmpt "D", 163 Box	1	WC
3F-40-2500		Shelf, Additional, (1), Cmpt "D", 163 Box	1	WC
	<	SHELF- COMPARTMENT "E": Note: Electrical shelf is deleted.	1	WC
3F-50-3500		Shelf, Adjustable, (1), Cmpt "E", 163" Box SHELF- COMPARTMENT "F":	1	WC
3F-60-7500	< >	Shelf, Fixed, Exterior Compt, Located:  In compt: F Height from floor: 2" over oxygen access window. Wall one to wall three, this will be fixed to the top of the divider	1	WC
		COMPARTMENT / SHELF, MISC:	1	WC
3F-70-1700	< >	Reinforcement,Door,SCBA Bracket  6" x .250 flatbar OR 6" x .125 hat section reinforcement for SCBA brackets to hang on interior door skin (diamond plate).  Locations: Centered on leading compartment "E" door, and on compartment "D" door.  Engineering: Use whichever bracing method that will provide the best structural support.	2	WC
		WINDOWS:	1	WC
3P-10-5000		Windows, Upper, CS/Slider, Rear/Fixed, Privacy Tint, ILOS	1	WC
		MODULE ENTRY DOOR HANDLES:	1	WC
3U-30-5000	>	Handle, Paddle, Entry Doors, #J236 Key	1	WC
		EXTERIOR COMPT DOOR HANDLES:	1	WC
3U-40-0508	>	Handle, Compt, S/S, Blank, Max Grip Eberhard, J236	1	WC
3U-40-1000	< >	Handle, Paddle, Ext Compt, J236 Key, OBSOLETE	4	WC
		For all except "A" and "E"		
3U-40-6005		Handle, Entry, MaxGrip Eberhard,J236, Electric Locks EXTERIOR COMPT DOOR HANDLES W/ELECTRIC LOCKS	1	WC
3U-50-0050	< >	Handle, Compt, C/S, Max Grip Eberhard, J236, Electri A, Entry, B1, B2	4	WC
3U-50-0060	>	Handle, Compt, S/S, Max Grip Eberhard, J236, Electri ELECTRICAL LOCKS:	3	WC
3U-60-0500		Circuit, OEM Door Lock to activate Mod Doors	1	WC
3U-60-1000	< >	Door Locks,Electric Pop Lock, (1)DOOR, Enter Qty of Doors A, E, CS Entry, Rear Entry	4	WC



PART NO	S	DESCRIPTION	QTY	ID
		<b>ELECTRICAL LOCKS SWITCHING:</b>	1	WC
3U-60-1500	< >	Switch,Momentary Rocker,Activate Elect Door Locks Switch # 1 - Inside c/s door on face of squad bench, below oxygen bottle storage door, just above stepwell in ABS switch recess.  Switch # 2 - Inside rear doors on aisle-side face of curbside rear cabinet, just above squad bench lid. (See drawing.) Note: This will be recessed.	2	WC
3U-60-2000	< >	Switch, Stealth, Module Doors mount behind AVW grille, standard location. Passenger side.	1	WC
3U-60-3000	>	Relay Control Circuit, Electric PopLocks, For Max of 8 Doors DOOR HOLD OPENS:	1	WC
40-10-1000	< >	Hold Opens, Rear Doors, Cast, Grabber (4), 3 in., ILOS  for rear access doors,ilos.	1	WC
40-10-7200		Hold Open, Gas Strut, Ext Compt, 30lb, Std	5	WC
40-10-7205		Hold Open, Gas Strut, RF Compt, 30lb, Std DOOR PANELS:	1	WC
45-10-0500	<	Door Panels,CS-Care Caddy,rear-Diaplate  upper panels cs and rear mica.	1	WC
		<b>FENDER FLARES:</b>	1	WC
4A-10-1000		Flare, Fender, Rear, Black Rubber	1	WC
		<b>BUMPERS:</b>	1	WC
4F-11-2200	< >	Bumper Rear,W/Step Reinforcement,W/Lts,F3 Heavy reinforcement of bumper pontoons to minimize vibration. Rear step to be bolted in down position.	1	WC
4F-11-2300		Rear Bumper Pontoon Reinforcement	1	WC
4F-11-3000		Dock Bumpers, Black, On Rear, Mods	1	WC
4F-12-0500	X	Tape, Reflective, Red/White, on bumper step RUNNING BOARDS:	1	WC
4K-10-4000		Running Boards, F3, Standard, w/ Gator Grip SKIRTRAILS W/BODY SPACERS:	1	WC
4U-10-4500		Skirtrails, Rubber, 165/170 in Box STONE GUARDS (FRONT):	1	WC
4U-11-2000		Stone Guard, Front, Dia Plate, 13.38" KICKPLATES (w/STD. REAR STONEGUARDS):	1	WC
50-10-1000	<	Kickplate, W/Recess And (3) Truck Lts ***** DO NOT USE THIS OPTION ***** 600 series lights mounted in body above kick plate	1	WC
50-10-2100		Kickplate, W/Recess, No Light Holes,Pan MODULE ADD-ONS:	1	WC
55-30-SRO7	X <	Exhaust Bracket, Nederman, w/ Magnet (Ship Loose) See Nederman drawing for tailpipe requirements.  (SO-EXHST-233320)	1	
		<b>MUD FLAPS:</b>	1	WC
5A-10-1000		Mud Flaps, Rear, W/Logo PAINT/BELTS:	1	WC
			1	WC

PART NO	S	DESCRIPTION	QTY	ID
5F-10-3200		<p>&lt; &gt; Paint, Entire Unit, 20% Upch Sikkens FLNA30667 - Mack Red w/ clearcoat</p> <p>to match DuPont Mack Red</p> <p>Roof inside of roofrail weld perimeter to be white except for most rear 18" to be red as per above (as per LAFD)</p> <p>No white visible from street.</p>	1	WC
5F-10-4400		<p>&lt; &gt; Paint WC AVW Grille, 20% Upch Sikkens FLNA30667 - Mack Red w/ clearcoat</p>	1	WC
5K-10-6500		<p>PINSTRIPES: - PER ROLL</p> <p>Pinstripe, Reflective White 4 inch</p>	1	WC
5V-10-SR02	X	<p>ELECTRICAL SYSTEM:</p> <p>&lt; Switch Layout and Configuration, ECC CONTROL CONSOLE - HARNESS CONFIGURATION</p> <p>Ignition triggered solenoid selects batteries and brings power to the sequencer. Batteries are on a shut-down timer set to 30 minutes.</p> <p>UPPER TIER of Switches; ECC</p> <p>L - R - Label as below:</p> <ol style="list-style-type: none"> <li>1. Emergency Master (Sequencer) - Use larger paddle type switch for this function.</li> <li>2. City / Highway Switch (Pri/Sec)</li> <li>3. Opticom</li> <li>4. Headlight Flasher</li> <li>5. Light Bar (Front)</li> <li>6. Front Flashers (2) grille LED and (2) front LED</li> <li>7. Grille Lights (2 steady burn LEDs at upper AVW positions)</li> <li>8. LED's (intersection, rear fender, and side - 8 total)</li> <li>9. Rear Flashers (3 amber LED, 2 LED)</li> </ol> <p>-----</p> <p>The sequencer ("Emergency Master") enables functions individually switched in the upper tier in one of two ways.</p> <p>The switch to the right of the sequencer is a Pri / Sec ("City / Highway") group selector.</p> <p>In Primary "City" mode, ALL upper tier functions serviced by the sequencer are enabled and will operate if their respective switches are in the "on" position.</p> <p>In Secondary "Highway" mode, only certain sequenced switches are enabled with power.</p> <p>"Highway" mode power only to:</p>	1	WC

PART NO	S	DESCRIPTION	QTY	ID
		4. Headlight Flasher		
		7. Grille Lights		
		9. Rear Flashers		
		-----		
		LOWER TIER of Switches		
		L - R - Label as below:		
		10. Module Disconnect - (Battery switch hot.) - This switch controls power to action area lighting and circuit board courtesy light, rear dome lights, exhaust fan, suction, inverter. Does not enable functions 11 - 15 which are powered directly once batteries are selected. Use larger paddle type switch for this function.		
		11. Back-Up Alarm (w/ auto-reset, battery switch hot)		
		12. Left Scene (battery switch hot)		
		13. Right Scene (battery switch hot)		
		14. Front Scene (battery switch hot)		
		15. Rear Load (battery switch hot)		
		16. Patient Heat & A/C (battery switch hot)		
		(SO-SWTC-233320)		
		BATTERY SWITCHES:		
60-20-353E	<	Battery Config, F3, Fig 5B, Manual Sw, (2) OEM in RF Compt,  (3) Delco Group 31 batteries located in RF compt.  ONLY Module power is turned on/off. Chassis power is NOT turned off.  Manual Switch in the drivers seat base.	1 1	WC WC
60-21-010E	<	Timed Battery Switch,F3, Fig 5B (3) Group 31 battery relocated to RF compt.  Ignition triggered battery switch activation, with up to 30 minute timer to shut-down batteries if ignition is switched off.  W/Additional Switch Labeled: TIMER BYPASS (for emergency use only)  Locate switch on side of driver seat base to rear of EMERGENCY START switch. Located:	1	WC
60-30-0000	X	BATTERIES	1	
60-30-5100	X	Battery, Delco, 31-900, each, IATS	1	
60-30-6200	< >	Plug ,Jump Start,W/25' Cable with (1) male plug	1	WC

PART NO	S	DESCRIPTION	QTY	ID
		Goodall MFG. Male plug at one end and cable clamps at other end		
		Mount female end on ceiling of lower "A" battery compartment to left side, 1/2" interior of shelf edge so that it does not contact closed compartment door. Ensure that cable is loom clamped in battery compartment along ceiling so as not to interfere with battery tray.		
60-30-SR00	X	Battery, Delco, 31-900, each, ILOS	2	
		COAX CABLES/ANTENNAS:	1	WC
65-30-1000	< >	Coax Cable, (1) Each, Standard, Terminate: Terminate: behind Driver's Seat	1	WC
		With 6' pigtails		
65-30-1500	< >	Coax Cable, (1) Each, Additional, Terminate: Terminate:	5	WC
		(1) Behind Driver's Seat (4) Behind Passenger's Seat		
		With 6' pigtails		
		12VDC POWER SOURCES & OUTLETS:		
6A-22-200E	< >	Outlet, Cigar Lighter, STD, (2), A/A (1) in A/A (1) in R/F	1 1	WC WC
		POWER SOURCE, 12 VDC		
6A-23-2200	< >	Power Source, 12 VDC, 20 Amp (+-) (1) Powered by: Ignition Hot (1) Powered by: Battery Switch	1 2	WC WC
		Terminate: behind driver's seat		
6A-23-4300	< >	Power Source, 12 VDC, 50 Amp (+-)  Powered by: Constant Hot  Terminate: Behind Driver's Seat	1	WC
		SHORELINE INLETS:		
6F-80-4600	< >	Shoreline, Twistlock, 20A, ILOS (1) Streetside forward of "F" compartment. (1) Curbside forward of "A" compartment	1 2	WC WC
		110 VAC OUTLETS:		
6K-40-1000	<	Outlet, 110 VAC, Duplex, (2), STD  (1) outlet in action area (1) outlet in the right front cabinet, lower wall # 2 to left side apx. 9" above floor.	1 1	WC WC

PART NO	S	DESCRIPTION	QTY	ID
6P-10-3100	<	Blockheater,Engine,No Sw,Wired To Shoreline  No switch. Wired to Shoreline on Street Side	1	WC
7F-10-1500	<	INVERTERS: Inverter/Charger, FP1000, w/ Remote Mods Note: Wire charger function only to "live" operating batteries, not to "emergency start" batteries.  Mount in L2 cabinet.	1 1	WC WC
7U-10-7000		CONSOLES: Console, A/A, Wood, Angled	1	WC
7U-10-9000	>	Console, ECC, F2, F3, F7, 1997, with APC Module Cutout	1	WC
7U-11-SR01	X <	Console, Aux., Custom, for Radios, MDT Console, Custom  Gray mica covered 3/4" plywood with new edge banding. Width is 13.5" outside to outside dimension.  Top side is flat platform for MDT swivel bracket. Steep sloped face has angled down clipboard slot. Aft deck has flip-up door hinged rear with lever-latch to access interior storage. This door has a cut-out topside for drop-in plastic / rubber cup holder(s) at its forward edge either side of lever latch. Cup holders must be large enough to hold 32 oz. "Big Gulp" cups from 7-11, or equivalent. Dashboard facing side to have 6" x 4" cutout for ventilation apx. 3" over floor, with black plastic louver cover.  (SO-CONS-233320)	1	WC
D0-10-1000	<	GAUGES/METERS: Meter, Analog, Amps, TSD, Type 3/9 ECC panel / switch layout required w/ customer approval.	1 1	WC WC
D0-10-1500	< >	Meter, Analog, Volts, Datcon ECC panel / switch layout required w/ customer approval.	1	WC
DA-10-5000	< >	SEQUENCING/LOAD MANAGEMENT: Switch, Emergency Master, Seq See detailed function description earlier in work order.  ECC panel / switch layout required w/ customer approval.	1 1	WC WC
DA-11-3000	< >	Sequencer,Kussmaul,Load Manager, W/ Switch  W/Sequencer switch and override on console	1	WC
DF-20-5500		SIREN SPEAKERS: AVW Sys,Grille, 97+ F3, W/Lower Lights.Painted, ILOS	1 1	WC WC
DK-10-SR01	X <	SIRENS: Siren, Unitrol, TM-4, ILOS Mount in ECC per specific customer approved panel layout.  Siren to be constant hot.  No switch required on console. This function is to be wired through the applicable siren / horn selector switch on the Unitrol siren itself.	1	WC

PART NO	S	DESCRIPTION	QTY	ID
		(SO-SIREN-233320)		
		AIR HORNS:	1	WC
DP-10-9100	<	Airhorn, Buell, 5440, 10 & 12 inch with compressor in dead space on platform forward of A/C combo unit. Maintenance access via removal of 9S lights at curbside front corner of body.  Trumpets mounted thru lower bumper with notch out, as high as possible and protruding as little as possible forward.	1	WC
		SWITCHING OPTIONS FOR AIR HORNS & SIRENS:	1	WC
DP-11-5500	< >	Switch, Add, 12VDC Momentary Rocker. Cab Console - Centered	1	WC
		SWITCHES ADDITIONAL:	1	WC
DU-10-2000	< >	Switch, Add, 12VDC, (3) Position Rocker Special "City" and "Freeway" light group selector in lieu of "Primary / Secondary" switch.  Per switch lay-out listed under the console.	1	WC
DU-12-1000	<	Switch, Additional, 12VDC, Rocker (1) for front facing scene light  (1) for Opticom	2	WC
DU-12-2000	<	Switch, Momentary, Push Button for air horns....(1) each side of control console	2	WC
		AUDIBLE ALARMS:	1	WC
F0-11-4500	<	Alarm, Back-up, Auto Reset, ILOS See panel layout for location of switch.	1	WC
		VEHICLE EXTERIOR LIGHTING LIGHTBARS, WHELEN	1	WC
FK-25-0110	< >	LB,45KKFH,HRR-OPTI-RRH,RCRCRCR  on front ILOS warning lights with ICC lights on top of LB	1	WC
		WHELEN HALOGEN 9E WARNING LIGHTS:	1	WC
FU-30-200E	<	Light, 9H, Whelen, Clear, IATS  on center front	1	WC
FU-30-300E		Light, 9H, Whelen, Amber, IATS	2	WC
		WHELEN STROBE 9E WARNING LIGHTS:	1	WC
FU-35-100E	>	Light, 9S, Whelen, Red, ILOS	6	WC
FU-35-150E	>	Light, 9S, Whelen, Red, IATS	2	WC
FU-35-600E	>	Light, 9S, Whelen, Red/Amber, ILOS	2	WC
		WHELEN 6E FLANGES:	1	WC
H2-10-0050	<	Flange, 6E Series, (1) each for stop/brake, turn signal and reverse lights on rear	6	WC

PART NO	S	DESCRIPTION	QTY	ID
		WHELEN HALOGEN 7E WARNING LIGHTS	1	WC
H5-18-700E	>	Light, 7H, Red, IATS	2	WC
H5-18-850E	>	Light, 7H, Amber, ILOS	1	WC
H5-21-180E	>	Light, 7S, Whelen, Red, Linear, ILOS	2	WC
H5-21-190E	>	Light, 7S, Whelen, Red, Linear, IATS	2	WC
		7 SERIES LED LIGHTS:	1	WC
H5-56-001E		Light, Whelen, 7L, Red, ILOS	2	WC
		WHELEN FLANGES 7 SERIES LIGHTS	1	WC
H5-59-1000	<	Flange, Whelen, For 7E lights (1), Mods	6	WC
		(2) for front intersection lights		
		(2) for rear fender intersection lights		
		(1) for rear center amber		
		(1) for rear aux. brake light		
		CORNER CAP LIGHTS	1	WC
HF-11-6050	<	Corner Cap Lts, LED, (2) Amber (2) Red Corner Flashers	1	WC
		High intensity flashers. thru separate switch.		
		CLEARANCE LIGHTS:	1	WC
HF-12-9600		Light, Clearance, Red LED, ILOS	3	WC
		SCENE AND LOAD LIGHTS	1	WC
HK-20-110E	S <	Light, Halogen, Whelen, 9H, Clr, 8-32 Deg	4	WC
		(2) each side as scene lights		
HK-20-130E	S <	Light, Halogen, Whelen, 9H, Clr, 8-32 Deg	2	WC
		(2) on rear as load lights		
HK-20-7100	>	Scene Lights, C/S, Activated W/C/S Door	1	WC
		HALOGEN FLASHER(S):	1	WC
HU-24-7500		Flasher, Whelen AF-6016A C/D Spec	1	WC
		STROBE POWER SUPPLIES:	1	WC
HV-30-2000	< >	Flasher, Whelen, ISP-188	1	WC
		POWER:		
		FLASH:		
		SWITCHED:		
		HEADLIGHT FLASHER:	1	WC
J0-42-3500		Flasher, Headlight, Code 3, 710	1	WC
J0-42-7000	< >	Switch, Neutral Power for Opticom operation in drive gear only	1	WC
		HARNESS LAYOUT:	1	WC
J5-12-3000		Halogen, " E " Spec, Whelen, (1) Lightbar	1	WC
J5-14-SR01	X <	Quick Disconnect, ECC, Harness, ILOS	1	
		(SO-QUIK-233320)		
		STOP/TURN/TAIL LIGHTS:	1	WC
JA-10-1000		Light, License Tag, (2), Grote 60101, STD	1	WC

PART NO	S	DESCRIPTION	QTY	ID
JA-10-300E	<	Lights, Tail/Stop, Red, 6I, ILOS, Pair Locate on rear of module, above kickplate  TOP: Tail/Stop MIDDLE: Turn BOTTOM: Reverse	1	WC
JA-10-500E	<	Turn Arrow, Whelen 6I, Amber, ILOS, Pair Locate on rear of module, above kickplate  TOP: Tail/Stop MIDDLE: Turn BOTTOM: Reverse	1	WC
JA-10-800E	<	Lights, Reverse, Whelen 6H, ILOS, Pair Locate on rear of module, above kickplate  TOP: Tail/Stop MIDDLE: Turn BOTTOM: Reverse	1	WC
		MODULE FIBERGLASS HEADLINER:	1	WC
JK-10-4900		Headliner, Recessed, Closed End, Ty1/3-165/170	1	WC
		12VDC INT LIGHTING-HALOGEN & INCANDESCENT:	1	WC
JP-10-0505		Lights, Weldon, 8046-0320-80, (4) S/S, (3) C/S	1	WC
JP-10-7000	>	Light, Stepwell, Peterson, M126c	1	WC
		LIGHTS & MISCELLANEOUS:	1	WC
JR-50-1000		Spotlight, Handheld, 100,000 CP	1	WC
JR-50-4900	<	Light, Flexshaft, Little Lite LF12ERR, 12 inch passenger side of ECC	1	WC
JR-50-6A00	<	Light, Compt Door Ajar, 2.5" Red Trucklite, ILOS ILOS, Flashing, Trucklite.  Mount: In cab ceiling liner, centered, apx. 6" behind rear view mirror. For DOOR AJAR and COMPARTMENT AJAR functions together, in lieu of small lights on ECC.	1	WC
JR-50-7500	<	Light, Marker, 12VDC, Trucklite, Red, 4" in cab liner over front seat edge, passenger side, as night reading light.	1	WC
JR-60-4000	< >	Timer, 5 Minute, Constant Hot, Wired To:  LOCATION: By rear doors on B1 Cabinet WIRED TO: Streetside High Domes	1	WC
JR-60-5000	>	Circuit, Check Out Lights	1	WC
		CONDUIT:	1	WC
L5-10-4000	< >	Fan, Intake, W/Switch in A/A  LOCATION: in A/C cabinet by fresh air intake, switched with "Exhaust Fan"	1	WC
		RADIO STEREO & SPEAKERS:	1	WC
LA-10-1000		Radio, Sony, AM/FM/CD, ILO OEM	1	WC
		SUCTION PUMPS:	1	WC



PART NO	S	DESCRIPTION	QTY	ID
LP-10-0500	<	Suction Pump, Thomas, Standard Mount in cabinet L2 with inverter.	1	WC
		INSULATION:	1	WC
LU-10-1000		Insulation, Fiberglass, Unfaced	1	WC
		OVERHEAD GRABRAIL:	1	WC
N0-10-9000		Grabrail, Overhead, 117 In, Handicap Style	1	WC
N0-11-0500	< >	Handrails, (3), "L" Shape, 1", on Each Entry Door , ILOS	1	WC
		ILOS		
N5-14-5000	< >	Grabhandle, 18in, (1) Each, F7, IATS (1) 18" on curbside rear cabinet, squad bench side, with bottom set 16" above bench lid, inset from aisle apx. 4". This is for attendant seated at rear position on squad bench.  (1) at head end of squad bench on wall above bio-waste	3	WC
		O2 CYLINDER RACKS:	1	WC
NA-10-0500	>	Rack, Cylinder, W/C, For "M", STD	1	WC
		STRAPS, O2:	1	WC
NA-30-1000		Strap, Cylinder, Metal Hinged, "M", (2) Each, STD	1	WC
		O2 SYSTEMS COMPLETE:	1	WC
NF-50-1500	< >	O2 System, LF Stor, (2) O2/(1) Vac Outlet in A/A, (1) O2 C/S  ohio style (2) oxygen outlets in action area (1) vacuum outlet in action area (1) oxygen outlet cs wall at head of squad bench	1	WC
		SUCTION CONTAINERS:	1	WC
PA-10-5000	>	Suction, Container, Rico RS4X/1001C, w/Adapter	1	WC
		COT MOUNTS:	1	WC
PF-26-3100	< >	Cot Mount, Stryker 6360-30-10, Dual For Stryker 6500 Power Pro Cot - Center Mount Positon Only.	1	WC
PF-35-4200	>	Cot Mount, Stryker, Mods, Rear Safety Hook Installed	1	WC
PK-40-1000	X	COT PLATES	1	
PK-40-6200	<	Cot Plates, Stryker Cot Center Position only!	1	WC
		IV HOOKS:	1	WC
PP-20-8500	< >	IV Hook, Cast, Fold Down Recessed, ILOS (1) in liner apx. 6" aft of CPR side seat on streetside	1	WC
PP-20-9000	< >	IV Hook, Cast, Fold Down Recessed, IATS (1) in liner on curbside directly opposite above over edge of squad bench lid.	1	WC
		KICK PLATES STAINLESS STEEL, ON CABINETS:	1	WC
PU-10-1000		Kickplate, Brushed S/S, Face Of Squad Bench	1	WC
PU-10-2000		Kickplate, Brushed S/S, On Face of Basewall	1	WC
PU-10-3000		Kickplate, Brushed SS, Head of Squad Bench	1	WC
PU-10-5000		Kickplate, Brushed S/S, EVS Seatbase	1	WC
		MISC. INSTALLED HARDWARE/EQUIPMENT:	1	WC

PART NO	S	DESCRIPTION	QTY	ID
R5-10-0100		Trim,Alum, inside Floor Recess, IATS	1	WC
R5-10-0600	< >	Hook, For Turnouts, Ferno #559, Installed Located: TBD at pre-construction	1	WC
R5-10-6500		Squad Saver Bar, Fold Down, On C/S Wall, Mods	1	WC
R5-10-65SR	X <	Black, Ribbed Rubber Mat,In SB interior of squad bench, cut to size and set in loose (no glue)  (SO-MAT-233320)	1	
R5-10-8000	< >	Wrench, Oxygen, Tethered, Mods  in oxygen compt.	1	WC
RF-11-3000	>	Holder, Cylinder, Dual Floor, Ferno #516, Installed	1	WC
RU-05-0000		Interior Cabinets - Duralite Construction, Wood MICA COLOR:	1	WC
RU-14-1900		Mica,Dove Gray Over Pewter Brush SUB FLOORING:	1	WC
RZ-99-0025		Flooring, Wood, Type 3/7/9, Std FLOORING:	1	WC
T0-10-5000		Flooring, Tarkette, Optima Gray, ILOS ATTENDANT SEATS W/SEAMS:	1	WC
T5-11-3000	< >	Seat, EVS, W/Childseat, Gunmetal, ILOS, Mods  with EVS metal box as seatbase  Note: No Door, Leave Open	1	WC
T5-25-1500		SEAMLESS UPHOLSTERY: Uph, Smless, Gunmetal,W/Bio,No Post & Wheel	1	WC
TF-50-SR00	S < >	BULKHEAD CABINET: Bulkhead, Custom  Solid wall w/ largeLexan pass-thru window, ILOS.  No walk-through or sliding door.  (SO-BH-233320)	1	WC
TK-10-5100	>	O2 DOOR: Plexi Wrap Around W/Hinge	1	WC
TP-10-8000	<	Delete Sliding Door, Solid Bulkhead, w/ Pass Thru Window Large pass-thru window with hinged Lexan door.	1	WC
TU-19-3000		Cab,RF,No Healthguard,Combo AC,72" headroom RIGHT FRONT CABINET:	1	WC
TU-20-1400		Cab, RF, W/O Healthguard, AC/Combo RF CABINET DOORS W/COMBO A/C	1	WC
TU-21-7250		Door, None, Trim in Aluminum	1	WC
V0-00-SR01	X <	Eyelet, Stainless, (4)for Inventory Ties (2) on Cabinet "O" door at outer edges high, (2) adjacent to each on basewall fully aligned. This is for inventory security ties.  (SO-TIE-233320)	1	
V0-10-0500	>	HARDWARE,LATCHES AND LOCKS: Handle, C, Pull, Installed,(1) Ea,STD	1	WC
V0-10-0500	>	Handle, C, Pull, Installed,(1) Ea,STD	1	WC

PART NO	S	DESCRIPTION	QTY	ID
V0-10-2000		> Latch, Plunger Roller, Installed	1	WC
V0-10-2000		> Latch, Plunger Roller, Installed	2	WC
		SQUAD BENCH:	1	WC
V5-20-3800		Squad Bench, Bio-Waste @ Head	1	WC
		LID 165 INCH BOX:	1	WC
V5-62-2000		> Lid, Squad Bench, 50/50 W/Bio-Waste	1	WC
		HARDWARE:	1	WC
V5-80-1000		Handle, Paddle, Squad Bench, STD	2	WC
V5-82-0500		Strut, Gas, 30 LB, Installed, ILOS	2	WC
		CURBSIDE REAR CABINET:	1	WC
VF-20-4500	<	Cabinet, Curbside Rear, Std, 163 In, 72 HR	1	WC
		Note: See Grabrail requirement for this cabinet before installation.		
		CABINET H, BASEWALL 165", T3	1	WC
VH-H1-0100		H, Cabinet, full depth, std	1	WC
		CABINET I, BASEWALL 165", T3	1	WC
VH-I1-0400		I, Cabinet, Deleted	1	WC
		CABINET M, BASEWALL 165" & 170", T3	1	WC
VH-M1-0100		M, Cabinet, 1/2 height, std	1	WC
		CABINET O, BASEWALL 165" & 170", T3	1	WC
VH-O1-0100		O, Cabinet, full height, std	1	WC
		CABINET CPR, BASEWALL, 149", 153", 165" & 170", T1 & T3	1	WC
VH-Q0-0100		CPR, side seat, std	1	WC
VH-Q0-0200		CPR, side seat, drop down tray	1	WC
VH-Q0-0300		CPR, side seat, flip up lid	1	WC
		CABINET J, STREETSIDE UPPER 165", T3	1	WC
VI-J1-0300		J, Cabinet, 72" H.R.	1	WC
		CABINET K, STREETSIDE UPPER 165" & 170", T3	1	WC
VI-K1-0200		K, Cabinet, 72" H.R.	1	WC
		CABINET L, STREETSIDE UPPER 165" & 170", T3	1	WC
VI-L1-0150		L, Cabinet, L1, L2, L3, 3/4F 72" H.R.	1	WC
		CABINET OPTIONS:	1	WC
VK-15-3000		Cab H, Clear Lexan Slider	1	WC
VK-16-0000		Cab M, Clear Lexan Slider	1	WC
VK-16-5700		Cabinet "O", Wood Door At Hinged bottom	1	WC
		TELEMETRY AREA WORK SURFACE	1	WC
VP-10-5400		Telemetry Tray, ABS	1	WC
		CPR DROP DOWN TRAY WORK SURFACE	1	WC
VP-10-5600		CPR Drop Down Tray, ABS	1	WC
		ACTION AREA WORK SURFACE	1	WC
VP-10-5908		A/A Tray, 165"/170", W/O Bio, ABS, White	1	WC
		ACTION AREA 165/170 INCH BOX:	1	WC
VP-15-7000		Cab, A/A, Without Biowaste, 165/170 In	1	WC
VU-12-5000	X <	Security Tab Holes in Lexan H, I, J, M, L, R1, R2	7	
VU-14-4000		> Shelf, Interior, Adj, in Cabinet:	1	WC
VU-14-4000		> Shelf, Interior, Adj, in Cabinet:	1	WC
VU-14-4000		> Shelf, Interior, Adj, in Cabinet:	1	WC
VU-14-4000		> Shelf, Interior, Adj, in Cabinet:	1	WC
VU-14-4000		> Shelf, Interior, Adj, in Cabinet:	3	WC
VU-15-1000		Cab "J" Clear Lexan Slider	1	WC
VU-15-3000		Cab "K" Clear Lexan Slider	1	WC
VU-15-9000	<	Cab "L1" Wood Door	1	WC
		hinged on right.		
VU-16-2000		Cab "L2" Clear Lexan Slider	1	WC
VU-16-6000		Cab "L3" Clear Lexan Slider	1	WC
		VERTICAL DIVIDERS:	1	WC

PART NO	S	DESCRIPTION	QTY	ID
VU-45-1000		Divider, Vertical, Streetside Upper Cabinet	1	WC
		DRUG BOX:	1	WC
XX-19-0940	<	Fire Medic Emblems Installed	1	WC
		SHIP LOOSE		
		SHIP LOOSE ITEMS:	1	WC
YY-00-0001	X	As Built Wiring Diagrams	1	
YY-05-5000	<	Manual, Owners, Additional, Ship Loose	1	WC
		Total of (4) owners manuals for entire order		
YY-10-4000		Floor Mats, Throw In, Ford E-350 99+	1	WC
YY-10-6400		Ship Loose, W.C. Standard Items	1	WC
YY-13-3000		Spare Tire, Ship Loose	1	WC
		DECAL PACKAGES LOOSE:	1	WC
		WARRANTIES	1	WC
ZZ-10-0100		Warranty, Conversion, 12 Month/12K Miles, Std.	1	WC
ZZ-10-0200		Warranty, Paint, 12 Month/12K Miles, Std.	1	WC
ZZ-10-0300		Warranty, Structural, 15 Years, Std., Mods	1	WC
ZZ-10-1800	>	Warranty, Lifetime, Mod Electrical	1	WC
ZZ-10-9901	X	EMS & SHIP LOOSE EQUIPMENT	1	
ZZ-25-0003	X	Zico/Ziamatic SCBA Mounting Brackets	2	
ZZ-25-0009	X	Stryker Power Pro Cot & Accessories	1	
ZZ-25-0443	X	Stryker, 6252, Stair Chair	1	
ZZ-25-1030		REGULATOR, LARGE CYLINDER, PRESET 50PSI □ □	1	WC
ZZ-ZZ-0200	>	End Of Order	1	WC