

C-5

November 15, 2022

HONORABLE MAYOR AND CITY COUNCIL
City of Long Beach
California

RECOMMENDATION:

Find that the Project is exempt from further environmental review and affirm staff's determination (Categorical exemption CE 22-147) and finding that the project is exempt from the California Environmental Quality Act (CEQA) pursuant to Sections 15303 (Class 3 - New Construction or Conversion of Small Structures) and 153032 (Class 32 – Infill Development); and,

Approve Condition Use Permit findings and conditions of approval memorializing the City Council's August 16, 2022 action to uphold an appeal (APL22-003) and approve a Conditional Use Permit (CUP 18-001) for a new car wash located at 5005 Long Beach Boulevard in the Commercial Automobile-Oriented (CCA) Zoning District. (District 8)

DISCUSSION

On August 16, 2022, the City Council held a duly noticed public hearing on an applicant's appeal of the Planning Commission's March 17, 2022 decision to deny a Conditional Use Permit (CUP) for a new automated car wash at 5005 Long Beach Boulevard (Attachment A). The City Council considered City staff's presentation, public comments, along with an updated noise analysis and revised plans from the applicant and acted to uphold the appeal approving the CUP and affirming findings/determination that the project is exempt from CEQA. The findings, conditions of approval, and CEQA determination are being presented for the City Council's review, adoption, and affirmation.

Background

The project site is on a part of a 1.48-acre site. The site is developed with a stand-alone restaurant and gas station with a mini mart (Attachment B). The project site is located within the CCA zoning district and has a Neighborhood Serving Centers and Corridors-Low General Plan PlaceType Designation. The area to be developed abuts the playground areas of Dooley Elementary School to the north and west, a convenience store and drug store with a drive-through pharmacy (drive-through is currently closed) to the east across Long Beach Boulevard; to the south, across Del Amo Boulevard, is a gas station with a mini mart and single-family

residences; and a gas station with a drive-through car wash and mini mart is located catty-corner to the site across Long Beach Boulevard.

The automated self-service car wash is proposed to be located north of the mini mart and gas station abutting the northerly property line shared with the elementary school, adjacent to the school playground. An existing nine-foot perimeter wall serves as a buffer between the school and proposed car wash. The proposed car wash features a modern design with quality materials. The car wash tunnel would have a length of 100 feet and includes two drive-up lanes, each with a pay station and a queuing length of approximately 130 feet before the pay station. The proposed project includes 15 parking stalls for vacuuming. Access to the car wash would be from the existing southernmost curb cut along Long Beach Boulevard. The northerly curb cut will be closed, and a full height curb and sidewalk constructed in its place. Other site modifications include new landscaping, security cameras, and lighting. The car wash would operate between the hours of 7:00 am to 7:00 pm daily.

The applicant submitted an updated car wash design which extended the car wash tunnel in order to enclose the exit and turn the opening to the south, facing toward Del Amo Boulevard, and away from the elementary school. The revised design in combination with the additional absorption materials prescribed would lower the noise levels by at least 10 decibels (dBA) to 25.5 dBA through 34.7 dBA, below the city's threshold of 50 dBA (Attachment C). The City Council found that with the aforementioned design changes and with appropriate conditions, the proposed car wash project would be consistent with the general plan and operate in a manner compatible with the surrounding uses (Attachment D).

Conditions of approval have been added to ensure the use operates in a manner compatible with the surrounding uses including prohibitory conditions. Conditions of approval include, but are not limited to, an enclosed exit, installation of sound absorbing materials, prohibiting the use of outdoor speakers, signage informing patrons to keep their radios turned down, protection of pedestrian path during construction, and requirements for maintaining one staff person at the pay kiosk during all operating hours (Attachment E). These conditions have been reviewed and discussed with the applicant.

This matter was reviewed by Deputy City Attorney Erin Weesner-McKinley on October 27, 2022 and by Budget Analysis Officer Greg Sorensen on October 24, 2022.

Public Hearing Notice

Public hearing notices are not required to accept the findings to memorialize the August 16, 2022 action of the City Council. However, a courtesy notice of the item returning to the City Council was provided to individuals who previously submitted comments on the item. The August 16, 2022 City Council public hearing was duly noticed on July 27, 2022 in accordance with the requirements of Chapter 21.21 of the Long Beach Municipal Code (LBMC).

Environmental Review

Pursuant to the California Environmental Quality Act (CEQA) Section 15303, Class 3 (c) and Section 16332, Class 32, this project is eligible for a CEQA categorical exception for "New Construction" and "Infill Development Projects" as the project consists of a qualifying small structure in an urbanized area on a lot under five acres (CE-22-147). In accordance with CEQA, the proposed project is located within Long Beach, occupies less than five acres, and is surrounded by urban uses. The site is adequately served by all required utilities and public services. The project site has no value as a habitat for endangered, rare, or threatened species. Approval of the project would not result in any significant effects related to traffic, noise, air quality, or water quality as detailed in the findings (Attachment F).

TIMING CONSIDERATIONS

City Council action is requested on November 15, 2022.

FISCAL IMPACT

This recommendation has no staffing impact beyond the normal budgeted scope of duties and is consistent with City Council priorities. There is no fiscal or local job impact associated with this recommendation.

SUGGESTED ACTION:

Approve recommendation.

Respectfully submitted,



CHRISTOPHER KOONTZ, AICP
ACTING DIRECTOR
DEVELOPMENT SERVICES

APPROVED:



THOMAS B. MODICA
CITY MANAGER

ATTACHMENTS: A – VICINITY MAP
B – PLANS AND RENDERING
C – NOISE ANALYSIS (MARCH 2021)
D – FINDINGS
E – CONDITIONS OF APPROVAL
F – CEQA EXEMPTION FINDING



Subject Property:

APNs: 7132-028-017, 7132-028-019,
7132-028-039, & 7132-028-040
Application No. 1801-02
Council District 8
Zoning Code : CCA

Attachment A



80 40 0 80 160 Feet









Exhibit B



DIRECTIONAL ARROW/ GRAPHIC SCALE



VICINITY MAP



SITE INFORMATION

ITEM	SIZE	LOT %	AREA (SQ.FT.)
TOTAL LOT AREA	N/A	N/A	66,551.00
EXISTING FOOD MART	24'-2" x 38'-1"	1.42	920.3
EXISTING STORY STUCCO BUILDING	AS SHOWN	6.90	4,300
EXISTING CANOPY	91'-5" x 30'-0"	4.23	2,743
NEW CAR WASH	100'-0" x 20'-0"	3.08	2000

LOT INFORMATION
TOTAL LOT AREA = 66,551 SQ.FT.
1. BLISS CAR WASH = 24,532 SQ.FT.
2. C-STORE & GAS = 19,504 SQ.FT.
3. EXISTING BUILDING = 22,514 SF

PARKING REQUIREMENTS:

STORE : 920 SQ.FT. = 920/250 = 4 SPACES
STORY STUCCO BUILDING: 4,475 SQ.FT. = 4,300/100 = 43 SPACES
TOTAL REQUIRED: 47 SPACES

PARKING PROVIDED:

TOTAL OF 6 (17'x18'-HANDICAP PARKING)
11 (12'x18' - VACUUM SPACES)
46 (9'x18' STANDARD PARKING)

TOTAL: 63 SPACES

01/04/2019	ER
01/11/2019	IJ
01/14/2019	IJ
02/15/2019	SH
04/28/2020	SH
01/05/2020	SH
03/15/2021	SH
07/08/2022	SK
09/01/2022	
10/01/2022	
11/01/2022	
12/01/2022	
01/01/2023	
02/01/2023	
03/01/2023	
04/01/2023	
05/01/2023	
06/01/2023	
07/01/2023	
08/01/2023	

PLANS PREPARED BY:
A & S ENGINEERING
PLANNING ENGINEERING CONSTRUCTION MANAGEMENT
28405 SAND CANYON RD. SUITE 300 CANYON COUNTRY, CA 91387
PHONE # (661)250-9300 FAX # (661) 250-9333

Platinum Energy
30343 Comwood Street, Suite 200 Agoura Hills, CA 91301
Phone # (818) 206-5700
STORE # : -
ADDRESS: 5005 LONG BEACH BLVD
LONG BEACH, CA 90805

DRAWN
SH
CHECKED
DATE
10/30/2018
SHT. TITLE
PROPOSED SITE PLAN
SCALE
1"=20'-0"
SHEET
S1



20201 SW Birch Street, Suite 150
 Newport Beach, CA 92660
 P: 714-272-2302
Mike.Holritz@BridgeNet.us

July 28, 2022

Mr. Ahmad Ghaderi
A & S Engineering

Revised site design at the *5005 Long Beach Boulevard Car Wash* project
 Long Beach, California

Dear Mr. Ghaderi:

BridgeNet International previously performed an assessment of the projected car wash noise levels at the noise-sensitive areas (Dooley Elementary School) adjacent to the *5005 Long Beach Boulevard Car Wash* project (Report #2019-003-C; May 31, 2020). With the planned site design and equipment, the projected noise levels are listed in Table 1.

Table 1
PROJECTED NOISE LEVELS
(Original Site Design)

Location	L50 (dBA)
<u>Exit End</u>	
School Building to NW	43.0
School Playground to NW	51.7
School Playground to N	52.2
<u>Entrance End</u>	
School Playground to N	50.2
School Playground to NE	47.1
School Building to N	26.5

With the planned site design and equipment, the noise levels would meet the City's adjusted Noise Ordinance limits (i.e., with the adjustment for the measured ambient levels, the L50 standard would be 60 dBA).

Subsequently, the City requested that the developer go beyond the Noise Ordinance requirements, and that the project be designed to generate noise levels 7 dB below the adjusted Noise Ordinance limits. We performed a revised assessment (Report #2019-003-D; June 22, 2021) to determine the mitigation needed to accomplish this. In order to comply with this request, absorption (2,350 square feet of QuietFiber QF4) was included in the modeling of the car wash interior to absorb some of the noise. With this absorption, the noise levels would be reduced by approximately 7.5 dB, and the projected noise levels are listed in Table 2.

Table 2
PROJECTED NOISE LEVELS
(Original Site Design with Added Absorption)

Location	L50 (dBA)
<u>Exit End</u>	
School Building to NW	35.5
School Playground to NW	44.2
School Playground to N	44.7
<u>Entrance End</u>	
School Playground to N	42.7
School Playground to NE	37.6
School Building to N	19.0

The revised analysis showed that with the planned site design and equipment, and with the specified absorption added to the interior of the car wash building, the noise levels would be at least 7 dB below the City's adjusted Noise Ordinance limits (i.e., with the adjustment for the measured ambient levels, the L50 standard would be 60 dBA). It should be noted that these levels also meet the City's regular 50 dBA L50 standard (with no adjustment for measured ambient levels).

Since the preparation of that report, the developer has revised the site design. The current design calls for the exit end to be entirely enclosed, with solid walls and a solid roof. The exit opening will now face south (away from the school). Artist renderings of the project show roll-up doors at both the entrance and exit ends. However, these doors will remain open during car wash operations. With the current design, noise levels from the car wash operations are expected to be reduced by at least another 10 dB for receptors in the school area near the exit end. (Noise levels near the entrance end would not change significantly). The projected noise levels are listed in Table 3.

Table 3
PROJECTED NOISE LEVELS
(New Site Design with Added Absorption)

Location	L50 (dBA)
<u>Exit End</u>	
School Building to NW	25.5
School Playground to NW	34.2
School Playground to N	34.7
<u>Entrance End</u>	
School Playground to N	42.7
School Playground to NE	37.6
School Building to N	19.0

The most stringent noise standard is the 50 dBA L50 limit. With this revised site design and added absorption, noise levels from the car wash are now expected to be far below the Noise Ordinance limits (without including any adjustment for ambient).

With the new design, we would recommend that at least 50% of the added absorption be located in the exit area (after the blowers).

If you have any questions or require additional information, please do not hesitate to contact me.

Mike Holritz, INCE
Environmental Specialist
BridgeNet | A Tetra Tech Company

CONDITIONAL USE PERMIT FINDINGS

**Application No. 1801-02 (CUP 18-001)
5005 Long Beach Boulevard
November 15, 2022**

Pursuant to Section 21.25.206 of the Long Beach Municipal Code, a Conditional Use Permit can be granted only when positive findings are made consistent with the following criteria set forth in the Zoning Ordinance. These findings and staff analysis are presented for consideration, adoption and incorporation into the record of proceedings:

1. THE APPROVAL IS CONSISTENT WITH AND CARRIES OUT THE GENERAL PLAN, ANY APPLICABLE SPECIFIC PLANS SUCH AS THE LOCAL COASTAL PROGRAM AND ALL ZONING REGULATIONS OF THE APPLICABLE DISTRICT;

The project site (1.48 acres), which includes two (2) existing buildings (dine-in restaurant, gas station with mini mart) situated within the southerly portion of the project site and adjacent to Del Amo Boulevard and west of Long Beach Boulevard. The proposed self-service drive-through car wash would be located within the northerly portion of the project site, adjacent to the playground of Dooley Elementary School. This area most recently served as a passive parking area, which is now fenced off prohibiting its use. The project site has an underlying General Plan Designation of Neighborhood Serving Centers and Corridors-Low (NSC-L) which encourages a variety of commercial uses to meet consumers' daily needs and is within the Community Commercial - Automobile Oriented (CCA) Zoning District which is intended for retail and service-related uses capable of supporting the entire community. The NSC-L PlaceType also allows residential and mixed residential and commercial development.

The Administration Chapter of the Land Use Element of the General Plan (see pages 168-171), establishes that, "Conditional Use Permits are consistent if the proposed project carries out the policies of the Land Use Element and meets the PlaceType density and intensity levels." While no single project can implement all policies and goals, the proposed project as redesigned implements many of the expressed policies and goals following are the policies that with which the proposed car wash would be consistent.

UD STRATEGY No. 15: Consider vacant parcels as infill opportunities.

This lot serves as a passive use for parking and is underutilized. The proposed car wash would redevelop this area of the lot with a car wash that would enhance the property with a contemporary building, landscaping and provide new job opportunities and add a new car wash service to the area.

Policy UD Policy UD 2-3: Promote enhancement of the built environment through façade improvements, quality and context-sensitive infill development, and landscaping.

The proposed project makes improvements to the adjacent right of way through the closure of one

Policy UD 14-3: Allow new development projects to respond to their particular context and experiment with alternative development patterns while complementing their PlaceTypes.

Policy UD 14-5: Promote commercial center and corridor development compatibility with adjacent residential uses, including ensuring that project design and function minimizes the potential adverse impacts of vehicle access, parking and loading facilities, building massing, signage, lighting, trash enclosures, and noise generating uses and areas.

The project has been designed with a dual lane accommodating approximately 11 vehicles at on time and includes a bypass lane. The Traffic Impact Analysis prepared by Kimley Horn finds that the site configuration would accommodate the 95th percentile queue of seven vehicles at one time. Additional conditions will require that the applicant to maintain a staff person at the kiosk during business hours to trouble shoot any problems that may arise and further reduce opportunities for the traffic to spillover into the right-of-way.

LU Policy 16-8: Require an acoustical analysis prior to project approval for projects subject to CEQA review, for all noise sensitive projects located in an area with noise levels greater than 60 dBA CNEL. All new residential land uses shall be designed to maintain a standard of 45 dBA CNEL or less in building interiors, consistent with the General Plan. Noise reduction measures to achieve this noise level could include, but are not limited to, forced air ventilation so that windows can remain closed and/or upgraded wall and window assemblies.

Acoustical analysis was completed by Bridgenet. The project has been designed to enclose the car wash exit and face the opening to the south away from the adjacent elementary school. This design change in addition to the construction of sound absorbing materials

LU Policy 18-2: Enhance street corridors and spaces between buildings by incorporating small green areas, native and drought-tolerant landscaping and street trees.

Landscaping has been incorporated into the site design. Street trees will be required as a condition of approval. Landscaping will be designed to comply with the City's landscape efficiency ordinance.

The established purpose of the Zoning Code includes protecting institutional uses such as the adjacent Dooley Elementary School from the intrusion of incompatible uses (LBMC 20.10.020).

A 9-foot-high perimeter wall serves as a buffer between the school and car wash. The car wash tunnel is configured so that the exit is enclosed and faces away from the school. In addition to the configuration of the tunnel, the car wash would be constructed with additional sound absorbing materials that further reduce sound levels that would be experienced on the school property.

2. THE PROPOSED USE WILL NOT BE DETRIMENTAL TO THE SURROUNDING COMMUNITY INCLUDING PUBLIC HEALTH, SAFETY OR GENERAL WELFARE, ENVIRONMENTAL QUALITY OR QUALITY OF LIFE; AND

The proposed car wash with dual drive-through queuing lanes would be located within the northernmost portion of commercial that is currently unused and was most recently used for passive parking. The drive-through lanes are designed as dual queuing lanes that merge at the drive-through tunnel entrance. The drive-through lanes have also accommodated a by-pass or exit lane to exit the drive-through facility if so desired by the patron. The length of the queuing lanes between the car wash menu payment station and the driveway approach on Long Beach Boulevard is approximately 260 feet (130 feet each lane). Per the Focused Air Quality Analysis prepared by Rincon Consultants, Inc. on August 21, 2020, air quality emissions from the vehicles using the car wash would be below both regional and localized thresholds from the South Coast Air Quality Management District. Localized thresholds are used to determine impacts to the nearby community, such as the elementary school. The report concludes there is no significant impact from noise or air quality.

3. THE APPROVAL IS IN COMPLIANCE WITH ALL OF THE SPECIAL CONDITIONS FOR SPECIFIC CONDITIONAL USES, AS LISTED IN CHAPTER 21.52.

Section 21.52.206 states that the following conditions shall apply to auto repair shops, service stations, car washes, auto upholstery shops, auto parts and tire sales uses requiring a Conditional Use Permit:

A. The proposed use shall not intrude into a concentration of retail uses and not impede pedestrian circulation between retail uses.

As proposed the car wash will not intrude into a concentration of retail uses and not impede pedestrian circulation between retail uses as the car wash will be developed on a vacant and underutilized portion of an existing commercial development that consists of a dine-in restaurant and service station.

B. The proposed use shall not create unreasonable obstructions to traffic circulation around or near the site.

The proposed project fronts on Long Beach Boulevard, which serves as one of the designated school walking routes to the adjacent Dooley Elementary School. The project has been designed with a dual drive-through lane with approximately 130 feet of queuing length between the pay station and driveway for each lane. It is estimated that there will be up to 738 vehicle trips daily to the car wash or approximately 77 vehicle trips per hour if equally distributed throughout the day. With a total combined queue length of 260 feet between the pay station and driveway, there would be sufficient queue length to accommodate approximately 11 vehicles at one time. The Traffic Impact Analysis prepared by Kimley Horn finds that the site configuration would accommodate the 95th percentile queue of seven vehicles at one time. Conditions of approval have been incorporated to help ensure that vehicles do not queue within the right-of-way and that construction would be planned to minimize impacts on pedestrian traffic.

C. No curb cuts shall be permitted within forty feet (40') of any public roadway intersection.

The proposed car wash will not necessitate the need to create a new curb cut to accommodate ingress/egress from the project site. As demonstrated by the site plan, access will be achieved via an existing approach which currently serves the existing fueling facility.

D. No vehicles may be stored at the site for the purposes of sale, unless the use is also, vehicle sales lot or for use as parts for vehicles under repair.

The proposed car wash would not result in the need to store vehicles for sale or repair. The self-service drive-through car wash is designed as an ancillary use to the existing fueling facility. No vehicle storage, repairs or sales are associated with the current or proposed use.

E. The site shall comply with all applicable development standards for open storage and repair uses specified in chapter 21.45. "Special Development Standards".

As previously described above, the proposed car wash will not result in the need to store vehicles for sale or repair. The project as conditioned prohibits outdoor storage and repair uses. No vehicle storage, repairs or sales are associated with the current or proposed use.

F. In the CB District, such uses shall be limited to locations inside parking structures:

The subject property is located in the CCA Zoning District therefore, this condition is not applicable.

G. In the CR and CO zones, Conditional Use Permit shall be limited to the expansion of existing nonconforming uses;

The subject property is located in the CCA Zoning District. Therefore, this condition is not applicable.

4. THE RELATED DEVELOPMENT APPROVAL, IF APPLICABLE, IS CONSISTENT WITH THE GREEN BUILDING STANDARDS FOR PUBLIC AND PRIVATE DEVELOPMENT, AS LISTED IN SECTION 21.45.400

Section 21.45.400 specifies types of projects that require compliance with green building standards. The proposed use is only 2,000 square feet in size below the established 50,000 square foot minimum threshold requiring compliance with Section 21.45.400 and therefore, this section of the Municipal Code would not be applicable to the proposed use.

**CONDITIONAL USE PERMIT
CONDITIONS OF APPROVAL
Case No. 1801-02 (CUP 18-001)
5005 Long Beach Boulevard
Date: November 15, 2022**

Special Conditions:

1. A Conditional Use Permit to operate an automated car wash and 15 vacuum stations at 5005 Long Beach Boulevard.
2. This permit and all development rights hereunder shall terminate three years from the effective date (final action date or, if in the appealable area of the Coastal zone, 21 days after the local final action date) of this permit unless the use is commenced or a time extension is granted, based on a written and approved request submitted prior to the expiration of the three-year period as provided in.
3. The applicant shall construct the car wash to include all sound attenuating measures identified in the July 29, 2022 memo prepared by Bridgenet including:
 - a. A fully enclosed exit with an opening along the south elevation.
 - b. The incorporation of absorption materials, 2,350 square feet of QuietFiber QF4. Any substitution of materials or design shall be outlined by a qualified engineer and submitted for review approval by the Zoning Administrator.
4. The applicant shall obtain permits from the Public Works Department to paint the curb along the north side of Del Amo Boulevard (south of the project site and install "No Parking Any Time" signs along the sidewalk as recommended in the Kimley-Horn and Associates, March 2021 Traffic Impact Analysis.
5. Hours of operation for the car wash use shall be limited to 7:00 a.m. – 7:00 p.m. daily.
6. There shall be no overnight storage of vehicles on site.
7. No vehicle auto repair shall be performed on site.
8. No outside storage of any kinds is permitted on site.
9. The applicant shall ensure that all equipment doors, not including the roll up doors to the car wash tunnel, are closed during regular operation.
10. The project site is located along a designated Safe Route to school and is

approximately 300' north of a bus stop. The operator shall take reasonable action to ensure that vehicles are not queuing in the right-of-way including;

- a. Maintaining a minimum of one staff person at the pay kiosks during business hours.
 - b. Utilizing additional staff with mobile payment capabilities along the vehicle queue lane for collecting mobile payment and membership sign ups.
 - c. Directing patrons to the bypass lane in the event of a mechanical failure or other disruptions in service through the car wash tunnel or placing signage at the entry to the car wash queue that the car wash is temporarily closed.
 - d. The applicant shall prohibit the queuing of vehicles prior to operating hours.
11. If substantiated complaints of excessive noise or other nuisances including the queuing of vehicles in the right-of-way are received by the City, the applicant shall work cooperate with the Department of Development services to implement changes to the operation.
12. The use of outdoor speakers, including speakers on monitors and televisions shall be prohibited.
13. The applicant shall post signage at each vacuum station informing patrons to be considerate of neighbors and keep radios turned off.
14. The applicant shall maintain the premises and abutting sidewalk and parkway free of litter. The applicant shall remove trash from the site and abutting right-of-way not less than two times a day.
15. The applicant shall coordinate with the school district on truancies. Staff shall be trained to report unaccompanied minors who are present during school hours to the school district contact.
16. Prior to permit issuance the applicant shall notify the abutting school and the Long Beach Unified School District Facilities Development and Planning Department of the construction schedule as well as a contact information of a person on site who can respond to complaints regarding construction activities. Proof of notification shall be submitted to the Zoning Administrator.
17. The operator shall not permit vending machines for general merchandise including beverages and food (excluding items directly related to the car wash service provided are excluded) games, rides, etc. on the premise.

18. The proposed project is located along a designated Safe Route to School and approximately 300' north of a bus stop. To ensure that pedestrians are accommodated, the applicant shall submit a pedestrian access and protection plan to the Department of Development Services and the Department of Public Works for review and approval. The plan shall detail all pedestrian access closures and details for safe navigation around the project site during construction. The approved pedestrian access and protection plan shall be maintained on-site at all times during construction.
 - a. The Long Beach Unified School District Facilities Development and Planning Department and the principal of the abutting school shall be notified not less than ten working days prior to any lane or sidewalk closures along Long Beach Boulevard. As feasible, lane closures should occur outside of the busiest school traffic periods (after morning drop off and before afternoon pick up) or during school breaks to minimized pedestrian, bicycle and vehicle conflicts.
19. The applicant shall provide a landscape buffer along the east property that includes a hedge, berm, tree or other permitted landscape feature at least three feet in height to adequately screen the vehicle headlights.
20. The applicant shall comply with city's landscape ordinance for water efficiency. A landscape and irrigation plan shall be submitted as a separate plan check submittal concurrent with the plan check for the building. Building permits may be not issued until landscape plans are approved.
21. The applicant shall obtain permits for the installation of irrigation and tree wells along Long Beach Boulevard. Street trees shall be installed prior to certificate of occupancy.
22. The applicant shall construct a trash enclosure which shall be designed and provided for this project as per Section 21.46.080 of the Long Beach Municipal Code within nine months from the issuance of the business license for the use. The designated trash area shall not abut a street or public walkway and shall be placed at an inconspicuous location on the lot.
23. The proposed use shall be subject to an annual inspection as required by the Long Beach Municipal Code Section 21.25.412 for review of compliance with the conditions of approval. The applicant shall be required to pay an inspection fee as established by the City Council adopted fee schedule. The annual review shall be required at the time of the annual business license renewal.
24. Upon plan check submittal the applicant shall merge APN 7132-028-039 and 7132-017 into a single lot. The lot tie or merger must be completed prior to permit issuance.

25. The applicant shall have a reciprocal access agreement for ingress and egress purposes including exhibits from the adjoining lots (APN 7132-028-40 and 7132-028-019) prepared and submitted for review and approval by the Zoning Administrator. The covenant shall be submitted at the time of plan check review and recorded prior to permit issuance.
26. The existing pole sign may be repurposed for on-site signage.
27. No signs are approved as part of this entitlement.

Standard Conditions:

28. This permit shall be invalid if the owner(s) and/or applicant(s) have failed to return written acknowledgment of their acceptance of the conditions of approval on the *Conditions of Approval Acknowledgment Form* supplied by the Planning Bureau. This acknowledgment must be submitted within 30 days from the effective date of approval (final action date or, if in the appealable area of the Coastal Zone, 21 days after the local final action date).
29. If, for any reason, there is a violation of any of the conditions of this permit or if the use/operation is found to be detrimental to the surrounding community, including public health, safety or general welfare, environmental quality or quality of life, such shall cause the City to initiate revocation and termination procedures of all rights granted herewith.
30. In the event of transfer of ownership of the property involved in this application, the new owner shall be fully informed of the permitted use and development of said property as set forth by this permit together with all conditions that are a part thereof. These specific requirements must be recorded with all title conveyance documents at time of closing escrow.
31. This approval is required to comply with these conditions of approval as long as the use is on the subject site. As such, the site shall allow periodic re-inspections, at the discretion of city officials, to verify compliance. The property owner shall reimburse the City for the inspection cost as per the special building inspection specifications established by City Council (Long Beach Municipal Code Section 21.25.212).
32. All conditions of approval must be printed verbatim on all plans submitted for plan review to Long Beach Development Services. These conditions must be printed on the site plan or a subsequent reference page.
33. All operational conditions of approval of this permit must be posted in a location visible to the public, in such a manner as to be readable when the use is open for

business.

34. The Director of Long Beach Development Services is authorized to make minor modifications to the approved design plans or to any of the conditions of approval if such modifications shall not significantly change/alter the approved design/project. Any major modifications shall be reviewed by the Zoning Administrator or Planning Commission, respectively.
35. All landscaped areas must be maintained in a neat and healthy condition. Any dying or dead plants materials must be replaced with the minimum size and height plant(s) required by Chapter 21.42 (Landscaping) of the Zoning Regulations. At the discretion of City officials, a yearly inspection shall be conducted to verify that all irrigation systems are working properly and that the landscaping is in good healthy condition. The property owner shall reimburse the City for the inspection cost as per the special building inspection specifications established by the City Council.
36. The property shall be developed and maintained in a neat, quiet, and orderly condition and operated in a manner so as not to be detrimental to adjacent properties and occupants. This shall encompass the maintenance of exterior facades of the building, designated parking areas serving the use, fences and the perimeter of the site (including all public parkways).
37. New exterior security bars, scissor gates, and roll-up doors applied to windows and pedestrian building entrances shall be prohibited. Existing unpermitted security bars, scissor gates applied to pedestrian building entrance must be removed.
38. Any graffiti found on site must be removed within 24 hours of its appearance.
39. All parking areas serving the site shall provide appropriate security lighting with light and glare shields so as to avoid any light intrusion onto adjacent or abutting residential buildings or neighborhoods pursuant to Section 21.41.259. Other security measures may be required to be provided to the satisfaction of the Chief of Police.
40. The operator of the approved use shall prevent loitering in all parking and landscaping areas serving the use during and after hours of operation. The operator must clean the parking and landscaping areas of trash debris on a daily basis. Failure to do so shall be grounds for permit revocation. If loitering problems develop, the Director of Planning and Building may require additional preventative measures such as but not limited to, additional lighting.
41. All structures shall conform to the Long Beach Building Code requirements. Notwithstanding this subject permit, all other required permits from the Building Bureau must be secured.

42. Separate building permits shall be required for fences, retaining walls, flagpoles, and pole mounted yard lighting foundations.
43. Approval of this development project is expressly conditioned upon payment (prior to building permit issuance or prior to Certificate of Occupancy, as specified in the applicable Ordinance or Resolution for the specific fee) of impact fees, connection fees and other similar fees based upon additional facilities needed to accommodate new development at established City service level standards, including, but not limited to, sewer capacity charges, Park Fees and Transportation Impact Fees.
44. The applicant shall file a separate plan check submittal to the Long Beach Fire Department for their review and approval prior to the issuance of a building permit.
45. Demolition, site preparation, and construction activities are limited to the following (except for the pouring of concrete which may occur as needed):
 - a. Weekdays and federal holidays: 7:00 a.m. to 7:00 p.m.;
 - b. Saturday: 9:00 a.m. - 6:00 p.m.; and
 - c. Sundays: not allowed
46. Any unused curb cuts shall be replaced with full height curb, gutter and sidewalk and shall be reviewed, approved and constructed to the specifications of the Director of Public Works.
47. The applicant shall defend, indemnify, and hold harmless the City of Long Beach, its agents, officers, and employees from any claim, action, or proceeding against the City of Long Beach or its agents, officers, or employees brought to attack, set aside, void, or annul an approval of the City of Long Beach, its advisory agencies, commissions, or legislative body concerning the processing of the proposal/entitlement or any action relating to, or arising out of such approval. At the discretion of the City and with the approval of the City Attorney, a deposit of funds by the applicant may be required in an amount sufficient to cover the anticipated litigation costs.

**CALIFORNIA ENVIRONMENTAL QUALITY ACT
STATEMENT OF SUPPORT
CLASS 3 (NEW CONSTRUCTION OR CONVERSION OF SMALL STRUCTURES);
AND
CLASS 32 (INFILL DEVELOPMENT) EXEMPTION DETERMINATION
5005 Long Beach Boulevard
(APN 7132-028-017, 7132-028-019, 7132-028-039, and 7132-028-040)
Application No. (1801-02) (CUP 18-001)
CE-22-147
November 15, 2022**

Section 15300 through 15333 of the California Environmental Quality Act (CEQA) establishes certain classes of projects as categorically exempt from the provisions of CEQA because they do not ordinarily result in a significant effect on the environment. The Project site is on one of four parcels totaling 1.48-acres. The site is developed with a stand-alone restaurant and gas station with a mini mart. The project site is located within the Commercial Automobile-Oriented Zoning District and has a Neighborhood Serving Centers and Corridors-Low (NSC-L) General Plan PlaceType Designation. The area to be developed abuts the playground areas of Dooley Elementary School to the north and west, a convenience store and drug store with a drive-through pharmacy (drive-through is currently closed) to the east across Long Beach Boulevard; to the south, across Del Amo Boulevard, is a gas station with a mini mart and single-family residences; and a gas station with a drive-through car wash and mini mart is located catty-corner to the site across Long Beach Boulevard.

The Project proposes to develop the existing parking area north of the mini mart with a 3,464-square-foot automated self-service car wash. The proposed car wash features a modern design with quality materials. The car wash tunnel would have a length of 100 feet and includes two drive-up lanes, each with a pay station and a queuing length of approximately 130 feet before each pay station. The proposed project includes 15 parking stalls for vacuuming. Access to the car wash would be from the existing southernmost curb cut along Long Beach Boulevard. The northerly curb cut will be closed, and a full height curb and sidewalk constructed in its place. Other site modifications include new landscaping, security cameras, and lighting. The car wash would operate between the hours of 7:00 am to 7:00 pm daily (Attachment A- Plans).

The aforementioned project qualifies for an exemption under CEQA Guidelines Section 15303 as a Class 3 new construction in an urbanized area not exceeded 10,000 square feet in size. The proposed project totals no more than 3,464 square feet and is located at 5005 Long Beach Boulevard in the City of Long Beach an urbanized area.

Additionally, analysis provides substantial evidence to support a conclusion that the proposed project also qualifies for an exemption under CEQA Guidelines Section 15332

as a Class 32 urban infill development and would not have a significant effect on the environment.

(a) THE PROJECT IS CONSISTENT WITH THE APPLICABLE GENERAL PLAN DESIGNATION AND ALL APPLICABLE GENERAL PLAN POLICIES AS WELL AS WITH APPLICABLE ZONING DESIGNATION AND REGULATIONS.

The site is located at the northwest corner of Long Beach Boulevard and Del Amo Boulevard. The site consists of multiple lots that total 66,551 square feet (1.52-acre) parcel. The site is currently developed with an existing restaurant, gas station and mini mart. The car wash would be located in the parking area on the north side of the mini mart.

The site has an underlying General Plan PlaceType designation of Neighborhood-Serving Center or Corridor-Low (NSC-L) which encourages low-rise, low-intensity mixed-use commercial centers and corridors designed to meet consumers' daily needs for goods and services close to residential areas. The property is zoned Community Commercial Automobile-Oriented (CCA) which is intended to provide retail and service uses for an entire community including convenience and comparison shopping for goods and associated services.

The Administration Chapter of the Land Use Element of the General Plan (see pages 168-171), establishes that, "Conditional Use Permits are consistent if the proposed project carries out the policies of the Land Use Element and meets the PlaceType density and intensity levels." Following are the policies that with which the proposed car wash would be consistent.

UD Strategy No. 15: Consider vacant parcels as infill opportunities.

This lot serves as a passive use for parking and is underutilized. The proposed car wash would redevelop this area of the lot with a car wash that would enhance the property with a contemporary building, landscaping and provide new job opportunities and add a new car wash service to the area.

Policy UD Policy UD 2-3: Promote enhancement of the built environment through façade improvements, quality and context-sensitive infill development, and landscaping.

The proposed project would be context-sensitive: first, it would be located on a long-vacant commercial site adjacent to an existing gasoline station and mini-mart, and would complement that use. Other adjacent uses include an existing restaurant currently under renovation. The proposed car wash would be separated from the adjacent school to the north by an existing nine-foot-tall masonry wall, and the building itself is arranged to buffer the school from activity in the interior of the site. Additionally, the main entrance and exit to the car wash are enclosed, the exit is

oriented toward Del Amo Boulevard, and the entrance is oriented to Long Beach Boulevard. The acoustical analyses prepared by BridgeNet determined the proposed car wash, as designed, would not result in any significant increase in existing noise levels on or adjacent to the site. Despite the location of the proposed car wash in an area with higher ambient noise levels, the project would comply with the standard noise thresholds in the Municipal Code. Additionally, the proposed project makes improvements to the adjacent right of way through the closure of one curb cut, reducing the number of locations at which vehicles cross the sidewalk.

Policy UD 14-3: Allow new development projects to respond to their particular context and experiment with alternative development patterns while complementing their PlaceTypes.

Policy UD 14-5: Promote commercial center and corridor development compatibility with adjacent residential uses, including ensuring that project design and function minimizes the potential adverse impacts of vehicle access, parking and loading facilities, building massing, signage, lighting, trash enclosures, and noise generating uses and areas.

The project has been designed with a dual lane queue accommodating approximately 11 vehicles at one time and includes a bypass lane. The Traffic Impact Analysis prepared by Kimley Horn finds that the site configuration would accommodate the 95th percentile queue of seven vehicles at one time, and conservatively assumes all vehicle trips to the project are unique and not shared with the existing gasoline station and mini-mart. Additional conditions will require that the applicant to maintain a staff person at the kiosk during business hours to trouble shoot any problems that may arise and further reduce opportunities for the traffic to spill over into the right-of-way. As described above, the proposed project includes context-sensitive uses and features, and will eliminate one of the existing curb cuts improving the pedestrian environment along this segment of Long Beach Boulevard which is part of the safe route to school.

LU Policy 16-8: Require an acoustical analysis prior to project approval for projects subject to CEQA review, for all noise sensitive projects located in an area with noise levels greater than 60 dBA CNEL. All new residential land uses shall be designed to maintain a standard of 45 dBA CNEL or less in building interiors, consistent with the General Plan. Noise reduction measures to achieve this noise level could include, but are not limited to, forced air ventilation so that windows can remain closed and/or upgraded wall and window assemblies.

Acoustical analysis was completed by Bridgenet. The project has been designed to enclose the car wash exit and face the opening to the south away from the adjacent elementary school. This design change in addition to the construction of sound absorbing materials would further reduce project noise levels, which already complied with the standard thresholds established in the Municipal Code.

LU Policy 18-2: Enhance street corridors and spaces between buildings by incorporating small green areas, native and drought-tolerant landscaping and street trees.

Landscaping has been incorporated into the site design. Street trees will be required as a condition of approval. Landscaping will be designed to comply with the City's landscape efficiency ordinance.

The established purpose of the Zoning Code includes protecting institutional uses such as the adjacent Dooley Elementary School from the intrusion of incompatible uses (LBMC 20.10.020).

A 9-foot-high perimeter masonry wall serves as a buffer between the school and car wash. The car wash tunnel is configured so that the exit is enclosed and faces away from the school. In addition to the configuration of the tunnel, the car wash would be constructed with additional sound absorbing materials that further reduce sound levels that would be experienced on the school property, and the location of the building would further buffer the school from activity on the project site and at the existing gasoline station and mini-mart to the south.

(b) THE PROPOSED DEVELOPMENT OCCURS WITHIN CITY LIMITS ON A PROJECT SITE OF NO MORE THAN FIVE ACRES SUBSTANTIALLY SURROUNDED BY URBAN USES.

The project site is entirely within the city limits of Long Beach, on a site that is 1.52-acre in size, which is less than maximum five acres specified. The area to developed is presently a parking lot. The site abuts the playground areas of Dooley Elementary School to the north and west, a convenience store and drug store with a drive-through pharmacy (drive-through is currently closed) to the east across Long Beach Boulevard; to the south, across Del Amo Boulevard, is a gas station with a mini mart and single-family residences; and a gas station with a drive-through car wash and mini mart is located catty-corner to the site across Long Beach Boulevard. These uses and areas above constitute the existing environment prior to the project that will not change as a result of the project.

(c) PROJECT SITE HAS NO VALUE AS HABITAT FOR ENDANGERED, RARE OR THREATENED SPECIES.

The project site is located within an urbanized area in the City of Long Beach. The site is developed with a restaurant, gas station, mini mart and surface parking lot. The area north of the mini mart that is to be developed with the car wash is

presently improved as asphalt-paved surface. The site has minimal ornamental landscaping and does not include any trees. This project would have a less than significant impact on endangered, rare, or threatened species or their habitat. New drought tolerant landscaping and trees will be provided as part of this project.

(d) APPROVAL OF THE PROJECT WOULD NOT RESULT IN ANY SIGNIFICANT EFFECTS RELATING TO TRAFFIC, NOISE, AIR QUALITY, OR WATER QUALITY.

Technical studies and subsequent clarifying responses were prepared for the proposed project for the topics of traffic, noise, air quality, and hazardous materials (Attachments B through E). Based on the analysis, and on compliance with the standard City requirements regarding runoff and water quality, the project would not exceed established thresholds in accordance with the CEQA Guidelines to constitute an impact on the surrounding environment related to the topics above.

Traffic

The project will not result in any significant effects relating to traffic within the area or on the local streets as detailed in the Traffic Impact Analysis, prepared by Kimley-Horn and Associates, Inc., dated March 2021 (Attachment B). The project would generate 738 daily trips, 64 morning peak hour trips and 74 evening peak hour trips. This assessment of daily trips is a worst-case scenario as it did not discount the number of trips for pass by/dual purpose trips that would likely occur with the adjacent gas station.

City of Long Beach Traffic Impact Analysis Guidelines (June 2020), establish that Level of Service D as an acceptable threshold for operating conditions for intersections. The Traffic Impact Analysis prepared by Kimley-Horn evaluated key intersections and found that the existing level service was presently operating at a Level of Service F. In accordance with the City of Long Beach Traffic Impact Analysis Guidelines (June 2020), even with the existing deficiency, the addition of project trips would not impose a significant impact on the study intersections of Del Amo Boulevard at Virginia Avenue, Del Amo Boulevard at Long Beach Boulevard. The project involved local serving retail of less than 50,000 square feet and would not require further VMT analysis

The project incorporates two queueing lanes. Queueing capacity was evaluated based on similar facilities and the assessment found that typical Peak number of queued vehicles to be 1 to 4 vehicles on a Friday and 3 to 8 vehicles on a Saturday, with fewer vehicles outside of these peaks. The 95th percentile, which is estimated to be 7 vehicles in its worst case among the observed Friday and Saturday, would occur more frequently than the site peak and is within the capacity of the proposed project.

Air Quality

The project will not result in any significant effects relating to air quality or greenhouse gas (GHG) as detailed in the Air Quality and Greenhouse Gas Emissions Impact Analysis for the Project prepared by Vista Environmental, October 26, 2020 (Attachment C). The criteria air pollution and GHG emissions impacts created by the proposed project have been analyzed through use of CalEEMod Version 2016.3.2. This analysis found that implementation of the State and South Coast Air Quality Management District (SCAQMD) air quality and GHG emissions reductions regulations, including but not limited to Rule 403 (Fugitive Dust) and Rule 461 (Gasoline Dispensing Facilities), were adequate to limit criteria pollutants, toxic air contaminants, odors, and GHG emissions from the proposed project to less than significant levels. The project would have to comply with all regulatory compliance measures established including: 1) demolition, grading and construction activities in compliance with SCAQMD Rule 403; 2) odors: compliance with provision of SCAQMD Rule 402; 3) engine idling in accordance with Section 2485 of Title 13 of California code of Regulations; 4) emission standards in accordance with Section 93114 of Title 17 of the California Code of Regulations; and 5) architectural coatings in compliance with SCAQMD Rule 1113. Because the Project would be subject to all of the state regulatory compliance measures, the Project would not result in any significant air quality or GHG impacts.

Noise

The project as designed would not result in any significant effects related to noise as detailed in the Noise Impact Analysis prepared by Bridgenet (July 2022 and March 2020) (Attachment D and E). This analysis found that operation of the car wash through the project configuration and design construction would produce sound well below the established sound levels permitted by Chapter 8.80 of Title 8 of Long Beach Municipal Code regulating noise. Additionally, all construction activities would be required to comply with LBMC Chapter 8.80.202 regulations for construction. Through compliance with the design and regulations of the Long Beach Municipal code the project all noise and vibration impacts would be less than significant.

Water Quality

The proposed Project, like all other qualifying developments in the City must comply with the Long Beach Municipal Code (LBMC) and other applicable regulatory requirements to protect stormwater quality and prevent runoff in excess of existing conditions.

As reflected in the project description, the Project Site entirely comprises impermeable asphalt surfacing. The Project is a non-residential development that will require a building permit, and the proposed site plan would modify more than 500 square feet. of impervious surface area (Attachment A); therefore, the Project must comply with the City's *Low Impact Development, Best Management Practices Design Manual* (the "BMP Manual"). (LBMC Section 18.74.030, subd. A.1 and B.) The City will verify calculations and Project compliance—as with all projects—through the LID plan review process. (Section 18.74.040).

The Project must evaluate the use of infiltration, capture, evapotranspiration, treatment, and/or reuse of stormwater, unless one or more of those methods are demonstrated to be technically infeasible according to standards established in the BMP Manual. Further, the capture, use, and/or treatment mechanisms must meet certain minimum size or capacity requirements. Table 3.2 of the BMP Manual lists the site-specific source control measures and their corresponding design features or elements to manage, capture, and treat stormwater flows. Notably, and as stated above, the Project Site surface entirely comprises asphalt paving and is entirely impermeable. Consequently, the Project will not increase impermeable area and therefore will not increase stormwater flow volumes. Other required elements of the program include percolation testing to establish whether the Project site can feasibly accommodate infiltration, or whether alternative measures of capture and treatment are warranted. Table 4.1 in the BMP Manual provides the criteria for infiltration as a best management practice ("BMP"), and Appendix D provides the volume calculation and design guidelines for infiltration. Table 4.2 provides the criteria for capture and use as a BMP. In addition to identifying BMPs, the BMP Manual provides design criteria and requirements, construction requirements, and operation and maintenance requirements. (See, e.g., sections 4.4 and Appendix D [infiltration], 4.5 [capture and use], and 4.6 and Appendix E [biofiltration] for discussions of the specific requirements of different types of BMPs.) Additionally, where complete on-site compliance is not demonstrated, developers must pay an offsite mitigation fee to fund improvements in other locations in the City, within the same sub-watershed as the Project, at which BMP installation and operation are feasible and would achieve, "at least the same level of water quality protection as if all of the runoff was retained [on the Project site]." (LBMC Section 18.74.050; BMP Manual section 5.1).

Because the Project would be subject to all of the City's regulatory compliance measures, would need to demonstrate compliance with numeric standards regarding capture, retention, treatment, and reuse—as well as treatment and pollution reductions, the Project would not result in any significant water quality impact.

Therefore, as detailed in the attached technical analyses, approval of the project would not result in any significant effects relating to traffic, noise, air quality, or water quality.

(e) THE SITE CAN BE ADEQUATELY SERVED BY ALL REQUIRED UTILITIES AND PUBLIC SERVICES.

The project site is presently developed with a commercial building and a gas station, a similar condition to the proposed project. The site is currently served by utilities and public services, such as Southern California Edison (electricity), Long Beach Energy Resources (natural gas), and Long Beach Water Department. While the proposed 3,464 square-foot car wash building increases the total building area on site, the Project can adequately be served by utilities by way of new water, sewer, electricity, and natural gas connection, that would be undertaken as part of the building permitting process.

CEQA Section 15300.2 provides specific instance where exceptions to the established Classes of Exemptions including the Class 3 and Class 32 -Infill Exemption are superseded; none of those conditions were found to apply to this project.

(a) LOCATION. CLASSES 3, 4, 5, 6, AND 11 ARE QUALIFIED BY CONSIDERATION OF WHERE THE PROJECT IS TO BE LOCATED – A PROJECT THAT IS ORDINARILY INSIGNIFICANT IN ITS IMPACT ON THE ENVIRONMENT MAY IN A PARTICULARLY SENSITIVE ENVIRONMENT BE SIGNIFICANT. THEREFORE, THESE CLASSES ARE CONSIDERED TO APPLY ALL INSTANCES, EXCEPT WHERE THE PROJECT MAY IMPACT ON AN ENVIRONMENTAL RESOURCE OF HAZARDOUS OR CRITICAL CONCERN WHERE DESIGNATED, PRECISELY MAPPED, AND OFFICIALLY ADOPTED PURSUANT TO LAW BY FEDERAL, STATE, OR LOCAL AGENCIES.

The site of the new car wash is currently improved with asphalt parking lot. The site abuts two other lots developed with a gas station, mini mart and restaurant that will be used to provide vehicle ingress and egress to the site. A review of the Regional Water Quality Control Board's GeoTracker database shows that there are no active LUST clean-up sites within 1,000-foot radius of the site. However, there is a closed case on for LUST on the gas station portion of the project site. The case was closed in October of 2013.

(b) CUMULATIVE IMPACT. ALL EXEMPTIONS FOR THESE CLASSES ARE INAPPLICABLE WHEN THE CUMULATIVE IMPACT OF SUCCESSIVE PROJECTS OF THE SAME TYPE IN THE SAME PLACE, OVER TIME IS SIGNIFICANT.

Technical studies were prepared for the proposed project for the topics of traffic, noise, air quality, and hazardous materials, see Attachments B through E. All reports concluded that the project would not exceed established CEQA thresholds to constitute an impact on the surrounding environment related to the topics above.

There are no projects in the vicinity of the project site that would result in cumulative impact with respect to traffic, noise, water quality and utilities and public services.

(c) SIGNIFICANT EFFECT. A CATEGORICAL EXEMPTION SHALL NOT BE USED FOR AN ACTIVITY WHERE THERE IS A REASONABLE POSSIBILITY THAT THE ACTIVITY WILL HAVE A SIGNIFICANT EFFECT ON THE ENVIRONMENT DUE TO UNUSUAL CIRCUMSTANCES.

The site is currently developed with a commercial building and gas station within an urbanized area in the City of Long Beach. The site is surrounded by urban uses (restaurant, school, gas station/convenience store, drug store) and is flat in topography. There is no sensitive habitat on the site or any other site conditions that would represent unusual circumstances. The site location would not represent an exception to this exemption.

(d) SCENIC HIGHWAYS. A CATEGORICAL EXEMPTION SHALL NOT BE USED FOR A PROJECT WHICH MAY RESULT IN DAMAGE TO SCENIC RESOURCES, INCLUDING BUT NOT LIMITED TO, TREES, HISTORIC BUILDINGS, ROCK OUTCROPPINGS, OR SIMILAR RESOURCES, WITHIN A HIGHWAY OFFICIALLY DESIGNATED AS A STATE SCENIC HIGHWAY. THIS DOES NOT APPLY TO IMPROVEMENTS WHICH ARE REQUIRED AS MITIGATION BY AN ADOPTED NEGATIVE DECLARATION OR CERTIFIED EIR.

The Proposed Project is located in an established commercial area at the intersection of two major roadways, and would have no impact as it relates to substantially damaging scenic resources, including but not limited to trees, rock outcroppings, and historic buildings within a State scenic highway due to the fact that there are no State-designed scenic highways in the City of Long Beach. There are no protected trees or unique geologic features on the site. The proposed project would not damage any scenic resources within an officially designated scenic highway.

(e) HAZARDOUS WASTE SITES. A CATEGORICAL EXEMPTION SHALL NOT BE USED FOR A PROJECT LOCATED ON A SITE WHICH IS INCLUDED ON ANY LIST COMPILED PURSUANT TO SECTION 65962.5 OF THE GOVERNMENT CODE.

The site of the new car wash is currently improved with asphalt parking lot. The site abuts two other lots developed with a gas station, mini mart and restaurant that will be used to provide vehicle ingress and egress to the site. A review of the Regional Water Quality Control Board's GeoTracker database shows that there are no active LUST clean-up sites within 1,000-foot radius of the site. However, there is a closed LUST case on the gas station portion of the project site due to

potential contamination of aquifer for drinking water supply. The case was closed in October of 2013 and all monitoring wells removed in December of 2013.


(f) HISTORICAL RESOURCES. A CATEGORICAL EXEMPTION SHALL NOT BE USED FOR A PROJECT WHICH MAY CAUSE A SUBSTANTIAL ADVERSE CHANGE IN THE SIGNIFICANCE OF A HISTORICAL RESOURCE.

There are no known historical resources located on the project site and the current development is not designated as a historic landmark or located within a historic district. The Project would not affect a historical resource.


Attachments:

- A – Plans
- B - Traffic Impact Assessment for the Car Wash Development Project in the City of Long Beach (Kimley Horn, March 2021)
- C – Air Quality and Greenhouse Gas Study, (Rincon Consultants, Inc. June 2021)
- D – Revised Noise Analysis (BridgeNet International, July 2022)
- E – Noise Analysis (BridgeNet International, March 2020)






DIRECTIONAL ARROW/ GRAPHIC SCALE



GRAPHIC SCALE
1"=20'-0"

VICINITY MAP



SITE INFORMATION

ITEM	SIZE	LOT %	AREA (SQ.FT.)
TOTAL LOT AREA	N/A	N/A	66,551.00
EXISTING FOOD MART	24'-2" x 38'-1"	1.42	920.3
EXISTING STORY STUCCO BUILDING	AS SHOWN	6.90	4,300
EXISTING CANOPY	91'-5" x 30'-0"	4.23	2,743
NEW CAR WASH	100'-0" x 20'-0"	3.08	2000

LOT INFORMATION
TOTAL LOT AREA = 66,551 SQ.FT.
1. BLISS CAR WASH = 24,532 SQ.FT.
2. C-STORE & GAS = 19,504 SQ.FT.
3. EXISTING BUILDING = 22,514 SF

PARKING REQUIREMENTS:

STORE : 920 SQ.FT. = 920/250 = 4 SPACES
STORY STUCCO BUILDING: 4,475 SQ.FT. = 4,300/100 = 43 SPACES
TOTAL REQUIRED: 47 SPACES

PARKING PROVIDED:

TOTAL OF 6 (17'x18'-HANDICAP PARKING)
11 (12'x18' - VACUUM SPACES)
46 (9'x18' STANDARD PARKING)

TOTAL: 63 SPACES

01/04/2019	ER
01/11/2019	IJ
01/14/2019	IJ
02/15/2019	SH
04/28/2020	SH
01/05/2020	SH
03/15/2021	SH
07/08/2022	SK
09/01/2022	
10/01/2022	
11/01/2022	
12/01/2022	
01/01/2023	
02/01/2023	
03/01/2023	
04/01/2023	
05/01/2023	
06/01/2023	
07/01/2023	
08/01/2023	

PLANS PREPARED BY:
A & S ENGINEERING
PLANNING ENGINEERING CONSTRUCTION MANAGEMENT
28405 SAND CANYON RD. SUITE 300 CANYON COUNTRY, CA 91387
PHONE # (661)250-9300 FAX # (661) 250-9333

Platinum Energy
30343 Comwood Street, Suite 200 Agoura Hills, CA 91301
Phone # (818) 206-5700
STORE # :
ADDRESS: 5005 LONG BEACH BLVD
LONG BEACH, CA 90805

DRAWN
SH
CHECKED
DATE
10/30/2018
SHT. TITLE
PROPOSED SITE PLAN
SCALE
1"=20'-0"
SHEET
S1



Traffic Impact Analysis

for the:

Car Wash Development Project

In the City of Long Beach

Prepared for:

A & S Engineering, Inc.

March, 2021

Kimley»»Horn

TRAFFIC IMPACT ANALYSIS
FOR THE PROPOSED CAR WASH DEVELOPMENT PROJECT

IN THE
CITY OF LONG BEACH

Prepared for:

A & S Engineering, Inc.

Prepared by:

Kimley-Horn and Associates, Inc.
1100 W Town and Country Road, Suite 700
Orange, CA 92868

March, 2021

TRAFFIC IMPACT ANALYSIS
FOR THE CAR WASH DEVELOPMENT PROJECT
IN THE CITY OF LONG BEACH

TABLE OF CONTENTS

INTRODUCTION.....	1
PROJECT DESCRIPTION	1
ANALYSIS SCENARIOS AND METHODOLOGY	4
Analysis Scenarios	4
ANALYSIS METHODOLOGY	4
Significant Impact Criteria	5
AREA CONDITIONS.....	6
Existing Street System.....	6
Existing Transit Services.....	8
Existing Bike Facilities	8
Existing Traffic Volumes.....	8
Project Trip Generation	13
Project Trip Distribution and Assignment	13
Opening Year 2022 Conditions.....	16
Opening Year 2022 With Project Conditions.....	16
<i>Intersection Analysis – Existing Conditions</i>	22
<i>Intersection Analysis – Opening Year 2022 Conditions</i>	23
<i>Intersection Analysis – Opening Year 2022 With Project Conditions</i>	24
Queuing Data Collection	25
Projected Queue Requirements for the Proposed Project	25
MULTIMODAL ANALYSIS	29
Sight Distance Analysis	30
FINDINGS AND CONCLUSIONS	32

APPENDICES

Appendix A	Approved Scope of Study Form
Appendix B	Traffic Data Collection Sheets
Appendix C	Supplemental Trip Generation Information
Appendix D	Cumulative Project Information
Appendix E	Intersection Analysis Worksheets
Appendix F	Drive-Through Queuing Data

LIST OF FIGURES

Figure 1 – Vicinity Map	2
Figure 2 – Project Site Plan	3
Figure 3 – General Plan Street Classification System	7
Figure 4 – Existing Local Transit Routes	9
Figure 5 – Existing Bicycle Network.....	10
Figure 6 – Existing Lane Configuration and Traffic Control	11
Figure 7 – Existing Traffic Volumes.....	12
Figure 8 – Trip Distribution	14
Figure 9 – Project-Related Traffic Volumes	15
Figure 10 – Cumulative Project Locations.....	18
Figure 11 – Cumulative Project Traffic Volumes	19
Figure 12 – Opening Year 2022 Traffic Volumes	20
Figure 13 – Opening Year 2022 With Project Traffic Volumes	21
Figure 14 – Queuing Capacity	28
Figure 15 – Intersection Sight Distance at Del Amo Boulevard and Project Driveways (Existing Conditions).....	31

LIST OF TABLES

Table 1 – Summary of Project Trip Generation	13
Table 2 – Summary of Cumulative Projects	17
Table 3 – Summary of Intersection Operations – Existing Conditions	22
Table 4 – Summary of Intersection Operations – Opening Year 2022 Conditions	23
Table 5 – Summary of Intersection Operations – Opening Year 2022 With Project Conditions	24
Table 6 - Summary of Drive-Through Queuing Data Collection - Friday.....	26
Table 7 - Summary of Drive-Through Queuing Data Collection - Saturday	27
Table 8 – Sight Distance Requirements.....	30

TRAFFIC IMPACT ANALYSIS
FOR THE PROPOSED CAR WASH DEVELOPMENT PROJECT
IN THE CITY OF LONG BEACH

INTRODUCTION


This traffic impact analysis has been prepared to evaluate the project-related traffic impacts associated with the proposed car wash development located at 5005 Long Beach Boulevard in the City of Long Beach, California. The analysis assesses the project impact by providing an analysis of existing and future conditions, with project traffic and with cumulative project traffic. This Traffic Impact Analysis (TIA) document follows the assumptions established during discussions with the City of Long Beach staff and the approved Scope of Study Form. The approved Scope of Study form is provided in *Appendix A*.

This report has been prepared in accordance with the City of Long Beach Traffic Impact Analysis Guidelines, dated June 2020.

PROJECT DESCRIPTION

The proposed project will be developed on the northwest corner of Del Amo Boulevard and Long Beach Boulevard in the City of Long Beach, California. The project site location is shown in its regional setting on Figure 1. The project will involve the development of a 3,058-square-foot automated car wash with a 2,000-square-foot car wash tunnel and 15 vacuum pumps; and 1,058 square feet of equipment rooms and office space; and will be constructed at an existing gas station with convenience store. The project site plan is shown on Figure 2. The project will be constructed in a single phase. For purposes of this analysis, the project is assumed to open in 2022, to provide a conservative assessment of future conditions.

The site is bounded by Dooley Elementary School to the north and west, a gas station and restaurant to the south, and Long Beach Boulevard to the east. Ingress to the site will be provided via two unsignalized driveways: one right-in right-out (RIRO) only driveway along Long Beach Boulevard and one RIRO only driveway along Del Amo Boulevard. Egress from the site will be provided via two unsignalized RIRO only driveways along Del Amo Boulevard. The Project would share ingress with the existing gas station and egress with the existing restaurant.



NOT TO SCALE

FIGURE 1
VICINITY MAP




FIGURE 2
SITE PLAN

ANALYSIS SCENARIOS AND METHODOLOGY

Analysis Scenarios

Based on the City's guidelines and per the approved Scope of Study, this traffic analysis provides an evaluation of morning and evening peak hour operations for the following scenarios:

- Existing Conditions
- Opening Year 2022
- Opening Year 2022 With Project

Any mitigation measures for the future conditions will be identified, if necessary.

The study area was determined with input from City Staff through the scoping process. A copy of the approved Scope of Study Form, as previously mentioned, is provided in *Appendix A*. The following study intersections were identified for evaluation:

Study Intersections:

1. Virginia Avenue at Del Amo Boulevard
2. Long Beach Boulevard at Del Amo Boulevard
3. Long Beach Boulevard at 51st Street

ANALYSIS METHODOLOGY

The Synchro 10 software (Trafficware) was used to analyze the peak hour operations of both signalized and unsignalized intersections. Synchro 10 uses the methodologies outlined in the latest Highway Capacity Manual.

The Highway Capacity Manual, 6th Edition (HCM 6), published by the Transportation Research Board (TRB), establishes a system whereby highway facilities are rated for their ability to accommodate traffic volumes. The terminology "Level of Service" is used to provide a qualitative evaluation based on certain quantitative calculations, which are related to empirical values.

Level of Service (LOS) for signalized and unsignalized intersections is defined in terms of average vehicle delay, which is a measure of driver discomfort, frustration, fuel consumption, and loss of travel time. Specifically, LOS criteria are stated in terms of the average control delay per vehicle for the peak 15-minute period within the hour analyzed. The average control delay includes initial deceleration delay, queue move-up time, and final acceleration time, in addition to the stop delay. The Level of Service criteria for the various LOS designations are summarized on the following chart.

LEVEL OF SERVICE DESCRIPTIONS HCM METHODOLOGY			
LOS	Average Delay (sec / vehicle)		Description
	Signalized	Unsignalized	
A	< 10.0	< 10.0	LOS A represents free flow. Individual users are virtually unaffected by the presence of others in the traffic stream.
B	> 10.0 - 20.0	> 10.0 - 15.0	LOS B represents stable flow, but the presence of others in the traffic stream begins to be noticeable. Freedom to select desired speeds is relatively unaffected, but there is a slight decline in the freedom to maneuver.
C	> 20.0 - 35.0	> 15.0 - 25.0	LOS C is in the range of stable flow, but marks the beginning of operation in which individual users become affected by interaction with others in the traffic stream.
D	> 35.0 - 55.0	> 25.0 - 35.0	LOS D represents high-density, but stable flow. Speed and freedom to maneuver are restricted, and the driver experiences a generally poor level of comfort and convenience.
E	> 55.0 - 80.0	> 35.0 - 50.0	LOS E represents operating conditions at or near the capacity of the intersection. All speeds are reduced to a low, but relatively uniform level. Small increases in flow will cause breakdowns in traffic movement.
F	> 80.0	> 50.0	LOS F represents forced, or breakdown flow. This condition occurs when the amount of traffic approaching the intersection exceeds the volume which can pass through the intersection, resulting in queues and congestion.

Significant Impact Criteria

The City of Long Beach has established LOS D as the threshold for acceptable service level for peak hour intersection volumes. Based on the City of Long Beach Traffic Impact Analysis Guidelines, the following criteria shall determine if the addition of project traffic would be responsible for deficiencies in the intersection LOS:

Signalized Intersections

- If, under without project conditions, the intersection operates at LOS D or better and the addition of project trips result in an unacceptable LOS (E or F).
- If, under without project conditions, the intersection operates at an unacceptable LOS (E or F) the project increases average control delay at the intersection by 2.5 seconds or more.
- If, under project conditions, the 95th percentile queue length exceeds the available storage length at any turn bay.

Unsignalized Intersections

- If, under project conditions, the intersection operates at an unacceptable LOS (E or F).
- If the intersection meets the peak-hour traffic signal warrant after the addition of project traffic. If the intersection meets the peak-hour traffic signal warrant, all other applicable warrants must also be assessed.

AREA CONDITIONS

This section summarizes the existing roadway circulation network, peak-hour traffic volumes, and existing operating conditions and Level of Service at the study intersections.

Existing Street System

Regional access to the site is provided by the I-710 and the I-405 Freeways. The I-710 Freeway is located approximately 0.5 miles west of the project site. The I-710 Freeway can be accessed via SR-91 Artesia Freeway and the I-405 Freeway. SR-91 Artesia Freeway runs in the east-west direction and is located approximately 2 miles north of the project site. The I-405 Freeway runs in the east-west direction and is located approximately 2 miles south of the project site.

Local access to the project vicinity is provided by several roadways. Roadway classifications were taken from the City of Long Beach Mobility Element. These roadway classifications are shown on Figure 3.

Del Amo Boulevard is a six-lane divided roadway with three lanes in each direction and a raised median within the project vicinity. Parking is permitted on both sides of the street. The posted speed limit is 40 miles per hour. The street is oriented in the east-west direction. Del Amo Boulevard is classified as a Major Avenue in the City of Long Beach Mobility Plan.

Long Beach Boulevard is a four-lane divided roadway with two lanes in each direction and a raised median within the project vicinity. Restricted parking is permitted on both sides of the street. The posted speed limit is 35 miles per hour, and 25 miles per hour just north of Del Amo Boulevard when children are present. The street is oriented in the north-south direction. Long Beach Boulevard is classified as a Boulevard in the City of Long Beach Mobility Plan.

Virginia Avenue is a two-lane undivided roadway with one lane in each direction. Parking is permitted on both sides of the street. The speed limit is 25 miles per hour. The street is oriented in the north-south direction. Virginia Avenue is classified as a Local Street in the City of Long Beach Mobility Plan.

51st Street is a two-lane undivided roadway with one lane in each direction. Parking is permitted on both sides of the street, west of the project site. The speed limit is 25 miles per hour. The street is oriented in the east-west direction. 51st Street is classified as a Local Street in the City of Long Beach Mobility Plan.




FIGURE 3
GENERAL PLAN STREET CLASSIFICATION SYSTEM
SOURCE: CITY OF LONG BEACH MOBILITY ELEMENT

Existing Transit Services

Long Beach Transit Route 51 is a bus route that travels along Long Beach Boulevard within the vicinity of the project. Route 51 operates seven days a week and provides transportation services to the Cities of Long Beach and Signal Hill.

Long Beach Transit Route 191 is a bus route that travels along Del Amo Boulevard within the vicinity of the project. Route 191 operates seven days a week and provides transportation services to the Cities of Long Beach, Carson, Lakewood, Cerritos, and Hawaiian Gardens.

Long Beach Transit Route 192 is a bus route that travels along Long Beach Boulevard and Del Amo Boulevard within the vicinity of the project. Route 192 operates seven days a week and provides transportation services to the Cities of Long Beach, Carson, Cerritos, and Artesia.

Metro Local Line 60 is a bus route that travels along Long Beach Boulevard within the vicinity of the project. Line 60 operates seven days a week and provides transportation services to the Cities of Long Beach, Compton, Lynwood, South Gate, Huntington Park, Vernon, and Los Angeles.

A map of Existing Local Transit Routes in the City are shown on Figure 4.

Existing Bike Facilities

There are no existing bike facilities in the immediate vicinity of the project. A map of the Existing Bicycle Network in the City can be found on Figure 5.

Existing Traffic Volumes

Existing morning peak period (7:00 to 9:00 AM) and evening peak period (4:00 to 6:00 PM) turning movement counts were collected for all study intersections. The counts were completed in February, 2021. Due to impacts of the ongoing COVID-19 pandemic on current traffic patterns and on closures of local schools and businesses, an approach to factor count volumes was taken into consideration. Historical traffic data for the intersection of Long Beach Boulevard at Del Amo Boulevard was provided by City staff. These volumes were collected in May, 2018. These historical counts were grown with an ambient growth of 1.5% per year to 2021, to be consistent with newly collected traffic volumes. Overall COVID adjustment factors were then determined based on a comparison of grown historical counts and current counts. These factors, which were then rounded up to be conservative, were a 65% increase in the AM and a 25% increase in the PM over traffic volumes collected in 2021. Traffic counts collected in February, 2021 were increased by 65% in the AM and 25% in the PM to obtain “Existing” traffic volumes for use in the analysis.

The existing lane configurations and traffic control at the study intersections are shown in Figure 6. Existing peak hour turning movement volumes at the study intersections are shown in Figure 7. Peak hour intersection traffic count worksheets are provided in *Appendix B*.







FIGURE 5
EXISTING BICYCLE NETWORK
SOURCE: CITY OF LONG BEACH MOBILITY ELEMENT



NOT TO SCALE



LEGEND:

- (X) = Study Intersection
- = Turn or Through Lane
- = Signal
- = Stop Sign
- D = Defacto Right Turn

FIGURE 6
EXISTING LANE CONFIGURATION AND
TRAFFIC CONTROL



FIGURE 7
EXISTING TRAFFIC VOLUMES

1. Virginia Avenue at Del Amo Boulevard	2. Long Beach Boulevard at Del Amo Boulevard
<p> $\begin{matrix} \swarrow 3/8 \\ \downarrow 2/0 \\ \nwarrow 7/13 \\ \swarrow 1858/1106 \\ \downarrow 8/21 \end{matrix}$ </p> <p> $\begin{matrix} \swarrow 13/18 \\ \downarrow 985/2179 \\ \nwarrow 15/19 \end{matrix}$ </p> <p> $\begin{matrix} \swarrow 12/6 \\ \downarrow 2/0 \\ \nwarrow 12/23 \end{matrix}$ </p>	<p> $\begin{matrix} \swarrow 267/119 \\ \downarrow 992/708 \\ \nwarrow 112/174 \end{matrix}$ </p> <p> $\begin{matrix} \swarrow 127/161 \\ \downarrow 1239/715 \\ \nwarrow 147/139 \end{matrix}$ </p> <p> $\begin{matrix} \swarrow 153/268 \\ \downarrow 604/1561 \\ \nwarrow 261/339 \end{matrix}$ </p> <p> $\begin{matrix} \swarrow 274/273 \\ \downarrow 427/853 \\ \nwarrow 56/153 \end{matrix}$ </p>
3. Long Beach Boulevard at 51st Street	
<p> $\begin{matrix} \swarrow 15/16 \\ \downarrow 1366/1036 \\ \nwarrow 2/3 \end{matrix}$ </p> <p> $\begin{matrix} \swarrow 17/16 \\ \downarrow 26/18 \end{matrix}$ </p> <p> $\begin{matrix} \swarrow 18/38 \\ \downarrow 678/245 \end{matrix}$ </p>	

LEGEND:

- = Study Intersection
- xx/yy = AM/PM Peak Hour Volumes

PROJECT TRAFFIC

Project Trip Generation

Due to the limited data within the Institute of Transportation Engineers (ITE) Trip Generation Manual, daily and peak hour trips for the proposed project were determined based on data provided by the applicant for an existing BLISS Car Wash located at 4294 University Parkway in San Bernardino, CA and for an existing BLISS Car Wash located at 600 N Rose Drive in Placentia, CA. Transaction data in 2019 was provided and averaged on a daily basis to indicate the number of vehicles utilizing the car wash facility each hour. Data between these two sites, which are similar in operation to the proposed project, was averaged for trip generation purposes.

Daily, morning peak hour, and evening peak hour trip generation estimates are summarized on Table 1 and supplemental trip generation data is presented in *Appendix C*. The project is estimated to generate 738 daily trips, 64 morning peak hour trips, and 74 evening peak hour trips. These values reflect site volumes on a Friday, which tends to generate higher volumes than on a typical weekday.

Table 1 – Summary of Project Trip Generation									
Land Use	Quantity	Unit	Trip Generation Estimates						
			Daily	AM Peak Hour			PM Peak Hour		
				In	Out	Total	In	Out	Total
Automated Car Wash	3.058	KSF	738	32	32	64	37	37	74
1 Source: Existing BLISS Car Wash at 4294 University Parkway, San Bernardino CA Existing BLISS Car Wash at 600 N Rose Drive, Placentia, CA									

Project Trip Distribution and Assignment

Project trip distribution and assignment assumptions for the proposed project were developed with approval from the City Traffic Engineering staff. Trip distribution assumptions are shown on Figure 8.

Based on the proposed project trip distribution, project trips were assigned through the study intersections. Figure 9 shows new project trips that would be added to the study intersections.




FIGURE 8
TRIP DISTRIBUTION ASSUMPTIONS


LEGEND:



Project Site

XX%

Trip Distribution
Percentage



NOT TO SCALE



1. Virginia Avenue at Del Amo Boulevard		2. Long Beach Boulevard at Del Amo Boulevard	
	$\leftarrow 8/9$ $\leftarrow 24/28$		$\leftarrow 8/9$
$8/9 \rightarrow$		$16/19 \rightarrow$ $8/9 \rightarrow$ $8/9 \rightarrow$	$8/9 \rightarrow$
3. Long Beach Boulevard at 51st Street			
	$\leftarrow 8/9$		
	$8/9 \rightarrow$		

LEGEND:


-  = Study Intersection
- xx/yy = AM/PM Peak Hour Volumes

FIGURE 9
PROJECT-RELATED TRAFFIC VOLUMES

PROJECTED FUTURE TRAFFIC

Opening Year 2022 Conditions

Opening Year 2022 traffic forecasts were developed using the following “build-up” forecasting method:

- Existing traffic volumes, plus
- An annual ambient growth rate of 1.5% per year to the Existing traffic volumes, plus
- Cumulative projects traffic
 - Cumulative projects consist of projects that have been approved but are not yet built and fully occupied, as well as projects that are in various stages of the application and approval process, but have not yet been approved. These projects are considered to be “reasonably foreseeable,” and must therefore be included in the Cumulative Projects analysis.



Cumulative Project information was obtained from City of Long Beach Staff at the start of the study process. The complete list of cumulative projects is provided in *Appendix D*. For the purpose of this traffic study, the projects were assessed for their proximity to the project site and for their potential to contribute traffic through the study intersections based on their approved or pending land uses. Therefore, not all cumulative projects are anticipated to affect the study area. A summary of the Cumulative Projects is provided on Table 2. The location of the Cumulative Projects in relation to the project site is shown on Figure 10. Cumulative project-related trips at study intersections are shown on Figure 11. Opening Year 2022 peak hour traffic volumes are shown on Figure 12.

Opening Year 2022 With Project Conditions

Project-related traffic was added to the Opening Year 2022 traffic volumes to develop the Opening Year 2022 With Project peak hour forecasts, which are shown on Figure 13.

TABLE 2
SUMMARY OF CUMULATIVE PROJECTS

Proj #	Description	Land Use	Quantity	Units	Trip Generation Estimates						
					Daily	AM Peak Hour			PM Peak Hour		
						In	Out	Total	In	Out	Total
1	6151-6191 Atlantic Ave	Mixed Use	18.047	KSF	681	11	6	17	33	36	69
2	5801 Atlantic Ave	Multifamily Housing (Mid-Rise)	84	DU	457	8	22	30	23	14	37
		Shopping Center	4.600	KSF	174	3	2	5	8	9	17
3	5721 Lime Ave	Multifamily Housing (Mid-Rise)	15	DU	82	1	4	5	4	3	7
4	5450 Cherry Ave	High-Turnover (Sit-Down) Restaurant	6.000	KSF	673	33	27	60	36	22	58
5	5100 Long Beach Blvd	Multifamily Housing (Mid-Rise)	38	DU	207	4	10	14	10	7	17
6	4800 Long Beach Blvd	Multifamily Housing (Mid-Rise)	20	DU	109	2	5	7	5	3	8
7	4000 Via Oro Ave	Manufacturing	517.037	KSF	2,032	247	74	321	108	239	347
8	4251 Long Beach Blvd	Medical-Dental Office Building	8.559	KSF	298	19	5	24	8	21	29
9	712 Baker St	Multifamily Housing (Mid-Rise)	226	DU	1,229	21	60	81	61	39	100
		Single-Family Detached Housing	7	DU	66	1	4	5	4	3	7
10	3435-3459 Long Beach Blvd and 3464 Locust Ave	General Office Building	104.227	KSF	1,015	104	17	121	19	101	120
11	3450 Long Beach Blvd	General Office Building	15.200	KSF	148	15	2	17	3	15	18
Total Project Trips					4,897	469	238	707	322	512	834
DU = Dwelling Unit, KSF = 1,000 square feet											




NOT TO SCALE

LEGEND:

(X) = Cumulative Project Location

FIGURE 10
CUMULATIVE PROJECT LOCATIONS



NOT TO SCALE



1. Virginia Avenue at Del Amo Boulevard		2. Long Beach Boulevard at Del Amo Boulevard	
	← 9/14	5/4 ↕ 12/2	← 3/6
8/14 →		2/5 → 2/7 → 4/2 →	1/4 → 2/12 →
3. Long Beach Boulevard at 51st Street			
	← 12/2		
	2/12 →		

LEGEND:

- (X) = Study Intersection
- xx/yy = AM/PM Peak Hour Volumes

FIGURE 11
CUMULATIVE PROJECT
TRAFFIC VOLUMES



FIGURE 12
OPENING YEAR 2022
TRAFFIC VOLUMES

1. Virginia Avenue at Del Amo Boulevard	2. Long Beach Boulevard at Del Amo Boulevard
<div> <div> <div>3/8</div> <div>2/0</div> <div>3/0</div> </div> <div> <div>7/13</div> <div>1895/1137</div> <div>8/21</div> </div> </div> <div> <div>13/18</div> <div>1008/2226</div> <div>15/19</div> </div> <div> <div>12/6</div> <div>2/0</div> <div>12/23</div> </div>	<div> <div>276/125</div> <div>1019/722</div> <div>114/177</div> </div> <div> <div>129/163</div> <div>1261/732</div> <div>149/141</div> </div>

157/277

615/1591


269/346

279/281

435/878

57/155

LEGEND:

-  = Study Intersection
 xx/yy = AM/PM Peak Hour
 Volumes



1. Virginia Avenue at Del Amo Boulevard	2. Long Beach Boulevard at Del Amo Boulevard
3. Long Beach Boulevard at 51st Street	

LEGEND:

- = Study Intersection
- xx/yy = AM/PM Peak Hour Volumes

FIGURE 13
OPENING YEAR 2022 WITH PROJECT
TRAFFIC VOLUMES

TRAFFIC ANALYSIS

The study intersections were analyzed in accordance with the analysis methodology described earlier in this report for the following scenarios:

- Existing Conditions
- Opening Year 2022
- Opening Year 2022 With Project

Intersection Analysis – Existing Conditions

The study intersections were analyzed for Existing Conditions. Intersection Level of Service worksheets are provided in *Appendix E*. The Existing Conditions analysis results and Level of Service for the study intersections are presented in Table 3. Review of this table indicates that the following study intersection currently operates at an unacceptable Level of Service (F) in both peak periods:

- #1 – Del Amo Boulevard at Virginia Avenue

Table 3 – Summary of Intersection Operations – Existing Conditions					
Int. #	Intersection	Intersection Control	Peak Hour	Delay (sec/veh)	LOS
1	Del Amo Boulevard at Virginia Avenue	TWSC	AM	266.7	F
			PM	190.1	F
2	Del Amo Boulevard at Long Beach Boulevard	Signal	AM	48.7	D
			PM	47.9	D
3	Long Beach Boulevard at 51st Street	Signal	AM	2.7	A
			PM	2.5	A

TWSC – Two-Way Stop Control

The 95th Percentile queue length at the turn bays of the signalized study intersections were analyzed for the Existing Conditions. Queuing worksheets are provided in *Appendix E*. Results indicate that the queue of the northbound left and southbound left lanes at the following intersection exceed the capacity of the turn bay:

- #2 – Del Amo Boulevard at Long Beach Boulevard

Intersection Analysis – Opening Year 2022 Conditions

The study intersections were analyzed for the Opening Year 2022 Conditions. Intersection Level of Service worksheets are provided in *Appendix E*. The Opening Year 2022 Conditions analysis results and Level of Service for the study intersections are presented in Table 4. Review of this table indicates that the following study intersection would continue to operate at an unacceptable Level of Service (F) in both peak periods:

- #1 – Del Amo Boulevard at Virginia Avenue

Table 4 – Summary of Intersection Operations – Opening Year 2022 Conditions					
Int. #	Intersection	Intersection Control	Peak Hour	Delay (sec/veh)	LOS
1	Del Amo Boulevard at Virginia Avenue	TWSC	AM	266.7	F
			PM	253.3	F
2	Del Amo Boulevard at Long Beach Boulevard	Signal	AM	50.6	D
			PM	50.3	D
3	Long Beach Boulevard at 51st Street	Signal	AM	2.7	A
			PM	2.5	A

The 95th Percentile queue length at the turn bays of the signalized study intersections were analyzed for the Opening Year 2022 Conditions. Queuing worksheets are provided in *Appendix E*. Results indicate that the queue of the northbound left and southbound left lanes at the following intersection exceed the capacity of the turn bay:

- #2 – Del Amo Boulevard at Long Beach Boulevard

Intersection Analysis – Opening Year 2022 With Project Conditions

The study intersections were analyzed for the Opening Year 2022 With Project Conditions in accordance with the analysis methodology described earlier in this report. Intersection Level of Service worksheets are provided in *Appendix E*. The Opening Year 2022 with Project Conditions analysis results and Level of Service for the study intersections are presented in Table 5. Review of this table indicates that the following study intersection would continue to operate at an unacceptable Level of Service (F) in both peak periods:

- #1 – Del Amo Boulevard at Virginia Avenue

Table 5 – Summary of Intersection Operations – Opening Year 2022 With Project Conditions							
				Without Project		With Project	
Int. #	Intersection	Intersection Control	Peak Hour	Delay (sec/veh)	LOS	Delay (sec/veh)	LOS
1	Del Amo Boulevard at Virginia Avenue	TWSC	AM	266.7	F	383.4	F
			PM	253.3	F	647.6	F
2	Del Amo Boulevard at Long Beach Boulevard	Signal	AM	50.6	D	52.3	D
			PM	50.3	D	51.5	D
3	Long Beach Boulevard at 51st Street	Signal	AM	2.7	A	2.8	A
			PM	2.5	A	2.5	A

The 95th Percentile queue length at the turn bays of the signalized study intersections were analyzed for the Opening Year 2022 With Project Conditions. Queuing worksheets are provided in *Appendix E*. Results indicate that the queue of the northbound left and southbound left lanes at the following intersection exceed the capacity of the turn bay:

- #2 – Del Amo Boulevard at Long Beach Boulevard

This is an existing deficiency and the addition of project trips would not impose a significant impact on the study intersection.

QUEUING ANALYSIS

Kimley-Horn performed a queueing analysis to evaluate the adequacy of the drive-through queueing capacity for the proposed project.

The opening to the drive-through lane would be located at the southeast corner of the project site, and would wrap around the east, north, and west sides of the project in a counter-clockwise direction. The drive-through would provide two side-by-side entry lanes and two transaction kiosks. After the transaction kiosks, the two lanes would merge back into a single drive-through lane and proceed through the car wash. There would be approximately 260 feet of total queueing capacity (approximately 130 feet per lane) from the opening of the two drive-through lanes to the two transaction kiosks. This would provide a queueing capacity of 10 to 13 vehicles, assuming 20 to 25 feet per vehicle, from the beginning of the drive-through lanes to the transaction kiosks.

Queueing Data Collection

Drive-through queueing observations and counts were conducted at the following existing car wash site:

- 4294 University Pkwy, San Bernardino

This site location was selected for queueing data collection because of the following site characteristics that are similar to the proposed project:

- Location has drive-through lane with similar project size
- Located adjacent to an existing gas station
- Located within 1 mile of an interstate
- Located along a major roadway

The drive-through activity at the data collection site was observed on a Friday from 2:00 PM to 6:00 PM and a Saturday from 10:00 PM to 2:00 PM, during the periods of peak demand. The drive-through queueing data can be found in *Appendix F*.

The results of the observations are summarized on Table 6 and Table 7 for the Friday and Saturday peak periods, respectively. The data summary on these tables present the observed Average queue, the Peak queue, and the 95th Percentile queue. The peak activity at each site was observed to occur intermittently, with an ebb and flow pattern throughout each peak with periods of lower queueing activity between peaks.


Projected Queue Requirements for the Proposed Project

Assuming the proposed Car Wash development would experience similar queueing activity to the studied site, the typical Peak number of queued vehicles is estimated to be 1 to 4 vehicles on a Friday and 3 to 8 vehicles on a Saturday, with fewer vehicles outside of these peaks. The 95th percentile, which is estimated to be 7 vehicles in its worst case among the observed Friday and Saturday, would occur more frequently than the site peak and is within the capacity of the proposed project with fewer vehicles outside of these peaks.

The proposed project's drive-through lane would have enough stacking distance for approximately 10-13 vehicles, and there are no anticipated disruptions to onsite circulation resulting from this project queue. Queues are not anticipated to block the main drive aisles that provide access to other portions of the site. The proposed site location and queueing capacity is provided on Figure 14.

Table 6 - Summary of Drive-Through Queuing Data Collection - Friday	
Site Average	
Time	Vehicles
2:00-2:15PM	1.5
2:15-2:30PM	1.3
2:30-2:45PM	0.7
2:45-3:00PM	0.8
3:00-3:15PM	1.1
3:15-3:30PM	1.5
3:30-3:45PM	0.5
3:45-4:00PM	1.0
4:00-4:15PM	1.6
4:15-4:30PM	1.1
4:30-4:45PM	2.1
4:45-5:00PM	1.3
5:00-5:15PM	0.7
5:15-5:30PM	1.0
5:30-5:45PM	1.0
5:45-6:00PM	0.7
Site Peak	
2:00-2:15PM	3.0
2:15-2:30PM	3.0
2:30-2:45PM	2.0
2:45-3:00PM	2.0
3:00-3:15PM	3.0
3:15-3:30PM	3.0
3:30-3:45PM	1.0
3:45-4:00PM	2.0
4:00-4:15PM	4.0
4:15-4:30PM	3.0
4:30-4:45PM	3.0
4:45-5:00PM	3.0
5:00-5:15PM	2.0
5:15-5:30PM	3.0
5:30-5:45PM	2.0
5:45-6:00PM	2.0
Site 95 th %-ile ¹	
2:00-2:15PM	3.0
2:15-2:30PM	3.0
2:30-2:45PM	1.5
2:45-3:00PM	2.0
3:00-3:15PM	2.2
3:15-3:30PM	3.0
3:30-3:45PM	1.0
3:45-4:00PM	2.0
4:00-4:15PM	3.3
4:15-4:30PM	2.4
4:30-4:45PM	3.0
4:45-5:00PM	2.6
5:00-5:15PM	1.6
5:15-5:30PM	2.5
5:30-5:45PM	2.0
5:45-6:00PM	1.7
¹ 95th percentile = The queue will be less than the queue shown 95% of the time.	

Table 7 - Summary of Drive-Through Queuing Data Collection - Saturday	
Site Average	
Time	Vehicles
10:00-10:15AM	2.9
10:15-10:30AM	1.1
10:30-10:45AM	1.5
10:45-11:00AM	2.1
11:00-11:15AM	3.8
11:15-11:30AM	1.4
11:30-11:45AM	2.4
11:45-12:00PM	1.9
12:00-12:15PM	1.7
12:15-12:30PM	1.6
12:30-12:45PM	1.8
12:45-1:00PM	4.1
1:00-1:15PM	1.9
1:15-1:30PM	2.6
1:30-1:45PM	3.6
1:45-2:00PM	1.5
Site Peak	
10:00-10:15AM	5.0
10:15-10:30AM	3.0
10:30-10:45AM	3.0
10:45-11:00AM	5.0
11:00-11:15AM	6.0
11:15-11:30AM	3.0
11:30-11:45AM	5.0
11:45-12:00PM	3.0
12:00-12:15PM	3.0
12:15-12:30PM	3.0
12:30-12:45PM	4.0
12:45-1:00PM	7.0
1:00-1:15PM	4.0
1:15-1:30PM	5.0
1:30-1:45PM	8.0
1:45-2:00PM	3.0
Site 95 th %-ile ¹	
10:00-10:15AM	4.0
10:15-10:30AM	2.6
10:30-10:45AM	3.0
10:45-11:00AM	5.0
11:00-11:15AM	6.0
11:15-11:30AM	3.0
11:30-11:45AM	4.0
11:45-12:00PM	3.0
12:00-12:15PM	3.0
12:15-12:30PM	3.0
12:30-12:45PM	3.1
12:45-1:00PM	6.0
1:00-1:15PM	3.4
1:15-1:30PM	4.8
1:30-1:45PM	7.0
1:45-2:00PM	3.0
¹ 95th percentile = The queue will be less than the queue shown 95% of the time.	



MULTIMODAL ANALYSIS

Although there are no bike facilities in the immediate vicinity of the project, pedestrian access is provided via sidewalk on both sides of the roadways surrounding the project area, including Long Beach Boulevard and Del Amo Boulevard. Both signalized study intersections on Long Beach Boulevard possess pedestrian crosswalks with push buttons and signal heads, thereby providing connectivity to existing bus stops along Long Beach Boulevard and Del Amo Boulevard. The proposed project will maintain the existing pedestrian access routes.

Existing morning peak period (7:00 to 9:00 AM) and evening peak period (4:00 to 6:00 PM) pedestrian and bicycle volumes were collected at the study intersections. These counts were completed in February, 2021. Peak hour pedestrian and bicycle counts are provided in *Appendix B*. As traffic patterns have been significantly affected by the COVID-19 pandemic and students of Dooley Elementary School (immediately north of the project) have transitioned to distance-learning, pedestrian volumes for the school were developed by applying an appropriate factor to the total student population.

Studies by the Centers for Disease Control and Prevention (CDC) show that approximately 10% or less of students walk or bike to school on an average school morning in most (61.5%) schools. There were a total of 1,001 students enrolled at Dooley Elementary School in the 2018-2019 school year, as published by the Nation Center for Education Statistics (NCES). Therefore, after applying a 10% factor to the student population of 1,001 students, there are approximately 100 students that walk or bike to school on an average school-day morning.

It is assumed that the distribution of the Dooley Elementary School pedestrian and bicycle traffic would be 25% from each of the north, east, south and west directions. Based on these assumptions, the following student trip assignment information can be considered:

- Most of the 25 students from the north on Long Beach Boulevard would turn west onto 51st Street before the project to get to the main entrance of Dooley Elementary School and would not cross any project driveways;
- however, few (~5) students from the north might continue south toward Del Amo Boulevard and cross all project driveways along Long Beach Boulevard and Del Amo Boulevard;
- 25 students from the east would cross both project driveways along Del Amo Boulevard;
- 25 students from the south would cross both project driveways along Del Amo Boulevard;
- 25 students from the west would turn north before the project and would not cross any project driveways.

In summary, approximately 55 students would cross all project driveways along Del Amo Boulevard, and only few of these students would cross the project driveway along Long Beach Boulevard. In addition, there will be negligible amounts of existing pedestrian-foot traffic and bicycle traffic that would cross the project driveways. Furthermore, the total amount of pedestrian and bicycle traffic is not anticipated to significantly affect vehicle delay entering the project site.

Sight Distance Analysis

A sight distance analysis was performed at the project driveways along Del Amo Boulevard to evaluate the visibility from the project driveways for the right-turn movements. The existing intersection control are stop-control at the project driveways and free-flow along Del Amo Boulevard.

The sight distance standard used, Case B2, in this analysis are from the 2018 American Association of State Highway and Transportation Officials (AASHTO) – Geometric Design of Highways and Streets, Chapter 9 – Intersections (Intersection Sight Distance). Case B2 is used for right turners at a stopped position from a minor street. Table 8 shows the sight distance requirement evaluated for a 35-mph roadway.



Table 8 – Sight Distance Requirements				
Case	Passenger Car			
	45 mph	40 mph	35 mph	30 mph
B2	430 feet	385 feet	335 feet	290 feet

2018 American Association of State Highway and Transportation Officials (AASHTO) –
Geometric Design of Highways and Streets, Chapter 9 – Intersections (Intersection Sight Distance)

Drivers wanting to make a southbound right turn from the project driveways along Del Amo Boulevard would need approximately 335 feet of sight distance looking towards the east from Position 1 (driver is 7.5 feet behind the limit line) and Position 2 (driver is 2.5 feet behind the limit line). At Driveway 1 in the existing conditions, permitted on-street parking obstructs the view at both Positions 1 and 2, and the minimum sight distance requirements are not met looking towards the east. A representation of the Existing Intersection Sight Distance is shown on Figure 15. However, the visibility of pedestrians within the sidewalk as drivers approach the driveways is adequate.

The following improvement would improve the sight distance towards the east on Driveway 1 to meet the minimum sight distance requirement of 335 feet:

- Paint curb along the north side of Del Amo Boulevard (south of the project site) red and install “NO PARKING ANY TIME” signs along the sidewalk.



LEGEND:

- = Driver's Eye Position
- = Sight Line

FIGURE 15
INTERSECTION SIGHT DISTANCE AT DEL AMO BOULEVARD
AND PROJECT DRIVEWAYS (EXISTING CONDITIONS)

FINDINGS AND CONCLUSIONS

This traffic impact analysis has been prepared to evaluate the project-related traffic impacts associated with the proposed car wash development located 5005 Long Beach Boulevard in the City of Long Beach, California. The project is estimated to generate 738 daily trips, 64 morning peak hour trips, and 74 evening peak hour trips.

Existing traffic volumes were collected in February, 2021. Due to the impacts of COVID-19 on current traffic patterns, historical counts in the area were used to derive a factor to apply to recent counts. Traffic volumes collected in 2018 were increased by 65% in the AM and 25% in the PM to account for the decrease in traffic related to COVID-19.

Factored existing volumes, along with existing lane geometrics and traffic control at each intersection, were used in conducting peak hour Level of Service (LOS) analyses. Under Existing Conditions, the following study intersection currently operates at an unacceptable Level of Service (F) in both peak periods:

- #1 – Del Amo Boulevard at Virginia Avenue

The 95th Percentile queue length at the turn bays of the signalized study intersections were analyzed for the Existing Conditions. Results indicate that the queue of the northbound left and southbound left lanes at the following intersection exceed the capacity of the turn bay:

- #2 – Del Amo Boulevard at Long Beach Boulevard

An ambient growth of 1.5% and cumulative project traffic were added to the Existing scenario to develop the Opening Year 2022 scenario volumes. In the Opening Year 2022 scenario, the following study intersection would continue to operate at an unacceptable Level of Service (F) in both peak periods:

- #1 – Del Amo Boulevard at Virginia Avenue

The 95th Percentile queue length at the turn bays of the signalized study intersections were analyzed for the Opening Year 2022 Conditions. Results indicate that the queue of the northbound left and southbound left lanes at the following intersection exceed the capacity of the turn bay:

- #2 – Del Amo Boulevard at Long Beach Boulevard

Proposed project trips were added to the Opening Year 2022 traffic volumes to determine the traffic volumes for the Opening Year 2022 With Project scenario. In the Opening Year 2022 With Project scenario, the following study intersection would continue to operate at an unacceptable Level of Service (F) in both peak periods:

- #1 – Del Amo Boulevard at Virginia Avenue

The 95th Percentile queue length at the turn bays of the signalized study intersections were analyzed for the Opening Year 2022 With Project Conditions. Results indicate that the queue of the northbound left and southbound left lanes at the following intersection exceed the capacity of the turn bay:

- #2 – Del Amo Boulevard at Long Beach Boulevard

This is an existing deficiency and the addition of project trips would not impose a significant impact on the study intersection.

The drive-through capacity would be approximately 220 feet (110 feet per lane) from the opening of the two drive-through lanes to the two transaction kiosks, providing a queuing capacity of 9 to 11 vehicles, assuming 20 to 25 feet per vehicle. Drive-through queuing data collection at a similar site and analysis shows that the typical Peak queue expected at the project site would be 3 to 8 vehicles. The 95th Percentile queue, which is estimated to be 7 vehicles in its worst case, would occur more frequently than the site peak and is within the capacity of the proposed project. These queue lengths are within the capacity provided by the proposed site layout.

Although there are no bike facilities in the immediate vicinity of the project, pedestrian access is provided via sidewalk on both sides of the roadways surrounding the project area, including Long Beach Boulevard and Del Amo Boulevard. Appropriate factoring was applied to the Dooley student population of 1,001 students, to determine that approximately 100 students walk or bike to school on an average school-day morning.

Based on trip distribution assumptions, about 55 students would cross all project driveways along Del Amo Boulevard, and only 5 of these students would cross the project driveway along Long Beach Boulevard. Existing pedestrian-foot traffic and bicycle traffic is negligible; therefore, the total amount of pedestrian and bicycle traffic is not anticipated to significantly affect vehicle delay entering the project site.

A sight distance analysis was performed at the project driveways along Del Amo Boulevard to evaluate the visibility from the project driveways for the right-turn movements. Per sight distance standard Case B2, drivers wanting to make a southbound right turn from the project driveways along Del Amo Boulevard would need approximately 335 feet of sight distance looking towards the east. At Driveway 1, permitted on-street parking obstructs the view at both Positions 1 (driver is 7.5 feet behind the limit line) and 2 (driver is 2.5 feet behind the limit line), and the minimum sight distance requirements are not met.

The recommended improvement to improve the sight distance to meet the standard requirement for Case B2 from Driveway 1 is to paint the curb along the north side of Del Amo Boulevard (south of the project site) red and install "NO PARKING ANY TIME" signs along the sidewalk.

The 95th Percentile queue length at the turn bays of the signalized study intersections were analyzed for the Opening Year 2022 With Project Conditions. Results indicate that the queue of the northbound left and southbound left lanes at the following intersection exceed the capacity of the turn bay:

- #2 – Del Amo Boulevard at Long Beach Boulevard

This is an existing deficiency and the addition of project trips would not impose a significant impact on the study intersection.

The drive-through capacity would be approximately 260 feet (130 feet per lane) from the opening of the two drive-through lanes to the two transaction kiosks, providing a queuing capacity of 10 to 13 vehicles, assuming 20 to 25 feet per vehicle. Drive-through queuing data collection at a similar site and analysis shows that the typical Peak queue expected at the project site would be 3 to 8 vehicles. The 95th Percentile queue, which is estimated to be 7 vehicles in its worst case, would occur more frequently than the site peak and is within the capacity of the proposed project. These queue lengths are within the capacity provided by the proposed site layout.

Although there are no bike facilities in the immediate vicinity of the project, pedestrian access is provided via sidewalk on both sides of the roadways surrounding the project area, including Long Beach Boulevard and Del Amo Boulevard. Appropriate factoring was applied to the Dooley student population of 1,001 students, to determine that approximately 100 students walk or bike to school on an average school-day morning.

Based on trip distribution assumptions, about 55 students would cross all project driveways along Del Amo Boulevard, and only 5 of these students would cross the project driveway along Long Beach Boulevard. Existing pedestrian-foot traffic and bicycle traffic is negligible; therefore, the total amount of pedestrian and bicycle traffic is not anticipated to significantly affect vehicle delay entering the project site.

A sight distance analysis was performed at the project driveways along Del Amo Boulevard to evaluate the visibility from the project driveways for the right-turn movements. Per sight distance standard Case B2, drivers wanting to make a southbound right turn from the project driveways along Del Amo Boulevard would need approximately 335 feet of sight distance looking towards the east. At Driveway 1, permitted on-street parking obstructs the view at both Positions 1 (driver is 7.5 feet behind the limit line) and 2 (driver is 2.5 feet behind the limit line), and the minimum sight distance requirements are not met.

The recommended improvement to improve the sight distance to meet the standard requirement for Case B2 from Driveway 1 is to paint the curb along the north side of Del Amo Boulevard (south of the project site) red and install "NO PARKING ANY TIME" signs along the sidewalk.

APPENDIX A

APPROVED SCOPE OF STUDY FORM



January 12, 2021

Alexis Oropeza
Long Beach Development Services
411 West Ocean Boulevard, 3rd Floor
Long Beach, CA 90802

RE: *Traffic Impact Analysis Scoping Agreement for the Proposed Development at the Car Wash Project at 5005 Long Beach Boulevard*

Dear Ms. Oropeza:

Kimley-Horn and Associates, Inc. is pleased to submit this Scoping Agreement for the proposed car wash development at 5005 Long Beach Boulevard in the City of Long Beach. The scope of the traffic impact analysis is summarized below. This scope of work is based on the review comments and recommendations provided by LSA in their peer review letter dated September 2020, and on the City of Long Beach Traffic Impact Analysis Guidelines (June 2020). The Scoping Agreement for Traffic Impact Analysis form is included in the Appendix.

Project Description

The applicant proposes a development consisting of a 3,058-square-foot automated car wash at an existing gas station with convenience store located at the northwest corner of Del Amo Boulevard and Long Beach Boulevard. The project, in its local setting, is shown on Figure 1. The project site plan is shown on Figure 2.

Study Scenarios

The following study scenarios will be included for analysis:

- Existing Conditions
- Opening Year 2021
- Opening Year 2021 with Project

Study Methodology

Intersection Level of Service calculations will be based on the latest version of the Highway Capacity Manual (HCM) Methodology for unsignalized and signalized intersections.

Project Trip Distribution

Project trip distribution assumptions for the Plus Project conditions are shown on Figure 3.

Background Traffic

The project is anticipated to be open in 2021. Existing traffic volumes will be grown at a rate of 1.5% per year to account for ambient growth between Existing and Opening Year scenarios. Additionally,

traffic from cumulative projects within a five-mile radius of the proposed site will be included in the Opening Year scenario. A list of these projects will be provided by City of Long Beach staff.

Project Trip Generation

Due to the limited data within the Institute of Transportation Engineers (ITE) Trip Generation Manual, daily and peak hour trips for the proposed project were determined based on data provided by the applicant for an existing BLISS Car Wash located at 4294 University Parkway in San Bernardino, CA and for an existing BLISS Car Wash located at 600 N Rose Drive in Placentia, CA. Transaction data in 2019 was provided and averaged on a daily basis to indicate the number of vehicles utilizing the car wash facility each hour. Data between these two sites, which are similar in operation to the proposed project, was averaged for trip generation purposes. This information is summarized in Table 1 for the morning and the evening peak hour, with the data sheet attached in the Appendix. The values here reflect site volumes on a Friday, which tends to generate higher volumes than on a typical weekday.

TABLE 1 SUMMARY OF PROJECT TRIP GENERATION									
Land Use	Quantity	Unit	Trip Generation Estimates						
			Daily	AM Peak Hour			PM Peak Hour		
				In	Out	Total	In	Out	Total
Automated Car Wash	3.058	KSF	738	32	32	64	37	37	74
1 Source: Existing BLISS Car Wash at 4294 University Parkway, San Bernardino CA Existing BLISS Car Wash at 600 N Rose Drive, Placentia, CA									

Study Intersections

The following study intersections are proposed:

1. Virginia Avenue/Del Amo Boulevard
2. Long Beach Boulevard/Del Amo Boulevard
3. Long Beach Boulevard/51st Street

Traffic Counts

Peak hour traffic counts at intersections are typically conducted on a weekday during the morning and evening peak periods (7:00AM – 9:00AM, 4:00PM-6:00PM). Data will be collected at each study intersection and will be factored to account for any anomalies resulting from the impacts of Covid-19 on traffic. This factor will be determined based on a traffic count provided by the city, which was conducted in 2018 at the intersection of Long Beach Boulevard and Del Amo Boulevard.

Queuing Analysis


Queueing analysis will be conducted to demonstrate that the 95th percentile queue can be contained within the project site without disrupting the flow of traffic along Long Beach Boulevard. Queueing data will be collected at a similar existing BLISS car wash site, between 2PM and 6PM on a Friday and between 10AM and 2PM on a Saturday, to demonstrate peak operating conditions during the week and weekend.

Multimodal Analysis

Bicycle and pedestrian volumes will be obtained on Long Beach Boulevard and Del Amo Boulevard. Volumes will be derived from historic data from the City, if available, or from counts. Due to the nature of the current Covid-19 situation, the adjacent school will be contacted to obtain information regarding the student population. This information will be used to estimate the number of students walking to school, in the absence of in-person classes during the pandemic.

Additionally, a sight distance analysis will be conducted at the project driveways along Long Beach Boulevard and along Del Amo Boulevard to demonstrate that conflicts would not be present in the proposed design.

APPENDIX



NOT TO SCALE

FIGURE 1
VICINITY MAP






FIGURE 2
SITE PLAN



NOT TO SCALE

FIGURE 3
TRIP DISTRIBUTION ASSUMPTIONS

LEGEND:



Project Site

XX%

Trip Distribution
Percentage

Scoping Agreement for Traffic Impact Analysis

This Scoping Agreement acknowledges the Transportation Impact Study for the following Project will be prepared in accordance with the City of Long Beach's Transportation Impact Study Guidelines:

A. Project Information

Project Name:	CUP 1801-02: Proposed Automated Car Wash
Project Location:	5005 Long Beach Boulevard, Long Beach CA
Project Description:	Construction of a new 3,058-square-foot automated car wash facility at an existing gas station with convenient store at the northwest corner of Del Amo Blvd and Long Beach Blvd.

Project Site Plan Attached? (required) ☒ Yes ☐ No

B. Trip Generation

Source of Trip Generation Rates ☐ ITE Trip Generation ☒ Other Historical Data

	In	Out	Total
AM Trips	<u>32</u>	<u>32</u>	<u>64</u>
PM Trips	<u>37</u>	<u>37</u>	<u>74</u>
Daily Trips	<u>369</u>	<u>369</u>	<u>738</u>

Internal Trips	<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No	Trip Discount %	<hr/>
Pass-by Trips	<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No	Trip Discount %	<hr/>

Trip Geographic Distribution N 25 % S 25 % E 25 % W 25 %

Map of Project trip distribution % at Study intersections attached? ☒ Yes ☐ No

C. Study Area and Assumptions

Project Completion Year	2021	Annual Growth Rate	1.5	% per year
-------------------------	------	--------------------	-----	------------

Related Projects List attached? (*obtain from City*) ☐ Yes ☒ No TO BE PROVIDED BY CITY STAFF

List of Study Intersection (attach map)

- | | |
|---|---|
| 1 <u>Virginia Avenue/Del Amo Blvd</u> | 2 <u>Long Beach Boulevard/Del Amo Boulevard</u> |
| 3 <u>Long Beach Boulevard/51st Street</u> | 4 _____ |
| 5 _____ | 6 _____ |
| 7 _____ | 8 _____ |
| 9 _____ | 10 _____ |
| 11 _____ | 12 _____ |
| 13 _____ | 14 _____ |
| 15 _____ | 16 _____ |
| 17 _____ | 18 _____ |
| 19 _____ | 20 _____ |

D. Other Jurisdictional Impacts

Is the project within any other Agency's sphere of influence ☐ Yes ☒ No

If yes, name of Jurisdiction

E. Contact Information

Consultant

Name: Kimley-Horn and Associates, Inc.
Address: 765 The City Drive, Suite 200
Orange, CA 92868
Telephone: 714-939-1030
Email: tim.chan@kimley-horn.com

Developer

A & S Engineering
28405 Sand Canyon Road, Suite B
Canyon Country, CA 91387
661-250-9300
ahmadg@asengineer.com

Approved by:



Consultant's Representative

1/12/20

Date

City of Long Beach Representative

Date

Single Wash Avg Hourly Volume: San Bernadino June-December 2019

Hour of E..	Event Date Time						
	Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
7	12	16	10	11	12	16	13
8	18	17	17	18	18	22	27
9	27	21	19	20	18	26	33
10	30	21	18	17	19	24	33
11	33	22	19	20	20	24	39
12	33	26	21	21	21	29	40
13	31	24	21	21	23	27	36
14	30	24	20	19	22	26	34
15	29	25	21	21	23	31	31
16	29	25	23	26	24	31	30
17	23	25	26	23	25	30	24
18	20	21	21	24	23	27	22
Grand To..	311	268	233	226	237	309	348

Avg Daily Vol broken down by Event Date Time Weekday vs. Event Date Time Hour. The data is filtered on Site, EventDate Year and EventDate Month. The Site filter keeps San Bernadino. The EventDate Year filter keeps 2019. The EventDate Month filter excludes January, February, March, April and May. The view is filtered on Event Date Time Hour, which keeps 12 members.

Bliss Placentia

	For the Day	For the Day	For the Day	For the Day	Average
	7/5/2019	7/12/2019	7/19/2019	7/26/2019	
	Hourly Washes	Hourly Washes	Hourly Washes	Hourly Washes	
Washes by Hour					
7 AM Wash Count	8	18	17	33	19
8 AM Wash Count	18	20	28	43	27
9 AM Wash Count	29	36	36	51	38
10 AM Wash Count	37	23	34	50	36
11 AM Wash Count	40	31	31	52	39
12 PM Wash Count	39	26	37	45	37
1 PM Wash Count	40	28	25	53	37
2 PM Wash Count	36	29	35	50	38
3 PM Wash Count	36	37	31	47	38
4 PM Wash Count	45	35	35	53	42
5 PM Wash Count	36	31	40	54	40
6 PM Wash Count	16	48	44	48	39
TOTAL	380	362	393	579	429

From: Alexis Oropeza <Alexis.Oropeza@longbeach.gov>
Sent: Friday, January 22, 2021 12:11 AM
To: Chan, Tim
Subject: FW: 5005 Long Beach Blvd. (Car Wash)
Attachments: Scoping Agreement Form - January 2021.pdf

Hi Tim,

The parameters outlined in the revised scope dated January 12th and attached to this email is accepted.

Sincerely,
Alexis Oropeza
Current Planning Officer

Long Beach Development Services | Planning Bureau
T 562.570.6413 F 562.570.6068
411 West Ocean Blvd., 3rd Floor | Long Beach, CA 90802
Alexis.Oropeza@longbeach.gov | www.lbds.info



APPENDIX B

TRAFFIC DATA COLLECTION SHEETS

National Data & Surveying Services

Intersection Turning Movement Count

Location: Virginia Ave & Del Amo Blvd
City: Long Beach
Control: 2-Way Stop(NB/SB)

Project ID: 21-020034-001
Date: 2/9/2021

Total

NS/EW Streets:	Virginia Ave				Virginia Ave				Del Amo Blvd				Del Amo Blvd				
AM	NORTHBOUND				SOUTHBOUND				EASTBOUND				WESTBOUND				TOTAL
	0 NL	1 NT	0 NR	0 NU	0 SL	1 ST	0 SR	0 SU	1 EL	3 ET	0 ER	0 EU	1 WL	3 WT	0 WR	0 WU	
7:00 AM	2	0	1	0	0	0	6	0	0	99	2	1	0	254	0	0	365
7:15 AM	2	0	1	0	1	1	0	0	0	128	3	1	0	269	3	0	409
7:30 AM	2	0	1	0	0	0	1	0	1	142	1	0	0	308	1	0	457
7:45 AM	3	0	1	0	1	0	0	0	3	164	3	0	0	310	0	1	486
8:00 AM	0	1	4	0	0	0	1	0	2	163	2	1	2	239	0	2	417
8:15 AM	4	0	0	0	0	0	0	0	0	158	1	0	0	229	0	2	394
8:30 AM	2	0	2	0	0	0	0	0	1	178	0	1	1	207	0	2	394
8:45 AM	0	0	1	0	0	0	0	1	0	174	3	1	0	205	1	0	386
TOTAL VOLUMES :	NL 15	NT 1	NR 11	NU 0	SL 2	ST 1	SR 8	SU 1	EL 7	ET 1206	ER 15	EU 5	WL 3	WT 2021	WR 5	WU 7	TOTAL 3308
APPROACH %'s :	55.56%	3.70%	40.74%	0.00%	16.67%	8.33%	66.67%	8.33%	0.57%	97.81%	1.22%	0.41%	0.15%	99.26%	0.25%	0.34%	
PEAK HR :	07:15 AM - 08:15 AM																TOTAL
PEAK HR VOL :	7	1	7	0	2	1	2	0	6	597	9	2	2	1126	4	3	1769
PEAK HR FACTOR :	0.583	0.250	0.438	0.000	0.500	0.250	0.500	0.000	0.500	0.910	0.750	0.500	0.250	0.908	0.333	0.375	0.910
	0.750				0.625				0.903				0.912				

PM	NORTHBOUND				SOUTHBOUND				EASTBOUND				WESTBOUND				TOTAL
	0 NL	1 NT	0 NR	0 NU	0 SL	1 ST	0 SR	0 SU	1 EL	3 ET	0 ER	0 EU	1 WL	3 WT	0 WR	0 WU	
4:00 PM	1	0	6	0	0	0	1	0	2	385	2	1	1	204	2	3	608
4:15 PM	0	0	5	0	0	0	0	0	2	392	2	0	4	243	2	2	652
4:30 PM	2	0	6	0	0	0	0	0	2	402	2	3	1	234	2	2	656
4:45 PM	1	0	3	0	0	0	1	0	2	456	4	1	1	225	2	2	698
5:00 PM	0	0	4	0	0	0	3	0	1	438	7	0	7	223	2	2	687
5:15 PM	2	0	5	0	0	0	2	0	4	447	2	1	1	203	4	1	672
5:30 PM	3	0	5	0	0	0	1	0	0	389	2	2	2	241	3	0	648
5:45 PM	1	0	4	0	0	0	1	0	1	440	2	0	0	188	1	0	638
TOTAL VOLUMES :	NL 10	NT 0	NR 38	NU 0	SL 0	ST 0	SR 9	SU 0	EL 14	ET 3349	ER 23	EU 8	WL 17	WT 1761	WR 18	WU 12	TOTAL 5259
APPROACH %'s :	20.83%	0.00%	79.17%	0.00%	0.00%	0.00%	100.00%	0.00%	0.41%	98.67%	0.68%	0.24%	0.94%	97.40%	1.00%	0.66%	
PEAK HR :	04:30 PM - 05:30 PM																TOTAL
PEAK HR VOL :	5	0	18	0	0	0	6	0	9	1743	15	5	10	885	10	7	2713
PEAK HR FACTOR :	0.625	0.000	0.750	0.000	0.000	0.000	0.500	0.000	0.563	0.956	0.536	0.417	0.357	0.946	0.625	0.875	0.972
	0.719				0.500				0.957				0.954				

National Data & Surveying Services Intersection Turning Movement Count

Location: Virginia Ave & Del Amo Blvd
City: Long Beach
Control: 2-Way Stop(NB/SB)

Project ID: 21-020034-001
Date: 2/9/2021

Bikes

NS/EW Streets:	Virginia Ave				Virginia Ave				Del Amo Blvd				Del Amo Blvd				
AM	NORTHBOUND				SOUTHBOUND				EASTBOUND				WESTBOUND				TOTAL
	0 NL	1 NT	0 NR	0 NU	0 SL	1 ST	0 SR	0 SU	1 EL	3 ET	0 ER	0 EU	1 WL	3 WT	0 WR	0 WU	
7:00 AM	0	0	0	0	0	0	0	0	0	1	0	0	0	1	0	0	2
7:15 AM	0	0	0	0	0	0	0	0	0	1	0	0	0	1	0	0	2
7:30 AM	0	0	0	0	0	0	0	0	0	2	0	0	0	2	0	0	4
7:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	1
8:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
8:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
8:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
8:45 AM	0	0	0	0	0	0	0	0	0	3	0	0	0	1	0	0	4
TOTAL VOLUMES :	NL 0	NT 0	NR 0	NU 0	SL 0	ST 0	SR 0	SU 0	EL 0	ET 7	ER 0	EU 0	WL 0	WT 6	WR 0	WU 0	TOTAL 13
APPROACH %'s :									0.00%	100.00%	0.00%	0.00%	0.00%	100.00%	0.00%	0.00%	
PEAK HR :	07:15 AM - 08:15 AM																TOTAL
PEAK HR VOL :	0	0	0	0	0	0	0	0	0	3	0	0	0	4	0	0	7
PEAK HR FACTOR :	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.375	0.000	0.000	0.000	0.500	0.000	0.000	0.438
										0.375				0.500			

PM	NORTHBOUND				SOUTHBOUND				EASTBOUND				WESTBOUND				TOTAL
	0 NL	1 NT	0 NR	0 NU	0 SL	1 ST	0 SR	0 SU	1 EL	3 ET	0 ER	0 EU	1 WL	3 WT	0 WR	0 WU	
4:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	1
4:30 PM	0	0	0	0	0	0	0	0	0	1	0	0	0	1	0	0	2
4:45 PM	1	0	0	0	0	0	1	0	0	3	0	0	0	0	0	0	5
5:00 PM	0	0	0	0	0	0	0	0	0	2	0	0	0	1	0	0	3
5:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
5:30 PM	0	0	0	0	0	0	0	0	0	2	0	0	0	0	0	0	2
5:45 PM	0	0	0	0	0	0	0	0	1	1	0	0	0	1	0	0	3
TOTAL VOLUMES :	NL 1	NT 0	NR 0	NU 0	SL 0	ST 0	SR 1	SU 0	EL 1	ET 9	ER 0	EU 0	WL 0	WT 4	WR 0	WU 0	TOTAL 16
APPROACH %'s :	100.00%	0.00%	0.00%	0.00%	0.00%	0.00%	100.00%	0.00%	10.00%	90.00%	0.00%	0.00%	0.00%	100.00%	0.00%	0.00%	
PEAK HR :	04:30 PM - 05:30 PM																TOTAL
PEAK HR VOL :	1	0	0	0	0	0	1	0	0	6	0	0	0	2	0	0	10
PEAK HR FACTOR :	0.25	0.000	0.000	0.000	0.000	0.000	0.250	0.000	0.000	0.500	0.000	0.000	0.000	0.500	0.000	0.000	0.500
										0.500				0.500			

National Data & Surveying Services

Intersection Turning Movement Count

Location: Virginia Ave & Del Amo Blvd
City: Long Beach

Project ID: 21-020034-001
Date: 2/9/2021

Pedestrians (Crosswalks)

NS/EW Streets:	Virginia Ave		Virginia Ave		Del Amo Blvd		Del Amo Blvd		
AM	NORTH LEG		SOUTH LEG		EAST LEG		WEST LEG		
	EB	WB	EB	WB	NB	SB	NB	SB	TOTAL
	7:00 AM	1	0	0	0	0	0	0	1
	7:15 AM	3	3	0	1	1	0	1	9
	7:30 AM	0	0	0	0	0	1	0	1
	7:45 AM	0	1	0	1	0	0	0	2
	8:00 AM	1	1	0	0	0	0	0	2
	8:15 AM	0	3	1	0	0	0	0	4
	8:30 AM	0	1	3	0	0	0	0	4
	8:45 AM	0	2	0	0	0	0	0	2
TOTAL VOLUMES : APPROACH %'s :	EB 5 31.25%	WB 11 68.75%	EB 4 66.67%	WB 2 33.33%	NB 1 50.00%	SB 1 50.00%	NB 1 100.00%	SB 0 0.00%	TOTAL 25
PEAK HR :	07:15 AM - 08:15 AM								TOTAL
PEAK HR VOL : PEAK HR FACTOR :	4 0.333 0.375	5 0.417	0 0.500	2 0.500	1 0.250 0.500	1 0.250	1 0.250 0.250	0 0.250	14 0.389

PM	NORTH LEG		SOUTH LEG		EAST LEG		WEST LEG		
	EB	WB	EB	WB	NB	SB	NB	SB	TOTAL
	4:00 PM	0	0	0	0	0	0	0	0
	4:15 PM	0	0	0	1	0	0	0	1
	4:30 PM	2	0	2	1	0	0	0	5
	4:45 PM	0	2	0	2	0	0	0	4
	5:00 PM	0	0	0	0	0	0	0	0
	5:15 PM	2	0	0	0	0	0	0	2
	5:30 PM	1	0	0	1	0	0	0	2
	5:45 PM	0	0	1	0	1	0	0	2
TOTAL VOLUMES : APPROACH %'s :	EB 5 71.43%	WB 2 28.57%	EB 3 37.50%	WB 5 62.50%	NB 1 100.00%	SB 0 0.00%	NB 0	SB 0	TOTAL 16
PEAK HR :	04:30 PM - 05:30 PM								TOTAL
PEAK HR VOL : PEAK HR FACTOR :	4 0.500 0.750	2 0.250	2 0.250	3 0.375 0.417	0	0	0	0	11 0.550

National Data & Surveying Services

Intersection Turning Movement Count

Location: Long Beach Blvd & Del Amo Blvd
City: Long Beach
Control: Signalized

Project ID: 21-020034-002
Date: 2/9/2021

Total

NS/EW Streets:	Long Beach Blvd				Long Beach Blvd				Del Amo Blvd				Del Amo Blvd				
AM	NORTHBOUND				SOUTHBOUND				EASTBOUND				WESTBOUND				TOTAL
	1 NL	2 NT	1 NR	0 NU	1 SL	2 ST	1 SR	0 SU	2 EL	3 ET	1 ER	0 EU	2 WL	3 WT	1 WR	0 WU	
7:00 AM	31	45	3	0	11	86	22	0	19	65	14	0	11	185	13	0	505
7:15 AM	44	61	7	0	10	110	46	0	27	76	24	0	12	176	13	0	606
7:30 AM	46	74	7	0	18	127	37	0	14	79	42	0	22	213	22	0	701
7:45 AM	55	63	4	0	13	171	52	0	23	98	38	0	20	205	19	1	762
8:00 AM	34	51	12	0	17	138	36	0	31	108	37	0	25	173	18	0	680
8:15 AM	31	71	11	0	20	165	37	0	23	81	41	2	21	160	18	0	681
8:30 AM	42	69	19	0	17	132	29	0	18	117	53	0	14	136	22	0	668
8:45 AM	35	65	19	0	21	140	35	0	23	109	39	0	22	139	15	0	662
TOTAL VOLUMES :	NL 318	NT 499	NR 82	NU 0	SL 127	ST 1069	SR 294	SU 0	EL 178	ET 733	ER 288	EU 2	WL 147	WT 1387	WR 140	WU 1	TOTAL 5265
APPROACH %'s :	35.37%	55.51%	9.12%	0.00%	8.52%	71.74%	19.73%	0.00%	14.82%	61.03%	23.98%	0.17%	8.78%	82.81%	8.36%	0.06%	
PEAK HR :	07:30 AM - 08:30 AM																TOTAL
PEAK HR VOL :	166	259	34	0	68	601	162	0	91	366	158	2	88	751	77	1	2824
PEAK HR FACTOR :	0.755	0.875	0.708	0.000	0.850	0.879	0.779	0.000	0.734	0.847	0.940	0.250	0.880	0.881	0.875	0.250	0.927
	0.904				0.880				0.876				0.892				

PM	NORTHBOUND				SOUTHBOUND				EASTBOUND				WESTBOUND				TOTAL
	1 NL	2 NT	1 NR	0 NU	1 SL	2 ST	1 SR	0 SU	2 EL	3 ET	1 ER	0 EU	2 WL	3 WT	1 WR	0 WU	
4:00 PM	44	158	35	0	24	141	29	0	48	268	64	0	23	129	38	0	1001
4:15 PM	57	151	29	0	42	135	34	0	40	324	65	0	18	159	33	0	1087
4:30 PM	58	157	27	0	30	144	35	0	52	269	71	0	42	150	35	0	1070
4:45 PM	52	175	31	0	29	138	22	0	55	323	79	0	28	140	30	0	1102
5:00 PM	59	165	28	0	33	143	28	0	56	305	65	0	29	140	28	1	1080
5:15 PM	44	160	21	0	41	143	19	0	37	336	76	0	28	143	38	0	1086
5:30 PM	63	182	42	0	36	143	26	0	65	285	51	1	25	149	33	0	1101
5:45 PM	38	105	32	0	47	134	25	0	51	328	59	2	20	130	37	0	1008
TOTAL VOLUMES :	NL 415	NT 1253	NR 245	NU 0	SL 282	ST 1121	SR 218	SU 0	EL 404	ET 2438	ER 530	EU 3	WL 213	WT 1140	WR 272	WU 1	TOTAL 8535
APPROACH %'s :	21.69%	65.50%	12.81%	0.00%	17.40%	69.15%	13.45%	0.00%	11.97%	72.24%	15.70%	0.09%	13.10%	70.11%	16.73%	0.06%	
PEAK HR :	04:45 PM - 05:45 PM																TOTAL
PEAK HR VOL :	218	682	122	0	139	567	95	0	213	1249	271	1	110	572	129	1	4369
PEAK HR FACTOR :	0.865	0.937	0.726	0.000	0.848	0.991	0.848	0.000	0.819	0.929	0.858	0.250	0.948	0.960	0.849	0.250	0.991
	0.890				0.977				0.949				0.971				

National Data & Surveying Services

Intersection Turning Movement Count

Location: Long Beach Blvd & Del Amo Blvd
 City: Long Beach
 Control: Signalized

Project ID: 21-020034-002
 Date: 2/9/2021

Bikes

NS/EW Streets:	Long Beach Blvd				Long Beach Blvd				Del Amo Blvd				Del Amo Blvd				
AM	NORTHBOUND				SOUTHBOUND				EASTBOUND				WESTBOUND				TOTAL
	1 NL	2 NT	1 NR	0 NU	1 SL	2 ST	1 SR	0 SU	2 EL	3 ET	1 ER	0 EU	2 WL	3 WT	1 WR	0 WU	
7:00 AM	0	0	0	0	0	0	0	0	0	1	0	0	0	0	0	0	1
7:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	1
7:30 AM	0	1	0	0	0	0	0	0	0	1	2	0	0	2	0	0	6
7:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	1
8:00 AM	0	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	1
8:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
8:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
8:45 AM	0	0	1	0	0	0	0	0	0	1	1	0	1	1	0	0	5
TOTAL VOLUMES :	NL 0	NT 1	NR 1	NU 0	SL 1	ST 0	SR 0	SU 0	EL 0	ET 3	ER 3	EU 0	WL 1	WT 5	WR 0	WU 0	TOTAL 15
APPROACH %'s :	0.00%	50.00%	50.00%	0.00%	100.00%	0.00%	0.00%	0.00%	0.00%	50.00%	50.00%	0.00%	16.67%	83.33%	0.00%	0.00%	
PEAK HR :	07:30 AM - 08:30 AM																TOTAL
PEAK HR VOL :	0	1	0	0	1	0	0	0	0	1	2	0	0	3	0	0	8
PEAK HR FACTOR :	0.000	0.250	0.000	0.000	0.250	0.000	0.000	0.000	0.000	0.250	0.250	0.000	0.000	0.375	0.000	0.000	0.333
	0.250				0.250				0.250				0.375				

PM	NORTHBOUND				SOUTHBOUND				EASTBOUND				WESTBOUND				TOTAL
	1 NL	2 NT	1 NR	0 NU	1 SL	2 ST	1 SR	0 SU	2 EL	3 ET	1 ER	0 EU	2 WL	3 WT	1 WR	0 WU	
4:00 PM	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
4:15 PM	0	1	0	0	0	1	1	0	0	0	0	0	0	0	0	0	3
4:30 PM	0	3	0	0	0	1	0	0	1	0	0	0	0	0	0	0	5
4:45 PM	0	2	0	0	0	1	0	0	0	2	0	0	0	1	0	0	6
5:00 PM	0	1	0	0	0	0	0	0	0	1	0	0	0	0	0	0	2
5:15 PM	0	0	0	0	0	1	0	0	0	1	0	0	0	0	0	0	2
5:30 PM	0	2	0	0	1	1	0	0	1	0	0	0	0	0	0	0	5
5:45 PM	0	0	0	0	0	0	0	0	0	2	0	0	0	0	0	0	2
TOTAL VOLUMES :	NL 0	NT 10	NR 0	NU 0	SL 1	ST 5	SR 1	SU 0	EL 2	ET 6	ER 0	EU 0	WL 0	WT 1	WR 0	WU 0	TOTAL 26
APPROACH %'s :	0.00%	100.00%	0.00%	0.00%	14.29%	71.43%	14.29%	0.00%	25.00%	75.00%	0.00%	0.00%	0.00%	100.00%	0.00%	0.00%	
PEAK HR :	04:45 PM - 05:45 PM																TOTAL
PEAK HR VOL :	0	5	0	0	1	3	0	0	1	4	0	0	0	1	0	0	15
PEAK HR FACTOR :	0.00	0.625	0.000	0.000	0.250	0.750	0.000	0.000	0.250	0.500	0.000	0.000	0.000	0.250	0.000	0.000	0.625
	0.625				0.500				0.625				0.250				

National Data & Surveying Services

Intersection Turning Movement Count

Location: Long Beach Blvd & Del Amo Blvd
City: Long Beach

Project ID: 21-020034-002
Date: 2/9/2021

Pedestrians (Crosswalks)

NS/EW Streets:	Long Beach Blvd		Long Beach Blvd		Del Amo Blvd		Del Amo Blvd		
AM	NORTH LEG		SOUTH LEG		EAST LEG		WEST LEG		TOTAL
	EB	WB	EB	WB	NB	SB	NB	SB	
7:00 AM	0	3	0	0	0	0	0	2	5
7:15 AM	6	1	0	0	0	0	3	1	11
7:30 AM	1	1	1	0	1	3	0	0	7
7:45 AM	0	1	0	3	0	1	3	0	8
8:00 AM	1	1	0	0	1	1	0	1	5
8:15 AM	0	5	0	1	1	2	0	3	12
8:30 AM	0	1	2	2	1	2	3	1	12
8:45 AM	0	0	3	3	1	5	2	2	16
TOTAL VOLUMES :	EB 8	WB 13	EB 6	WB 9	NB 5	SB 14	NB 11	SB 10	TOTAL 76
APPROACH %'s :	38.10%	61.90%	40.00%	60.00%	26.32%	73.68%	52.38%	47.62%	
PEAK HR :	07:30 AM - 08:30 AM								TOTAL
PEAK HR VOL :	2	8	1	4	3	7	3	4	32
PEAK HR FACTOR :	0.500	0.400	0.250	0.333	0.750	0.583	0.250	0.333	0.667
	0.500		0.417		0.625		0.583		

PM	NORTH LEG		SOUTH LEG		EAST LEG		WEST LEG		TOTAL
	EB	WB	EB	WB	NB	SB	NB	SB	
4:00 PM	1	2	2	1	2	0	1	1	10
4:15 PM	0	1	2	3	0	4	0	2	12
4:30 PM	3	0	2	0	3	4	3	0	15
4:45 PM	2	3	0	0	0	1	1	3	10
5:00 PM	1	1	1	0	2	0	1	5	11
5:15 PM	2	0	3	3	2	3	3	0	16
5:30 PM	2	2	1	0	1	3	1	5	15
5:45 PM	0	0	1	0	2	0	0	1	4
TOTAL VOLUMES :	EB 11	WB 9	EB 12	WB 7	NB 12	SB 15	NB 10	SB 17	TOTAL 93
APPROACH %'s :	55.00%	45.00%	63.16%	36.84%	44.44%	55.56%	37.04%	62.96%	
PEAK HR :	04:45 PM - 05:45 PM								TOTAL
PEAK HR VOL :	7	6	5	3	5	7	6	13	52
PEAK HR FACTOR :	0.875	0.500	0.417	0.250	0.625	0.583	0.500	0.650	0.813
	0.650		0.333		0.600		0.792		

National Data & Surveying Services

Intersection Turning Movement Count

Location: Long Beach Blvd & W 51st St
City: Long Beach
Control: Signalized

Project ID: 21-020034-003
Date: 2/9/2021

Total

NS/EW Streets:	Long Beach Blvd				Long Beach Blvd				W 51st St				W 51st St				
AM	NORTHBOUND				SOUTHBOUND				EASTBOUND				WESTBOUND				TOTAL
	1 NL	2 NT	0 NR	0 NU	0 SL	2 ST	0 SR	0 SU	0 EL	1 ET	0 ER	0 EU	0 WL	0 WT	0 WR	0 WU	
7:00 AM	1	74	0	0	0	127	2	0	2	0	0	0	0	0	0	0	206
7:15 AM	1	97	0	0	0	171	2	0	3	0	2	0	0	0	0	0	276
7:30 AM	5	102	0	0	0	176	3	0	0	0	3	0	0	0	0	0	289
7:45 AM	4	107	0	2	0	245	4	0	1	0	2	0	0	0	0	0	365
8:00 AM	3	91	0	0	0	187	1	1	3	0	5	0	0	0	0	0	291
8:15 AM	1	104	0	0	0	219	3	0	3	0	6	0	0	0	0	0	336
8:30 AM	1	109	0	0	0	177	1	0	3	0	3	0	0	0	0	0	294
8:45 AM	3	97	0	1	0	195	3	0	3	0	3	0	0	0	0	0	305
TOTAL VOLUMES :	NL 19	NT 781	NR 0	NU 3	SL 0	ST 1497	SR 19	SU 1	EL 18	ET 0	ER 24	EU 0	WL 0	WT 0	WR 0	WU 0	TOTAL 2362
APPROACH %'s :	2.37%	97.26%	0.00%	0.37%	0.00%	98.68%	1.25%	0.07%	42.86%	0.00%	57.14%	0.00%					
PEAK HR :	07:45 AM - 08:45 AM																TOTAL
PEAK HR VOL :	9	411	0	2	0	828	9	1	10	0	16	0	0	0	0	0	1286
PEAK HR FACTOR :	0.563	0.943	0.000	0.250	0.000	0.845	0.563	0.250	0.833	0.000	0.667	0.000	0.000	0.000	0.000	0.000	0.881
	0.934				0.841				0.722								
PM	NORTHBOUND				SOUTHBOUND				EASTBOUND				WESTBOUND				TOTAL
	1 NL	2 NT	0 NR	0 NU	0 SL	2 ST	0 SR	0 SU	0 EL	1 ET	0 ER	0 EU	0 WL	0 WT	0 WR	0 WU	
4:00 PM	11	222	0	1	0	211	4	0	1	0	4	0	0	0	0	0	454
4:15 PM	7	229	0	1	0	226	1	0	4	0	0	0	0	0	0	0	468
4:30 PM	2	236	0	0	0	213	6	0	4	0	5	0	0	0	0	0	466
4:45 PM	5	263	0	1	0	203	3	0	1	0	2	0	0	0	0	0	478
5:00 PM	6	224	0	1	0	184	3	2	2	0	3	0	0	0	0	0	425
5:15 PM	6	246	0	1	0	227	4	0	3	0	4	0	0	0	0	0	491
5:30 PM	8	263	0	2	0	215	3	0	7	0	5	0	0	0	0	0	503
5:45 PM	7	207	0	0	0	204	2	0	3	0	5	0	0	0	0	0	428
TOTAL VOLUMES :	NL 52	NT 1890	NR 0	NU 7	SL 0	ST 1683	SR 26	SU 2	EL 25	ET 0	ER 28	EU 0	WL 0	WT 0	WR 0	WU 0	TOTAL 3713
APPROACH %'s :	2.67%	96.97%	0.00%	0.36%	0.00%	98.36%	1.52%	0.12%	47.17%	0.00%	52.83%	0.00%					
PEAK HR :	04:45 PM - 05:45 PM																TOTAL
PEAK HR VOL :	25	996	0	5	0	829	13	2	13	0	14	0	0	0	0	0	1897
PEAK HR FACTOR :	0.781	0.947	0.000	0.625	0.000	0.913	0.813	0.250	0.464	0.000	0.700	0.000	0.000	0.000	0.000	0.000	0.943
	0.940				0.913				0.563								

National Data & Surveying Services

Intersection Turning Movement Count

Location: Long Beach Blvd & W 51st St
City: Long Beach
Control: Signalized

Project ID: 21-020034-003
Date: 2/9/2021

Bikes

NS/EW Streets:	Long Beach Blvd				Long Beach Blvd				W 51st St				W 51st St				
AM	NORTHBOUND				SOUTHBOUND				EASTBOUND				WESTBOUND				TOTAL
	1 NL	2 NT	0 NR	0 NU	0 SL	2 ST	0 SR	0 SU	0 EL	1 ET	0 ER	0 EU	0 WL	0 WT	0 WR	0 WU	
7:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
7:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
7:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
7:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
8:00 AM	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
8:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
8:30 AM	0	0	0	0	0	1	0	0	0	0	0	0	0	0	0	0	1
8:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
TOTAL VOLUMES :	NL 0	NT 1	NR 0	NU 0	SL 0	ST 1	SR 0	SU 0	EL 0	ET 0	ER 0	EU 0	WL 0	WT 0	WR 0	WU 0	TOTAL 2
APPROACH %'s :	0.00%	100.00%	0.00%	0.00%	0.00%	100.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	
PEAK HR :	07:45 AM - 08:45 AM																TOTAL
PEAK HR VOL :	0	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	2
PEAK HR FACTOR :	0.000	0.250	0.000	0.000	0.000	0.250	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.500
	0.250				0.250												
PM	NORTHBOUND				SOUTHBOUND				EASTBOUND				WESTBOUND				TOTAL
	1 NL	2 NT	0 NR	0 NU	0 SL	2 ST	0 SR	0 SU	0 EL	1 ET	0 ER	0 EU	0 WL	0 WT	0 WR	0 WU	
4:00 PM	0	1	0	0	0	0	0	0	1	0	0	0	0	0	0	0	2
4:15 PM	0	0	0	0	0	1	0	0	0	0	0	0	0	0	0	0	1
4:30 PM	0	1	0	0	0	1	0	0	1	0	0	0	0	0	0	0	3
4:45 PM	0	1	0	0	0	0	1	0	0	0	0	0	0	0	0	0	2
5:00 PM	0	3	0	0	0	0	0	0	0	0	0	0	0	0	0	0	3
5:15 PM	0	0	0	0	0	1	2	0	0	0	0	0	0	0	0	0	3
5:30 PM	0	4	0	0	0	2	0	0	0	0	0	0	0	0	0	0	6
5:45 PM	0	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	2
TOTAL VOLUMES :	NL 0	NT 11	NR 0	NU 0	SL 0	ST 6	SR 3	SU 0	EL 2	ET 0	ER 0	EU 0	WL 0	WT 0	WR 0	WU 0	TOTAL 22
APPROACH %'s :	0.00%	100.00%	0.00%	0.00%	0.00%	66.67%	33.33%	0.00%	100.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	
PEAK HR :	04:45 PM - 05:45 PM																TOTAL
PEAK HR VOL :	0	8	0	0	0	3	3	0	0	0	0	0	0	0	0	0	14
PEAK HR FACTOR :	0.00	0.500	0.000	0.000	0.000	0.375	0.375	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.583
	0.500				0.500												

National Data & Surveying Services

Intersection Turning Movement Count

Location: Long Beach Blvd & W 51st St
City: Long Beach

Project ID: 21-020034-003
Date: 2/9/2021

Pedestrians (Crosswalks)

NS/EW Streets:	Long Beach Blvd		Long Beach Blvd		W 51st St		W 51st St		
AM	NORTH LEG		SOUTH LEG		EAST LEG		WEST LEG		TOTAL
	EB	WB	EB	WB	NB	SB	NB	SB	
7:00 AM	3	0	0	0	0	0	3	1	7
7:15 AM	1	1	0	0	0	0	1	2	5
7:30 AM	0	0	0	0	0	0	0	1	1
7:45 AM	0	3	0	0	0	0	0	4	7
8:00 AM	1	2	0	0	0	0	0	1	4
8:15 AM	0	0	0	0	0	0	0	0	0
8:30 AM	0	1	0	0	0	0	0	0	1
8:45 AM	0	0	0	0	0	0	1	0	1
TOTAL VOLUMES :	EB 5	WB 7	EB 0	WB 0	NB 0	SB 0	NB 5	SB 9	TOTAL 26
APPROACH %'s :	41.67%	58.33%					35.71%	64.29%	
PEAK HR :	07:45 AM - 08:45 AM								TOTAL
PEAK HR VOL :	1	6	0	0	0	0	0	5	12
PEAK HR FACTOR :	0.250	0.500						0.313	0.429
	0.583							0.313	

PM	NORTH LEG		SOUTH LEG		EAST LEG		WEST LEG		TOTAL
	EB	WB	EB	WB	NB	SB	NB	SB	
4:00 PM	0	0	0	0	0	0	0	1	1
4:15 PM	0	0	0	0	0	0	1	1	2
4:30 PM	1	0	0	0	0	0	1	2	4
4:45 PM	1	1	0	0	0	0	4	2	8
5:00 PM	1	3	0	0	0	0	1	3	8
5:15 PM	1	0	0	0	0	0	1	0	2
5:30 PM	1	0	0	0	0	0	0	0	1
5:45 PM	0	0	0	0	0	0	1	0	1
TOTAL VOLUMES :	EB 5	WB 4	EB 0	WB 0	NB 0	SB 0	NB 9	SB 9	TOTAL 27
APPROACH %'s :	55.56%	44.44%					50.00%	50.00%	
PEAK HR :	04:45 PM - 05:45 PM								TOTAL
PEAK HR VOL :	4	4	0	0	0	0	6	5	19
PEAK HR FACTOR :	1.000	0.333					0.375	0.417	0.594
	0.500							0.458	

National Data & Surveying Services

Intersection Turning Movement Count

Location: Long Beach Blvd & Del Amo Blvd
 City: Long Beach
 Control: Signalized

Project ID: 18-05307-028
 Date: 5/23/2018

Total

NS/EW Streets:	Long Beach Blvd				Long Beach Blvd				Del Amo Blvd				Del Amo Blvd				
AM	NORTHBOUND				SOUTHBOUND				EASTBOUND				WESTBOUND				TOTAL
	1 NL	2 NT	1 NR	0 NU	1 SL	2 ST	1 SR	0 SU	2 EL	3 ET	1 ER	0 EU	2 WL	3 WT	1 WR	0 WU	
7:00 AM	44	97	13	0	15	115	53	0	23	108	25	2	16	351	40	0	902
7:15 AM	61	93	7	0	16	148	61	0	31	117	39	1	29	355	29	0	987
7:30 AM	55	96	10	0	30	148	59	0	29	142	41	1	16	424	25	0	1076
7:45 AM	72	121	14	0	25	185	77	0	33	121	43	1	36	342	21	0	1091
8:00 AM	54	102	8	0	19	148	63	0	49	174	66	1	34	390	24	0	1132
8:15 AM	70	119	14	0	29	171	52	0	25	146	58	1	22	354	34	0	1095
8:30 AM	79	103	18	0	38	154	33	0	24	207	58	3	43	319	23	0	1102
8:45 AM	63	107	12	0	28	146	46	0	44	153	70	3	23	329	20	0	1044
TOTAL VOLUMES :	NL	NT	NR	NU	SL	ST	SR	SU	EL	ET	ER	EU	WL	WT	WR	WU	TOTAL
APPROACH %'s :	498	838	96	0	200	1215	444	0	258	1168	400	13	219	2864	216	0	8429
	34.78%	58.52%	6.70%	0.00%	10.76%	65.36%	23.88%	0.00%	14.03%	63.51%	21.75%	0.71%	6.64%	86.81%	6.55%	0.00%	
PEAK HR :	07:45 AM - 08:45 AM																TOTAL
PEAK HR VOL :	275	445	54	0	111	658	225	0	131	648	225	6	135	1405	102	0	4420
PEAK HR FACTOR :	0.870	0.919	0.750	0.000	0.730	0.889	0.731	0.000	0.668	0.783	0.852	0.500	0.785	0.901	0.750	0.000	0.976
	0.935				0.866				0.865				0.916				

PM	NORTHBOUND				SOUTHBOUND				EASTBOUND				WESTBOUND				TOTAL
	1 NL	2 NT	1 NR	0 NU	1 SL	2 ST	1 SR	0 SU	2 EL	3 ET	1 ER	0 EU	2 WL	3 WT	1 WR	0 WU	
4:00 PM	45	132	23	0	45	131	30	0	71	393	85	0	15	159	36	0	1165
4:15 PM	49	166	24	0	42	136	31	0	54	358	81	0	38	175	39	1	1194
4:30 PM	44	142	24	0	53	157	29	0	66	412	89	0	27	159	27	1	1230
4:45 PM	45	158	32	0	32	163	36	0	59	364	86	2	41	185	34	0	1237
5:00 PM	52	165	20	0	40	173	31	0	66	417	91	0	29	149	36	0	1269
5:15 PM	50	205	25	0	47	154	28	0	72	401	75	1	41	188	26	0	1313
5:30 PM	58	184	28	0	46	140	31	0	55	433	79	1	30	172	35	0	1292
5:45 PM	50	180	30	0	42	145	31	0	52	389	84	0	31	222	33	0	1289
TOTAL VOLUMES :	NL	NT	NR	NU	SL	ST	SR	SU	EL	ET	ER	EU	WL	WT	WR	WU	TOTAL
APPROACH %'s :	393	1332	206	0	347	1199	247	0	495	3167	670	4	252	1409	266	2	9989
	20.35%	68.98%	10.67%	0.00%	19.35%	66.87%	13.78%	0.00%	11.42%	73.04%	15.45%	0.09%	13.06%	73.04%	13.79%	0.10%	
PEAK HR :	05:00 PM - 06:00 PM																TOTAL
PEAK HR VOL :	210	734	103	0	175	612	121	0	245	1640	329	2	131	731	130	0	5163
PEAK HR FACTOR :	0.905	0.895	0.858	0.000	0.931	0.884	0.976	0.000	0.851	0.947	0.904	0.500	0.799	0.823	0.903	0.000	0.983
	0.935				0.930				0.965				0.867				

APPENDIX C

SUPPLEMENTAL TRIP GENERATION INFORMATION

Single Wash Avg Hourly Volume: San Bernadino June-December 2019

Hour of E..	Event Date Time						
	Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
7	12	16	10	11	12	16	13
8	18	17	17	18	18	22	27
9	27	21	19	20	18	26	33
10	30	21	18	17	19	24	33
11	33	22	19	20	20	24	39
12	33	26	21	21	21	29	40
13	31	24	21	21	23	27	36
14	30	24	20	19	22	26	34
15	29	25	21	21	23	31	31
16	29	25	23	26	24	31	30
17	23	25	26	23	25	30	24
18	20	21	21	24	23	27	22
Grand To..	311	268	233	226	237	309	348

Avg Daily Vol broken down by Event Date Time Weekday vs. Event Date Time Hour. The data is filtered on Site, EventDate Year and EventDate Month. The Site filter keeps San Bernadino. The EventDate Year filter keeps 2019. The EventDate Month filter excludes January, February, March, April and May. The view is filtered on Event Date Time Hour, which keeps 12 members.

Bliss Placentia

	For the Day	For the Day	For the Day	For the Day	Average
	7/5/2019	7/12/2019	7/19/2019	7/26/2019	
	Hourly Washes	Hourly Washes	Hourly Washes	Hourly Washes	
Washes by Hour					
7 AM Wash Count	8	18	17	33	19
8 AM Wash Count	18	20	28	43	27
9 AM Wash Count	29	36	36	51	38
10 AM Wash Count	37	23	34	50	36
11 AM Wash Count	40	31	31	52	39
12 PM Wash Count	39	26	37	45	37
1 PM Wash Count	40	28	25	53	37
2 PM Wash Count	36	29	35	50	38
3 PM Wash Count	36	37	31	47	38
4 PM Wash Count	45	35	35	53	42
5 PM Wash Count	36	31	40	54	40
6 PM Wash Count	16	48	44	48	39
TOTAL	380	362	393	579	429

APPENDIX D

CUMULATIVE PROJECT INFORMATION

TOTAL CUMULATIVE PROJECTS TRAFFIC

- 1 Virginia Avenue at Del Amo Boulevard
- 2 Long Beach Boulevard at Del Amo Boulevard
- 3 Long Beach Boulevard at 51st Street

AM Peak Hour											
NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
0	0	0	0	0	0	0	8	0	0	9	0
1	2	0	0	12	5	2	2	4	0	3	0
0	2	0	0	12	0	0	0	0	0	0	0

- 1 Virginia Avenue at Del Amo Boulevard
- 2 Long Beach Boulevard at Del Amo Boulevard
- 3 Long Beach Boulevard at 51st Street

PM Peak Hour											
NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
0	0	0	0	0	0	0	14	0	0	14	0
4	12	0	0	2	4	5	7	2	0	6	0
0	12	0	0	2	0	0	0	0	0	0	0

Enter only in blue cells Yellow cells calculate

Int. #: 1 Virginia Avenue at Del Amo Boulevard

Mirror distribution? Y Entire Intersection

Mirror distribution?

Zone # 1 North Zone

Pk Hr	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In								10%				
Y	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	10%	0%
AM Out												
PM In	0%	0%	0%	0%	0%	0%	0%	10%	0%		0%	0%
PM Out	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	10%	0%

Zone # 2 5100 Long Beach Blvd

Pk Hr	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In								50%				
Y	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	50%	0%
AM Out												
PM In	0%	0%	0%	0%	0%	0%	0%	50%	0%	0%	0%	0%
PM Out	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	50%	0%

Zone # 3 4800 Long Beach Blvd

Pk Hr	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In												
Y	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
AM Out												
PM In	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
PM Out	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%

Zone # 4 4251 Long Beach Blvd

Pk Hr	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In								20%				
Y	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	20%	0%
AM Out												
PM In	0%	0%	0%	0%	0%	0%	0%	20%	0%	0%	0%	0%
PM Out	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	20%	0%

TOTAL CUMULATIVE PROJECTS TRAFFIC													
Pk Hr		NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In		0	0	0	0	0	0	0	8	0	0	0	0
AM Out		0	0	0	0	0	0	0	0	0	0	9	0
AM Tot		0	0	0	0	0	0	0	8	0	0	9	0
PM In		0	0	0	0	0	0	0	14	0	0	0	0
PM Out		0	0	0	0	0	0	0	0	0	0	14	0
PM Tot		0	0	0	0	0	0	0	14	0	0	14	0

Pk Hr	T Gen	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In	23	0	0	0	0	0	0	0	2	0	0	0	0
AM Out	34	0	0	0	0	0	0	0	0	0	0	3	0
PM In	68	0	0	0	0	0	0	0	7	0	0	0	0
PM Out	62	0	0	0	0	0	0	0	0	0	0	6	0

Pk Hr	T Gen	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In	4	0	0	0	0	0	0	0	2	0	0	0	0
AM Out	10	0	0	0	0	0	0	0	0	0	0	5	0
PM In	10	0	0	0	0	0	0	0	5	0	0	0	0
PM Out	7	0	0	0	0	0	0	0	0	0	0	4	0

Pk Hr	T Gen	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In	2	0	0	0	0	0	0	0	0	0	0	0	0
AM Out	5	0	0	0	0	0	0	0	0	0	0	0	0
PM In	5	0	0	0	0	0	0	0	0	0	0	0	0
PM Out	3	0	0	0	0	0	0	0	0	0	0	0	0

Pk Hr	T Gen	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In	19	0	0	0	0	0	0	0	4	0	0	0	0
AM Out	5	0	0	0	0	0	0	0	0	0	0	1	0
PM In	8	0	0	0	0	0	0	0	2	0	0	0	0
PM Out	21	0	0	0	0	0	0	0	0	0	0	4	0

Int. #: 1 Virginia Avenue at Del Amo Boulevard

Zone # 5 Southwest Zone

Pk Hr	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In												
Y	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
AM Out												
PM In	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
PM Out	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%

Zone # 6 South Zone

Pk Hr	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In												
Y	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
AM Out												
PM In	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
PM Out	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%

Pk Hr	T Gen	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In	269	0	0	0	0	0	0	0	0	0	0	0	0
AM Out	138	0	0	0	0	0	0	0	0	0	0	0	0
PM In	173	0	0	0	0	0	0	0	0	0	0	0	0
PM Out	281	0	0	0	0	0	0	0	0	0	0	0	0

Pk Hr	T Gen	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In	119	0	0	0	0	0	0	0	0	0	0	0	0
AM Out	19	0	0	0	0	0	0	0	0	0	0	0	0
PM In	22	0	0	0	0	0	0	0	0	0	0	0	0
PM Out	116	0	0	0	0	0	0	0	0	0	0	0	0

Enter only in blue cells Yellow cells calculate

Int. #: 2 Long Beach Boulevard at Del Amo Boulevard

Y

Zone # 1 North Zone

Pk Hr	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In								10%				
Y	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	10%	0%
AM Out												
PM In	0%	0%	0%	0%	0%	0%	0%	10%	0%		0%	0%
PM Out	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	10%	0%

Zone # 2 5100 Long Beach Blvd

Pk Hr	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In							50%					
Y	0%	0%	0%	0%	0%	50%	0%	0%	0%	0%	0%	0%
AM Out												
PM In	0%	0%	0%	0%	0%	0%	50%	0%	0%	0%	0%	0%
PM Out	0%	0%	0%	0%	0%	50%	0%	0%	0%	0%	0%	0%

Zone # 3 4800 Long Beach Blvd

Pk Hr	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In												
Y	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
AM Out												
PM In	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
PM Out	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%

Zone # 4 4251 Long Beach Blvd

Pk Hr	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In									20%			
Y	20%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
AM Out												
PM In	0%	0%	0%	0%	0%	0%	0%	0%	20%	0%	0%	0%
PM Out	20%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%

Zone # 5 Southwest Zone

TOTAL CUMULATIVE PROJECTS TRAFFIC													
Pk Hr		NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In		0	0	0	0	12	0	2	2	4	0	0	0
AM Out		1	2	0	0	0	5	0	0	0	0	3	0
AM Tot		1	2	0	0	12	5	2	2	4	0	3	0
PM In		0	0	0	0	2	0	5	7	2	0	0	0
PM Out		4	12	0	0	0	4	0	0	0	0	6	0
PM Tot		4	12	0	0	2	4	5	7	2	0	6	0

Pk Hr	T Gen	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In	23	0	0	0	0	0	0	0	2	0	0	0	0
AM Out	34	0	0	0	0	0	0	0	0	0	0	3	0
PM In	68	0	0	0	0	0	0	0	7	0	0	0	0
PM Out	62	0	0	0	0	0	0	0	0	0	0	6	0

Pk Hr	T Gen	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In	4	0	0	0	0	0	0	2	0	0	0	0	0
AM Out	10	0	0	0	0	0	5	0	0	0	0	0	0
PM In	10	0	0	0	0	0	0	5	0	0	0	0	0
PM Out	7	0	0	0	0	0	4	0	0	0	0	0	0

Pk Hr	T Gen	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In	2	0	0	0	0	0	0	0	0	0	0	0	0
AM Out	5	0	0	0	0	0	0	0	0	0	0	0	0
PM In	5	0	0	0	0	0	0	0	0	0	0	0	0
PM Out	3	0	0	0	0	0	0	0	0	0	0	0	0

Pk Hr	T Gen	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In	19	0	0	0	0	0	0	0	0	4	0	0	0
AM Out	5	1	0	0	0	0	0	0	0	0	0	0	0
PM In	8	0	0	0	0	0	0	0	0	2	0	0	0
PM Out	21	4	0	0	0	0	0	0	0	0	0	0	0

Int. #: 2 Long Beach Boulevard at Del Amo Boulevard

Pk Hr	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In												
Y	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
AM Out												
PM In	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
PM Out	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%

Zone # 6 South Zone

Pk Hr	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In					10%							
Y	0%	10%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
AM Out												
PM In	0%	0%	0%	0%	10%	0%	0%	0%	0%	0%	0%	0%
PM Out	0%	10%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%

Pk Hr	T Gen	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In	269	0	0	0	0	0	0	0	0	0	0	0	0
AM Out	138	0	0	0	0	0	0	0	0	0	0	0	0
PM In	173	0	0	0	0	0	0	0	0	0	0	0	0
PM Out	281	0	0	0	0	0	0	0	0	0	0	0	0

Pk Hr	T Gen	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In	119	0	0	0	0	12	0	0	0	0	0	0	0
AM Out	19	0	2	0	0	0	0	0	0	0	0	0	0
PM In	22	0	0	0	0	2	0	0	0	0	0	0	0
PM Out	116	0	12	0	0	0	0	0	0	0	0	0	0

Int. #: 3 Long Beach Boulevard at 51st Street

Y

TOTAL CUMULATIVE PROJECTS TRAFFIC													
Pk Hr		NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In		0	0	0	0	12	0	0	0	0	0	0	0
AM Out		0	2	0	0	0	0	0	0	0	0	0	0
AM Tot		0	2	0	0	12	0	0	0	0	0	0	0
PM In		0	0	0	0	2	0	0	0	0	0	0	0
PM Out		0	12	0	0	0	0	0	0	0	0	0	0
PM Tot		0	12	0	0	2	0	0	0	0	0	0	0

Zone # 1 North Zone

Pk Hr	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In												
Y	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
AM Out												
PM In	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
PM Out	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%

Pk Hr	T Gen	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In	23	0	0	0	0	0	0	0	0	0	0	0	0
AM Out	34	0	0	0	0	0	0	0	0	0	0	0	0
PM In	68	0	0	0	0	0	0	0	0	0	0	0	0
PM Out	62	0	0	0	0	0	0	0	0	0	0	0	0

Zone # 2 5100 Long Beach Blvd

Pk Hr	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In												
Y	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
AM Out												
PM In	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
PM Out	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%

Pk Hr	T Gen	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In	4	0	0	0	0	0	0	0	0	0	0	0	0
AM Out	10	0	0	0	0	0	0	0	0	0	0	0	0
PM In	10	0	0	0	0	0	0	0	0	0	0	0	0
PM Out	7	0	0	0	0	0	0	0	0	0	0	0	0

Zone # 3 4800 Long Beach Blvd

Pk Hr	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In												
Y	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
AM Out												
PM In	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
PM Out	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%

Pk Hr	T Gen	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In	2	0	0	0	0	0	0	0	0	0	0	0	0
AM Out	5	0	0	0	0	0	0	0	0	0	0	0	0
PM In	5	0	0	0	0	0	0	0	0	0	0	0	0
PM Out	3	0	0	0	0	0	0	0	0	0	0	0	0

Zone # 4 4251 Long Beach Blvd

Pk Hr	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In												
Y	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
AM Out												
PM In	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
PM Out	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%

Pk Hr	T Gen	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In	19	0	0	0	0	0	0	0	0	0	0	0	0
AM Out	5	0	0	0	0	0	0	0	0	0	0	0	0
PM In	8	0	0	0	0	0	0	0	0	0	0	0	0
PM Out	21	0	0	0	0	0	0	0	0	0	0	0	0

Zone # 5 Southwest Zone

Int. #:		3 Long Beach Boulevard at 51st Street										
Pk Hr	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In												
Y	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
AM Out												
PM In	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
PM Out	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%

Zone #	6	South Zone										
--------	---	------------	--	--	--	--	--	--	--	--	--	--

Pk Hr	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In					10%							
Y	0%	10%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%
AM Out												
PM In	0%	0%	0%	0%	10%	0%	0%	0%	0%	0%	0%	0%
PM Out	0%	10%	0%	0%	0%	0%	0%	0%	0%	0%	0%	0%

Pk Hr	T Gen	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In	269	0	0	0	0	0	0	0	0	0	0	0	0
AM Out	138	0	0	0	0	0	0	0	0	0	0	0	0
PM In	173	0	0	0	0	0	0	0	0	0	0	0	0
PM Out	281	0	0	0	0	0	0	0	0	0	0	0	0

Pk Hr	T Gen	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
AM In	119	0	0	0	0	12	0	0	0	0	0	0	0
AM Out	19	0	2	0	0	0	0	0	0	0	0	0	0
PM In	22	0	0	0	0	2	0	0	0	0	0	0	0
PM Out	116	0	12	0	0	0	0	0	0	0	0	0	0

APPENDIX E

INTERSECTION ANALYSIS WORKSHEETS

























HCM 6th TWSC

1: Del Amo Blvd & Virginia Ave

Intersection												
Int Delay, s/veh	2.2											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↰ ↑↑↑			↰ ↑↑↑		↰		↕			↕	
Traffic Vol, veh/h	13	985	15	8	1858	7	12	2	12	3	2	3
Future Vol, veh/h	13	985	15	8	1858	7	12	2	12	3	2	3
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	80	-	-	95	-	40	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	92	92	92	92	92	92	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	14	1071	16	9	2020	8	13	2	13	3	2	3
Major/Minor	Major1			Major2			Minor1			Minor2		
Conflicting Flow All	2028	0	0	1087	0	0	1934	3153	544	2495	3153	1010
Stage 1	-	-	-	-	-	-	1107	1107	-	2038	2038	-
Stage 2	-	-	-	-	-	-	827	2046	-	457	1115	-
Critical Hdwy	5.34	-	-	5.34	-	-	6.44	6.54	7.14	6.44	6.54	7.14
Critical Hdwy Stg 1	-	-	-	-	-	-	7.34	5.54	-	7.34	5.54	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.74	5.54	-	6.74	5.54	-
Follow-up Hdwy	3.12	-	-	3.12	-	-	3.82	4.02	3.92	3.82	4.02	3.92
Pot Cap-1 Maneuver	121	-	-	355	-	-	70	11	414	31	11	204
Stage 1	-	-	-	-	-	-	168	284	-	36	99	-
Stage 2	-	-	-	-	-	-	301	98	-	505	282	-
Platoon blocked, %		-	-		-	-						
Mov Cap-1 Maneuver	121	-	-	355	-	-	50	9	414	22	9	204
Mov Cap-2 Maneuver	-	-	-	-	-	-	50	9	-	22	9	-
Stage 1	-	-	-	-	-	-	149	251	-	32	97	-
Stage 2	-	-	-	-	-	-	282	96	-	429	249	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	0.5			0.1			133.2			266.7		
HCM LOS							F			F		
Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1				
Capacity (veh/h)	53	121	-	-	355	-	-	21				
HCM Lane V/C Ratio	0.533	0.117	-	-	0.024	-	-	0.414				
HCM Control Delay (s)	133.2	38.6	-	-	15.4	-	-	266.7				
HCM Lane LOS	F	E	-	-	C	-	-	F				
HCM 95th %tile Q(veh)	2.1	0.4	-	-	0.1	-	-	1.2				

HCM 6th Signalized Intersection Summary

2: Del Amo Blvd & Long Beach Blvd

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	153	604	261	147	1239	127	274	427	56	112	992	267
Future Volume (veh/h)	153	604	261	147	1239	127	274	427	56	112	992	267
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	166	657	284	160	1347	138	298	464	61	122	1078	290
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	2	2	2
Cap, veh/h	198	1397	434	215	1422	441	319	1523	679	149	1185	528
Arrive On Green	0.06	0.27	0.27	0.06	0.28	0.28	0.18	0.43	0.43	0.08	0.33	0.33
Sat Flow, veh/h	3456	5106	1585	3456	5106	1585	1781	3554	1585	1781	3554	1585
Grp Volume(v), veh/h	166	657	284	160	1347	138	298	464	61	122	1078	290
Grp Sat Flow(s),veh/h/ln	1728	1702	1585	1728	1702	1585	1781	1777	1585	1781	1777	1585
Q Serve(g_s), s	5.6	12.7	18.8	5.4	30.6	8.2	19.5	10.2	2.7	8.0	34.4	17.7
Cycle Q Clear(g_c), s	5.6	12.7	18.8	5.4	30.6	8.2	19.5	10.2	2.7	8.0	34.4	17.7
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	198	1397	434	215	1422	441	319	1523	679	149	1185	528
V/C Ratio(X)	0.84	0.47	0.65	0.74	0.95	0.31	0.94	0.30	0.09	0.82	0.91	0.55
Avail Cap(c_a), veh/h	198	1397	434	233	1422	441	319	1523	679	238	1230	548
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	55.3	35.9	38.1	54.6	41.9	33.8	48.0	22.3	20.1	53.4	37.8	32.2
Incr Delay (d2), s/veh	25.7	1.1	7.5	11.2	14.2	1.8	33.9	0.1	0.1	11.3	10.0	1.1
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	3.1	5.3	8.1	2.6	14.3	3.3	11.5	4.2	1.0	4.0	16.2	6.8
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	81.0	37.0	45.6	65.8	56.1	35.6	81.8	22.4	20.2	64.7	47.8	33.3
LnGrp LOS	F	D	D	E	E	D	F	C	C	E	D	C
Approach Vol, veh/h		1107			1645			823			1490	
Approach Delay, s/veh		45.8			55.3			43.7			46.3	
Approach LOS		D			E			D			D	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	11.9	36.9	25.7	44.0	11.3	37.5	14.4	55.3				
Change Period (Y+Rc), s	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5				
Max Green Setting (Gmax), s	8.0	31.8	21.2	41.0	6.8	33.0	15.8	46.4				
Max Q Clear Time (g_c+I1), s	7.4	20.8	21.5	36.4	7.6	32.6	10.0	12.2				
Green Ext Time (p_c), s	0.0	4.0	0.0	3.1	0.0	0.3	0.1	3.4				
Intersection Summary												
HCM 6th Ctrl Delay			48.7									
HCM 6th LOS			D									

HCM 6th Signalized Intersection Summary

3: Long Beach Blvd & 51st St



Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	YY		Y	↑↑	↑↑	
Traffic Volume (veh/h)	17	26	18	678	1366	15
Future Volume (veh/h)	17	26	18	678	1366	15
Initial Q (Qb), veh	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00	1.00	1.00			1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No	No	
Adj Sat Flow, veh/h/ln	1900	1900	1870	1870	1870	1870
Adj Flow Rate, veh/h	18	28	20	737	1485	16
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	0	0	2	2	2	2
Cap, veh/h	28	43	352	2912	2951	32
Arrive On Green	0.04	0.04	0.82	0.82	0.82	0.82
Sat Flow, veh/h	636	989	350	3647	3695	39
Grp Volume(v), veh/h	47	0	20	737	732	769
Grp Sat Flow(s), veh/h/ln	661	0	350	1777	1777	1863
Q Serve(g_s), s	1.8	0.0	1.2	3.1	8.3	8.3
Cycle Q Clear(g_c), s	1.8	0.0	9.6	3.1	8.3	8.3
Prop In Lane	0.38	0.60	1.00			0.02
Lane Grp Cap(c), veh/h	73	0	352	2912	1456	1527
V/C Ratio(X)	0.65	0.00	0.06	0.25	0.50	0.50
Avail Cap(c_a), veh/h	684	0	352	2912	1456	1527
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	0.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	30.9	0.0	3.3	1.4	1.8	1.8
Incr Delay (d2), s/veh	9.2	0.0	0.3	0.2	0.3	0.3
Initial Q Delay(d3), s/veh	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%), veh/ln	0.9	0.0	0.1	0.3	0.6	0.6
Unsig. Movement Delay, s/veh						
LnGrp Delay(d), s/veh	40.2	0.0	3.6	1.6	2.1	2.1
LnGrp LOS	D	A	A	A	A	A
Approach Vol, veh/h	47			757	1501	
Approach Delay, s/veh	40.2			1.6	2.1	
Approach LOS	D			A	A	
Timer - Assigned Phs	2			4		6
Phs Duration (G+Y+Rc), s	58.4			7.4		58.4
Change Period (Y+Rc), s	4.5			4.5		4.5
Max Green Setting (Gmax), s	53.9			27.1		53.9
Max Q Clear Time (g_c+l1), s	11.6			3.8		10.3
Green Ext Time (p_c), s	6.6			0.1		15.9

Intersection Summary

HCM 6th Ctrl Delay	2.7
HCM 6th LOS	A

Notes

User approved volume balancing among the lanes for turning movement.

























HCM 6th TWSC

1: Del Amo Blvd & Virginia Ave

Intersection												
Int Delay, s/veh	2.2											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↱ ↑↑↑			↱ ↑↑↑		↱		↕			↕	
Traffic Vol, veh/h	18	2179	19	21	1106	13	6	0	23	0	0	8
Future Vol, veh/h	18	2179	19	21	1106	13	6	0	23	0	0	8
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	80	-	-	95	-	40	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	92	92	92	92	92	92	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	20	2368	21	23	1202	14	7	0	25	0	0	9
Major/Minor	Major1			Major2			Minor1			Minor2		
Conflicting Flow All	1216	0	0	2389	0	0	2946	3681	1195	2235	3677	601
Stage 1	-	-	-	-	-	-	2419	2419	-	1248	1248	-
Stage 2	-	-	-	-	-	-	527	1262	-	987	2429	-
Critical Hdwy	5.34	-	-	5.34	-	-	6.44	6.54	7.14	6.44	6.54	7.14
Critical Hdwy Stg 1	-	-	-	-	-	-	7.34	5.54	-	7.34	5.54	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.74	5.54	-	6.74	5.54	-
Follow-up Hdwy	3.12	-	-	3.12	-	-	3.82	4.02	3.92	3.82	4.02	3.92
Pot Cap-1 Maneuver	307	-	-	79	-	-	16	5	153	45	5	380
Stage 1	-	-	-	-	-	-	19	63	-	133	243	-
Stage 2	-	-	-	-	-	-	459	239	-	240	62	-
Platoon blocked, %		-	-		-	-						
Mov Cap-1 Maneuver	307	-	-	79	-	-	12	3	153	28	3	380
Mov Cap-2 Maneuver	-	-	-	-	-	-	12	3	-	28	3	-
Stage 1	-	-	-	-	-	-	18	59	-	124	172	-
Stage 2	-	-	-	-	-	-	318	169	-	188	58	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	0.1			1.3			190.1			14.7		
HCM LOS							F			B		
Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1				
Capacity (veh/h)	45	307	-	-	79	-	-	380				
HCM Lane V/C Ratio	0.7	0.064	-	-	0.289	-	-	0.023				
HCM Control Delay (s)	190.1	17.5	-	-	68.1	-	-	14.7				
HCM Lane LOS	F	C	-	-	F	-	-	B				
HCM 95th %tile Q(veh)	2.7	0.2	-	-	1.1	-	-	0.1				

HCM 6th Signalized Intersection Summary

2: Del Amo Blvd & Long Beach Blvd

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	268	1561	339	139	715	161	273	853	153	174	709	119
Future Volume (veh/h)	268	1561	339	139	715	161	273	853	153	174	709	119
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No			No			No		
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	291	1697	368	151	777	175	297	927	166	189	771	129
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	2	2	2
Cap, veh/h	301	1778	552	174	1590	494	286	1113	496	220	982	438
Arrive On Green	0.09	0.35	0.35	0.05	0.31	0.31	0.16	0.31	0.31	0.12	0.28	0.28
Sat Flow, veh/h	3456	5106	1585	3456	5106	1585	1781	3554	1585	1781	3554	1585
Grp Volume(v), veh/h	291	1697	368	151	777	175	297	927	166	189	771	129
Grp Sat Flow(s),veh/h/ln	1728	1702	1585	1728	1702	1585	1781	1777	1585	1781	1777	1585
Q Serve(g_s), s	9.2	35.4	21.5	4.7	13.5	9.3	17.5	26.5	8.8	11.4	21.9	7.0
Cycle Q Clear(g_c), s	9.2	35.4	21.5	4.7	13.5	9.3	17.5	26.5	8.8	11.4	21.9	7.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	301	1778	552	174	1590	494	286	1113	496	220	982	438
V/C Ratio(X)	0.97	0.95	0.67	0.87	0.49	0.35	1.04	0.83	0.33	0.86	0.79	0.29
Avail Cap(c_a), veh/h	301	1778	552	174	1590	494	286	1361	607	273	1335	595
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	49.7	34.7	30.2	51.5	30.5	29.1	45.8	34.8	28.8	46.9	36.5	31.1
Incr Delay (d2), s/veh	43.0	13.0	6.3	34.0	1.1	2.0	64.0	3.8	0.4	19.9	2.2	0.4
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	5.7	16.0	8.9	2.8	5.5	3.8	12.7	11.7	3.3	6.2	9.6	2.7
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	92.6	47.8	36.5	85.5	31.6	31.1	109.9	38.7	29.1	66.8	38.7	31.5
LnGrp LOS	F	D	D	F	C	C	F	D	C	E	D	C
Approach Vol, veh/h	2356			1103			1390			1089		
Approach Delay, s/veh	51.5			38.9			52.7			42.7		
Approach LOS	D			D			D			D		
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	10.0	42.5	22.0	34.7	14.0	38.5	18.0	38.7				
Change Period (Y+Rc), s	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5				
Max Green Setting (Gmax), s	5.5	38.0	17.5	41.0	9.5	34.0	16.7	41.8				
Max Q Clear Time (g_c+I1), s	6.7	37.4	19.5	23.9	11.2	15.5	13.4	28.5				
Green Ext Time (p_c), s	0.0	0.5	0.0	5.3	0.0	5.5	0.2	5.7				
Intersection Summary												
HCM 6th Ctrl Delay	47.9											
HCM 6th LOS	D											

HCM 6th Signalized Intersection Summary

3: Long Beach Blvd & 51st St



Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	Y		Y	↑↑	↑↑	
Traffic Volume (veh/h)	16	18	38	1245	1036	16
Future Volume (veh/h)	16	18	38	1245	1036	16
Initial Q (Qb), veh	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00	1.00	1.00			1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No	No	
Adj Sat Flow, veh/h/ln	1900	1900	1870	1870	1870	1870
Adj Flow Rate, veh/h	17	20	41	1353	1126	17
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	0	0	2	2	2	2
Cap, veh/h	29	34	476	2930	2954	45
Arrive On Green	0.04	0.04	0.82	0.82	0.82	0.82
Sat Flow, veh/h	749	881	492	3647	3677	54
Grp Volume(v), veh/h	38	0	41	1353	558	585
Grp Sat Flow(s),veh/h/ln	674	0	492	1777	1777	1861
Q Serve(g_s), s	1.5	0.0	1.5	7.1	5.3	5.3
Cycle Q Clear(g_c), s	1.5	0.0	6.8	7.1	5.3	5.3
Prop In Lane	0.45	0.53	1.00			0.03
Lane Grp Cap(c), veh/h	64	0	476	2930	1465	1534
V/C Ratio(X)	0.60	0.00	0.09	0.46	0.38	0.38
Avail Cap(c_a), veh/h	690	0	476	2930	1465	1534
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	0.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	31.0	0.0	2.3	1.6	1.5	1.5
Incr Delay (d2), s/veh	8.6	0.0	0.4	0.5	0.2	0.2
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.7	0.0	0.1	0.5	0.3	0.3
Unsig. Movement Delay, s/veh						
LnGrp Delay(d),s/veh	39.6	0.0	2.7	2.2	1.6	1.6
LnGrp LOS	D	A	A	A	A	A
Approach Vol, veh/h	38			1394	1143	
Approach Delay, s/veh	39.6			2.2	1.6	
Approach LOS	D			A	A	
Timer - Assigned Phs	2			4		6
Phs Duration (G+Y+Rc), s	58.5			7.0		58.5
Change Period (Y+Rc), s	4.5			4.5		4.5
Max Green Setting (Gmax), s	54.0			27.0		54.0
Max Q Clear Time (g_c+I1), s	9.1			3.5		7.3
Green Ext Time (p_c), s	15.8			0.1		10.1
Intersection Summary						
HCM 6th Ctrl Delay			2.5			
HCM 6th LOS			A			
Notes						
User approved volume balancing among the lanes for turning movement.						

























HCM 6th TWSC

1: Del Amo Blvd & Virginia Ave

Intersection												
Int Delay, s/veh	2.2											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↱ ↱↱↱			↱ ↱↱↱		↱		↕			↕	
Traffic Vol, veh/h	13	1008	15	8	1895	7	12	2	12	3	2	3
Future Vol, veh/h	13	1008	15	8	1895	7	12	2	12	3	2	3
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	80	-	-	95	-	40	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	92	92	92	92	92	92	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	14	1096	16	9	2060	8	13	2	13	3	2	3
Major/Minor	Major1			Major2			Minor1			Minor2		
Conflicting Flow All	2068	0	0	1112	0	0	1975	3218	556	2545	3218	1030
Stage 1	-	-	-	-	-	-	1132	1132	-	2078	2078	-
Stage 2	-	-	-	-	-	-	843	2086	-	467	1140	-
Critical Hdwy	5.34	-	-	5.34	-	-	6.44	6.54	7.14	6.44	6.54	7.14
Critical Hdwy Stg 1	-	-	-	-	-	-	7.34	5.54	-	7.34	5.54	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.74	5.54	-	6.74	5.54	-
Follow-up Hdwy	3.12	-	-	3.12	-	-	3.82	4.02	3.92	3.82	4.02	3.92
Pot Cap-1 Maneuver	115	-	-	345	-	-	66	10	406	29	10	198
Stage 1	-	-	-	-	-	-	161	276	-	34	94	-
Stage 2	-	-	-	-	-	-	294	93	-	499	274	-
Platoon blocked, %		-	-		-	-						
Mov Cap-1 Maneuver	115	-	-	345	-	-	47	9	406	20	9	198
Mov Cap-2 Maneuver	-	-	-	-	-	-	47	9	-	20	9	-
Stage 1	-	-	-	-	-	-	141	242	-	30	92	-
Stage 2	-	-	-	-	-	-	275	91	-	420	241	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	0.5			0.1			141.6			266.7		
HCM LOS							F			F		
Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1				
Capacity (veh/h)	51	115	-	-	345	-	-	21				
HCM Lane V/C Ratio	0.554	0.123	-	-	0.025	-	-	0.414				
HCM Control Delay (s)	141.6	40.6	-	-	15.7	-	-	266.7				
HCM Lane LOS	F	E	-	-	C	-	-	F				
HCM 95th %tile Q(veh)	2.1	0.4	-	-	0.1	-	-	1.2				

HCM 6th Signalized Intersection Summary

2: Del Amo Blvd & Long Beach Blvd

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	157	615	269	149	1261	129	279	435	57	114	1019	276
Future Volume (veh/h)	157	615	269	149	1261	129	279	435	57	114	1019	276
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	171	668	292	162	1371	140	303	473	62	124	1108	300
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	2	2	2
Cap, veh/h	194	1445	449	197	1449	450	307	1506	672	151	1196	534
Arrive On Green	0.06	0.28	0.28	0.06	0.28	0.28	0.17	0.42	0.42	0.08	0.34	0.34
Sat Flow, veh/h	3456	5106	1585	3456	5106	1585	1781	3554	1585	1781	3554	1585
Grp Volume(v), veh/h	171	668	292	162	1371	140	303	473	62	124	1108	300
Grp Sat Flow(s),veh/h/ln	1728	1702	1585	1728	1702	1585	1781	1777	1585	1781	1777	1585
Q Serve(g_s), s	5.9	12.9	19.3	5.5	31.3	8.3	20.2	10.5	2.8	8.2	35.8	18.4
Cycle Q Clear(g_c), s	5.9	12.9	19.3	5.5	31.3	8.3	20.2	10.5	2.8	8.2	35.8	18.4
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	194	1445	449	197	1449	450	307	1506	672	151	1196	534
V/C Ratio(X)	0.88	0.46	0.65	0.82	0.95	0.31	0.99	0.31	0.09	0.82	0.93	0.56
Avail Cap(c_a), veh/h	194	1445	449	197	1449	450	307	1506	672	238	1223	546
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	55.8	35.2	37.5	55.5	41.8	33.5	49.2	22.8	20.6	53.6	38.1	32.3
Incr Delay (d2), s/veh	33.8	1.1	7.2	23.3	13.9	1.8	48.0	0.1	0.1	11.8	11.9	1.3
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	3.4	5.4	8.3	3.0	14.6	3.4	13.0	4.4	1.0	4.1	17.1	7.2
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	89.6	36.3	44.7	78.9	55.6	35.3	97.2	22.9	20.6	65.4	49.9	33.6
LnGrp LOS	F	D	D	E	E	D	F	C	C	E	D	C
Approach Vol, veh/h		1131			1673			838			1532	
Approach Delay, s/veh		46.5			56.2			49.6			48.0	
Approach LOS		D			E			D			D	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	11.3	38.2	25.0	44.6	11.2	38.3	14.6	55.0				
Change Period (Y+Rc), s	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5				
Max Green Setting (Gmax), s	6.8	33.7	20.5	41.0	6.7	33.8	15.9	45.6				
Max Q Clear Time (g_c+I1), s	7.5	21.3	22.2	37.8	7.9	33.3	10.2	12.5				
Green Ext Time (p_c), s	0.0	4.3	0.0	2.3	0.0	0.4	0.1	3.5				
Intersection Summary												
HCM 6th Ctrl Delay			50.6									
HCM 6th LOS			D									

HCM 6th Signalized Intersection Summary

3: Long Beach Blvd & 51st St



Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	Y		Y	↑↑	↑↑	
Traffic Volume (veh/h)	17	26	18	690	1398	15
Future Volume (veh/h)	17	26	18	690	1398	15
Initial Q (Qb), veh	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00	1.00	1.00			1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No	No	
Adj Sat Flow, veh/h/ln	1900	1900	1870	1870	1870	1870
Adj Flow Rate, veh/h	18	28	20	750	1520	16
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	0	0	2	2	2	2
Cap, veh/h	28	43	342	2912	2952	31
Arrive On Green	0.04	0.04	0.82	0.82	0.82	0.82
Sat Flow, veh/h	636	989	338	3647	3696	38
Grp Volume(v), veh/h	47	0	20	750	749	787
Grp Sat Flow(s), veh/h/ln	661	0	338	1777	1777	1864
Q Serve(g_s), s	1.8	0.0	1.3	3.2	8.7	8.7
Cycle Q Clear(g_c), s	1.8	0.0	10.0	3.2	8.7	8.7
Prop In Lane	0.38	0.60	1.00			0.02
Lane Grp Cap(c), veh/h	73	0	342	2912	1456	1527
V/C Ratio(X)	0.65	0.00	0.06	0.26	0.51	0.52
Avail Cap(c_a), veh/h	684	0	342	2912	1456	1527
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(l)	1.00	0.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	30.9	0.0	3.4	1.4	1.9	1.9
Incr Delay (d2), s/veh	9.2	0.0	0.3	0.2	0.3	0.3
Initial Q Delay(d3), s/veh	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%), veh/ln	0.9	0.0	0.1	0.3	0.6	0.7
Unsig. Movement Delay, s/veh						
LnGrp Delay(d), s/veh	40.2	0.0	3.7	1.6	2.2	2.2
LnGrp LOS	D	A	A	A	A	A
Approach Vol, veh/h	47			770	1536	
Approach Delay, s/veh	40.2			1.6	2.2	
Approach LOS	D			A	A	
Timer - Assigned Phs	2			4		6
Phs Duration (G+Y+Rc), s	58.4			7.4		58.4
Change Period (Y+Rc), s	4.5			4.5		4.5
Max Green Setting (Gmax), s	53.9			27.1		53.9
Max Q Clear Time (g_c+l1), s	12.0			3.8		10.7
Green Ext Time (p_c), s		6.8		0.1		16.6

Intersection Summary

HCM 6th Ctrl Delay	2.7
HCM 6th LOS	A

Notes

























User approved volume balancing among the lanes for turning movement.

HCM 6th TWSC
1: Del Amo Blvd & Virginia Ave

Intersection												
Int Delay, s/veh	2.7											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↱ ↑↑↑			↱ ↑↑↑		↱		↕			↕	
Traffic Vol, veh/h	18	2226	19	21	1137	13	6	0	23	0	0	8
Future Vol, veh/h	18	2226	19	21	1137	13	6	0	23	0	0	8
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	80	-	-	95	-	40	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	92	92	92	92	92	92	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	20	2420	21	23	1236	14	7	0	25	0	0	9
Major/Minor	Major1			Major2			Minor1			Minor2		
Conflicting Flow All	1250	0	0	2441	0	0	3011	3767	1221	2290	3763	618
Stage 1	-	-	-	-	-	-	2471	2471	-	1282	1282	-
Stage 2	-	-	-	-	-	-	540	1296	-	1008	2481	-
Critical Hdwy	5.34	-	-	5.34	-	-	6.44	6.54	7.14	6.44	6.54	7.14
Critical Hdwy Stg 1	-	-	-	-	-	-	7.34	5.54	-	7.34	5.54	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.74	5.54	-	6.74	5.54	-
Follow-up Hdwy	3.12	-	-	3.12	-	-	3.82	4.02	3.92	3.82	4.02	3.92
Pot Cap-1 Maneuver	296	-	-	74	-	-	14	4	147	42	4	370
Stage 1	-	-	-	-	-	-	17	59	-	126	234	-
Stage 2	-	-	-	-	-	-	450	231	-	232	58	-
Platoon blocked, %		-	-		-	-						
Mov Cap-1 Maneuver	296	-	-	74	-	-	10	3	147	25	3	370
Mov Cap-2 Maneuver	-	-	-	-	-	-	10	3	-	25	3	-
Stage 1	-	-	-	-	-	-	16	55	-	117	161	-
Stage 2	-	-	-	-	-	-	303	159	-	180	54	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	0.1			1.3			253.3			15		
HCM LOS							F			C		
Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1				
Capacity (veh/h)	38	296	-	-	74	-	-	370				
HCM Lane V/C Ratio	0.83	0.066	-	-	0.308	-	-	0.024				
HCM Control Delay (s)	253.3	18	-	-	74	-	-	15				
HCM Lane LOS	F	C	-	-	F	-	-	C				
HCM 95th %tile Q(veh)	3.1	0.2	-	-	1.1	-	-	0.1				

HCM 6th Signalized Intersection Summary

2: Del Amo Blvd & Long Beach Blvd

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	277	1591	346	141	732	163	281	878	155	177	722	125
Future Volume (veh/h)	277	1591	346	141	732	163	281	878	155	177	722	125
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	301	1729	376	153	796	177	305	954	168	192	785	136
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	2	2	2
Cap, veh/h	329	1757	545	172	1526	474	282	1131	504	222	1012	451
Arrive On Green	0.10	0.34	0.34	0.05	0.30	0.30	0.16	0.32	0.32	0.12	0.28	0.28
Sat Flow, veh/h	3456	5106	1585	3456	5106	1585	1781	3554	1585	1781	3554	1585
Grp Volume(v), veh/h	301	1729	376	153	796	177	305	954	168	192	785	136
Grp Sat Flow(s),veh/h/ln	1728	1702	1585	1728	1702	1585	1781	1777	1585	1781	1777	1585
Q Serve(g_s), s	9.5	37.1	22.5	4.9	14.3	9.7	17.5	27.6	8.9	11.7	22.4	7.4
Cycle Q Clear(g_c), s	9.5	37.1	22.5	4.9	14.3	9.7	17.5	27.6	8.9	11.7	22.4	7.4
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	329	1757	545	172	1526	474	282	1131	504	222	1012	451
V/C Ratio(X)	0.92	0.98	0.69	0.89	0.52	0.37	1.08	0.84	0.33	0.86	0.78	0.30
Avail Cap(c_a), veh/h	329	1757	545	172	1526	474	282	1339	597	273	1319	588
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	49.5	35.9	31.1	52.2	32.2	30.6	46.5	35.1	28.7	47.4	36.3	30.9
Incr Delay (d2), s/veh	29.3	18.0	7.0	38.9	1.3	2.3	76.7	4.4	0.4	20.5	2.2	0.4
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	5.4	17.5	9.4	3.0	5.9	4.0	13.6	12.3	3.4	6.4	9.8	2.8
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	78.8	54.0	38.1	91.1	33.4	32.8	123.2	39.5	29.1	67.9	38.5	31.3
LnGrp LOS	E	D	D	F	C	C	F	D	C	E	D	C
Approach Vol, veh/h		2406			1126			1427			1113	
Approach Delay, s/veh		54.6			41.2			56.2			42.7	
Approach LOS		D			D			E			D	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	10.0	42.5	22.0	35.9	15.0	37.5	18.3	39.7				
Change Period (Y+Rc), s	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5				
Max Green Setting (Gmax), s	5.5	38.0	17.5	41.0	10.5	33.0	16.9	41.6				
Max Q Clear Time (g_c+l1), s	6.9	39.1	19.5	24.4	11.5	16.3	13.7	29.6				
Green Ext Time (p_c), s	0.0	0.0	0.0	5.3	0.0	5.4	0.2	5.5				
Intersection Summary												
HCM 6th Ctrl Delay			50.3									
HCM 6th LOS			D									

HCM 6th Signalized Intersection Summary

3: Long Beach Blvd & 51st St



Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	Y		Y	↑↑	↑↑	
Traffic Volume (veh/h)	16	18	39	1276	1054	16
Future Volume (veh/h)	16	18	39	1276	1054	16
Initial Q (Qb), veh	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00	1.00	1.00			1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No	No	
Adj Sat Flow, veh/h/ln	1900	1900	1870	1870	1870	1870
Adj Flow Rate, veh/h	17	20	42	1387	1146	17
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	0	0	2	2	2	2
Cap, veh/h	29	34	468	2930	2955	44
Arrive On Green	0.04	0.04	0.82	0.82	0.82	0.82
Sat Flow, veh/h	749	881	483	3647	3678	53
Grp Volume(v), veh/h	38	0	42	1387	568	595
Grp Sat Flow(s),veh/h/ln	674	0	483	1777	1777	1861
Q Serve(g_s), s	1.5	0.0	1.6	7.4	5.4	5.4
Cycle Q Clear(g_c), s	1.5	0.0	7.0	7.4	5.4	5.4
Prop In Lane	0.45	0.53	1.00			0.03
Lane Grp Cap(c), veh/h	64	0	468	2930	1465	1534
V/C Ratio(X)	0.60	0.00	0.09	0.47	0.39	0.39
Avail Cap(c_a), veh/h	690	0	468	2930	1465	1534
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(l)	1.00	0.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	31.0	0.0	2.4	1.7	1.5	1.5
Incr Delay (d2), s/veh	8.6	0.0	0.4	0.6	0.2	0.2
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.7	0.0	0.1	0.6	0.3	0.3
Unsig. Movement Delay, s/veh						
LnGrp Delay(d),s/veh	39.6	0.0	2.8	2.2	1.7	1.6
LnGrp LOS	D	A	A	A	A	A
Approach Vol, veh/h	38			1429	1163	
Approach Delay, s/veh	39.6			2.2	1.6	
Approach LOS	D			A	A	
Timer - Assigned Phs	2			4		6
Phs Duration (G+Y+Rc), s	58.5			7.0		58.5
Change Period (Y+Rc), s	4.5			4.5		4.5
Max Green Setting (Gmax), s	54.0			27.0		54.0
Max Q Clear Time (g_c+l1), s	9.4			3.5		7.4
Green Ext Time (p_c), s	16.4			0.1		10.4
Intersection Summary						
HCM 6th Ctrl Delay			2.5			
HCM 6th LOS			A			

Notes

























User approved volume balancing among the lanes for turning movement.

HCM 6th TWSC
1: Del Amo Blvd & Virginia Ave

Intersection												
Int Delay, s/veh	3.1											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↰ ↱ ↲ ↳			↰ ↱ ↲ ↳		↰		↰ ↱			↰ ↱	
Traffic Vol, veh/h	13	1016	15	32	1903	7	12	2	12	3	2	3
Future Vol, veh/h	13	1016	15	32	1903	7	12	2	12	3	2	3
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	80	-	-	95	-	40	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	92	92	92	92	92	92	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	14	1104	16	35	2068	8	13	2	13	3	2	3
Major/Minor	Major1			Major2			Minor1			Minor2		
Conflicting Flow All	2076	0	0	1120	0	0	2038	3286	560	2609	3286	1034
Stage 1	-	-	-	-	-	-	1140	1140	-	2138	2138	-
Stage 2	-	-	-	-	-	-	898	2146	-	471	1148	-
Critical Hdwy	5.34	-	-	5.34	-	-	6.44	6.54	7.14	6.44	6.54	7.14
Critical Hdwy Stg 1	-	-	-	-	-	-	7.34	5.54	-	7.34	5.54	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.74	5.54	-	6.74	5.54	-
Follow-up Hdwy	3.12	-	-	3.12	-	-	3.82	4.02	3.92	3.82	4.02	3.92
Pot Cap-1 Maneuver	114	-	-	342	-	-	60	9	404	26	9	197
Stage 1	-	-	-	-	-	-	159	274	-	30	88	-
Stage 2	-	-	-	-	-	-	272	87	-	496	272	-
Platoon blocked, %		-	-		-	-						
Mov Cap-1 Maneuver	114	-	-	342	-	-	38	7	404	16	7	197
Mov Cap-2 Maneuver	-	-	-	-	-	-	38	7	-	16	7	-
Stage 1	-	-	-	-	-	-	139	240	-	26	79	-
Stage 2	-	-	-	-	-	-	234	78	-	417	239	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	0.5			0.3			202.1			\$ 383.4		
HCM LOS							F			F		
Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1				
Capacity (veh/h)	41	114	-	-	342	-	-	16				
HCM Lane V/C Ratio	0.689	0.124	-	-	0.102	-	-	0.543				
HCM Control Delay (s)	202.1	41	-	-	16.7	-	-	\$ 383.4				
HCM Lane LOS	F	E	-	-	C	-	-	F				
HCM 95th %tile Q(veh)	2.6	0.4	-	-	0.3	-	-	1.4				
Notes												
~: Volume exceeds capacity		\$: Delay exceeds 300s			+: Computation Not Defined				*: All major volume in platoon			

HCM 6th Signalized Intersection Summary

2: Del Amo Blvd & Long Beach Blvd

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	173	623	277	149	1269	129	287	435	57	114	1019	276
Future Volume (veh/h)	173	623	277	149	1269	129	287	435	57	114	1019	276
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	188	677	301	162	1379	140	312	473	62	124	1108	300
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	2	2	2
Cap, veh/h	194	1445	449	197	1449	450	307	1506	672	151	1196	534
Arrive On Green	0.06	0.28	0.28	0.06	0.28	0.28	0.17	0.42	0.42	0.08	0.34	0.34
Sat Flow, veh/h	3456	5106	1585	3456	5106	1585	1781	3554	1585	1781	3554	1585
Grp Volume(v), veh/h	188	677	301	162	1379	140	312	473	62	124	1108	300
Grp Sat Flow(s),veh/h/ln	1728	1702	1585	1728	1702	1585	1781	1777	1585	1781	1777	1585
Q Serve(g_s), s	6.5	13.1	20.0	5.5	31.6	8.3	20.5	10.5	2.8	8.2	35.8	18.4
Cycle Q Clear(g_c), s	6.5	13.1	20.0	5.5	31.6	8.3	20.5	10.5	2.8	8.2	35.8	18.4
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	194	1445	449	197	1449	450	307	1506	672	151	1196	534
V/C Ratio(X)	0.97	0.47	0.67	0.82	0.95	0.31	1.02	0.31	0.09	0.82	0.93	0.56
Avail Cap(c_a), veh/h	194	1445	449	197	1449	450	307	1506	672	238	1223	546
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	56.1	35.3	37.8	55.5	41.8	33.5	49.3	22.8	20.6	53.6	38.1	32.3
Incr Delay (d2), s/veh	54.8	1.1	7.8	23.3	14.6	1.8	55.9	0.1	0.1	11.8	11.9	1.3
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	4.3	5.4	8.6	3.0	14.8	3.4	13.8	4.4	1.0	4.1	17.1	7.2
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	110.9	36.4	45.6	78.9	56.4	35.3	105.2	22.9	20.6	65.4	49.9	33.6
LnGrp LOS	F	D	D	E	E	D	F	C	C	E	D	C
Approach Vol, veh/h		1166			1681			847			1532	
Approach Delay, s/veh		50.8			56.8			53.1			48.0	
Approach LOS		D			E			D			D	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	11.3	38.2	25.0	44.6	11.2	38.3	14.6	55.0				
Change Period (Y+Rc), s	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5				
Max Green Setting (Gmax), s	6.8	33.7	20.5	41.0	6.7	33.8	15.9	45.6				
Max Q Clear Time (g_c+I1), s	7.5	22.0	22.5	37.8	8.5	33.6	10.2	12.5				
Green Ext Time (p_c), s	0.0	4.2	0.0	2.3	0.0	0.2	0.1	3.5				
Intersection Summary												
HCM 6th Ctrl Delay			52.3									
HCM 6th LOS			D									

HCM 6th Signalized Intersection Summary

3: Long Beach Blvd & 51st St



Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Volume (veh/h)	17	26	18	698	1406	15
Future Volume (veh/h)	17	26	18	698	1406	15
Initial Q (Qb), veh	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00	1.00	1.00			1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No	No	
Adj Sat Flow, veh/h/ln	1900	1900	1870	1870	1870	1870
Adj Flow Rate, veh/h	18	28	20	759	1528	16
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	0	0	2	2	2	2
Cap, veh/h	28	43	340	2912	2952	31
Arrive On Green	0.04	0.04	0.82	0.82	0.82	0.82
Sat Flow, veh/h	636	989	335	3647	3696	38
Grp Volume(v), veh/h	47	0	20	759	753	791
Grp Sat Flow(s), veh/h/ln	661	0	335	1777	1777	1864
Q Serve(g_s), s	1.8	0.0	1.3	3.2	8.7	8.8
Cycle Q Clear(g_c), s	1.8	0.0	10.1	3.2	8.7	8.8
Prop In Lane	0.38	0.60	1.00			0.02
Lane Grp Cap(c), veh/h	73	0	340	2912	1456	1527
V/C Ratio(X)	0.65	0.00	0.06	0.26	0.52	0.52
Avail Cap(c_a), veh/h	684	0	340	2912	1456	1527
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	0.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	30.9	0.0	3.4	1.4	1.9	1.9
Incr Delay (d2), s/veh	9.2	0.0	0.3	0.2	0.3	0.3
Initial Q Delay(d3), s/veh	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%), veh/ln	0.9	0.0	0.1	0.3	0.7	0.7
Unsig. Movement Delay, s/veh						
LnGrp Delay(d), s/veh	40.2	0.0	3.8	1.6	2.2	2.2
LnGrp LOS	D	A	A	A	A	A
Approach Vol, veh/h	47			779	1544	
Approach Delay, s/veh	40.2			1.6	2.2	
Approach LOS	D			A	A	
Timer - Assigned Phs	2			4		6
Phs Duration (G+Y+Rc), s	58.4			7.4		58.4
Change Period (Y+Rc), s	4.5			4.5		4.5
Max Green Setting (Gmax), s	53.9			27.1		53.9
Max Q Clear Time (g_c+l1), s	12.1			3.8		10.8
Green Ext Time (p_c), s	6.9			0.1		16.7
Intersection Summary						
HCM 6th Ctrl Delay			2.8			
HCM 6th LOS			A			

Notes

User approved volume balancing among the lanes for turning movement.

























HCM 6th TWSC

1: Del Amo Blvd & Virginia Ave

Intersection												
Int Delay, s/veh	7.3											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↰ ↱ ↲ ↳			↰ ↱ ↲ ↳		↰ ↱		↰ ↱			↰ ↱	
Traffic Vol, veh/h	18	2235	19	49	1146	13	6	0	23	0	0	8
Future Vol, veh/h	18	2235	19	49	1146	13	6	0	23	0	0	8
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	80	-	-	95	-	40	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	92	92	92	92	92	92	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	20	2429	21	53	1246	14	7	0	25	0	0	9
Major/Minor	Major1			Major2			Minor1			Minor2		
Conflicting Flow All	1260	0	0	2450	0	0	3084	3846	1225	2364	3842	623
Stage 1	-	-	-	-	-	-	2480	2480	-	1352	1352	-
Stage 2	-	-	-	-	-	-	604	1366	-	1012	2490	-
Critical Hdwy	5.34	-	-	5.34	-	-	6.44	6.54	7.14	6.44	6.54	7.14
Critical Hdwy Stg 1	-	-	-	-	-	-	7.34	5.54	-	7.34	5.54	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.74	5.54	-	6.74	5.54	-
Follow-up Hdwy	3.12	-	-	3.12	-	-	3.82	4.02	3.92	3.82	4.02	3.92
Pot Cap-1 Maneuver	293	-	-	73	-	-	13	4	146	37	4	368
Stage 1	-	-	-	-	-	-	17	58	-	113	217	-
Stage 2	-	-	-	-	-	-	412	213	-	231	58	-
Platoon blocked, %		-	-		-	-						
Mov Cap-1 Maneuver	293	-	-	73	-	-	~ 5	1	146	12	1	368
Mov Cap-2 Maneuver	-	-	-	-	-	-	~ 5	1	-	12	1	-
Stage 1	-	-	-	-	-	-	16	54	-	105	59	-
Stage 2	-	-	-	-	-	-	110	58	-	178	54	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	0.1			5.5			\$ 647.6			15		
HCM LOS							F			C		
Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1				
Capacity (veh/h)	21	293	-	-	73	-	-	368				
HCM Lane V/C Ratio	1.501	0.067	-	-	0.73	-	-	0.024				
HCM Control Delay (s)	\$ 647.6	18.2	-	-	134.5	-	-	15				
HCM Lane LOS	F	C	-	-	F	-	-	C				
HCM 95th %tile Q(veh)	4.2	0.2	-	-	3.4	-	-	0.1				
Notes												
~: Volume exceeds capacity		\$: Delay exceeds 300s		+: Computation Not Defined					*: All major volume in platoon			

HCM 6th Signalized Intersection Summary

2: Del Amo Blvd & Long Beach Blvd

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	296	1600	355	141	741	163	290	878	155	177	722	125
Future Volume (veh/h)	296	1600	355	141	741	163	290	878	155	177	722	125
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No			No			No		
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	322	1739	386	153	805	177	315	954	168	192	785	136
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	2	2	2
Cap, veh/h	380	1769	549	171	1461	453	272	1129	503	222	1028	458
Arrive On Green	0.11	0.35	0.35	0.05	0.29	0.29	0.15	0.32	0.32	0.12	0.29	0.29
Sat Flow, veh/h	3456	5106	1585	3456	5106	1585	1781	3554	1585	1781	3554	1585
Grp Volume(v), veh/h	322	1739	386	153	805	177	315	954	168	192	785	136
Grp Sat Flow(s),veh/h/ln	1728	1702	1585	1728	1702	1585	1781	1777	1585	1781	1777	1585
Q Serve(g_s), s	10.2	37.5	23.4	4.9	14.9	10.0	17.0	27.8	9.0	11.8	22.4	7.4
Cycle Q Clear(g_c), s	10.2	37.5	23.4	4.9	14.9	10.0	17.0	27.8	9.0	11.8	22.4	7.4
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	380	1769	549	171	1461	453	272	1129	503	222	1028	458
V/C Ratio(X)	0.85	0.98	0.70	0.89	0.55	0.39	1.16	0.85	0.33	0.87	0.76	0.30
Avail Cap(c_a), veh/h	389	1769	549	171	1461	453	272	1330	593	263	1311	585
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	48.6	36.0	31.4	52.5	33.6	31.9	47.1	35.4	28.9	47.7	36.0	30.7
Incr Delay (d2), s/veh	15.7	17.8	7.4	40.3	1.5	2.5	103.5	4.6	0.4	22.0	2.1	0.4
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	5.1	17.7	9.8	3.0	6.2	4.1	15.2	12.4	3.4	6.5	9.8	2.8
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	64.3	53.8	38.7	92.9	35.1	34.4	150.5	39.9	29.3	69.8	38.1	31.1
LnGrp LOS	E	D	D	F	D	C	F	D	C	E	D	C
Approach Vol, veh/h	2447			1135			1437			1113		
Approach Delay, s/veh	52.8			42.8			62.9			42.7		
Approach LOS	D			D			E			D		
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	10.0	43.0	21.5	36.6	16.7	36.3	18.3	39.8				
Change Period (Y+Rc), s	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5				
Max Green Setting (Gmax), s	5.5	38.5	17.0	41.0	12.5	31.5	16.4	41.6				
Max Q Clear Time (g_c+l1), s	6.9	39.5	19.0	24.4	12.2	16.9	13.8	29.8				
Green Ext Time (p_c), s	0.0	0.0	0.0	5.3	0.0	5.1	0.1	5.5				
Intersection Summary												
HCM 6th Ctrl Delay	51.5											
HCM 6th LOS	D											
Notes												

HCM 6th Signalized Intersection Summary

3: Long Beach Blvd & 51st St



Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	Y		Y	↑↑	↑↑	
Traffic Volume (veh/h)	16	18	39	1285	1063	16
Future Volume (veh/h)	16	18	39	1285	1063	16
Initial Q (Qb), veh	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00	1.00	1.00			1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No	No	
Adj Sat Flow, veh/h/ln	1900	1900	1870	1870	1870	1870
Adj Flow Rate, veh/h	17	20	42	1397	1155	17
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	0	0	2	2	2	2
Cap, veh/h	29	34	465	2930	2956	43
Arrive On Green	0.04	0.04	0.82	0.82	0.82	0.82
Sat Flow, veh/h	749	881	479	3647	3678	53
Grp Volume(v), veh/h	38	0	42	1397	572	600
Grp Sat Flow(s), veh/h/ln	674	0	479	1777	1777	1861
Q Serve(g_s), s	1.5	0.0	1.6	7.4	5.5	5.5
Cycle Q Clear(g_c), s	1.5	0.0	7.1	7.4	5.5	5.5
Prop In Lane	0.45	0.53	1.00			0.03
Lane Grp Cap(c), veh/h	64	0	465	2930	1465	1534
V/C Ratio(X)	0.60	0.00	0.09	0.48	0.39	0.39
Avail Cap(c_a), veh/h	690	0	465	2930	1465	1534
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	0.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	31.0	0.0	2.4	1.7	1.5	1.5
Incr Delay (d2), s/veh	8.6	0.0	0.4	0.6	0.2	0.2
Initial Q Delay(d3), s/veh	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%), veh/ln	0.7	0.0	0.1	0.6	0.3	0.3
Unsig. Movement Delay, s/veh						
LnGrp Delay(d), s/veh	39.6	0.0	2.8	2.2	1.7	1.7
LnGrp LOS	D	A	A	A	A	A
Approach Vol, veh/h	38			1439	1172	
Approach Delay, s/veh	39.6			2.2	1.7	
Approach LOS	D			A	A	
Timer - Assigned Phs	2			4		6
Phs Duration (G+Y+Rc), s	58.5			7.0		58.5
Change Period (Y+Rc), s	4.5			4.5		4.5
Max Green Setting (Gmax), s	54.0			27.0		54.0
Max Q Clear Time (g_c+I1), s	9.4			3.5		7.5
Green Ext Time (p_c), s	16.6			0.1		10.5

Intersection Summary













HCM 6th Ctrl Delay	2.5
HCM 6th LOS	A

Notes

User approved volume balancing among the lanes for turning movement.

Queues

2: Del Amo Blvd & Long Beach Blvd

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	166	657	284	160	1347	138	298	464	61	122	1078	290
v/c Ratio	0.85	0.48	0.47	0.70	0.96	0.26	0.95	0.32	0.09	0.64	0.91	0.45
Control Delay	90.5	38.3	10.2	71.0	58.1	7.0	88.2	25.4	1.8	65.9	49.5	14.6
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	90.5	38.3	10.2	71.0	58.1	7.0	88.2	25.4	1.8	65.9	49.5	14.6
Queue Length 50th (ft)	67	157	26	63	377	1	231	127	0	91	413	66
Queue Length 95th (ft)	#130	198	102	#110	#478	50	#407	175	11	154	#536	146
Internal Link Dist (ft)	870			702			406			729		
Turn Bay Length (ft)	225			100	145			100	205	60	190	
Base Capacity (vph)	196	1358	598	230	1410	536	315	1437	699	235	1219	656
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.85	0.48	0.47	0.70	0.96	0.26	0.95	0.32	0.09	0.52	0.88	0.44

Intersection Summary

95th percentile volume exceeds capacity, queue may be longer.
Queue shown is maximum after two cycles.

Queues

3: Long Beach Blvd & 51st St



Lane Group	EBL	NBL	NBT	SBT
Lane Group Flow (vph)	46	20	737	1501
v/c Ratio	0.26	0.08	0.24	0.49
Control Delay	20.1	2.9	1.9	3.0
Queue Delay	0.0	0.0	0.0	0.0
Total Delay	20.1	2.9	1.9	3.0
Queue Length 50th (ft)	7	1	31	87
Queue Length 95th (ft)	35	7	54	147
Internal Link Dist (ft)	416		729	235
Turn Bay Length (ft)		145		
Base Capacity (vph)	654	250	3047	3041
Starvation Cap Reductn	0	0	0	0
Spillback Cap Reductn	0	0	0	0
Storage Cap Reductn	0	0	0	0
Reduced v/c Ratio	0.07	0.08	0.24	0.49
Intersection Summary				

Queues

2: Del Amo Blvd & Long Beach Blvd

03/10/2021



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	291	1697	368	151	777	175	297	927	166	189	771	129
v/c Ratio	1.07	1.05	0.62	0.96	0.54	0.32	1.15	0.73	0.27	0.82	0.64	0.21
Control Delay	127.5	78.1	27.3	119.7	38.0	12.1	148.7	38.1	13.5	77.7	36.2	5.5
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	127.5	78.1	27.3	119.7	38.0	12.1	148.7	38.1	13.5	77.7	36.2	5.5
Queue Length 50th (ft)	~128	~526	157	61	186	26	~271	331	37	143	263	0
Queue Length 95th (ft)	#220	#623	264	#130	230	84	#448	410	90	#256	331	42
Internal Link Dist (ft)		870			702			406			729	
Turn Bay Length (ft)	225		100	145		100	205		60	190		
Base Capacity (vph)	271	1610	590	157	1440	540	258	1263	626	246	1209	625
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	1.07	1.05	0.62	0.96	0.54	0.32	1.15	0.73	0.27	0.77	0.64	0.21

Intersection Summary

~ Volume exceeds capacity, queue is theoretically infinite.

Queue shown is maximum after two cycles.

95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

Queues

3: Long Beach Blvd & 51st St













03/10/2021



Lane Group	EBL	NBL	NBT	SBT
Lane Group Flow (vph)	37	41	1353	1143
v/c Ratio	0.22	0.10	0.42	0.36
Control Delay	21.4	2.3	2.1	1.8
Queue Delay	0.0	0.0	0.0	0.0
Total Delay	21.4	2.3	2.1	1.8
Queue Length 50th (ft)	7	0	0	0
Queue Length 95th (ft)	32	10	120	92
Internal Link Dist (ft)	416		729	235
Turn Bay Length (ft)		145		
Base Capacity (vph)	647	409	3207	3202
Starvation Cap Reductn	0	0	0	0
Spillback Cap Reductn	0	0	0	0
Storage Cap Reductn	0	0	0	0
Reduced v/c Ratio	0.06	0.10	0.42	0.36
Intersection Summary				

Queues

2: Del Amo Blvd & Long Beach Blvd

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	171	668	292	162	1371	140	303	473	62	124	1108	300
v/c Ratio	0.89	0.47	0.47	0.83	0.95	0.26	1.00	0.33	0.09	0.64	0.93	0.47
Control Delay	97.9	36.8	9.5	88.1	57.2	7.1	101.3	26.0	1.9	66.1	51.7	16.5
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	97.9	36.8	9.5	88.1	57.2	7.1	101.3	26.0	1.9	66.1	51.7	16.5
Queue Length 50th (ft)	69	157	25	65	383	2	-238	132	0	93	430	79
Queue Length 95th (ft)	#136	197	100	#126	#483	51	#424	181	12	155	#562	162
Internal Link Dist (ft)	870				702				406			
Turn Bay Length (ft)	225	100		145	100		205	60		190		
Base Capacity (vph)	192	1435	625	195	1439	545	303	1418	691	235	1215	648
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.89	0.47	0.47	0.83	0.95	0.26	1.00	0.33	0.09	0.53	0.91	0.46

Intersection Summary

- ~ Volume exceeds capacity, queue is theoretically infinite.
Queue shown is maximum after two cycles.
- # 95th percentile volume exceeds capacity, queue may be longer.
Queue shown is maximum after two cycles.

Queues













3: Long Beach Blvd & 51st St



Lane Group	EBL	NBL	NBT	SBT
Lane Group Flow (vph)	46	20	750	1536
v/c Ratio	0.26	0.08	0.25	0.51
Control Delay	20.1	3.0	2.0	3.1
Queue Delay	0.0	0.0	0.0	0.0
Total Delay	20.1	3.0	2.0	3.1
Queue Length 50th (ft)	7	1	32	91
Queue Length 95th (ft)	35	7	55	153
Internal Link Dist (ft)	416		729	235
Turn Bay Length (ft)		145		
Base Capacity (vph)	654	239	3047	3041
Starvation Cap Reductn	0	0	0	0
Spillback Cap Reductn	0	0	0	0
Storage Cap Reductn	0	0	0	0
Reduced v/c Ratio	0.07	0.08	0.25	0.51
Intersection Summary				

Queues

2: Del Amo Blvd & Long Beach Blvd

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	301	1729	376	153	796	177	305	954	168	192	785	136
v/c Ratio	0.96	1.02	0.61	0.93	0.54	0.32	1.13	0.83	0.28	0.81	0.72	0.23
Control Delay	93.3	65.9	26.3	109.0	36.8	11.4	137.8	42.7	8.5	73.9	39.2	5.7
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	93.3	65.9	26.3	109.0	36.8	11.4	137.8	42.7	8.5	73.9	39.2	5.7
Queue Length 50th (ft)	120	~534	160	61	191	23	~278	345	16	143	269	0
Queue Length 95th (ft)	#216	#642	274	#132	239	82	#463	427	66	#259	337	43
Internal Link Dist (ft)		870			702			406			729	
Turn Bay Length (ft)	225		100	145		100	205		60	190		
Base Capacity (vph)	315	1693	614	165	1470	554	271	1290	663	262	1271	655
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.96	1.02	0.61	0.93	0.54	0.32	1.13	0.74	0.25	0.73	0.62	0.21

Intersection Summary

- ~ Volume exceeds capacity, queue is theoretically infinite.
Queue shown is maximum after two cycles.
- # 95th percentile volume exceeds capacity, queue may be longer.
Queue shown is maximum after two cycles.

Queues













3: Long Beach Blvd & 51st St



Lane Group	EBL	NBL	NBT	SBT
Lane Group Flow (vph)	37	42	1387	1163
v/c Ratio	0.22	0.11	0.43	0.36
Control Delay	21.4	2.3	2.1	1.8
Queue Delay	0.0	0.0	0.0	0.0
Total Delay	21.4	2.3	2.1	1.8
Queue Length 50th (ft)	7	0	0	0
Queue Length 95th (ft)	32	11	124	94
Internal Link Dist (ft)	416		729	235
Turn Bay Length (ft)		145		
Base Capacity (vph)	647	399	3207	3202
Starvation Cap Reductn	0	0	0	0
Spillback Cap Reductn	0	0	0	0
Storage Cap Reductn	0	0	0	0
Reduced v/c Ratio	0.06	0.11	0.43	0.36
Intersection Summary				

Queues

2: Del Amo Blvd & Long Beach Blvd

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	188	677	301	162	1379	140	312	473	62	124	1108	300
v/c Ratio	0.98	0.47	0.48	0.83	0.96	0.26	1.03	0.33	0.09	0.64	0.93	0.47
Control Delay	116.4	36.9	9.8	88.1	58.1	7.1	108.0	26.0	1.9	66.1	51.7	16.7
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	116.4	36.9	9.8	88.1	58.1	7.1	108.0	26.0	1.9	66.1	51.7	16.7
Queue Length 50th (ft)	76	159	28	65	386	2	-259	132	0	93	430	81
Queue Length 95th (ft)	#153	199	105	#126	#488	51	#440	181	12	155	#562	163
Internal Link Dist (ft)	870			702			406			729		
Turn Bay Length (ft)	225			100	145			100	205	60	190	
Base Capacity (vph)	192	1435	628	195	1439	545	303	1418	691	235	1215	646
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.98	0.47	0.48	0.83	0.96	0.26	1.03	0.33	0.09	0.53	0.91	0.46

Intersection Summary

~ Volume exceeds capacity, queue is theoretically infinite.

Queue shown is maximum after two cycles.

95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

Queues













3: Long Beach Blvd & 51st St



Lane Group	EBL	NBL	NBT	SBT
Lane Group Flow (vph)	46	20	759	1544
v/c Ratio	0.26	0.08	0.25	0.51
Control Delay	20.1	3.0	2.0	3.1
Queue Delay	0.0	0.0	0.0	0.0
Total Delay	20.1	3.0	2.0	3.1
Queue Length 50th (ft)	7	1	32	92
Queue Length 95th (ft)	35	7	56	155
Internal Link Dist (ft)	416		729	235
Turn Bay Length (ft)		145		
Base Capacity (vph)	654	237	3047	3041
Starvation Cap Reductn	0	0	0	0
Spillback Cap Reductn	0	0	0	0
Storage Cap Reductn	0	0	0	0
Reduced v/c Ratio	0.07	0.08	0.25	0.51
Intersection Summary				

Queues

2: Del Amo Blvd & Long Beach Blvd

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	322	1739	386	153	805	177	315	954	168	192	785	136
v/c Ratio	0.86	1.01	0.62	0.93	0.57	0.33	1.21	0.83	0.28	0.82	0.72	0.23
Control Delay	74.2	62.4	26.2	111.0	38.4	11.8	165.6	43.5	8.6	76.5	39.3	5.6
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	74.2	62.4	26.2	111.0	38.4	11.8	165.6	43.5	8.6	76.5	39.3	5.6
Queue Length 50th (ft)	128	~533	165	61	198	24	~303	348	17	145	271	0
Queue Length 95th (ft)	#214	#640	280	#132	246	84	#491	430	66	#266	340	44
Internal Link Dist (ft)	870				702				406			
Turn Bay Length (ft)	225			100	145			100	205	60	190	
Base Capacity (vph)	373	1725	625	164	1415	538	261	1281	659	252	1262	652
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.86	1.01	0.62	0.93	0.57	0.33	1.21	0.74	0.25	0.76	0.62	0.21

Intersection Summary

~ Volume exceeds capacity, queue is theoretically infinite.

Queue shown is maximum after two cycles.

95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

Queues

3: Long Beach Blvd & 51st St



Lane Group	EBL	NBL	NBT	SBT
Lane Group Flow (vph)	37	42	1397	1172
v/c Ratio	0.22	0.11	0.44	0.37
Control Delay	21.4	2.4	2.1	1.8
Queue Delay	0.0	0.0	0.0	0.0
Total Delay	21.4	2.4	2.1	1.8
Queue Length 50th (ft)	7	0	0	0
Queue Length 95th (ft)	32	11	125	95
Internal Link Dist (ft)	416		729	235
Turn Bay Length (ft)		145		
Base Capacity (vph)	647	395	3207	3202
Starvation Cap Reductn	0	0	0	0
Spillback Cap Reductn	0	0	0	0
Storage Cap Reductn	0	0	0	0
Reduced v/c Ratio	0.06	0.11	0.44	0.37
Intersection Summary				

APPENDIX F

DRIVE-THROUGH QUEUING DATA

Prepared by National Data & Surveying Services

Queue Movement Study

Project#: 21-020035-001

Location: 76 Car Wash Drive Thru at 4294 University Pkwy

City: San Bernardino, CA

Day: Saturday

Date: 2/6/2021

Interval	Drive Thru Lane Queue	Remarks
1:39:40 PM	1	
1:40:34 PM	0	
1:42:08 PM	1	
1:42:24 PM	2	
1:42:49 PM	1	
1:43:34 PM	2	
1:44:00 PM	1	
1:45:27 PM	0	
1:46:05 PM	1	
1:47:11 PM	2	
1:47:18 PM	3	
1:47:59 PM	2	
1:48:11 PM	3	
1:48:53 PM	2	
1:49:59 PM	1	
1:51:06 PM	0	
1:57:43 PM	1	
1:58:32 PM	2	
1:58:35 PM	1	
TOTAL	782	



5005 Long Beach Boulevard Project

Air Quality and Greenhouse Gas Study

prepared for

A & S Engineering

28405 Sand Canyon Road, Suite B
Canyon Country, California 91387
Contact: Ahmad Ghaderi

prepared by

Rincon Consultants, Inc.

250 East 1st Street, Suite 1400
Los Angeles, California 90012

June 2021



RINCON CONSULTANTS, INC.

Environmental Scientists | Planners | Engineers

rinconconsultants.com

Table of Contents

1	Project Description and Impact Summary	1
1.1	Introduction	1
1.2	Project Summary	2
2	Air Quality	7
2.1	Environmental and Regulatory Setting.....	7
2.2	Impact Analysis	14
3	Greenhouse Gas Emissions.....	24
3.1	Background	24
3.2	Impact Analysis	32
4	Conclusions and Recommendations.....	37
5	References	39

Tables

Table 1	Summary of Impacts	1
Table 2	Federal and State Ambient Air Quality Standards	9
Table 3	Ambient Air Quality at the Nearest Monitoring Stations	13
Table 4	SCAQMD Regional Significance Thresholds	17
Table 5	SCAQMD LSTs (SRA-4)	18
Table 6	Project Construction Emissions	19
Table 7	Project Operational Emissions - Regional	20
Table 8	Project Operational Emissions - Local.....	21
Table 9	Estimated Construction Greenhouse Gas Emissions	35
Table 10	Estimated Annual Greenhouse Gas Emissions	35

Figures

Figure 1	Regional Location Map	4
Figure 2	Project Site Location	5
Figure 3	Site Plan	6

Appendices

Appendix A CalEEMod Output Files

Appendix B On-site Exhaust Emissions Calculations

1 Project Description and Impact Summary

1.1 Introduction

This study analyzes the potential air quality and greenhouse gas (GHG) impacts of the proposed 5005 Long Beach Boulevard project (herein referred to as “proposed project” or “project”) in Long Beach, California. Rincon Consultants, Inc. (Rincon) prepared this study under contract to A & S Engineering for the City of Long Beach to use in support of the environmental documentation being prepared pursuant to the California Environmental Quality Act (CEQA). The purpose of this study is to analyze the project’s air quality and GHG impacts related to both temporary construction activity and long-term operation of the project. The conclusions of this study are summarized in Table 1, followed by the Regulatory Compliance Measures (RCMs) required for the project.

Table 1 Summary of Impacts

Impact Statement	Proposed Project’s Level of Significance	Applicable RCMs
Air Quality		
Conflict with or obstruct implementation of the applicable air quality plan?	Less than significant impact	None
Result in a cumulatively considerable net increase of any criteria pollutant for which the project region is in non-attainment under an applicable federal or state ambient air quality standard?	Less than significant impact	RCM-1 and RCM-3 through RCM-5
Expose sensitive receptors to substantial pollutant concentrations?	Less than significant impact	None
Result in other emissions (such as those leading to odors) adversely affecting a substantial number of people?	Less than significant impact	RCM-2
Greenhouse Gas Emissions		
Generate GHG emissions, either directly or indirectly, that may have a significant impact on the environment?	Less than significant impact	None
Conflict with an applicable plan, policy or regulation adopted for the purpose of reducing the emissions of GHGs?	Less than significant impact	None

Regulatory Compliance Measures

RCMs are existing requirements and reasonably anticipated standard conditions that are based on local, State, or federal regulations and laws that are frequently required independently of CEQA review and serve to offset or prevent specific impacts. RCMs are not included as mitigation measures in the environmental clearance document because the project is required to comply with RCMs through State and local regulations.

RCM-1 Demolition, Grading, and Construction Activities: Compliance with Provisions of SCAQMD Rule 403

The project shall comply with all applicable standards of the Southern California Air Quality Management District (SCAQMD), including the following provisions of Rule 403:

- All unpaved demolition and construction areas shall be wetted at least twice daily during excavation and construction, and temporary dust covers shall be used to reduce dust emissions and meet SCAQMD Rule 403. Wetting could reduce fugitive dust by as much as 50 percent.
- The construction area shall be kept sufficiently dampened to control dust caused by grading and hauling, and at all times provide reasonable control of dust caused by wind.
- All clearing, earth moving, or excavation activities shall be discontinued during periods of high winds (i.e., greater than 15 mph), in order to prevent excessive amounts of dust.
- All dirt/soil shall be secured by trimming, watering, or other appropriate means to prevent spillage and dust.
- All dirt/soil materials transported off-site shall be either sufficiently watered or securely covered to prevent excessive amounts of dust.
- General contractors shall maintain and operate construction equipment to minimize exhaust emissions.
- Trucks having no current hauling activity shall not idle but be turned off.

RCM-2 Odors: Compliance with Provisions of SCAQMD Rule 402

The project shall comply with the following provision of SCAQMD Rule 402: a person shall not discharge from any source whatsoever such quantities of air contaminants or other material which cause injury, detriment, nuisance, or annoyance to any considerable number of persons or to the public, or which endanger the comfort, repose, health or safety of any such persons or the public, or which cause, or have a natural tendency to cause, injury or damage to business or property.

RCM-3 Engine Idling

In accordance with Section 2485 of Title 13 of the California Code of Regulations, the idling of all diesel-fueled commercial vehicles (weighing over 10,000 pounds) during construction shall be limited to five minutes at any location.

RCM-4 Emission Standards

In accordance with Section 93115 of Title 17 of the California Code of Regulations, operation of any stationary, diesel-fueled, compression-ignition engines shall meet specified fuel and fuel additive requirements and emission standards.

RCM-5 Architectural Coatings: Compliance with SCAQMD Rule 1113

The project shall comply with SCAQMD Rule 1113 limiting the volatile organic compound (VOC) content of architectural coatings.

1.2 Project Summary

Project Location

The 0.46-acre project site (Assessor Parcel Number [APN] 7132-028-019) is located in the City of Long Beach at 5005 Long Beach Boulevard (see Figure 1 and Figure 2). The project site is zoned Community Commercial Automobile-Oriented (CCA) with a General Plan Land Use designation of Neighborhood Serving Center or Corridor Moderate Density (NSC-L) within the Long Beach 2040 Plan Area. The project site is currently an existing food mart and gas station with a parking lot area.

See Figure 1 and Figure 2 for the project site location in a regional context and local context, respectively.

The surrounding area is a mixture of commercial and residential uses. Interstate 710 (I-710) is located approximately 0.6 mile west of the project site. The properties to the north are zoned CCA and consists of Dooley Elementary School. The property to the west is a dine in restaurant also zoned CCA. Residences are located further to the west, at an approximate distance of 400 feet from the project site and are zoned Multi-Family Residential/Townhouse (R-3-T). Commercial properties to the south across Del Amo Boulevard are zoned CCA and are developed with one-gas station and food mart. Single-family residences to the south across Del Amo Boulevard are zoned R-3-T. The properties to the east are zoned Community R-3-N Commercial (CCN) and are developed with mixed retail. Del Amo Gardens retirement home is located approximately 450 feet east of the project site and is zoned Moderate-density Multiple Residential (R-4-R).


Project Description

The project site is located at 5005 Long Beach Boulevard in the City of Long Beach, near the Long Beach Boulevard and Del Amo Boulevard intersection. The project includes a Conditional Use Permit to construct and operate a new 3,058-square-foot detached self-service automated car wash (2,000-square-foot care wash tunnel and 1,058 square feet of equipment rooms and office space) and 15 vacuum parking spaces to an existing food mart and gas station along the north property line (see Figure 3). The project would not use emergency back-up generators. The express car wash would use a conveyer system to move multiple vehicles at once. The queue line for the car wash would be able to handle eight vehicles.

Construction

For the purposes of this analysis, project construction is assumed to commence in September 2021. Construction activities are assumed to occur five days a week.

Figure 1 Regional Location Map



Imagery provided by Esri and its licensors © 2020.

★ Project Location





Fig. 1 Regional Location

Figure 2 Project Site Location



Figure 3 Site Plan



2 Air Quality

2.1 Environmental and Regulatory Setting

Local Climate and Meteorology

The project site is in the South Coast Air Basin (SCAB), which is bounded by the Pacific Ocean to the west and the San Gabriel, San Bernardino, and San Jacinto Mountains to the north and east. The SCAB includes all of Orange County and the non-desert portions of Los Angeles, Riverside, and San Bernardino Counties, in addition to the San Geronio Pass area in Riverside County. The regional climate in the SCAB is semi-arid and is characterized by warm summers, mild winters, infrequent seasonal rainfall, moderate daytime onshore breezes, and moderate humidity. The air quality in the SCAB is primarily influenced by meteorology and a wide range of emission sources, such as dense population centers, substantial vehicular traffic, and industry.

Air pollutant emissions in the SCAB are generated primarily by stationary and mobile sources. Stationary sources can be divided into two major subcategories: point and area sources. Point sources occur at a specific location and are often identified by an exhaust vent or stack. Examples include boilers or combustion equipment that produce electricity or generate heat. Area sources are widely distributed and include such sources as residential and commercial water heaters, painting operations, lawn mowers, agricultural fields, landfills, and some consumer products. Mobile sources refer to emissions from motor vehicles, including tailpipe and evaporative emissions, and are classified as either on-road or off-road. On-road sources may be legally operated on roadways and highways. Off-road sources include aircraft, ships, trains, and self-propelled construction equipment. Air pollutants can also be generated by the natural environment, such as when high winds suspend fine dust particles.

Figure 4 shows the typical wind direction in the Long Beach area. As shown in the figure, the primary wind direction is from the northwest, as evidenced by the purple tails of the wind speed (15 to 20 miles per hour) from the northwest. This indicates that the wind would, on average, blow pollutants away from the car wash to the southeast away from Dooley Elementary School.



[LGB] LONG BEACH AIRPORT
 Windrose Plot
 Time Bounds: 01 Jan 1970 01:00 AM - 23 Feb 2021 11:53 PM America/Los_Angeles




Figure 4. Long Beach Airport Windrose Plot.
 Source: Iowa Environmental Mesonet 2021

Air Quality Regulation

Federal and California Clean Air Acts

The federal and state governments have established ambient air quality standards for the protection of public health. The United States Environmental Protection Agency (USEPA) is the federal agency designated to administer air quality regulation, while the California Air Resources Board (CARB) is the state equivalent within the California Environmental Protection Agency (CalEPA). County-level air districts provide local management of air quality. CARB has established air quality standards and is responsible for the control of mobile emission sources, while the local air

districts are responsible for enforcing standards and regulating stationary sources. CARB has established 15 air basins statewide, including the SCAB.

The USEPA has set primary national ambient air quality standards (NAAQS) for ozone (O₃), carbon monoxide (CO), nitrogen dioxide (NO₂), sulfur dioxide (SO₂), particulate matter with diameters of up to ten microns (PM₁₀) and up to 2.5 microns (PM_{2.5}), and lead. Primary standards are those levels of air quality deemed necessary, with an adequate margin of safety, to protect public health. In addition, California has established health-based ambient air quality standards (known as the California ambient air quality standards [CAAQS]) for these and other pollutants, some of which are more stringent than the federal standards. Table 2 lists the current federal and state standards for regulated pollutants.

Table 2 Federal and State Ambient Air Quality Standards

Pollutant	Averaging Time	Federal Primary Standards	California Standards
Ozone	1-Hour	–	0.09 ppm
	8-Hour	0.070 ppm	0.070 ppm
CO	8-Hour	9.0 ppm	9.0 ppm
	1-Hour	35.0 ppm	20.0 ppm
NO ₂	Annual	0.053 ppm	0.030 ppm
	1-Hour	0.100 ppm	0.18 ppm
SO ₂	Annual	.030 ppm	–
	24-Hour	0.14 ppm	0.04 ppm
	1-Hour	0.075 ppm	0.25 ppm
PM ₁₀	Annual	–	20 µg/m ³
	24-Hour	150 µg/m ³	50 µg/m ³
PM _{2.5}	Annual	12 µg/m ³	12 µg/m ³
	24-Hour	35 µg/m ³	–
Lead	30-Day Average	–	1.5 µg/m ³
	3-Month Average	0.15 µg/m ³	–
Visibility Reducing Particles	8-Hour	–	Extinction of 0.23 per kilometer
Sulfates	24-Hour	–	25 µg/m ³
Hydrogen Sulfide	1-Hour	–	0.03 ppm (42 µg/m ³)
Vinyl Chloride	24-Hour	–	0.01 ppm (26 µg/m ³)

ppm = parts per million; µg/m³ = micrograms per cubic meter

Source: CARB 2016

SCAQMD is the designated air quality control agency in the SCAB, which is a non-attainment area for the federal standards for ozone and PM_{2.5} and the state standards for ozone, PM₁₀, and PM_{2.5}. The Los Angeles County portion of the SCAB is also designated non-attainment for lead (SCAQMD 2016). The SCAB is designated unclassifiable or in attainment for all other federal and state standards.

Safer Affordable Fuel-Efficient Vehicles Rule

On September 27, 2019, the USEPA and the National Highway Safety Administration published the Safer Affordable Fuel-Efficient (SAFE) Vehicles Rule Part One: One National Program. The Part One Rule revokes California's authority to set its own GHG emissions standards and zero-emission vehicle mandates in California. To account for the effects of the Part One Rule, CARB released off-model adjustment factors on November 20, 2019 to adjust criteria air pollutant emissions outputs from the EMFAC model. These off-model adjustment factors are to be applied by multiplying the emissions calculated for light- and medium-duty vehicles by the adjustment factor. With the incorporation of these adjustment factors, operational emissions generated by light-duty automobiles, light-duty trucks, and medium-duty trucks associated with project-related vehicle trips at the year 2021, would be approximately 0.01 percent greater for ROG, 0.09 percent greater for particulate matter, 0.02 percent greater for NO_x, and 0.05 percent greater for CO. These increases would have a negligible impact on overall operational emissions generated by the project and would not alter the significance of the project's operational emissions as discussed further below.

Air Pollutants of Primary Concern

Primary criteria pollutants are emitted directly from a source (e.g., vehicle tailpipe, an exhaust stack of a factory, etc.) into the atmosphere. Primary criteria pollutants include CO, NO₂, PM₁₀, PM_{2.5}, SO₂, and lead. Ozone is considered a secondary criteria pollutant because it is created by atmospheric chemical and photochemical reactions between reactive organic gases (ROG) and nitrogen oxides (NO_x). The following subsections describe the characteristics, sources, and health and atmospheric effects of critical air contaminants.

Ozone

Ozone is produced by a photochemical reaction (triggered by sunlight) between NO_x and ROG.¹ Nitrogen oxides are formed during the combustion of fuels, while ROG are formed during combustion and evaporation of organic solvents. Because ozone requires sunlight to form, it usually occurs in substantial concentrations between the months of April and October. Ozone is a pungent, colorless, toxic gas with direct health effects on humans including respiratory and eye irritation and possible changes in lung functions. Groups most sensitive to ozone include children, the elderly, people with respiratory disorders, and people who exercise strenuously outdoors.

Carbon Monoxide

Carbon monoxide is a local pollutant that is found in high concentrations only near fuel combustion equipment and other sources of CO. The primary source of CO, a colorless, odorless, poisonous gas, is automobile traffic. Therefore, elevated concentrations are usually only found near areas of high traffic volumes. Carbon monoxide's health effects are related to its affinity for hemoglobin in the blood. At high concentrations, CO reduces the amount of oxygen in the blood, causing heart difficulty in people with chronic diseases, reduced lung capacity, and impaired mental abilities.

¹ CARB defines VOC and ROG similarly as, "any compound of carbon excluding CO, carbon dioxide, carbonic acid, metallic carbides or carbonates, and ammonium carbonate," with the exception that VOC are compounds that participate in atmospheric photochemical reactions (CARB 2009). For the purposes of this analysis, ROG and VOC are considered comparable in terms of mass emissions and the term ROG is used in this report.). SCAQMD uses the term VOC to denote organic precursors.

Nitrogen Dioxide

Nitrogen dioxide is a by-product of fuel combustion, with the primary source being motor vehicles and industrial boilers and furnaces. The principal form of nitrogen oxide produced by combustion is nitric oxide (NO), but NO reacts rapidly to form NO₂, creating the mixture of NO and NO₂ commonly called NO_x. Nitrogen dioxide is an acute irritant. A relationship between NO₂ and chronic pulmonary fibrosis may exist, and an increase in bronchitis in young children at concentrations below 0.3 parts per million (ppm) may occur. Nitrogen dioxide absorbs blue light, gives a reddish-brown cast to the atmosphere, and reduces visibility. It can also contribute to the formation of ozone/smog and acid rain.

Sulfur Dioxide

Sulfur dioxide is a colorless, pungent, irritating gas formed primarily by the combustion of sulfur-containing fossil fuels. When SO₂ oxidizes in the atmosphere, it forms sulfur trioxide. Collectively, these pollutants are referred to as sulfur oxides (SO_x). In humid atmospheres, SO₂ can also form sulfuric acid mist, which can eventually react to produce sulfate particulates that can inhibit visibility. Combustion of high sulfur-content fuels is the major source of SO₂, while chemical plants, sulfur recovery plants, and metal processing are minor contributors. At sufficiently high concentrations, SO₂ irritates the upper respiratory tract. At lower concentrations, when in conjunction with particulates, SO₂ appears to do still greater harm by injuring lung tissues. This compound also constricts the breathing passages, especially in people with asthma and people involved in moderate to heavy exercise. Sulfur dioxide causes respiratory irritation, including wheezing, shortness of breath, and coughing. Long-term SO₂ exposure has been associated with increased risk of mortality from respiratory or cardiovascular disease. Sulfur oxides, in combination with moisture and oxygen, can yellow leaves on plants, dissolve marble, and eat away iron and steel.

Suspended Particulates

Atmospheric particulate matter is comprised of finely divided solids and liquids such as dust, soot, aerosols, fumes, and mists. The particulates that are of particular concern are PM₁₀ (small particulate matter that measures no more than 10 microns in diameter) and PM_{2.5} (fine particulate matter that measures no more than 2.5 microns in diameter). The characteristics, sources, and potential health effects associated with PM₁₀ and PM_{2.5} can be different. Major man-made sources of PM₁₀ are agricultural operations, industrial processes, combustion of fossil fuels, construction, demolition operations, and entrainment of road dust into the atmosphere. Natural sources include windblown dust, wildfire smoke, and sea spray salt. The finer PM_{2.5} particulates are generally associated with combustion processes as well as formation in the atmosphere as a secondary pollutant through chemical reactions. PM_{2.5} is more likely to penetrate deeply into the lungs and poses a serious health threat to all groups, but particularly to the elderly, children, and those with respiratory problems. More than half of the small and fine particulate matter that is inhaled into the lungs remains there, which can cause permanent lung damage. These materials can damage health by interfering with the body's mechanisms for clearing the respiratory tract or by acting as carriers of an absorbed toxic substance.

Lead

Lead is a metal found naturally in the environment, as well as in manufacturing products. Lead occurs in the atmosphere as particulate matter. The major sources of lead emissions historically

have been mobile and industrial sources. In the early 1970s, the USEPA set national regulations to gradually reduce the lead content in gasoline. In 1975, unleaded gasoline was introduced for motor vehicles equipped with catalytic converters. The USEPA completed the ban prohibiting the use of leaded gasoline in highway vehicles in December 1995. As a result of the USEPA's regulatory efforts to remove lead from gasoline, atmospheric lead concentrations have declined substantially over the past several decades. The most dramatic reductions in lead emissions occurred prior to 1990 due to the removal of lead from gasoline sold for most highway vehicles. Lead emissions were further reduced substantially between 1990 and 2008, with reductions occurring in the metals industries in part due to national emissions standards for hazardous air pollutants (USEPA 2013). As a result of phasing out leaded gasoline, metal processing is currently the primary source of lead emissions. The highest levels of lead in the air are generally found near lead smelters. Other stationary sources include waste incinerators, utilities, and lead-acid battery manufacturers. Lead may cause a range of health effects, including anemia, kidney disease, and neuromuscular and neurological dysfunction (in severe cases). The proposed project does not include any stationary sources of lead emissions. Therefore, implementation of the project would not result in substantial emissions of lead, and this pollutant is not discussed further in this analysis.

Toxic Air Contaminants

Toxic air contaminants (TACs) are a diverse group of air pollutants that may cause or contribute to an increase in deaths or serious illness or that may pose a present or potential hazard to human health. TACs include both organic and inorganic chemical substances that may be emitted from a variety of common sources, including gasoline stations, motor vehicles, dry cleaners, industrial operations, painting operations, and research and teaching facilities. One of the main sources of TACs in California is diesel engines that emit exhaust containing solid material known as diesel particulate matter (DPM; CARB 2011). TACs are different than the criteria pollutants previously discussed because ambient air quality standards have not been established for TACs. TACs occurring at extremely low levels may still cause health effects, and it is typically difficult to identify levels of exposure that do not produce adverse health effects. TAC impacts are described by carcinogenic risk and by chronic (i.e., of long duration) and acute (i.e., severe but of short duration) adverse effects on human health.

Current Air Quality

The project site is located within the 90th percentile or top 10 percent for the most pollution burdened, as outlined in Map LU-6 of the City's updated Land Use Element (City of Long Beach 2019a). This map is derived from the California Office of Environmental Health Hazard Assessment's Cal EnviroScreen which uses environmental, health, and socioeconomic information to assess the pollution burden and vulnerability of populations by census tract.

The SCAQMD operates a network of air quality monitoring stations throughout the SCAB. The purpose of the monitoring stations is to measure ambient concentrations of pollutants and to determine whether ambient air quality meets the NAAQS and CAAQS. The monitoring station closest to the project is the Long Beach - Route 710 Near Road station located at the off and on-ramp of Interstate 710 onto Long Beach Boulevard, approximately 1.1 miles west of the project site. This station reports monitoring data for NO₂ and PM_{2.5}, but not ozone and PM₁₀. Therefore, ozone and PM₁₀ concentrations were obtained from the next closest station with available data, which is the Long Beach – 2425 Webster Street Station monitoring station located approximately 3.5 miles southwest of the project site. Table 3 indicates the number of days that the NAAQS and CAAQS has

been exceeded at these stations in each of the last three years. The data indicate that the state PM₁₀ standards were exceeded each year from 2017 to 2019 and federal standards were exceeded in 2019, and the federal PM_{2.5} was exceeded in 2017 and 2019. No other state or federal standards were exceeded at this monitoring station.

Table 3 Ambient Air Quality at the Nearest Monitoring Stations

Pollutant	2017	2018	2019
Ozone (ppm), Eight-Hour Average ¹	0.068	0.063	0.064
Number of days of state exceedances (>0.070 ppm)	0	0	0
Number of days of federal exceedances (>0.070 ppm)	0	0	0
Ozone (ppm), Worst Hour ¹	0.082	0.074	0.075
Number of days of state exceedances (>0.09 ppm)	0	0	0
Nitrogen Dioxide (ppm), Worst Hour ²	0.116	0.0903	0.0977
Number of days of state exceedances (>0.18 ppm)	0	0	0
Particulate Matter <10 microns (µg/m ³), Worst 24 Hours ¹	79.0	84.0	155.8
Number of days of state exceedances (>50 µg/m ³)	10	4	4
Number of days of federal exceedances (>150 µg/m ³)	0	0	1
Particulate Matter <2.5 microns (µg/m ³), Worst 24 Hours ²	85.4	103.8	36.7
Number of days of federal exceedances (>35 µg/m ³)	8	9	1

¹ Data obtained from the Long Beach – 2425 Webster Street.

² Data obtained from the Long Beach – Route 710 Near Road

Source: CARB 2020a

Air Quality Management Plan

Under state law, the SCAQMD is required to prepare a plan for air quality improvement for pollutants for which its jurisdiction is in non-compliance. The SCAQMD updates the plan every three years. Each iteration of the SCAQMD's Air Quality Management Plan (AQMP) is an update of the previous plan and has a 20-year horizon. The latest AQMP, the 2016 AQMP, was adopted on March 3, 2017. It incorporates new scientific data and notable regulatory actions that have occurred since adoption of the 2012 AQMP, including the approval of the new federal eight-hour ozone standard of 0.070 ppm that was finalized in 2015. The Final 2016 AQMP addresses several state and federal planning requirements and incorporates new scientific information, primarily in the form of updated emissions inventories, ambient measurements, and meteorological air quality models. The Southern California Association of Governments' (SCAG) projections for socio-economic data (e.g., population, housing, employment by industry) and transportation activities from the 2016 Regional Transportation Plan/Sustainable Communities Strategy (2016 RTP/SCS) are integrated into the 2016 AQMP. The 2016 AQMP builds upon the approaches taken in the 2012 AQMP for the attainment of federal PM and ozone standards and highlights the significant amount of reductions to be achieved. It emphasizes the need for interagency planning to identify additional strategies to

achieve reductions within the timeframes allowed under the federal Clean Air Act, especially in the area of mobile sources. The 2016 AQMP also includes a discussion of emerging issues and opportunities, such as fugitive toxic particulate emissions, zero-emission mobile source control strategies, and the interacting dynamics among climate, energy, and air pollution. The 2016 AQMP also demonstrates strategies for attainment of the new federal eight-hour ozone standard and vehicle miles travelled emissions offsets, pursuant to recent USEPA requirements (SCAQMD 2017).

Sensitive Receptors

Ambient air quality standards have been established to represent the levels of air quality considered sufficient, with a margin of safety, to protect public health and welfare. They are designed to protect that segment of the public most susceptible to respiratory distress, such as children under 14; the elderly over 65; people engaged in strenuous work or exercise; and people with cardiovascular and chronic respiratory diseases. Therefore, the majority of sensitive receptor locations are schools, hospitals, and residences. Sensitive receptors in the project vicinity include Dooley Elementary School located immediately north of the project site as well as single family residences located across Del Amo Boulevard, approximated 120 feet south of the project site.

2.2 Impact Analysis

This air quality analysis conforms to the methodologies recommended in the SCAQMD's *CEQA Air Quality Handbook* (1993) and supplemental guidance provided by the SCAQMD, including recommended thresholds for emissions associated with both construction and operation of the project (SCAQMD 2015).

Methodology

The project's construction and operational emissions were estimated using the California Emissions Estimator Model (CalEEMod), version 2016.3.2. CalEEMod uses project-specific information, including the project's land uses, square footages for different uses (e.g., automobile care center, parking lot), and location, to estimate a project's construction and operational emissions.

Construction Emissions

Construction emissions modeled include emissions generated by construction equipment used on-site and emissions generated by vehicle trips associated with construction, such as worker and vendor trips. Emissions were modeled assuming construction of a 3,058 square-foot car wash and 15 parking spaces. Construction phases involved in the construction process are assumed to include site preparation, grading, building construction, paving, and architectural coating. For the purposes of this analysis, the start of construction was assumed to begin in September 2021.

No import or export of soil would be required as it would be balanced on site. Material export would include exporting the removed existing asphalt, which would occur over an approximate 0.46 acre. The existing asphalt surface was estimated to be 4 inches thick with a mass of 145 pounds per cubic foot (National Asphalt Pavement Association, n.d.), resulting in the export of 485 tons of debris. The site preparation phase default in CalEEMod was extended to one week from one day to account for export of debris.

Other details such as construction schedule (outside of the site preparation phase) and equipment use were based on CalEEMod defaults. Architectural coating phase was assumed to start halfway

into building construction to account for coating as segments of the building are constructed. In addition, as detailed in Section 1, *Project Description and Impact Summary*, it was assumed that project construction would comply with all applicable regulatory standards, including SCAQMD Rule 403 (RCM-1 Fugitive Dust), SCAQMD Rule 402 (RCM-2 Odor Compliance), Section 2485 of Title 13 of the California Code of Regulations (RCM-3 Engine Idling), Section 93115 of Title 17 of the California Code of Regulations (RCM-4 Emission Standards) and Rule 1113 (RCM-5 Architectural Coatings).

Operational Emissions

CalEEMod does not contain a land use directly correlated to a car wash use; the project's car wash was attributed to the "Automobile Care Center" land use subtype, with mobile, energy, and water use modified for the unique characteristics of a car wash, as described below and in Section 3.2. Operational sources of criteria pollutant emissions include mobile source emissions (i.e., vehicle emissions), energy emissions, and area source emissions.

ENERGY SOURCES

Emissions from energy use include electricity and natural gas use. The emissions factors for natural gas combustion are based on USEPA's AP-42 (*Compilation of Air Pollutant Emissions Factors*) and California Climate Action Registry (CCAR) General Reporting Protocol (CCAR 2009). Electricity emissions only apply to GHG emissions (as the energy is generated off-site and therefore may not be relevant for local and regional air quality conditions) and are calculated by multiplying the energy use times the carbon intensity of the utility district per kilowatt hour (CAPCOA 2017). The default electricity consumption values in CalEEMod include the CEC-sponsored California Commercial End Use Survey (CEUS) and Residential Appliance Saturation Survey (RASS) studies. CalEEMod currently incorporates California's 2016 Title 24 building energy efficiency standards.

Data from professional car wash industry surveys and reports were used to estimate the energy requirements for the proposed car wash. The annual number of vehicles that would be washed for the project was estimated based on a 2015 industry survey, which reported an average of approximately 80,000 vehicles per year for exterior-only automated conveyor car washes (Professional Car Washing 2017). The energy requirements for the car wash were estimated using car wash industry survey cost averages of \$0.50 per vehicle for electricity and \$0.12 per vehicle for natural gas (Professional Car Washing 2014). The cost of \$0.50 for electricity was converted to 4.69 kilowatt hours (kwh) per vehicle for electricity based on an average cost of \$0.1066 per kwh for commercial customers in the U.S. in 2017 (U.S. Energy Information Administration [USEIA] 2018a) for a total annual electricity use of 375,200 kwh per year. The cost of \$0.12 for natural gas was converted to 15.79 kilo-British Thermal Units (kBtu) per vehicle for natural gas based average cost of \$7.88 per 1,000 cubic feet² for commercial customers in the U.S. in 2017 (USEIA 2018b) for a total annual natural gas use of 1,263,200 kBtu per year.

AREA SOURCES

Emissions associated with area sources, including consumer products, landscape maintenance, and architectural coating were calculated in CalEEMod and utilize standard emission rates from CARB, USEPA, and emission factor values provided by the local air district (CAPCOA 2017).

² For natural gas, 1,000 cubic feet = 1,037 kBtu

MOBILE SOURCES

Mobile source emissions consist of emissions generated by customers to the project site and vehicles using the car wash. According to the project's Traffic Impact Analysis (Kimley Horn 2021), the project would generate 738 trips per day.

ON-SITE EXHAUST EMISSIONS

Criteria pollutant emissions of CO, PM₁₀, PM_{2.5}, SO₂, and the ozone precursors ROG and NO_x, would occur from vehicles using the project site. Emissions from the vehicles of customers who utilize the car wash, including the queue, are running exhaust emissions, which occur as the user slowly moves through the car wash. Running exhaust emissions occur after the engine is warmed up and the emissions control system in the vehicle have reached full operating temperature. As the vehicles would be in operation the entire time while in queue or in the car wash (i.e., no engine start up or shut off), only emissions associated with a running engine are calculated.

Emission factors used to calculate running exhaust emissions were obtained from the California Air Resources Board's (CARB's) Emission FACTor 2017 database software (EMFAC2017). EMFAC2017 produces emissions factors for each mode of engine operations specific to various vehicle classes and emissions control technologies for a range of vehicle speeds, soak times, variable start times, and ambient temperatures. Inputs in EMFAC2017 included calendar year, the air district, vehicle model year, fuel types, and speeds. The flowing parameters were used to develop the emission factors:

Calendar Year: 2020

Air District: SCAQMD

Vehicle Model Years: All years aggregated

Fuel Type: All

Speeds: 5 miles per hour (mph) (the lowest speed available)

The vehicles would be idling for a portion of their time in the queue and while going through the car wash; therefore, idle time emissions for light-duty vehicles is incorporated into the running exhaust emissions by multiplying the emission factors by five per the EMFAC2017 Guidance manual.

The emission factors for the EMFAC2017 vehicle passenger vehicle categories (LDA, LDT1, LDT2, and MDV) were weighted according to the vehicle miles traveled (VMT) for each vehicle category, and after weighting were averaged to obtain one emission factor per pollutant. Emission factors are provided in grams per mile. Although vehicles would only travel approximately 350 feet through the queue and car wash at the project site, the emissions factors used were the most conservative, i.e. all vehicles are modeled at idle for the entire period. Emissions of air quality pollutants in this analysis are compared to the regional thresholds and LSTs.

According to the project applicant, it would take each vehicle approximately five minutes to use the car wash. Since the car wash can move multiple vehicles through at once, according to the project applicant the maximum queuing and carwash process time for a vehicle would be in the range of 6-10 minutes. For the calculations, it was conservatively assumed that each vehicle would be running on site for 10 minutes. According to the project's Traffic Impact Analysis (Kimley Horn 2021), the project would generate 738 trips per day. Therefore, it was assumed that 369 vehicles would pass through the car wash per day.

These exhaust emission factors were added to the CalEEMod emissions results to demonstrate the project's total emissions.

Significance Thresholds

To determine whether a project would result in a significant impact to air quality, Appendix G of the CEQA Guidelines requires consideration of whether a project would:

1. Conflict with or obstruct implementation of the applicable air quality plan
2. Result in a cumulatively considerable net increase of any criteria pollutant for which the project region is in non-attainment under an applicable federal or state ambient air quality standard
3. Expose sensitive receptors to substantial pollutant concentrations
4. Result in other emissions (such as those leading to odors) adversely affecting a substantial number of people

Regional Significance Thresholds

The SCAQMD recommends quantitative regional significance thresholds for temporary construction activities and long-term project operation in the SCAB, shown in Table 4.

Table 4 SCAQMD Regional Significance Thresholds

Construction Thresholds	Operational Thresholds
75 pounds per day of VOC	55 pounds per day of VOC
100 pounds per day of NO _x	55 pounds per day of NO _x
550 pounds per day of CO	550 pounds per day of CO
150 pounds per day of SO _x	150 pounds per day of SO _x
150 pounds per day of PM ₁₀	150 pounds per day of PM ₁₀
55 pounds per day of PM _{2.5}	55 pounds per day of PM _{2.5}
Source: SCAQMD 2019	

Localized Significance Thresholds

In addition to the above regional thresholds, the SCAQMD has developed Localized Significance Thresholds (LSTs) in response to the Governing Board's Environmental Justice Enhancement Initiative (1-4), which was prepared to update the *CEQA Air Quality Handbook* (1993). LSTs were devised in response to concern regarding exposure of individuals to criteria pollutants in local communities and have been developed for NO_x, CO, PM₁₀, and PM_{2.5}. LSTs represent the maximum emissions from a project that will not cause or contribute to an air quality exceedance of the most stringent applicable federal or State ambient air quality standard at the nearest sensitive receptor, taking into consideration ambient concentrations in each source receptor area (SRA), distance to the sensitive receptor, and project size. By taking into consideration ambient concentrations in each SRA, LSTs are able to account for the existing conditions of an area – if an area is more polluted than others, it will have stricter LSTs. The LST values in SRA-4, where the project is located, are some of the strictest in the entire SCAQMD region. For example, for the gradual conversion of NO_x to NO₂ during construction or operation on a 1-acre site, the limits are the 2nd strictest out of 38 SRAs, only behind SRA-12 (South Central LA County). SRA-4 also has the lowest possible thresholds of one pound per day for PM₁₀ and PM_{2.5}.

LSTs have been developed for emissions generated in construction areas up to five acres in size. However, LSTs only apply to emissions in a fixed stationary location and are not applicable to mobile sources, such as cars on a roadway (SCAQMD 2008). As such, LSTs are typically applied only to

construction emissions because the majority of operational emissions are associated with project-generated vehicle trips.

The SCAQMD provides LST lookup tables for project sites that measure one, two, or five acres. Operation of the car wash would occur on an area less than one acre in size; therefore, this analysis utilizes the one-acre LSTs. LSTs are provided for receptors at 82 to 1,640 feet from the project disturbance boundary to the sensitive receptors. Operational activity of the car wash and queue line would occur approximately 25 feet to 100 feet from the school to the north. According to the SCAQMD's publication, *Final LST Methodology*, projects with boundaries located closer than 82 feet to the nearest receptor should use the LSTs for receptors located at 82 feet. Therefore, the analysis below uses the LST values for 82 feet. In addition, as stated above, the project is in SRA-4 (South Coastal LA County). LSTs for operation in SRA-4 on a 1-acre site with a receptor 82 feet away are shown in Table 5.

Table 5 SCAQMD LSTs (SRA-4)

Pollutant	Allowable Emissions for a 1-acre Site in SRA 4 for a Receptor 82 Feet Away (lbs/day)	
	Construction	Operation
Gradual conversion of NO _x to NO ₂	57	57
CO	585	585
PM ₁₀	4	1
PM _{2.5}	3	1

Source: SCAQMD 2009

Project Impacts

Threshold 1	Would the project conflict with or obstruct implementation of the applicable air quality plan? LESS THAN SIGNIFICANT
--------------------	---

A project may be inconsistent with the AQMP if it would generate population, housing, or employment growth exceeding the forecasts used in the development of the AQMP. The 2016 AQMP relies on local general plans and the demographic forecasts contained in the SCAG 2016 RTP/SCS in its own projections for managing air quality in the SCAB. As such, projects that propose development that is consistent with the growth anticipated by SCAG's growth projections and/or the General Plan would not conflict with the SCAQMD AQMP. In the event that a project would propose development that is less dense than anticipated by the growth projections, the project would likewise be consistent with the AQMP.

The employment growth forecasts in SCAG's 2016 RTP/SCS for the City estimate that the total number of jobs would increase from 153,200 in 2012 to 181,700 in 2040, for an increase of 28,500 jobs. The minor increase in employment anticipated from a car wash (i.e., several employees) would be within the SCAG's projected 2040 employment increase of 2,500 jobs and the project would not cause employment in the City to exceed official regional employment projections.

In addition, the AQMP provides strategies and measures to reach attainment with the thresholds for 8-hour and 1-hour ozone and PM_{2.5}. As shown in Table 6 and Table 7 below, the project would not generate criteria pollutant emissions that would exceed SCAQMD thresholds for ozone precursors

(ROG and NO_x) and PM_{2.5}. Since the project's employment would be within SCAG 2016 forecasts, the project would be consistent with the AQMP and impacts would be less than significant.

Threshold 2 Would the project result in a cumulatively considerable net increase of any criteria pollutant for which the project region is in non-attainment under an applicable federal or state ambient air quality standard? **LESS THAN SIGNIFICANT**

Construction Impacts

Table 6 summarizes the estimated maximum daily emissions of pollutants associated with construction of the proposed project. As shown below, VOC, NO_x, CO, SO₂, PM₁₀, and PM_{2.5} emissions would not exceed SCAQMD regional thresholds or LSTs. Because air pollutant emissions generated by project construction would not exceed SCAQMD's regional significance thresholds or LSTs, project construction would not result in a cumulatively considerable net increase of any criteria pollutant for which the project region is in non-attainment, and impacts would be less than significant.

Table 6 Project Construction Emissions

Year	Maximum Emissions (lbs./day)					
	VOC	NO _x	CO	SO ₂ [±]	PM ₁₀	PM _{2.5}
Maximum Daily Emissions	6	10	8	<1	<1	<1
SCAQMD Regional Thresholds	75	100	550	150	150	55
Threshold Exceeded?	No	No	No	No	No	No
Maximum Daily On-site Emissions	6	8	8	<1	<1	<1
SCAQMD Localized Significance Thresholds (LSTs)	N/A	57	585	N/A	4	3
Threshold Exceeded?	N/A	No	No	N/A	No	No

Notes: All emissions modeling was completed using CalEEMod. See Appendix A for modeling results. Some numbers may not add up due to rounding. Emission data is pulled from "mitigated" results, which account for compliance with regulatory compliance measures. Emissions presented are the highest of the winter and summer modeled emissions. Maximum on-site emissions are the highest emissions that would occur on the project site from on-site sources such as heavy construction equipment and architectural coatings and excludes off-site emissions from sources such as construction worker vehicle trips and haul truck trips.

Operational Impacts

REGIONAL EMISSIONS

Table 7 summarizes the project's area, energy, and mobile operational emissions by emission source, as well as the project's on-site exhaust emissions with a 10-minute maximum trip and with 369 vehicles per day through the car wash, compared to regional standards. The majority of project-related operational emissions would result from vehicle trips to and from the site. As shown in Table 7, operational criteria pollutant emissions would not exceed SCAQMD regional thresholds for criteria pollutants. Therefore, the project would not contribute substantially to an existing or projected regional air quality violation, and impacts would be less than significant.

Table 7 Project Operational Emissions - Regional

Emission Source	Maximum Daily Emissions (lbs./day)					
	VOC	NO _x	CO	SO ₂	PM ₁₀	PM _{2.5}
Area	<1	<1	<1	<1	<1	<1
Energy	<1	<1	<1	<1	<1	<1
Mobile	<1	4	8	<1	2	<1
On-site Exhaust	<1	<1	<1	<1	<1	<1
Total Project Emissions - Regional	1	5	8	<1	2	<1
SCAQMD Regional Thresholds	55	55	550	150	150	55
Threshold Exceeded?	No	No	No	No	No	No

Notes: Area, energy, and mobile emissions modeling was completed using CalEEMod; see Appendix A for modeling results. On-site exhaust emission calculations are included in Appendix B. Some numbers may not add up due to rounding. Emission data is pulled from "mitigated" results that include compliance with regulatory compliance measures. Emissions presented are the highest of the winter and summer modeled emissions.

LOCAL EMISSIONS

LSTs only apply to emissions in a fixed stationary location and are not applicable to mobile sources, such as cars on a roadway (SCAQMD 2008). Therefore, the project's local operational emissions without off-site mobile emissions are shown in Table 8, which summarizes the project's area and energy operational emissions, as well as the project's on-site exhaust emissions with a 10-minute maximum trip and with 369 vehicles per day through the car wash. As shown in Table 8, operational criteria pollutant emissions would be well below the SCAQMD local thresholds for criteria pollutants. As a further example of the negligible emissions from the project's operational use compared to SCAQMD LSTs, it would take approximately 375,000 vehicles using the car wash per day to result in PM₁₀ criteria pollutant emissions that would exceed the SCAQMD LSTs for SRA-4. These emissions are so low compared to operational LSTs because these thresholds are developed to capture the most important contributors to local air quality concerns, such as warehouse uses with a substantial amount of heavy trucks in use or industrial point sources. Land uses such as a car wash that only have light-duty vehicle use result in negligible emissions as modern light-duty vehicles are relatively efficient in terms of the local criteria pollutants they generate compared to industrial sources or heavy-duty trucks.

Table 8 Project Operational Emissions - Local

Emission Source	Maximum Daily Emissions (lbs./day)					
	VOC	NO _x	CO	SO ₂	PM ₁₀	PM _{2.5}
Area	0.0711	0.00002	0.00185	0	0.00001	0.00001
Energy	0.0357	0.3242	0.2724	0.00195	0.0246	0.0246
On-site Exhaust	0.010	0.012	0.162	0.001	0.001	0.001
Total Project Emissions - Local	0.1168	0.33622	0.43625	0.00295	0.02561	0.02561
SCAQMD Localized Significance Thresholds (LSTs)	N/A	57	585	N/A	1	1
Threshold Exceeded?	No	No	No	No	No	No

Notes: Area and energy emissions modeling was completed using CalEEMod; see Appendix A for modeling results. On-site exhaust emission calculations are included in Appendix B. Some numbers may not add up due to rounding. Emission data is pulled from “mitigated” results that include compliance with regulatory compliance measures. Emissions presented are the highest of the winter and summer modeled emissions.

Further reducing localized pollutants from the project site to nearby land uses (e.g., Dooley Elementary School) would be the nine-foot cinderblock wall at the northern property boundary. As this wall would be located at a higher height than the exhaust of any vehicle that would use the car wash, it would have the effect of blocking some pollutants that may be emitted by the project’s users. In addition, as shown in Figure 4, the typical and strongest wind direction in the project area is from the northwest, which would typically blow pollutants away from the adjacent school and towards the southeast. Students at Dooley Elementary School using the playground facilities to the north of the project site would face much greater exposure from vehicles on Long Beach Boulevard, which contains tens of thousands of vehicles per day and is only separated from the playground by a chain-link fence, not a block wall like the project site.

Given the aforementioned, the project would not contribute substantially to an existing or projected local air quality violation, and would not have a substantial localized impact to nearby sensitive receptors (e.g., Dooley Elementary School) from criteria pollutant emissions. Impacts would be less than significant.

Cumulative Impacts

The cumulative context for air quality is regional. The SCAB is designated a nonattainment area for the federal and state one-hour and eight-hour ozone standards, the state PM₁₀ standards, the federal 24-hour PM_{2.5} standard, and the federal and state annual PM_{2.5} standard. SCAB is in attainment of all other federal and state standards. The project would contribute particulate matter and the ozone precursors ROG and NO_x to the area during construction and operation. As described above, regional emissions during construction would not violate an air quality standard or contribute substantially to an existing or projected air quality violation; and would be less than significant. With respect to localized impacts, the consideration of cumulative construction particulate matter impacts is limited to cases when projects constructed simultaneously are within a few hundred yards of each other because of: (1) the combination of the short range (distance) of particulate dispersion (especially when compared to gaseous pollutants); and (2) the SCAQMD’s required dust control measures which further limit particulate dispersion from a project site.

Therefore, with the implementation of dust control measures, the unlikelihood that construction would occur within a few hundred yards of major off-site construction, and compliance with SCAQMD regional construction emission thresholds, the project would not contribute a cumulatively considerable amount of pollutants from construction emissions.

Threshold 3 Would the project expose sensitive receptors to substantial pollutant concentrations? LESS THAN SIGNIFICANT

Localized Carbon Monoxide Hotspot Impact

A CO hotspot is a localized concentration of CO that is above a CO ambient air quality standard. Localized CO hotspots can occur at intersections with heavy peak hour traffic. Specifically, hotspots can be created at intersections where traffic levels are sufficiently high such that the local CO concentration exceeds the federal one-hour standard of 35.0 parts per million (ppm) or the federal and state eight-hour standard of 9.0 ppm (CARB 2016).

The entire SCAB is in conformance with state and federal CO standards, and most air quality monitoring stations no longer report CO levels. No stations within the vicinity of the project site have monitored CO in the last eight years. In 2012, the Long Beach – 2425 Webster Street station detected an eight-hour maximum CO concentration of 2.6 ppm, which is substantially below the state and federal standard of 9.0 ppm (CARB 2020a). As shown in Table 6, maximum daily CO emissions generated by project construction would be 8 pounds, and maximum on-site emissions generated by project construction would be 8 pounds, which would not exceed SCAQMD's regional threshold (550 pounds per day) or LST (585 pounds per day) for CO. Likewise, as shown in Table 7, project operations from area, energy, and mobile emissions sources combined would result a net increase in maximum daily CO emissions of approximately 7 pounds. Both the SCAQMD's regional thresholds and LSTs are designed to be protective of public health. Based on the low background level of CO in the project area, ever-improving vehicle emissions standards for new cars in accordance with state and federal regulations, and the project's low level of operational CO emissions, the project would not create new CO hotspots. Therefore, the proposed project would not expose sensitive receptors to substantial CO concentrations, and localized air quality impacts related to CO hot spots would be less than significant.

Toxic Air Contaminants (TACs)

CONSTRUCTION IMPACTS

Construction-related activities would result in short-term, project-generated emissions of diesel particulate matter (DPM) exhaust emissions from off-road, heavy-duty diesel equipment for site preparation grading, building construction, and other construction activities. DPM was identified as a toxic air contaminant (TAC) by CARB in 1998. The potential cancer risk from the inhalation of DPM (discussed in the following paragraphs) outweighs the potential non-cancer health impacts (CARB 2017a).

Generation of DPM from construction projects typically occurs in a single area for a short period. Construction of the proposed project would occur over approximately five years. The dose to which the receptors are exposed is the primary factor used to determine health risk. Dose is a function of the concentration of a substance or substances in the environment and the extent of exposure that person has with the substance. Dose is positively correlated with time, meaning that a longer exposure period would result in a higher exposure level for the Maximally Exposed Individual. The

risks estimated for a Maximally Exposed Individual are higher if a fixed exposure occurs over a longer period of time. According to the OEHHA, health risk assessments, which determine the exposure of sensitive receptors to toxic emissions, should be based on a 30-year exposure period (assumed to be the approximate time that a person spends in a household). OEHHA recommends this risk be bracketed with 9-year and 70-year exposure periods. Health risk assessments should be limited to the period/duration of activities associated with the project.

The maximum PM_{2.5} emissions, which is used to represent DPM emissions for this analysis, would occur during site preparation and grading activities. While site preparation and grading emissions represent the worst-case condition, such activities would only occur for approximately two weeks, less than two percent, one percent, and 0.2 percent of the typical health risk calculation period of 9 years, 30 years, and 70 years, respectively. PM_{2.5} emissions would decrease for the remaining construction period because construction activities such as building construction and paving would require less construction equipment. Therefore, given the aforementioned, DPM generated by project construction is not expected to create conditions where the probability that the Maximally Exposed Individual would contract cancer is greater than 10 in one million or to generate ground-level concentrations of noncarcinogenic TACs that exceed a Hazard Index greater than one for the Maximally Exposed Individual. This impact would be less than significant.

OPERATIONAL IMPACTS

Sources of operational TAC's include, but are not limited to, land uses such as freeways and high-volume roadways, truck distribution centers, ports, rail yards, refineries, chrome plating facilities, dry cleaners using perchloroethylene, and gasoline dispensing facilities. Project operation does not involve any of these uses; therefore, it is not considered a source of TACs. Therefore, impacts would be less than significant.

<p>Threshold 4 Would the project result in other emissions (such as those leading to odors) adversely affecting a substantial number of people? LESS THAN SIGNIFICANT</p>

For construction activities, odors would be short-term in nature and are subject to SCAQMD Rule 402 *Nuisance* (CARB 2018a). Construction activities would be temporary and transitory and associated odors would cease upon construction completion. Accordingly, the proposed project would not create objectionable odors affecting a substantial number of people during construction, and short-term impacts would be less than significant.

Common sources of operational odor complaints include sewage treatment plants, landfills, recycling facilities, and agricultural uses. The proposed project would not include these uses as the proposed project entails basic car wash uses that do not typically emit odors. Solid waste generated by the proposed on-site uses would be collected by a contracted waste hauler, ensuring that any odors resulting from on-site waste would be managed and collected in a manner to prevent the proliferation of odors. Operational odor impacts would be less than significant.

3 Greenhouse Gas Emissions

3.1 Background

This section analyzes GHG emissions associated with the project and potential impacts related to climate change.

Climate Change and Greenhouse Gases

Climate change is the observed increase in the average temperature of Earth's atmosphere and oceans along with other substantial changes in climate (such as wind patterns, precipitation, and storms) over an extended period of time. The term "climate change" is often used interchangeably with the term "global warming," but "climate change" is preferred to "global warming" because it helps convey that there are other changes in addition to rising temperatures. The baseline against which these changes are measured originates in historical records identifying temperature changes that have occurred in the past, such as during previous ice ages. The global climate is continuously changing, as evidenced by repeated episodes of substantial warming and cooling documented in the geologic record. The rate of change has typically been incremental, with warming or cooling trends occurring over the course of thousands of years. The past 10,000 years have been marked by a period of incremental warming, as glaciers have steadily retreated across the globe. However, scientists have observed acceleration in the rate of warming during the past 150 years. Per the United Nations Intergovernmental Panel on Climate Change (IPCC), the understanding of anthropogenic warming and cooling influences on climate has led to a high confidence (95 percent or greater chance) that the global average net effect of human activities has been the dominant cause of warming since the mid-20th century (IPCC 2014).

Gases that absorb and re-emit infrared radiation in the atmosphere are called greenhouse gases (GHGs). The gases that are widely seen as the principal contributors to human-induced climate change include carbon dioxide (CO₂), methane (CH₄), nitrous oxides (N₂O), fluorinated gases such as hydrofluorocarbons (HFCs) and perfluorocarbons (PFCs), and sulfur hexafluoride (SF₆). Water vapor is excluded from the list of GHGs because it is short-lived in the atmosphere, and its atmospheric concentrations are largely determined by natural processes, such as oceanic evaporation.

GHGs are emitted by both natural processes and human activities. Of these gases, CO₂ and CH₄ are emitted in the greatest quantities from human activities. Emissions of CO₂ are largely by-products of fossil fuel combustion, whereas CH₄ results from off-gassing associated with agricultural practices and landfills. Man-made GHGs, many of which have greater heat-absorption potential than CO₂, include fluorinated gases and SF₆ (USEPA 2020). Different types of GHGs have varying global warming potentials (GWPs). The GWP of a GHG is the potential of a gas or aerosol to trap heat in the atmosphere over a specified timescale (generally, 100 years). Because GHGs absorb different amounts of heat, a common reference gas (CO₂) is used to relate the amount of heat absorbed to the amount of the gas emissions, referred to as "carbon dioxide equivalent" (CO₂e), and is the amount of a GHG emitted multiplied by its GWP. Carbon dioxide has a 100-year GWP of one. By contrast, methane CH₄ has a GWP of 25, meaning its global warming effect is 25 times greater than carbon dioxide on a molecule per molecule basis (IPCC 2007).

The accumulation of GHGs in the atmosphere regulates the earth's temperature. Without the natural heat trapping effect of GHGs, Earth's surface would be about 34° C cooler (CalEPA 2006).

However, emissions from human activities, particularly the consumption of fossil fuels for electricity production and transportation, have elevated the concentration of these gases in the atmosphere beyond the level of naturally occurring concentrations.

Greenhouse Gas Emissions Inventory

Worldwide anthropogenic emissions of GHGs were approximately 46,000 million metric tons (MMT, or gigatonne) CO₂e in 2010 (IPCC 2014). CO₂ emissions from fossil fuel combustion and industrial processes contributed about 65 percent of total emissions in 2010. Of anthropogenic GHGs, CO₂ was the most abundant, accounting for 76 percent of total 2010 emissions. Methane emissions accounted for 16 percent of the 2010 total, while N₂O and fluorinated gases accounted for 6 percent and 2 percent respectively (IPCC 2014).

Total United States (U.S.) GHG emissions were 6,676.6 MMT CO₂e in 2018. Since 1990, total U.S. emissions have increased by an average annual rate of 0.13 percent for a total increase of 3.7 percent since 1990. Emissions increased by 2.9 percent from 2017 to 2018. The increase from 2017 to 2018 was primarily the result of increased fossil fuel combustion due to several factors, including increased energy use from greater heating and cooling needs due to a colder winter and hotter summer in 2018 as compared to 2017. In 2018, the industrial and transportation end-use sectors accounted for 29 percent and 28 percent, respectively, of GHG emissions while the residential and commercial end-use sectors each accounted for 16 percent of GHG emissions with electricity emissions distributed among the various sectors (USEPA 2020).

Based on the CARB's California Greenhouse Gas Inventory for 2000-2017, California produced 424.1 MMT CO₂e in 2017. The major source of GHG emissions in California is transportation, contributing 41 percent of the state's total GHG emissions. The industrial sector is the second largest source, contributing 24 percent of the state's GHG emissions, while electric power accounts for approximately 15 percent (CARB 2019a). California emissions are due in part to its large size and large population compared to other states. However, a factor that reduces California's per capita fuel use and GHG emissions, as compared to other states, is its relatively mild climate. In 2016, the State of California achieved its 2020 GHG emission reduction target as emissions fell below 431 MMT CO₂e (CARB 2019a). The annual 2030 statewide target emissions level is 260 MMT CO₂e (CARB 2017b).

Potential Effects of Climate Change

Globally, climate change has the potential to affect numerous environmental resources though potential impacts related to future air temperatures and precipitation patterns. Scientific modeling predicts that continued GHG emissions at or above current rates would induce more extreme climate changes during the 21st century than were observed during the 20th century. Each of the past three decades has been warmer than all the previous decades in the instrumental record, and the five warmest years in the 1880-2019 record have all occurred since 2015 with nine of the 10 warmest years occurring since 2005. The observed global mean surface temperature in 2019 was approximately 0.95°C (1.71 degrees Fahrenheit) higher than the average global mean surface temperature over the period from 1880 to 2019 (National Oceanic and Atmospheric Administration 2019). Furthermore, several independently analyzed data records of global and regional Land-Surface Air Temperature (LSAT) obtained from station observations are in agreement that LSAT as well as sea surface temperatures have increased. Due to past and current activities, anthropogenic GHG emissions are increasing global mean surface temperature at a rate of 0.2°C per decade. In

addition to these findings, there are identifiable signs that global warming is currently taking place, including substantial ice loss in the Arctic over the past two decades (IPCC 2014 and 2018).

According to *California's Fourth Climate Change Assessment*, statewide temperatures from 1986 to 2016 were approximately 1 to 2 degrees Fahrenheit (°F) higher than those recorded from 1901 to 1960. Potential impacts of climate change in California may include loss in water supply from snowpack, sea level rise, more extreme heat days per year, more large forest fires, and more drought years (State of California 2018). While there is growing scientific consensus about the possible effects of climate change at a global and statewide level, current scientific modeling tools are unable to predict what local impacts may occur with a similar degree of accuracy. In addition to statewide projections, *California's Fourth Climate Change Assessment* includes regional reports that summarize climate impacts and adaptation solutions for nine regions of the state as well as regionally-specific climate change case studies (State of California 2018). Below is a summary of some of the potential effects that could be experienced in California as a result of climate change.

Air Quality

Higher temperatures, which are conducive to air pollution formation, could worsen air quality in California. Climate change may increase the concentration of ground-level ozone, but the magnitude of the effect, and therefore its indirect effects, are uncertain. As temperatures have increased in recent years, the area burned by wildfires throughout the state has increased, and wildfires have been occurring at higher elevations in the Sierra Nevada Mountains (State of California 2018). If higher temperatures continue to be accompanied by an increase in the incidence and extent of large wildfires, air quality would worsen. However, if higher temperatures are accompanied by wetter, rather than drier conditions, the rains would tend to temporarily clear the air of particulate pollution and reduce the incidence of large wildfires, thereby ameliorating the pollution associated with wildfires. Additionally, severe heat accompanied by drier conditions and poor air quality could increase the number of heat-related deaths, illnesses, and asthma attacks throughout the state (California Natural Resources Agency 2009).

In the Los Angeles region, changes in meteorological conditions under climate change will affect future air quality. Regional stagnation conditions may occur more often in the future, which would increase pollutant concentrations (State of California 2018b). Hotter future temperatures will act to increase surface ozone concentrations both due to chemistry producing more ozone and higher rates of biogenic emissions, while increases of water vapor also influence chemistry by increasing ozone production in already polluted areas. Changes in ozone may increase in the future however, changes in particulate matter are less certain. Projected changes by 2050 are generally not statistically significant (State of California 2018b).

Water Supply

Analysis of paleoclimatic data (such as tree-ring reconstructions of stream flow and precipitation) indicates a history of naturally and widely varying hydrologic conditions in California and the west, including a pattern of recurring and extended droughts. Year-to-year variability in statewide precipitation levels has increased since 1980, meaning that wet and dry precipitation extremes have become more common (California Department of Water Resources 2018). This uncertainty regarding future precipitation trends complicates the analysis of future water demand, especially where the relationship between climate change and its potential effect on water demand is not well understood. However, the average early spring snowpack in the western United States, including the Sierra Nevada Mountains, decreased by about 10 percent during the last century. During the

same period, sea level rose over 5.9 inches along the central and southern California coast (State of California 2018). The Sierra snowpack provides the majority of California's water supply by accumulating snow during the state's wet winters and releasing it slowly during the state's dry springs and summers. A warmer climate is predicted to reduce the fraction of precipitation falling as snow and result in less snowfall at lower elevations, thereby reducing the total snowpack (DWR 2008; State of California 2018). The State of California projects that average spring snowpack in the Sierra Nevada and other mountain catchments in central and northern California will decline by approximately 66 percent from its historical average by 2050 (State of California 2018).

Like the rest of the state, the Greater Los Angeles region is expected to face a challenging combination of decreased water supply and increased water demand (State of California 2018b). Greater interannual variability of rainfall and sharp decreases in snowpack will create surface water limitations for the region. Although the effect of climate change on average precipitation in the region is still unclear, more frequent occurrences of extreme events like the 2011-2016 drought could substantially decrease groundwater recharge, which is essential for the sustainability of agriculture in the region since the vast majority of water used in agriculture in the region is groundwater from local wells. Furthermore, higher temperatures mean that dry years will more quickly develop into severe drought conditions.

Hydrology and Sea Level Rise

Climate change could potentially affect the intensity and frequency of storms and flooding. Furthermore, climate change has the potential to induce substantial sea level rise in the coming century (State of California 2018). The rising sea level increases the likelihood and risk of flooding. The rate of increase of global mean sea levels over the 2001-2010 decade, as observed by satellites, ocean buoys and land gauges, was approximately 3.2 mm per year, which is double the observed 20th century trend of 1.6 mm per year. As a result, global mean sea levels averaged over the last decade were about 8 inches higher than those of 1880 (World Meteorological Organization 2013). Sea levels are rising faster now than in the previous two millennia, and the rise is expected to accelerate, even with robust GHG emission control measures. The most recent IPCC report predicts a mean sea-level rise of 10 to 37 inches by 2100 (IPCC 2018). A rise in sea levels could completely erode 31 to 67 percent of southern California beaches, result in flooding of approximately 370 miles of coastal highways during 100-year storm events, jeopardize California's water supply due to salt water intrusion, and induce groundwater flooding and/or exposure of buried infrastructure (State of California 2018). In addition, increased CO₂ emissions can cause oceans to acidify due to the carbonic acid it forms. Increased storm intensity and frequency could affect the ability of flood-control facilities, including levees, to handle storm events.

As discussed above, climate change could potentially affect the amount of snowfall, rainfall, and snow pack; the intensity and frequency of storms; flood hydrographs (flash floods, rain or snow events, coincidental high tide and high runoff events); sea level rise and coastal flooding; coastal erosion; and the potential for salt water intrusion. In the Greater Los Angeles region, despite small changes in average precipitation, dry and wet extremes are both expected to increase (State of California 2018b). By the late 21st century, the wettest day of the year is expected to increase across most of the region. Increased frequency and severity of atmospheric river events are also projected to occur for this region.

Agriculture

California has a \$50 billion annual agricultural industry that produces over a third of the country's vegetables and two-thirds of the country's fruits and nuts (California Department of Food and Agriculture 2019). Higher CO₂ levels can stimulate plant production and increase plant water-use efficiency. However, if temperatures rise and drier conditions prevail, certain regions of agricultural production could experience water shortages of up to 16 percent; water demand could increase as hotter conditions lead to the loss of soil moisture; crop-yield could be threatened by water-induced stress and extreme heat waves; and plants may be susceptible to new and changing pest and disease outbreaks (State of California 2018). In addition, temperature increases could change the time of year certain crops, such as wine grapes, bloom or ripen, and thereby affect their quality (California Climate Change Center 2006). More frequent droughts could substantially decrease groundwater recharge and therefore adversely affect agricultural operations that use groundwater from local wells (State of California 2018b). This could contribute to higher food prices and shortages.

Ecosystems and Wildlife

Climate change and the potential resulting changes in weather patterns could have ecological effects on a global and local scale. Increasing concentrations of GHGs are likely to accelerate the rate of climate change. Scientists project that the annual average maximum daily temperatures in California could rise by 4.4 to 5.8°F in the next 50 years and by 5.6 to 8.8°F in the next century (State of California 2018a). Soil moisture is likely to decline in many regions, and intense rainstorms are likely to become more frequent. Rising temperatures could have four major impacts on plants and animals related to: (1) timing of ecological events; (2) geographic distribution and range; (3) species' composition and the incidence of nonnative species within communities; and (4) ecosystem processes, such as carbon cycling and storage (Parmesan 2006; State of California 2018). Increases in wildfire would further remove sensitive habitat; increased severity in droughts would potentially starve plants and animals of water; and sea level rise will affect sensitive coastal ecosystems.

Regulatory Setting

The following regulations address both climate change and GHG emissions.

Federal Regulations

FEDERAL CLEAN AIR ACT

The U.S. Supreme Court in *Massachusetts et al. v. Environmental Protection Agency et al.* ([2007] 549 U.S. 497) held that the USEPA has the authority to regulate motor-vehicle GHG emissions under the federal Clean Air Act. The USEPA issued a Final Rule for mandatory reporting of GHG emissions in October 2009. This Final Rule applies to fossil fuel suppliers, industrial gas suppliers, direct GHG emitters, and manufacturers of heavy-duty and off-road vehicles and vehicle engines and requires annual reporting of emissions. In 2012, the USEPA issued a Final Rule that establishes the GHG permitting thresholds that determine when Clean Air Act permits under the New Source Review Prevention of Significant Deterioration (PSD) and Title V Operating Permit programs are required for new and existing industrial facilities.

In *Utility Air Regulatory Group v. Environmental Protection Agency* (134 Supreme Court 2427 [2014]), the U.S. Supreme Court held the USEPA may not treat GHGs as an air pollutant for purposes of determining whether a source can be considered a major source required to obtain a PSD or

Title V permit. The Court also held that PSD permits otherwise required based on emissions of other pollutants may continue to require limitations on GHG emissions based on the application of Best Available Control Technology.

SAFER AFFORDABLE FUEL-EFFICIENT VEHICLES RULE

On September 27, 2019, the USEPA and the National Highway Safety Administration published the SAFE Vehicles Rule Part One: One National Program. The Part One Rule revokes California's authority to set its own GHG emissions standards and zero-emission vehicle mandates in California. To account for the effects of the Part One Rule, CARB released off-model adjustment factors on November 20, 2019 to adjust criteria air pollutant emissions outputs from the EMFAC model. The Final SAFE Rule (i.e., Part Two) then relaxed federal GHG emissions and Corporate Average Fuel Economy (CAFE) standards to increase in stringency at only about 1.5 percent per year from model year 2020 levels over model years 2021– 2026 (CARB 2020b). The previously established emission standards and related fuel economy standards would have achieved about four percent per year improvements through model year 2025. Therefore, CARB has prepared off-model CO₂ emissions adjustment factors for both the EMFAC2014 and EMFAC2017 models to account for the impact of the SAFE Vehicles Rule (CARB 2020c). With the incorporation of these adjustment factors, operational emission factors for CO₂ generated by light-duty automobiles, light-duty trucks, and medium-duty trucks associated with project-related vehicle trips may increase by approximately one percent (in 2020) up to as much as 17 percent (in 2050) compared to non-adjusted estimates. These increases would not alter the significance of the operational GHG emissions from development facilitated by the project as discussed further below.

California Regulations

CARB is responsible for the coordination and oversight of state and local air pollution control programs in California. California has numerous regulations aimed at reducing the state's GHG emissions. These initiatives are summarized below.

CALIFORNIA GLOBAL WARMING SOLUTIONS ACT OF 2006 (ASSEMBLY BILL 32 AND SENATE BILL 32)

The "California Global Warming Solutions Act of 2006," Assembly Bill (AB) 32, outlines California's major legislative initiative for reducing GHG emissions. AB 32 codifies the statewide goal of reducing GHG emissions to 1990 levels by 2020 and requires CARB to prepare a Scoping Plan that outlines the main state strategies for reducing GHG emissions to meet the 2020 target. In addition, AB 32 requires CARB to adopt regulations to require reporting and verification of statewide GHG emissions. Based on this guidance, CARB approved a 1990 statewide GHG level and 2020 target of 431 MMT CO₂e. On December 11, 2008, CARB approved the Climate Change Scoping Plan, which included measures to address GHG emission reduction strategies related to energy efficiency, water use, and recycling and solid waste, among other sectors (CARB 2008). Many of the GHG emission reduction measures included in the Scoping Plan (e.g., Low Carbon Fuel Standard and Cap-and-Trade) have been adopted since the plan's approval.

CARB approved the 2013 Scoping Plan Update in May 2014. The update defined CARB's climate change priorities for the next five years and set the groundwork to reach post-2020 statewide goals. The update highlighted California's progress toward meeting the "near-term" 2020 GHG emission reduction goals defined in the original Scoping Plan. It also evaluated how to align the state's longer term GHG reduction strategies with other state policy priorities, including those for water, waste, natural resources, clean energy, transportation, and land use (CARB 2014).

On September 8, 2016, the governor signed Senate Bill (SB) 32 into law, extending the California Global Warming Solutions Act of 2006 by requiring the state to further reduce GHG emissions to 40 percent below 1990 levels by 2030 (the other provisions of AB 32 remain unchanged). On December 14, 2017, CARB adopted the 2017 Scoping Plan, which provides a framework for achieving the 2030 target. The 2017 Scoping Plan relies on the continuation and expansion of existing policies and regulations, such as the Cap-and-Trade Program, and implementation of recently adopted policies and legislation, such as SB 1383 (detailed below). The 2017 Scoping Plan also puts an increased emphasis on innovation, adoption of existing technology, and strategic investment to support its strategies. As with the 2013 Scoping Plan Update, the 2017 Scoping Plan does not provide project-level thresholds for land use development. Instead, it recommends that local governments adopt policies and locally appropriate quantitative thresholds consistent with statewide per capita goals of six metric tons (MT) of CO₂e by 2030 and two MT CO₂e by 2050 (CARB 2017b). As stated in the 2017 Scoping Plan, these goals may be appropriate for plan-level analyses (city, county, sub-regional, or regional level), but not for specific individual projects because they include all emissions sectors in the state (CARB 2017b).

SENATE BILL 375

SB 375, signed in August 2008, enhances the state's ability to reach AB 32 goals by directing the CARB to develop regional GHG emission reduction targets to be achieved from passenger vehicles by 2020 and 2035. SB 375 aligns regional transportation planning efforts, regional GHG reduction targets, and affordable housing allocations. Metropolitan Planning Organizations (MPOs) are required to adopt a Sustainable Communities Strategy (SCS), which allocates land uses in the MPO's Regional Transportation Plan. Qualified projects consistent with an approved SCS or Alternative Planning Strategy (categorized as "transit priority projects") would receive incentives to streamline CEQA processing.

On March 22, 2018, CARB adopted updated regional targets for reducing GHG emissions from 2005 levels by 2020 and 2035. SCAG was assigned targets of an 8 percent reduction in GHGs from transportation sources by 2020 and a 19 percent reduction in GHGs from transportation sources by 2035. In the SCAG region, SB 375 also provides the option for the coordinated development of sub regional plans by the sub regional councils of governments and the county transportation commissions to meet SB 375 requirements.

SENATE BILL 1383

Adopted in September 2016, SB 1383 requires CARB to approve and begin implementing a comprehensive strategy to reduce emissions of short-lived climate pollutants. SB 1383 requires the strategy to achieve the following reduction targets by 2030:

- Methane – 40 percent below 2013 levels
- Hydrofluorocarbons – 40 percent below 2013 levels
- Anthropogenic black carbon – 50 percent below 2013 levels

SB 1383 also requires the California Department of Resources Recycling and Recovery (CalRecycle) in consultation with the CARB, to adopt regulations that achieve specified targets for reducing organic waste in landfills.

SENATE BILL 100

Adopted on September 10, 2018, SB 100 supports the reduction of GHG emissions from the electricity sector by accelerating the state's Renewables Portfolio Standard Program, which was last updated by SB 350 in 2015. SB 100 requires electricity providers to increase procurement from eligible renewable energy resources to 33 percent of total retail sales by 2020, 44 percent by 2024, 60 percent by 2030, and 100 percent by 2045.

EXECUTIVE ORDER B-55-18

On September 10, 2018, the governor issued Executive Order B-55-18, which established a new statewide goal of achieving carbon neutrality by 2045 and maintaining net negative emissions thereafter. This goal is in addition to the existing statewide GHG reduction targets established by SB 375, SB 32, SB 1383, and SB 100.

CALIFORNIA ENVIRONMENTAL QUALITY ACT

Pursuant to the requirements of SB 97, the California Natural Resources Agency has adopted amendments to the CEQA Guidelines for determining the effects and feasible mitigation of GHG emissions. The adopted CEQA Guidelines provide general regulatory guidance on the analysis and mitigation of GHG emissions in CEQA documents while giving lead agencies the discretion to set quantitative or qualitative thresholds for the assessment and mitigation of GHGs and climate change impacts. To date, a variety of air districts have adopted quantitative significance thresholds for GHGs.

Regional and Local Regulations

2020-2045 REGIONAL TRANSPORTATION PLAN/SUSTAINABLE COMMUNITIES STRATEGY

On May 7, 2020, SCAG's Regional Council adopted the 2020-2045 RTP/SCS (titled Connect SoCal) for federal transportation conformity purposes and considered approval of the full plan and for all other purposes within 120 days of this date. Following initial adoption, SCAG formally adopted the 2020-2045 RTP/SCS on September 3, 2020 to provide a roadmap for sensible ways to expand transportation options, improve air quality and bolster Southern California's long-term economic viability. The 2020-2045 RTP/SCS builds upon the progress made through implementation of the 2016-2040 RTP/SCS and includes ten goals focused on promoting economic prosperity, improving mobility, protecting the environment, and supporting healthy/complete communities. The SCS implementation strategies include focusing growth near destinations and mobility options, promoting diverse housing choices, leveraging technology innovations, and supporting implementation of sustainability policies. The SCS establishes a land use vision of center-focused placemaking, concentrating growth in and near Priority Growth Areas, transferring of development rights, urban greening, creating greenbelts and community separators, and implementing regional advance mitigation (SCAG 2020b).

City of Long Beach Sustainable City Action Plan

The City of Long Beach's Sustainable City Action Plan (SCAP) was adopted in February 2010 (Long Beach 2010). The SCAP is intended to guide operational, policy, and financial decisions to create a more sustainable Long Beach. The SCAP includes initiatives, goals, and actions that will move Long Beach toward becoming a sustainable city. These goals and actions included in the SCAP relate to the following:

- Buildings & Neighborhoods
- Urban Nature
- Energy
- Waste Reduction
- Green Economy and Lifestyle
- Water
- Transportation

City of Long Beach Climate Action and Adaptation Plan

In 2017, the City of Long Beach began development of a Climate Action and Adaptation Plan (CAAP). The city released a draft plan in 2019, which has not yet been finalized (City of Long Beach 2019b). The CAAP aims to reduce communitywide GHG emissions, and help the city adapt to future climate change impacts. As part of the CAAP, the City conducted a communitywide GHG inventory to identify its baseline emissions footprint and is developing business-as-usual forecasts of emissions based on anticipated growth in population, employment, housing, and other factors in the community. In the next stages of the project, the City will establish GHG reduction targets and define local actions to achieve those targets. The CAAP will provide a framework for creating or updating policies, programs, practices, and incentives for Long Beach residents and businesses to reduce the City's GHG footprint and ensure the community and physical assets are better protected from the impacts of climate change. The policies, programs, practices, and incentives included in the CAAP will relate to the following:

- Public Health
- Parks and Open Space
- Water Supply
- Transportation
- Housing & Neighborhoods
- Energy
- Coastal Resources
- Wastewater/Stormwater

3.2 Impact Analysis

Significance Thresholds

Based on Appendix G of the CEQA Guidelines, impacts related to GHG emissions from the project would be significant if the project would:

- Generate greenhouse gas emissions, either directly or indirectly, that may have a significant impact on the environment
- Conflict with an applicable plan, policy or regulation adopted for the purpose of reducing the emissions of greenhouse gases

Individual projects do not generate enough GHG emissions to substantially influence climate change. However, physical changes caused by a project can contribute incrementally to cumulative effects that may be significant, even if individual changes resulting from a project are limited. The

issue of climate change typically involves an analysis of whether a project's contribution towards an impact would be cumulatively considerable. "Cumulatively considerable" means that the incremental effects of an individual project are significant when viewed in connection with the effects of past projects, other current projects, and probable future projects (CEQA Guidelines, Section 15064[h][1]).

To determine a project-specific threshold, guidance on GHG significance thresholds in the region from SCAQMD, the air district in which the project site is located, was used. The SCAQMD's GHG CEQA Significance Threshold Working Group considered a tiered approach to determine the significance of residential and commercial projects. The draft tiered approach is outlined in meeting minutes dated September 29, 2010 (SCAQMD 2010):

- **Tier 1.** If the project is exempt from further environmental analysis under existing statutory or categorical exemptions, there is a presumption of less than significant impacts with respect to climate change. If not, then the Tier 2 threshold should be considered.
- **Tier 2.** Consists of determining whether the project is consistent with a GHG reduction plan that may be part of a local general plan, for example. The concept embodied in this tier is equivalent to the existing concept of consistency in CEQA Guidelines Section 15064(h)(3), 15125(d) or 15152(a). Under this Tier, if the proposed project is consistent with the qualifying local GHG reduction plan, it is not significant for GHG emissions. If there is not an adopted plan, then a Tier 3 approach would be appropriate.
- **Tier 3.** Establishes a screening significance threshold level to determine significance. The Working Group has provided a recommendation of 3,000 MT CO₂e per year for commercial projects.
- **Tier 4.** Establishes a service population threshold to determine significance. The Working Group has provided a recommendation of 4.8 MT CO₂e per year for land use projects.

Tier 1 would not apply to the project as it is not exempt from environmental analysis. For Tier 2, while the City's CAAP is currently in draft form, it has not adopted a qualified GHG reduction plan at the time of this analysis. Therefore, for a project-specific threshold, the City of Long Beach has selected SCAQMD's 3,000 MT CO₂e per year threshold for commercial projects as the applicable project-specific threshold, in accordance with Tier 3. The SCAQMD's 3,000 MT CO₂e per year threshold is frequently used by jurisdictions across Southern California to determine GHG emissions impacts from commercial projects.

Methodology

Calculations of CO₂, CH₄, and N₂O emissions are provided to estimate the proposed project's potential GHG emissions. Calculations are based on the methodologies discussed in the CAPCOA (2008) *CEQA and Climate Change* white paper and guidance from CARB. GHG emissions associated with the proposed project were calculated using CalEEMod version 2016.3.2 (see Appendix B for CalEEMod results).

Construction Emissions

Construction emissions were modeled in accordance with the methodology outlined in Section 2.2, *Methodology*, under Section 2, *Air Quality*. Complete results from CalEEMod and assumptions can be viewed in Appendix B. In accordance with SCAQMD's recommendation, GHG emissions from construction of the proposed project were amortized over a 30-year period and added to annual

operational emissions to determine the project's total annual GHG emissions. Construction emissions are consistent for the project.

Operational Emissions

In CalEEMod, operational sources for area, energy, and mobile sources were modeled in accordance with the methodology outlined in Section 2.2, *Methodology*, under Section 2, *Air Quality*. As mentioned in Section 2.2, CalEEMod does not contain a land use directly correlated to a car wash use; the project's car wash was attributed to the "Automobile Care Center" land use subtype, with water use modified for the unique characteristics of a car wash, as described below

WASTE SOURCES

GHG emissions from waste generation were also calculated in CalEEMod and are based on the IPCC's methods for quantifying GHG emissions from solid waste using the degradable organic content of waste (CAPCOA 2017). Waste disposal rates by land use and overall composition of municipal solid waste in California was primarily based on data provided by the California Department of Resources Recycling and Recovery (CalRecycle).

WATER AND WASTEWATER SOURCES

GHG emissions from water and wastewater usage calculated in CalEEMod were based on the default electricity intensity from the CEC's 2006 Refining Estimates of Water-Related Energy Use in California using the average values for northern and southern California. A 20 percent reduction in indoor potable water use was incorporated in the model in accordance with CALGreen standards.

Data from professional car wash industry surveys and reports were used to estimate the water requirements for the proposed car wash. The annual number of vehicles washed for the project was estimated based on a 2015 industry survey which reported an average of approximately 80,000 vehicles per year for exterior-only automated conveyor car washes (Professional Car Washing 2017). According to a report on water conservation from the International Carwash Association, typical freshwater use for a friction type of conveyor car wash without water reclamation is 65.8 gallons per vehicle (International Carwash Association 2000). AB 2230, signed by the Governor in 2012, requires that any conveyor car wash installed after 2013 reuse a minimum of 60 percent of the water previously used in the wash or rinse cycles. Therefore, the proposed car wash would reclaim at least 39.5 gallons per vehicle for a total water use of 26.3 gallon per vehicle. Based on 80,000 vehicles washed per year, the estimated water use for the proposed car wash would be 2,104,000 gallons per year.

NITROUS OXIDE EMISSIONS

Because CalEEMod does not calculate N₂O emissions from mobile sources, N₂O emissions were quantified using guidance from CARB and the EMFAC2017 Emissions Inventory for the Los Angeles County region for the project's operational year (2021) using the EMFAC2011 categories (CARB 2019a and 2019b; see Appendix A for calculations).

Impact Analysis

Threshold 1	Would the project generate GHG emissions, either directly or indirectly, that may have a significant impact on the environment? LESS THAN SIGNIFICANT
--------------------	--

GHG Emissions Quantification

CONSTRUCTION EMISSIONS

As shown in Table 9, construction activity for the project would generate an estimated 62 MT of CO₂e. When amortized over a 30-year period, construction of the project would generate approximately 2 MT of CO₂e per year.

Table 9 Estimated Construction Greenhouse Gas Emissions

Construction Year	Annual Emissions MT CO ₂ e
2021	62
Amortized over 30 years	2
Notes: See Appendix A for modeling results. Some numbers may not add up precisely due to rounding considerations.	

OPERATIONAL AND TOTAL PROJECT EMISSIONS

Table 10 combines the construction and operational GHG emissions associated with development of the project. As shown, annual emissions from the proposed project would be approximately 651 MT of CO₂e. These emissions would not exceed SCAQMD's 3,000 MT per year threshold. Therefore, impacts from GHG emissions would be less than significant.

Table 10 Estimated Annual Greenhouse Gas Emissions

Emission Source	Annual Emissions MT CO ₂ e
Construction	2
Operational	
Area	<0.1
Energy	183
Mobile	455
Solid Waste	6
Water	8
Net Total	651
SCAQMD Threshold	3,000
Exceeds Threshold?	No
Notes: Emissions modeling was completed using CalEEMod, except for N ₂ O mobile emissions (see Section 3.1 for methodology). See Appendix A for modeling results and N ₂ O emissions calculations. Some numbers may not add up precisely due to rounding considerations.	

Threshold 2	Would the project conflict with an applicable plan, policy or regulation adopted for the purpose of reducing the emissions of GHGs? LESS THAN SIGNIFICANT
--------------------	--

Consistency with Applicable Plans and Policies

STATE POLICIES

There are numerous State plans, policies, and regulations adopted to reduce GHG emissions. The principal state plan and policy is AB 32, the California Global Warming Solutions Act of 2006, and the follow up, SB 32. The quantitative goal of AB 32 is to reduce GHG emissions to 1990 levels by 2020 and the goal of SB 32 is to reduce GHG emissions to 40 percent below 1990 levels by 2030. Pursuant to the SB 32 goal, the 2017 Scoping Plan was created to outline goals and measures for the State to achieve the reductions. The 2017 Scoping Plan's goals include reducing fossil fuel use and energy demand and maximizing recycling and diversion from landfills. The project would comply with the latest Title 24 Green Building Code and Building Efficiency Energy Standards and the AB 341 waste diversion goal of 75 percent. Therefore, the project is consistent with the applicable GHG reduction strategies in the 2017 Scoping Plan.

2020-2045 RTP/SCS

According to the 2020-2045 RTP/SCS, the updated targets for the SCAG region are eight percent below 2005 per capita emission levels by 2020 (this value is unchanged from the previous 2020 CARB target) and 19 percent below 2005 per capita emissions levels by 2035. The revised 2035 target is higher than the previous CARB target of 13 percent for the SCAG region. The 2020-2045 RTP/SCS includes implementation strategies for focusing growth near destinations and mobility options, promoting diverse housing choices, leveraging technology innovations, supporting implementation of sustainability policies, and promoting a green region. Further specific actions to reduce greenhouse gas emissions under the 2020-2045 RTP/SCS include designing transportation options that reduce the reliance on solo car trips, promoting low emission technologies such as electric vehicles and ride sharing, supporting statewide greenhouse gas emissions legislation, and pursuing funding opportunities to support local sustainable development projects that reduce GHG emissions. In general, a car wash use is planned to satisfy existing vehicle transportation demand and is inherently not oriented for sustainable transportation uses such as transit or rail. The car wash would be used by electric vehicles in a similar fashion to gasoline vehicles. Therefore, sustainable transportation initiatives would not apply to the project.

LOCAL POLICIES

The overarching goal of the City's SCAP and CAAP are to increase sustainability and reduce GHG emissions within the City. The project would comply with the latest Title 24 Green Building Code and Building Efficiency Energy Standards and the AB 341 waste diversion goal of 75 percent. This would be consistent with the overarching goals of the City's SCAP and CAAP.

SUMMARY

Given the above considerations regarding SCAG's 2020 RTP/SCS, the City's SCAP and CAAP, the 2017 Scoping Plan, and additional state requirements, the project is consistent with State and local policies for reducing GHG emissions, and no impacts would occur.

4 Conclusions and Recommendations

As detailed above, neither construction nor operation of the project would result in significant air quality or GHG emissions impacts. The project would be required to comply with the following RCMs, which were assumed in the modeling and analysis because the project is required to comply with them through state and local regulations.

Regulatory Compliance Measures

RCM-1 Demolition, Grading, and Construction Activities: Compliance with provisions of SCAQMD Rule 403.

The project shall comply with all applicable standards of the SCAQMD, including the following provisions of Rule 403:

- All unpaved demolition and construction areas shall be wetted at least twice daily during excavation and construction, and temporary dust covers shall be used to reduce dust emissions and meet SCAQMD Rule 403. Wetting could reduce fugitive dust by as much as 50 percent.
- The construction area shall be kept sufficiently dampened to control dust caused by grading and hauling, and at all times provide reasonable control of dust caused by wind.
- All clearing, earth moving, or excavation activities shall be discontinued during periods of high winds (i.e., greater than 15 miles per hour), so as to prevent excessive amounts of dust.
- All dirt/soil shall be secured by trimming, watering, or other appropriate means to prevent spillage and dust.
- All dirt/soil materials transported off-site shall be either sufficiently watered or securely covered to prevent excessive amounts of dust.
- General contractors shall maintain and operate construction equipment so as to minimize exhaust emissions.
- Trucks having no current hauling activity shall not idle but be turned off.

RCM-2 Odors: Compliance with Provisions of SCAQMD Rule 402

The project shall comply with the following provision of SCAQMD Rule 402: a person shall not discharge from any source whatsoever such quantities of air contaminants or other material which cause injury, detriment, nuisance, or annoyance to any considerable number of persons or to the public, or which endanger the comfort, repose, health or safety of any such persons or the public, or which cause, or have a natural tendency to cause, injury or damage to business or property.

RCM-3 Engine Idling

In accordance with Section 2485 of Title 13 of the California Code of Regulations, the idling of all diesel-fueled commercial vehicles (weighing over 10,000 pounds) during construction shall be limited to five minutes at any location.

RCM-4 Emission Standards

In accordance with Section 93115 of Title 17 of the California Code of Regulations, operation of any stationary, diesel-fueled, compression-ignition engines shall meet specified fuel and fuel additive requirements and emission standards.

RCM-5 Architectural Coatings: Compliance with SCAQMD Rule 1113

The project shall comply with SCAQMD Rule 1113 limiting the volatile organic compound (VOC) content of architectural coatings.

5 References

- Association of Environmental Professionals (AEP). 2016. Final White Paper Beyond 2020 and Newhall: A Field Guide to New CEQA Greenhouse Gas Thresholds and Climate Action Plan Targets for California. https://califaep.org/docs/AEP-2016_Final_White_Paper.pdf. Accessed November 2020.
- California Air Pollution Control Officers Association (CAPCOA). 2008. CEQA and Climate Change: Addressing Climate Change through California Environmental Quality Act (CEQA). January 2008.
- _____. 2017. California Emissions Estimator Model User's Guide Version 2016.3.2 (accessed November 2020).
- California Air Resources Board (CARB). 2005. Air Quality and Land Use Handbook: A Community Health Perspective. April 2005. <https://www.arb.ca.gov/ch/handbook.pdf> (accessed November 2020).
- _____. 2008. Climate Change Scoping Plan. December 2008. https://www.arb.ca.gov/cc/scopingplan/document/adopted_scoping_plan.pdf (accessed November 2020).
- _____. 2009. Definitions of VOC and ROG. January. Available at: https://ww3.arb.ca.gov/ei/speciate/voc_rog_dfn_1_09.pdf
- _____. 2011 Health Effects of Diesel Exhaust. <http://www.arb.ca.gov/research/diesel/diesel-health.htm> (accessed November 2020).
- _____. 2014. AB 32 Scoping Plan Website. Updated June 2014. <http://www.arb.ca.gov/cc/scopingplan/scopingplan.htm> (accessed November 2020).
- _____. 2016. Ambient Air Quality Standards. Last modified: May 4, 2016. <http://www.arb.ca.gov/research/aaqs/aaqs2.pdf> (accessed November 2020).
- _____. 2017a. *2017 Amendments Health Risk Analysis*. <https://ww2.arb.ca.gov/resources/documents/health-risk-assessment> (accessed November 2020).
- _____. 2017b. California's 2017 Climate Change Scoping Plan. December 14, 2017. https://www.arb.ca.gov/cc/scopingplan/scoping_plan_2017.pdf (accessed November 2020).
- _____. 2018. EMFAC2017 Volume III – Technical Documentation v.1.0.2. July 20, 2018. <https://ww3.arb.ca.gov/msei/downloads/emfac2017-volume-iii-technical-documentation.pdf> (accessed November 2020).
- _____. 2019a. California Greenhouse Gas Emissions for 2000 to 2017 – Trends of Emissions and Other Indicators. [webpage]. <https://ww3.arb.ca.gov/cc/inventory/data/data.htm> (accessed November 2020).
- _____. 2019b. EMFAC2017 Web Database. <https://www.arb.ca.gov/emfac/2017/> (accessed November 2020).

- _____. 2020a. Top 4 Summary: Select Pollutant, Years, & Area.
<https://www.arb.ca.gov/adam/topfour/topfour1.php> (accessed November 2020).
- _____. 2020b. Announcement: EMFAC Off-Model Adjustment Factors for Carbon Dioxide (CO₂) Emissions to Account for the SAFE Vehicles Rule Part One and the Final SAFE Rule. June 26. Available at:
https://ww3.arb.ca.gov/msei/announcement_emfac_off_model%20adjustment-6262020-final.pdf
- _____. 2020c. EMFAC Off-Model Adjustment Factors for Carbon Dioxide (CO₂) Emissions to Account for the SAFE Vehicles Rule Part One and the Final SAFE Rule. June 26. Available at:
https://ww3.arb.ca.gov/msei/emfac_off_model_co2_adjustment_factors_06262020-final.pdf
- California Climate Change Center (CCCC). 2006. Climate Scenarios for California.
- California Department of Finance (DOF). 2019. “E-5 Population and Housing Estimates for Cities, Counties, and the State, 2011-2019, with 2010 Census Benchmark.” Last modified: May 2019. <http://www.dof.ca.gov/Forecasting/Demographics/Estimates/E-5/> (accessed November 2020).
- California Department of Food and Agriculture. 2019. “2018 Crop Year – Top 10 Commodities for California Agriculture.” California Agricultural Production Statistics. [web page].
<https://www.cdafa.ca.gov/statistics/> (accessed November 2020).
- California Department of Resources Recycling and Recovery (CalRecycle). 2015. AB 341 Report to the Legislature. August 2015. <https://www2.calrecycle.ca.gov/Publications/Download/1168> (accessed November 2020).
- California Department of Water Resources. 2018. Indicators of Climate Change in California. Sacramento, CA. May 2018.
- California Environmental Protection Agency. 2006. Climate Action Team Report to Governor Schwarzenegger and the Legislature. March 2006.
- California Energy Commission (CEC). 2018. “2019 Building Energy Efficiency Standards.” March 2018.
- California Natural Resources Agency. 2009. 2009 California Climate Adaptation Strategy. March 2009. http://resources.ca.gov/docs/climate/Statewide_Adaptation_Strategy.pdf (accessed November 2020).
- Intergovernmental Panel on Climate Change (IPCC). 2007. Summary for Policymakers. In: Climate Change 2007: The Physical Science Basis. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change.
- _____. 2014. Climate Change 2014: Mitigation of Climate Change. Summary for Policymakers - Contribution of Working Group III to the Fifth Assessment Report of the Intergovernmental Panel on Climate Change. Cambridge University Press, Cambridge, United Kingdom and New York, NY, USA.
- _____. 2018. Summary for Policymakers. In: Global warming of 1.5°C. An IPCC Special Report on the impacts of global warming of 1.5°C above pre-industrial levels and related global greenhouse gas emission pathways, in the context of strengthening the global response to the threat of climate change, sustainable development, and efforts to eradicate poverty. <https://www.ipcc.ch/sr15/> (accessed November 2020).

- Iowa Environmental Mesonet. 2021. February 21. Long Beach Airport Windrose Plot. Available at: https://mesonet.agron.iastate.edu/sites/windrose.phtml?station=LGB&network=CA_ASOS
- Kimley Horn. 2021. Traffic Impact Analysis, Car Wash Development Project in the City of Long Beach. March.
- Long Beach, City of. 2010. Sustainable City Action Plan. <http://www.longbeach.gov/globalassets/sustainability/media-library/documents/nature-initiatives/action-plan/scap-final>. Accessed November 2020.
- _____. 2019a. City of Long Beach General Plan Land Use Element. December. Available at: <http://www.longbeach.gov/globalassets/lbds/media-library/documents/planning/advance/lueude/land-use-element-final-adopted-december-2019>
- _____. 2019b. Draft Climate Action and Adaptation Plan: Greenhouse Gas Emissions, Forecasts, and Targets. <http://www.longbeach.gov/globalassets/lbds/media-library/documents/planning/caap/caap-greenhouse-gas--ghg--emissions-forecasts-and-targets--draft-released-053119-logos>. Accessed November 2020.
- National Asphalt Pavement Association. How to Determine Quantities. Available at: https://web.archive.org/web/20190722150051/http://www.asphaltpavement.org/index.php?option=com_content&task=view&id=144&Itemid=227
- National Highway Traffic Safety Administration. 2020. “Fact Sheet: SAFE Vehicles Rule.” [web page]. <https://www.nhtsa.gov/corporate-average-fuel-economy/safe-fact-sheet> (accessed November 2020).
- National Oceanic and Atmospheric Administration. 2020. “Global Climate Report for Annual 2019.” State of the Climate. January 2020. <https://www.ncdc.noaa.gov/sotc/global/201813> (accessed November 2020).
- Parmesan, C. August 2006. Ecological and Evolutionary Responses to Recent Climate Change. *Annual Review of Ecological Evolutionary Systems* 37:637-669.
- South Coast Air Quality Management District (SCAQMD). 1993. CEQA Air Quality Handbook. April 1993.
- _____. 2005. Guidance Document for Addressing Air Quality Issues in General Plans and Local Planning. May 6, 2005. <http://www.aqmd.gov/docs/default-source/planning/air-quality-guidance/complete-guidance-document.pdf> (accessed November 2020).
- _____. 2008. Final Localized Significance Threshold Methodology. July 2008. <http://www.aqmd.gov/docs/default-source/ceqa/handbook/localized-significance-thresholds/final-lst-methodology-document.pdf> (accessed November 2020).
- _____. 2009. Appendix C – Mass Rate LST Look-up Tables. Last modified: October 21, 2009. <http://www.aqmd.gov/docs/default-source/ceqa/handbook/localized-significance-thresholds/appendix-c-mass-rate-lst-look-up-tables.pdf?sfvrsn=2> (accessed November 2020).
- _____. 2016. National Ambient Air Quality Standards (NAAQS) and California Ambient Air Quality Standards (CAAQS) Attainment Status for South Coast Air Basin. <http://www.aqmd.gov/docs/default-source/clean-air-plans/air-quality-management-plans/naaqs-caaqs-feb2016.pdf?sfvrsn=2> (accessed November 2020).

- _____. 2017. Final 2016 Air Quality Management Plan (AQMP). March 3, 2017 (accessed November 2020).
- _____. 2019. SCAQMD Air Quality Significance Thresholds. Last modified: April 2019. <http://www.aqmd.gov/docs/default-source/ceqa/handbook/scaqmd-air-quality-significance-thresholds.pdf> (accessed November 2020).
- Southern California Association of Governments (SCAG). 2016 Regional Transportation Plan/Sustainable Communities Strategy (RTP/SCS). April 7, 2016.
- _____. 2019. Profile of the City of Long Beach. <https://www.scag.ca.gov/Documents/LosAngeles.pdf> (accessed November 2020).
- _____. 2020. Connect SoCal: The 2020-2045 Regional Transportation Plan/Sustainable Communities Strategy of the Southern California Association of Governments. Adopted May 7, 2020. <https://www.connectsocal.org/Documents/Adopted/fConnectSoCal-Plan.pdf> (accessed November 2020).
- State of California. 2018. California's Fourth Climate Change Assessment Statewide Summary Report. August 27, 2018. <http://www.climateassessment.ca.gov/state/> (accessed November 2020).
- United States Environmental Protection Agency (USEPA). 2020. Inventory of U.S. Greenhouse Gas Emissions and Sinks: 1990-2018. U. S. EPA #430-R-19-001. Washington, DC. April 13, 2020.
- World Meteorological Organization (WMO). 2013. A summary of current and climate change findings and figures: a WMO information note. March 2013. https://library.wmo.int/opac/index.php?lvl=notice_display&id=15892#.Wt9-Z8gvzIU (accessed November 2020).

Appendix A

CalEEMod Output Files

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

20-10163 Long Beach Car Wash Project

South Coast AQMD Air District, Winter

1.0 Project Characteristics

1.1 Land Usage

Land Uses	Size	Metric	Lot Acreage	Floor Surface Area	Population
Parking Lot	15.00	Space	0.13	6,000.00	0
Automobile Care Center	3.06	1000sqft	0.07	3,058.00	0

1.2 Other Project Characteristics

Urbanization	Urban	Wind Speed (m/s)	2.2	Precipitation Freq (Days)	31
Climate Zone	9			Operational Year	2022
Utility Company	Southern California Edison				
CO2 Intensity (lb/MWhr)	702.44	CH4 Intensity (lb/MWhr)	0.029	N2O Intensity (lb/MWhr)	0.006

1.3 User Entered Comments & Non-Default Data

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

Project Characteristics -

Land Use - sf obtained from client

Parking lot - 15 spaces from staff report. SF is CalEEMod default

Construction Phase - Site prep extended to one week to account for asphalt demo

Trips and VMT -

Grading - Ton of debris estimated from amount of asphalt to be removed

Vehicle Trips - Trip rated based on applicant estimate for cars per day (300 vehicles or 600 round trips)

Energy Use - car wash specific electricity and natural gas inputs

Water And Wastewater - car wash specific water usage

Construction Off-road Equipment Mitigation -

Table Name	Column Name	Default Value	New Value
tblConstructionPhase	NumDays	1.00	5.00
tblEnergyUse	NT24E	5.75	117.25
tblEnergyUse	NT24NG	4.45	394.75
tblEnergyUse	T24E	2.25	0.00
tblEnergyUse	T24NG	13.65	0.00
tblGrading	MaterialExported	0.00	485.00
tblLandUse	LandUseSquareFeet	3,060.00	3,058.00
tblVehicleTrips	ST_TR	23.72	242.00
tblVehicleTrips	SU_TR	11.88	242.00
tblVehicleTrips	WD_TR	23.72	242.00
tblWater	IndoorWaterUseRate	287,888.19	0.00
tblWater	OutdoorWaterUseRate	176,447.60	2,104,000.00

2.0 Emissions Summary

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

2.1 Overall Construction (Maximum Daily Emission)**Unmitigated Construction**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Year	lb/day										lb/day					
2021	0.8427	10.2929	7.9077	0.0175	0.8645	0.4481	1.2727	0.4434	0.4122	0.8328	0.0000	1,775.995 1	1,775.995 1	0.3616	0.0000	1,785.035 4
2022	6.2121	7.1268	7.5972	0.0131	0.2012	0.3724	0.4987	0.0534	0.3426	0.3563	0.0000	1,215.561 1	1,215.561 1	0.3597	0.0000	1,223.217 1
Maximum	6.2121	10.2929	7.9077	0.0175	0.8645	0.4481	1.2727	0.4434	0.4122	0.8328	0.0000	1,775.995 1	1,775.995 1	0.3616	0.0000	1,785.035 4

Mitigated Construction

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Year	lb/day										lb/day					
2021	0.8427	10.2929	7.9077	0.0175	0.4662	0.4481	0.8587	0.2158	0.4122	0.6052	0.0000	1,775.995 1	1,775.995 1	0.3616	0.0000	1,785.035 4
2022	6.2121	7.1268	7.5972	0.0131	0.2012	0.3724	0.4987	0.0534	0.3426	0.3563	0.0000	1,215.561 1	1,215.561 1	0.3597	0.0000	1,223.217 1
Maximum	6.2121	10.2929	7.9077	0.0175	0.4662	0.4481	0.8587	0.2158	0.4122	0.6052	0.0000	1,775.995 1	1,775.995 1	0.3616	0.0000	1,785.035 4

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio-CO2	Total CO2	CH4	N2O	CO2e
Percent Reduction	0.00	0.00	0.00	0.00	37.38	0.00	23.37	45.81	0.00	19.14	0.00	0.00	0.00	0.00	0.00	0.00

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

2.2 Overall Operational**Unmitigated Operational**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Area	0.0711	2.0000e-005	1.8500e-003	0.0000		1.0000e-005	1.0000e-005		1.0000e-005	1.0000e-005		3.9500e-003	3.9500e-003	1.0000e-005		4.2100e-003
Energy	0.0357	0.3242	0.2724	1.9500e-003		0.0246	0.0246		0.0246	0.0246		389.0880	389.0880	7.4600e-003	7.1300e-003	391.4002
Mobile	0.9030	4.3859	8.1292	0.0265	2.1093	0.0224	2.1317	0.5644	0.0209	0.5852		2,699.0146	2,699.0146	0.1591		2,702.9922
Total	1.0098	4.7102	8.4035	0.0284	2.1093	0.0470	2.1563	0.5644	0.0455	0.6099		3,088.1065	3,088.1065	0.1666	7.1300e-003	3,094.3966

Mitigated Operational

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Area	0.0711	2.0000e-005	1.8500e-003	0.0000		1.0000e-005	1.0000e-005		1.0000e-005	1.0000e-005		3.9500e-003	3.9500e-003	1.0000e-005		4.2100e-003
Energy	0.0357	0.3242	0.2724	1.9500e-003		0.0246	0.0246		0.0246	0.0246		389.0880	389.0880	7.4600e-003	7.1300e-003	391.4002
Mobile	0.9030	4.3859	8.1292	0.0265	2.1093	0.0224	2.1317	0.5644	0.0209	0.5852		2,699.0146	2,699.0146	0.1591		2,702.9922
Total	1.0098	4.7102	8.4035	0.0284	2.1093	0.0470	2.1563	0.5644	0.0455	0.6099		3,088.1065	3,088.1065	0.1666	7.1300e-003	3,094.3966

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio-CO2	Total CO2	CH4	N2O	CO2e
Percent Reduction	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

3.0 Construction Detail

Construction Phase

Phase Number	Phase Name	Phase Type	Start Date	End Date	Num Days Week	Num Days	Phase Description
1	Site Preparation	Site Preparation	9/1/2021	9/7/2021	5	5	
2	Grading	Grading	9/8/2021	9/9/2021	5	2	
3	Building Construction	Building Construction	9/10/2021	1/27/2022	5	100	
4	Paving	Paving	1/28/2022	2/3/2022	5	5	
5	Architectural Coating	Architectural Coating	2/4/2022	2/10/2022	5	5	

Acres of Grading (Site Preparation Phase): 2.5

Acres of Grading (Grading Phase): 0

Acres of Paving: 0.13

Residential Indoor: 0; Residential Outdoor: 0; Non-Residential Indoor: 4,587; Non-Residential Outdoor: 1,529; Striped Parking Area: 360 (Architectural Coating – sqft)

OffRoad Equipment

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

Phase Name	Offroad Equipment Type	Amount	Usage Hours	Horse Power	Load Factor
Site Preparation	Graders	1	8.00	187	0.41
Site Preparation	Tractors/Loaders/Backhoes	1	8.00	97	0.37
Grading	Concrete/Industrial Saws	1	8.00	81	0.73
Grading	Rubber Tired Dozers	1	1.00	247	0.40
Grading	Tractors/Loaders/Backhoes	2	6.00	97	0.37
Building Construction	Cranes	1	4.00	231	0.29
Building Construction	Forklifts	2	6.00	89	0.20
Building Construction	Tractors/Loaders/Backhoes	2	8.00	97	0.37
Paving	Cement and Mortar Mixers	4	6.00	9	0.56
Paving	Pavers	1	7.00	130	0.42
Paving	Rollers	1	7.00	80	0.38
Paving	Tractors/Loaders/Backhoes	1	7.00	97	0.37
Architectural Coating	Air Compressors	1	6.00	78	0.48

Trips and VMT

Phase Name	Offroad Equipment Count	Worker Trip Number	Vendor Trip Number	Hauling Trip Number	Worker Trip Length	Vendor Trip Length	Hauling Trip Length	Worker Vehicle Class	Vendor Vehicle Class	Hauling Vehicle Class
Site Preparation	2	5.00	0.00	48.00	14.70	6.90	20.00	LD_Mix	HDT_Mix	HHDT
Grading	4	10.00	0.00	0.00	14.70	6.90	20.00	LD_Mix	HDT_Mix	HHDT
Building Construction	5	4.00	1.00	0.00	14.70	6.90	20.00	LD_Mix	HDT_Mix	HHDT
Paving	7	18.00	0.00	0.00	14.70	6.90	20.00	LD_Mix	HDT_Mix	HHDT
Architectural Coating	1	1.00	0.00	0.00	14.70	6.90	20.00	LD_Mix	HDT_Mix	HHDT

3.1 Mitigation Measures Construction

Water Exposed Area

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

3.2 Site Preparation - 2021**Unmitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Fugitive Dust					0.5389	0.0000	0.5389	0.0586	0.0000	0.0586			0.0000			0.0000
Off-Road	0.6403	7.8204	4.0274	9.7300e-003		0.2995	0.2995		0.2755	0.2755		942.5842	942.5842	0.3049		950.2055
Total	0.6403	7.8204	4.0274	9.7300e-003	0.5389	0.2995	0.8384	0.0586	0.2755	0.3341		942.5842	942.5842	0.3049		950.2055

Unmitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0716	2.4576	0.5519	7.2200e-003	0.1678	7.6400e-003	0.1754	0.0460	7.3100e-003	0.0533		781.6275	781.6275	0.0554		783.0118
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000		0.0000
Worker	0.0231	0.0150	0.1693	5.2000e-004	0.0559	4.1000e-004	0.0563	0.0148	3.8000e-004	0.0152		51.7834	51.7834	1.3900e-003		51.8181
Total	0.0947	2.4726	0.7212	7.7400e-003	0.2236	8.0500e-003	0.2317	0.0608	7.6900e-003	0.0685		833.4109	833.4109	0.0568		834.8299

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

3.2 Site Preparation - 2021**Mitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Fugitive Dust					0.2425	0.0000	0.2425	0.0264	0.0000	0.0264			0.0000			0.0000
Off-Road	0.6403	7.8204	4.0274	9.7300e-003		0.2995	0.2995		0.2755	0.2755	0.0000	942.5842	942.5842	0.3049		950.2055
Total	0.6403	7.8204	4.0274	9.7300e-003	0.2425	0.2995	0.5420	0.0264	0.2755	0.3019	0.0000	942.5842	942.5842	0.3049		950.2055

Mitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0716	2.4576	0.5519	7.2200e-003	0.1678	7.6400e-003	0.1754	0.0460	7.3100e-003	0.0533		781.6275	781.6275	0.0554		783.0118
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000		0.0000
Worker	0.0231	0.0150	0.1693	5.2000e-004	0.0559	4.1000e-004	0.0563	0.0148	3.8000e-004	0.0152		51.7834	51.7834	1.3900e-003		51.8181
Total	0.0947	2.4726	0.7212	7.7400e-003	0.2236	8.0500e-003	0.2317	0.0608	7.6900e-003	0.0685		833.4109	833.4109	0.0568		834.8299

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

3.3 Grading - 2021**Unmitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Fugitive Dust					0.7528	0.0000	0.7528	0.4138	0.0000	0.4138			0.0000			0.0000
Off-Road	0.7965	7.2530	7.5691	0.0120		0.4073	0.4073		0.3886	0.3886		1,147.4338	1,147.4338	0.2138		1,152.7797
Total	0.7965	7.2530	7.5691	0.0120	0.7528	0.4073	1.1601	0.4138	0.3886	0.8024		1,147.4338	1,147.4338	0.2138		1,152.7797

Unmitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000		0.0000
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000		0.0000
Worker	0.0461	0.0300	0.3385	1.0400e-003	0.1118	8.2000e-004	0.1126	0.0296	7.6000e-004	0.0304		103.5668	103.5668	2.7800e-003		103.6362
Total	0.0461	0.0300	0.3385	1.0400e-003	0.1118	8.2000e-004	0.1126	0.0296	7.6000e-004	0.0304		103.5668	103.5668	2.7800e-003		103.6362

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

3.3 Grading - 2021**Mitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Fugitive Dust					0.3387	0.0000	0.3387	0.1862	0.0000	0.1862			0.0000			0.0000
Off-Road	0.7965	7.2530	7.5691	0.0120		0.4073	0.4073		0.3886	0.3886	0.0000	1,147.4338	1,147.4338	0.2138		1,152.7797
Total	0.7965	7.2530	7.5691	0.0120	0.3387	0.4073	0.7461	0.1862	0.3886	0.5748	0.0000	1,147.4338	1,147.4338	0.2138		1,152.7797

Mitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000		0.0000
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000		0.0000
Worker	0.0461	0.0300	0.3385	1.0400e-003	0.1118	8.2000e-004	0.1126	0.0296	7.6000e-004	0.0304		103.5668	103.5668	2.7800e-003		103.6362
Total	0.0461	0.0300	0.3385	1.0400e-003	0.1118	8.2000e-004	0.1126	0.0296	7.6000e-004	0.0304		103.5668	103.5668	2.7800e-003		103.6362

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

3.4 Building Construction - 2021**Unmitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Off-Road	0.7750	7.9850	7.2637	0.0114		0.4475	0.4475		0.4117	0.4117		1,103.2158	1,103.2158	0.3568		1,112.1358
Total	0.7750	7.9850	7.2637	0.0114		0.4475	0.4475		0.4117	0.4117		1,103.2158	1,103.2158	0.3568		1,112.1358

Unmitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000		0.0000
Vendor	2.9300e-003	0.0951	0.0253	2.5000e-004	6.4000e-003	2.0000e-004	6.6000e-003	1.8400e-003	1.9000e-004	2.0300e-003		26.4550	26.4550	1.7700e-003		26.4993
Worker	0.0185	0.0120	0.1354	4.2000e-004	0.0447	3.3000e-004	0.0450	0.0119	3.0000e-004	0.0122		41.4267	41.4267	1.1100e-003		41.4545
Total	0.0214	0.1071	0.1608	6.7000e-004	0.0511	5.3000e-004	0.0516	0.0137	4.9000e-004	0.0142		67.8817	67.8817	2.8800e-003		67.9537

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

3.4 Building Construction - 2021**Mitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Off-Road	0.7750	7.9850	7.2637	0.0114		0.4475	0.4475		0.4117	0.4117	0.0000	1,103.2158	1,103.2158	0.3568		1,112.1358
Total	0.7750	7.9850	7.2637	0.0114		0.4475	0.4475		0.4117	0.4117	0.0000	1,103.2158	1,103.2158	0.3568		1,112.1358

Mitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000		0.0000
Vendor	2.9300e-003	0.0951	0.0253	2.5000e-004	6.4000e-003	2.0000e-004	6.6000e-003	1.8400e-003	1.9000e-004	2.0300e-003		26.4550	26.4550	1.7700e-003		26.4993
Worker	0.0185	0.0120	0.1354	4.2000e-004	0.0447	3.3000e-004	0.0450	0.0119	3.0000e-004	0.0122		41.4267	41.4267	1.1100e-003		41.4545
Total	0.0214	0.1071	0.1608	6.7000e-004	0.0511	5.3000e-004	0.0516	0.0137	4.9000e-004	0.0142		67.8817	67.8817	2.8800e-003		67.9537

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

3.4 Building Construction - 2022**Unmitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Off-Road	0.6863	7.0258	7.1527	0.0114		0.3719	0.3719		0.3422	0.3422		1,103.939 3	1,103.939 3	0.3570		1,112.865 2
Total	0.6863	7.0258	7.1527	0.0114		0.3719	0.3719		0.3422	0.3422		1,103.939 3	1,103.939 3	0.3570		1,112.865 2

Unmitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000		0.0000
Vendor	2.7500e-003	0.0902	0.0240	2.5000e-004	6.4000e-003	1.7000e-004	6.5700e-003	1.8400e-003	1.6000e-004	2.0100e-003		26.2194	26.2194	1.7000e-003		26.2620
Worker	0.0174	0.0108	0.1250	4.0000e-004	0.0447	3.2000e-004	0.0450	0.0119	2.9000e-004	0.0122		39.9415	39.9415	1.0000e-003		39.9665
Total	0.0201	0.1010	0.1489	6.5000e-004	0.0511	4.9000e-004	0.0516	0.0137	4.5000e-004	0.0142		66.1609	66.1609	2.7000e-003		66.2285

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

3.4 Building Construction - 2022**Mitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Off-Road	0.6863	7.0258	7.1527	0.0114		0.3719	0.3719		0.3422	0.3422	0.0000	1,103.939 3	1,103.939 3	0.3570		1,112.865 2
Total	0.6863	7.0258	7.1527	0.0114		0.3719	0.3719		0.3422	0.3422	0.0000	1,103.939 3	1,103.939 3	0.3570		1,112.865 2

Mitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000		0.0000
Vendor	2.7500e-003	0.0902	0.0240	2.5000e-004	6.4000e-003	1.7000e-004	6.5700e-003	1.8400e-003	1.6000e-004	2.0100e-003		26.2194	26.2194	1.7000e-003		26.2620
Worker	0.0174	0.0108	0.1250	4.0000e-004	0.0447	3.2000e-004	0.0450	0.0119	2.9000e-004	0.0122		39.9415	39.9415	1.0000e-003		39.9665
Total	0.0201	0.1010	0.1489	6.5000e-004	0.0511	4.9000e-004	0.0516	0.0137	4.5000e-004	0.0142		66.1609	66.1609	2.7000e-003		66.2285

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

3.5 Paving - 2022**Unmitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Off-Road	0.6469	5.9174	7.0348	0.0113		0.2961	0.2961		0.2758	0.2758		1,035.8246	1,035.8246	0.3017		1,043.3677
Paving	0.0681					0.0000	0.0000		0.0000	0.0000			0.0000			0.0000
Total	0.7150	5.9174	7.0348	0.0113		0.2961	0.2961		0.2758	0.2758		1,035.8246	1,035.8246	0.3017		1,043.3677

Unmitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000		0.0000
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000		0.0000
Worker	0.0781	0.0487	0.5625	1.8000e-003	0.2012	1.4400e-003	0.2026	0.0534	1.3200e-003	0.0547		179.7366	179.7366	4.5100e-003		179.8494
Total	0.0781	0.0487	0.5625	1.8000e-003	0.2012	1.4400e-003	0.2026	0.0534	1.3200e-003	0.0547		179.7366	179.7366	4.5100e-003		179.8494

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

3.5 Paving - 2022**Mitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Off-Road	0.6469	5.9174	7.0348	0.0113		0.2961	0.2961		0.2758	0.2758	0.0000	1,035.824 6	1,035.824 6	0.3017		1,043.367 7
Paving	0.0681					0.0000	0.0000		0.0000	0.0000			0.0000			0.0000
Total	0.7150	5.9174	7.0348	0.0113		0.2961	0.2961		0.2758	0.2758	0.0000	1,035.824 6	1,035.824 6	0.3017		1,043.367 7

Mitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000		0.0000
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000		0.0000
Worker	0.0781	0.0487	0.5625	1.8000e-003	0.2012	1.4400e-003	0.2026	0.0534	1.3200e-003	0.0547		179.7366	179.7366	4.5100e-003		179.8494
Total	0.0781	0.0487	0.5625	1.8000e-003	0.2012	1.4400e-003	0.2026	0.0534	1.3200e-003	0.0547		179.7366	179.7366	4.5100e-003		179.8494

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

3.6 Architectural Coating - 2022**Unmitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Archit. Coating	6.0033					0.0000	0.0000		0.0000	0.0000			0.0000			0.0000
Off-Road	0.2045	1.4085	1.8136	2.9700e-003		0.0817	0.0817		0.0817	0.0817		281.4481	281.4481	0.0183		281.9062
Total	6.2078	1.4085	1.8136	2.9700e-003		0.0817	0.0817		0.0817	0.0817		281.4481	281.4481	0.0183		281.9062

Unmitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000		0.0000
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000		0.0000
Worker	4.3400e-003	2.7100e-003	0.0313	1.0000e-004	0.0112	8.0000e-005	0.0113	2.9600e-003	7.0000e-005	3.0400e-003		9.9854	9.9854	2.5000e-004		9.9916
Total	4.3400e-003	2.7100e-003	0.0313	1.0000e-004	0.0112	8.0000e-005	0.0113	2.9600e-003	7.0000e-005	3.0400e-003		9.9854	9.9854	2.5000e-004		9.9916

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

3.6 Architectural Coating - 2022**Mitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Archit. Coating	6.0033					0.0000	0.0000		0.0000	0.0000			0.0000			0.0000
Off-Road	0.2045	1.4085	1.8136	2.9700e-003		0.0817	0.0817		0.0817	0.0817	0.0000	281.4481	281.4481	0.0183		281.9062
Total	6.2078	1.4085	1.8136	2.9700e-003		0.0817	0.0817		0.0817	0.0817	0.0000	281.4481	281.4481	0.0183		281.9062

Mitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000		0.0000
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000	0.0000		0.0000
Worker	4.3400e-003	2.7100e-003	0.0313	1.0000e-004	0.0112	8.0000e-005	0.0113	2.9600e-003	7.0000e-005	3.0400e-003		9.9854	9.9854	2.5000e-004		9.9916
Total	4.3400e-003	2.7100e-003	0.0313	1.0000e-004	0.0112	8.0000e-005	0.0113	2.9600e-003	7.0000e-005	3.0400e-003		9.9854	9.9854	2.5000e-004		9.9916

4.0 Operational Detail - Mobile

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

4.1 Mitigation Measures Mobile

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Mitigated	0.9030	4.3859	8.1292	0.0265	2.1093	0.0224	2.1317	0.5644	0.0209	0.5852		2,699.0146	2,699.0146	0.1591		2,702.9922
Unmitigated	0.9030	4.3859	8.1292	0.0265	2.1093	0.0224	2.1317	0.5644	0.0209	0.5852		2,699.0146	2,699.0146	0.1591		2,702.9922

4.2 Trip Summary Information

Land Use	Average Daily Trip Rate			Unmitigated	Mitigated
	Weekday	Saturday	Sunday	Annual VMT	Annual VMT
Automobile Care Center	740.52	740.52	740.52	991,965	991,965
Parking Lot	0.00	0.00	0.00		
Total	740.52	740.52	740.52	991,965	991,965

4.3 Trip Type Information

Land Use	Miles			Trip %			Trip Purpose %		
	H-W or C-W	H-S or C-C	H-O or C-NW	H-W or C-W	H-S or C-C	H-O or C-NW	Primary	Diverted	Pass-by
Automobile Care Center	16.60	8.40	6.90	33.00	48.00	19.00	21	51	28
Parking Lot	16.60	8.40	6.90	0.00	0.00	0.00	0	0	0

4.4 Fleet Mix

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

Land Use	LDA	LDT1	LDT2	MDV	LHD1	LHD2	MHD	HHD	OBUS	UBUS	MCY	SBUS	MH
Automobile Care Center	0.549559	0.042893	0.201564	0.118533	0.015569	0.005846	0.021394	0.034255	0.002099	0.001828	0.004855	0.000709	0.000896
Parking Lot	0.549559	0.042893	0.201564	0.118533	0.015569	0.005846	0.021394	0.034255	0.002099	0.001828	0.004855	0.000709	0.000896

5.0 Energy Detail

Historical Energy Use: N

5.1 Mitigation Measures Energy

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
NaturalGas Mitigated	0.0357	0.3242	0.2724	1.9500e-003		0.0246	0.0246		0.0246	0.0246		389.0880	389.0880	7.4600e-003	7.1300e-003	391.4002
NaturalGas Unmitigated	0.0357	0.3242	0.2724	1.9500e-003		0.0246	0.0246		0.0246	0.0246		389.0880	389.0880	7.4600e-003	7.1300e-003	391.4002

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

5.2 Energy by Land Use - NaturalGas**Unmitigated**

	NaturalGas Use	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Land Use	kBTU/yr	lb/day										lb/day					
Automobile Care Center	3307.25	0.0357	0.3242	0.2724	1.9500e-003		0.0246	0.0246		0.0246	0.0246		389.0880	389.0880	7.4600e-003	7.1300e-003	391.4002
Parking Lot	0	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000		0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Total		0.0357	0.3242	0.2724	1.9500e-003		0.0246	0.0246		0.0246	0.0246		389.0880	389.0880	7.4600e-003	7.1300e-003	391.4002

Mitigated

	NaturalGas Use	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Land Use	kBTU/yr	lb/day										lb/day					
Automobile Care Center	3.30725	0.0357	0.3242	0.2724	1.9500e-003		0.0246	0.0246		0.0246	0.0246		389.0880	389.0880	7.4600e-003	7.1300e-003	391.4002
Parking Lot	0	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000		0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000
Total		0.0357	0.3242	0.2724	1.9500e-003		0.0246	0.0246		0.0246	0.0246		389.0880	389.0880	7.4600e-003	7.1300e-003	391.4002

6.0 Area Detail**6.1 Mitigation Measures Area**

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	lb/day										lb/day					
Mitigated	0.0711	2.0000e-005	1.8500e-003	0.0000		1.0000e-005	1.0000e-005		1.0000e-005	1.0000e-005		3.9500e-003	3.9500e-003	1.0000e-005		4.2100e-003
Unmitigated	0.0711	2.0000e-005	1.8500e-003	0.0000		1.0000e-005	1.0000e-005		1.0000e-005	1.0000e-005		3.9500e-003	3.9500e-003	1.0000e-005		4.2100e-003

6.2 Area by SubCategory

Unmitigated

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
SubCategory	lb/day										lb/day					
Architectural Coating	8.2200e-003					0.0000	0.0000		0.0000	0.0000			0.0000			0.0000
Consumer Products	0.0627					0.0000	0.0000		0.0000	0.0000			0.0000			0.0000
Landscaping	1.7000e-004	2.0000e-005	1.8500e-003	0.0000		1.0000e-005	1.0000e-005		1.0000e-005	1.0000e-005		3.9500e-003	3.9500e-003	1.0000e-005		4.2100e-003
Total	0.0711	2.0000e-005	1.8500e-003	0.0000		1.0000e-005	1.0000e-005		1.0000e-005	1.0000e-005		3.9500e-003	3.9500e-003	1.0000e-005		4.2100e-003

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

6.2 Area by SubCategory**Mitigated**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
SubCategory	lb/day										lb/day					
Architectural Coating	8.2200e-003					0.0000	0.0000		0.0000	0.0000			0.0000			0.0000
Consumer Products	0.0627					0.0000	0.0000		0.0000	0.0000			0.0000			0.0000
Landscaping	1.7000e-004	2.0000e-005	1.8500e-003	0.0000		1.0000e-005	1.0000e-005		1.0000e-005	1.0000e-005		3.9500e-003	3.9500e-003	1.0000e-005		4.2100e-003
Total	0.0711	2.0000e-005	1.8500e-003	0.0000		1.0000e-005	1.0000e-005		1.0000e-005	1.0000e-005		3.9500e-003	3.9500e-003	1.0000e-005		4.2100e-003

7.0 Water Detail**7.1 Mitigation Measures Water****8.0 Waste Detail****8.1 Mitigation Measures Waste****9.0 Operational Offroad**

Equipment Type	Number	Hours/Day	Days/Year	Horse Power	Load Factor	Fuel Type
----------------	--------	-----------	-----------	-------------	-------------	-----------

10.0 Stationary Equipment**Fire Pumps and Emergency Generators**

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Winter

Equipment Type	Number	Hours/Day	Hours/Year	Horse Power	Load Factor	Fuel Type
----------------	--------	-----------	------------	-------------	-------------	-----------

Boilers

Equipment Type	Number	Heat Input/Day	Heat Input/Year	Boiler Rating	Fuel Type
----------------	--------	----------------	-----------------	---------------	-----------

User Defined Equipment

Equipment Type	Number
----------------	--------

11.0 Vegetation

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

20-10163 Long Beach Car Wash Project

South Coast AQMD Air District, Annual

1.0 Project Characteristics

1.1 Land Usage

Land Uses	Size	Metric	Lot Acreage	Floor Surface Area	Population
Parking Lot	15.00	Space	0.13	6,000.00	0
Automobile Care Center	3.06	1000sqft	0.07	3,058.00	0

1.2 Other Project Characteristics

Urbanization	Urban	Wind Speed (m/s)	2.2	Precipitation Freq (Days)	31
Climate Zone	9			Operational Year	2022
Utility Company	Southern California Edison				
CO2 Intensity (lb/MWhr)	702.44	CH4 Intensity (lb/MWhr)	0.029	N2O Intensity (lb/MWhr)	0.006

1.3 User Entered Comments & Non-Default Data

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

Project Characteristics -

Land Use - sf obtained from client

Parking lot - 15 spaces from staff report. SF is CalEEMod default

Construction Phase - Site prep extended to one week to account for asphalt demo

Trips and VMT -

Grading - Ton of debris estimated from amount of asphalt to be removed

Vehicle Trips - Trip rated based on applicant estimate for cars per day (300 vehicles or 600 round trips)

Energy Use - car wash specific electricity and natural gas inputs

Water And Wastewater - car wash specific water usage

Construction Off-road Equipment Mitigation -

Table Name	Column Name	Default Value	New Value
tblConstructionPhase	NumDays	1.00	5.00
tblEnergyUse	NT24E	5.75	117.25
tblEnergyUse	NT24NG	4.45	394.75
tblEnergyUse	T24E	2.25	0.00
tblEnergyUse	T24NG	13.65	0.00
tblGrading	MaterialExported	0.00	485.00
tblLandUse	LandUseSquareFeet	3,060.00	3,058.00
tblVehicleTrips	ST_TR	23.72	242.00
tblVehicleTrips	SU_TR	11.88	242.00
tblVehicleTrips	WD_TR	23.72	242.00
tblWater	IndoorWaterUseRate	287,888.19	0.00
tblWater	OutdoorWaterUseRate	176,447.60	2,104,000.00

2.0 Emissions Summary

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

2.1 Overall Construction**Unmitigated Construction**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Year	tons/yr										MT/yr					
2021	0.0348	0.3609	0.3205	5.5000e-004	4.7900e-003	0.0193	0.0241	1.2800e-003	0.0178	0.0191	0.0000	48.2560	48.2560	0.0142	0.0000	48.6117
2022	0.0242	0.0862	0.0930	1.5000e-004	1.0000e-003	4.4900e-003	5.4800e-003	2.7000e-004	4.1500e-003	4.4200e-003	0.0000	13.5193	13.5193	3.8400e-003	0.0000	13.6152
Maximum	0.0348	0.3609	0.3205	5.5000e-004	4.7900e-003	0.0193	0.0241	1.2800e-003	0.0178	0.0191	0.0000	48.2560	48.2560	0.0142	0.0000	48.6117

Mitigated Construction

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Year	tons/yr										MT/yr					
2021	0.0348	0.3609	0.3205	5.5000e-004	3.6400e-003	0.0193	0.0230	9.8000e-004	0.0178	0.0188	0.0000	48.2559	48.2559	0.0142	0.0000	48.6116
2022	0.0242	0.0862	0.0930	1.5000e-004	1.0000e-003	4.4900e-003	5.4800e-003	2.7000e-004	4.1500e-003	4.4200e-003	0.0000	13.5192	13.5192	3.8400e-003	0.0000	13.6152
Maximum	0.0348	0.3609	0.3205	5.5000e-004	3.6400e-003	0.0193	0.0230	9.8000e-004	0.0178	0.0188	0.0000	48.2559	48.2559	0.0142	0.0000	48.6116

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Percent Reduction	0.00	0.00	0.00	0.00	19.86	0.00	3.92	19.35	0.00	1.32	0.00	0.00	0.00	0.00	0.00	0.00

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

Quarter	Start Date	End Date	Maximum Unmitigated ROG + NOX (tons/quarter)	Maximum Mitigated ROG + NOX (tons/quarter)
1	9-1-2021	11-30-2021	0.2936	0.2936
2	12-1-2021	2-28-2022	0.2099	0.2099
		Highest	0.2936	0.2936

2.2 Overall Operational

Unmitigated Operational

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Area	0.0130	0.0000	2.3000e-004	0.0000		0.0000	0.0000		0.0000	0.0000	0.0000	4.5000e-004	4.5000e-004	0.0000	0.0000	4.8000e-004
Energy	6.5100e-003	0.0592	0.0497	3.6000e-004		4.5000e-003	4.5000e-003		4.5000e-003	4.5000e-003	0.0000	182.3493	182.3493	6.1000e-003	2.1900e-003	183.1540
Mobile	0.1593	0.8121	1.4842	4.9000e-003	0.3769	4.0400e-003	0.3810	0.1010	3.7700e-003	0.1048	0.0000	453.8737	453.8737	0.0258	0.0000	454.5180
Waste						0.0000	0.0000		0.0000	0.0000	2.3730	0.0000	2.3730	0.1402	0.0000	5.8789
Water						0.0000	0.0000		0.0000	0.0000	0.0000	7.4479	7.4479	3.1000e-004	6.0000e-005	7.4746
Total	0.1788	0.8713	1.5342	5.2600e-003	0.3769	8.5400e-003	0.3855	0.1010	8.2700e-003	0.1093	2.3730	643.6713	646.0443	0.1724	2.2500e-003	651.0260

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

2.2 Overall Operational**Mitigated Operational**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Area	0.0130	0.0000	2.3000e-004	0.0000		0.0000	0.0000		0.0000	0.0000	0.0000	4.5000e-004	4.5000e-004	0.0000	0.0000	4.8000e-004
Energy	6.5100e-003	0.0592	0.0497	3.6000e-004		4.5000e-003	4.5000e-003		4.5000e-003	4.5000e-003	0.0000	182.3493	182.3493	6.1000e-003	2.1900e-003	183.1540
Mobile	0.1593	0.8121	1.4842	4.9000e-003	0.3769	4.0400e-003	0.3810	0.1010	3.7700e-003	0.1048	0.0000	453.8737	453.8737	0.0258	0.0000	454.5180
Waste						0.0000	0.0000		0.0000	0.0000	2.3730	0.0000	2.3730	0.1402	0.0000	5.8789
Water						0.0000	0.0000		0.0000	0.0000	0.0000	7.4479	7.4479	3.1000e-004	6.0000e-005	7.4746
Total	0.1788	0.8713	1.5342	5.2600e-003	0.3769	8.5400e-003	0.3855	0.1010	8.2700e-003	0.1093	2.3730	643.6713	646.0443	0.1724	2.2500e-003	651.0260

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Percent Reduction	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

3.0 Construction Detail**Construction Phase**

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

Phase Number	Phase Name	Phase Type	Start Date	End Date	Num Days Week	Num Days	Phase Description
1	Site Preparation	Site Preparation	9/1/2021	9/7/2021	5	5	
2	Grading	Grading	9/8/2021	9/9/2021	5	2	
3	Building Construction	Building Construction	9/10/2021	1/27/2022	5	100	
4	Paving	Paving	1/28/2022	2/3/2022	5	5	
5	Architectural Coating	Architectural Coating	2/4/2022	2/10/2022	5	5	

Acres of Grading (Site Preparation Phase): 2.5

Acres of Grading (Grading Phase): 0

Acres of Paving: 0.13

Residential Indoor: 0; Residential Outdoor: 0; Non-Residential Indoor: 4,587; Non-Residential Outdoor: 1,529; Striped Parking Area: 360 (Architectural Coating – sqft)

OffRoad Equipment

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

Phase Name	Offroad Equipment Type	Amount	Usage Hours	Horse Power	Load Factor
Site Preparation	Graders	1	8.00	187	0.41
Site Preparation	Tractors/Loaders/Backhoes	1	8.00	97	0.37
Grading	Concrete/Industrial Saws	1	8.00	81	0.73
Grading	Rubber Tired Dozers	1	1.00	247	0.40
Grading	Tractors/Loaders/Backhoes	2	6.00	97	0.37
Building Construction	Cranes	1	4.00	231	0.29
Building Construction	Forklifts	2	6.00	89	0.20
Building Construction	Tractors/Loaders/Backhoes	2	8.00	97	0.37
Paving	Cement and Mortar Mixers	4	6.00	9	0.56
Paving	Pavers	1	7.00	130	0.42
Paving	Rollers	1	7.00	80	0.38
Paving	Tractors/Loaders/Backhoes	1	7.00	97	0.37
Architectural Coating	Air Compressors	1	6.00	78	0.48

Trips and VMT

Phase Name	Offroad Equipment Count	Worker Trip Number	Vendor Trip Number	Hauling Trip Number	Worker Trip Length	Vendor Trip Length	Hauling Trip Length	Worker Vehicle Class	Vendor Vehicle Class	Hauling Vehicle Class
Site Preparation	2	5.00	0.00	48.00	14.70	6.90	20.00	LD_Mix	HDT_Mix	HHDT
Grading	4	10.00	0.00	0.00	14.70	6.90	20.00	LD_Mix	HDT_Mix	HHDT
Building Construction	5	4.00	1.00	0.00	14.70	6.90	20.00	LD_Mix	HDT_Mix	HHDT
Paving	7	18.00	0.00	0.00	14.70	6.90	20.00	LD_Mix	HDT_Mix	HHDT
Architectural Coating	1	1.00	0.00	0.00	14.70	6.90	20.00	LD_Mix	HDT_Mix	HHDT

3.1 Mitigation Measures Construction

Water Exposed Area

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

3.2 Site Preparation - 2021**Unmitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Fugitive Dust					1.3500e-003	0.0000	1.3500e-003	1.5000e-004	0.0000	1.5000e-004	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Off-Road	1.6000e-003	0.0196	0.0101	2.0000e-005		7.5000e-004	7.5000e-004		6.9000e-004	6.9000e-004	0.0000	2.1377	2.1377	6.9000e-004	0.0000	2.1550
Total	1.6000e-003	0.0196	0.0101	2.0000e-005	1.3500e-003	7.5000e-004	2.1000e-003	1.5000e-004	6.9000e-004	8.4000e-004	0.0000	2.1377	2.1377	6.9000e-004	0.0000	2.1550

Unmitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Hauling	1.8000e-004	6.2500e-003	1.3300e-003	2.0000e-005	4.1000e-004	2.0000e-005	4.3000e-004	1.1000e-004	2.0000e-005	1.3000e-004	0.0000	1.7921	1.7921	1.2000e-004	0.0000	1.7952
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Worker	5.0000e-005	4.0000e-005	4.4000e-004	0.0000	1.4000e-004	0.0000	1.4000e-004	4.0000e-005	0.0000	4.0000e-005	0.0000	0.1195	0.1195	0.0000	0.0000	0.1195
Total	2.3000e-004	6.2900e-003	1.7700e-003	2.0000e-005	5.5000e-004	2.0000e-005	5.7000e-004	1.5000e-004	2.0000e-005	1.7000e-004	0.0000	1.9115	1.9115	1.2000e-004	0.0000	1.9147

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

3.2 Site Preparation - 2021**Mitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Fugitive Dust					6.1000e-004	0.0000	6.1000e-004	7.0000e-005	0.0000	7.0000e-005	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Off-Road	1.6000e-003	0.0196	0.0101	2.0000e-005		7.5000e-004	7.5000e-004		6.9000e-004	6.9000e-004	0.0000	2.1377	2.1377	6.9000e-004	0.0000	2.1550
Total	1.6000e-003	0.0196	0.0101	2.0000e-005	6.1000e-004	7.5000e-004	1.3600e-003	7.0000e-005	6.9000e-004	7.6000e-004	0.0000	2.1377	2.1377	6.9000e-004	0.0000	2.1550

Mitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Hauling	1.8000e-004	6.2500e-003	1.3300e-003	2.0000e-005	4.1000e-004	2.0000e-005	4.3000e-004	1.1000e-004	2.0000e-005	1.3000e-004	0.0000	1.7921	1.7921	1.2000e-004	0.0000	1.7952
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Worker	5.0000e-005	4.0000e-005	4.4000e-004	0.0000	1.4000e-004	0.0000	1.4000e-004	4.0000e-005	0.0000	4.0000e-005	0.0000	0.1195	0.1195	0.0000	0.0000	0.1195
Total	2.3000e-004	6.2900e-003	1.7700e-003	2.0000e-005	5.5000e-004	2.0000e-005	5.7000e-004	1.5000e-004	2.0000e-005	1.7000e-004	0.0000	1.9115	1.9115	1.2000e-004	0.0000	1.9147

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

3.3 Grading - 2021**Unmitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Fugitive Dust					7.5000e-004	0.0000	7.5000e-004	4.1000e-004	0.0000	4.1000e-004	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Off-Road	8.0000e-004	7.2500e-003	7.5700e-003	1.0000e-005		4.1000e-004	4.1000e-004		3.9000e-004	3.9000e-004	0.0000	1.0409	1.0409	1.9000e-004	0.0000	1.0458
Total	8.0000e-004	7.2500e-003	7.5700e-003	1.0000e-005	7.5000e-004	4.1000e-004	1.1600e-003	4.1000e-004	3.9000e-004	8.0000e-004	0.0000	1.0409	1.0409	1.9000e-004	0.0000	1.0458

Unmitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Worker	4.0000e-005	3.0000e-005	3.5000e-004	0.0000	1.1000e-004	0.0000	1.1000e-004	3.0000e-005	0.0000	3.0000e-005	0.0000	0.0956	0.0956	0.0000	0.0000	0.0956
Total	4.0000e-005	3.0000e-005	3.5000e-004	0.0000	1.1000e-004	0.0000	1.1000e-004	3.0000e-005	0.0000	3.0000e-005	0.0000	0.0956	0.0956	0.0000	0.0000	0.0956

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

3.3 Grading - 2021**Mitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Fugitive Dust					3.4000e-004	0.0000	3.4000e-004	1.9000e-004	0.0000	1.9000e-004	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Off-Road	8.0000e-004	7.2500e-003	7.5700e-003	1.0000e-005		4.1000e-004	4.1000e-004		3.9000e-004	3.9000e-004	0.0000	1.0409	1.0409	1.9000e-004	0.0000	1.0458
Total	8.0000e-004	7.2500e-003	7.5700e-003	1.0000e-005	3.4000e-004	4.1000e-004	7.5000e-004	1.9000e-004	3.9000e-004	5.8000e-004	0.0000	1.0409	1.0409	1.9000e-004	0.0000	1.0458

Mitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Worker	4.0000e-005	3.0000e-005	3.5000e-004	0.0000	1.1000e-004	0.0000	1.1000e-004	3.0000e-005	0.0000	3.0000e-005	0.0000	0.0956	0.0956	0.0000	0.0000	0.0956
Total	4.0000e-005	3.0000e-005	3.5000e-004	0.0000	1.1000e-004	0.0000	1.1000e-004	3.0000e-005	0.0000	3.0000e-005	0.0000	0.0956	0.0956	0.0000	0.0000	0.0956

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

3.4 Building Construction - 2021**Unmitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Off-Road	0.0314	0.3234	0.2942	4.6000e-004		0.0181	0.0181		0.0167	0.0167	0.0000	40.5332	40.5332	0.0131	0.0000	40.8610
Total	0.0314	0.3234	0.2942	4.6000e-004		0.0181	0.0181		0.0167	0.0167	0.0000	40.5332	40.5332	0.0131	0.0000	40.8610

Unmitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Vendor	1.2000e-004	3.9200e-003	9.7000e-004	1.0000e-005	2.6000e-004	1.0000e-005	2.6000e-004	7.0000e-005	1.0000e-005	8.0000e-005	0.0000	0.9888	0.9888	6.0000e-005	0.0000	0.9904
Worker	6.8000e-004	5.0000e-004	5.6500e-003	2.0000e-005	1.7800e-003	1.0000e-005	1.7900e-003	4.7000e-004	1.0000e-005	4.8000e-004	0.0000	1.5482	1.5482	4.0000e-005	0.0000	1.5492
Total	8.0000e-004	4.4200e-003	6.6200e-003	3.0000e-005	2.0400e-003	2.0000e-005	2.0500e-003	5.4000e-004	2.0000e-005	5.6000e-004	0.0000	2.5370	2.5370	1.0000e-004	0.0000	2.5396

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

3.4 Building Construction - 2021**Mitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Off-Road	0.0314	0.3234	0.2942	4.6000e-004		0.0181	0.0181		0.0167	0.0167	0.0000	40.5332	40.5332	0.0131	0.0000	40.8609
Total	0.0314	0.3234	0.2942	4.6000e-004		0.0181	0.0181		0.0167	0.0167	0.0000	40.5332	40.5332	0.0131	0.0000	40.8609

Mitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Vendor	1.2000e-004	3.9200e-003	9.7000e-004	1.0000e-005	2.6000e-004	1.0000e-005	2.6000e-004	7.0000e-005	1.0000e-005	8.0000e-005	0.0000	0.9888	0.9888	6.0000e-005	0.0000	0.9904
Worker	6.8000e-004	5.0000e-004	5.6500e-003	2.0000e-005	1.7800e-003	1.0000e-005	1.7900e-003	4.7000e-004	1.0000e-005	4.8000e-004	0.0000	1.5482	1.5482	4.0000e-005	0.0000	1.5492
Total	8.0000e-004	4.4200e-003	6.6200e-003	3.0000e-005	2.0400e-003	2.0000e-005	2.0500e-003	5.4000e-004	2.0000e-005	5.6000e-004	0.0000	2.5370	2.5370	1.0000e-004	0.0000	2.5396

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

3.4 Building Construction - 2022**Unmitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Off-Road	6.5200e-003	0.0667	0.0680	1.1000e-004		3.5300e-003	3.5300e-003		3.2500e-003	3.2500e-003	0.0000	9.5140	9.5140	3.0800e-003	0.0000	9.5910
Total	6.5200e-003	0.0667	0.0680	1.1000e-004		3.5300e-003	3.5300e-003		3.2500e-003	3.2500e-003	0.0000	9.5140	9.5140	3.0800e-003	0.0000	9.5910

Unmitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Vendor	3.0000e-005	8.7000e-004	2.2000e-004	0.0000	6.0000e-005	0.0000	6.0000e-005	2.0000e-005	0.0000	2.0000e-005	0.0000	0.2299	0.2299	1.0000e-005	0.0000	0.2303
Worker	1.5000e-004	1.1000e-004	1.2200e-003	0.0000	4.2000e-004	0.0000	4.2000e-004	1.1000e-004	0.0000	1.1000e-004	0.0000	0.3501	0.3501	1.0000e-005	0.0000	0.3504
Total	1.8000e-004	9.8000e-004	1.4400e-003	0.0000	4.8000e-004	0.0000	4.8000e-004	1.3000e-004	0.0000	1.3000e-004	0.0000	0.5800	0.5800	2.0000e-005	0.0000	0.5806

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

3.4 Building Construction - 2022**Mitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Off-Road	6.5200e-003	0.0667	0.0680	1.1000e-004		3.5300e-003	3.5300e-003		3.2500e-003	3.2500e-003	0.0000	9.5140	9.5140	3.0800e-003	0.0000	9.5909
Total	6.5200e-003	0.0667	0.0680	1.1000e-004		3.5300e-003	3.5300e-003		3.2500e-003	3.2500e-003	0.0000	9.5140	9.5140	3.0800e-003	0.0000	9.5909

Mitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Vendor	3.0000e-005	8.7000e-004	2.2000e-004	0.0000	6.0000e-005	0.0000	6.0000e-005	2.0000e-005	0.0000	2.0000e-005	0.0000	0.2299	0.2299	1.0000e-005	0.0000	0.2303
Worker	1.5000e-004	1.1000e-004	1.2200e-003	0.0000	4.2000e-004	0.0000	4.2000e-004	1.1000e-004	0.0000	1.1000e-004	0.0000	0.3501	0.3501	1.0000e-005	0.0000	0.3504
Total	1.8000e-004	9.8000e-004	1.4400e-003	0.0000	4.8000e-004	0.0000	4.8000e-004	1.3000e-004	0.0000	1.3000e-004	0.0000	0.5800	0.5800	2.0000e-005	0.0000	0.5806

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

3.5 Paving - 2022**Unmitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Off-Road	1.6200e-003	0.0148	0.0176	3.0000e-005		7.4000e-004	7.4000e-004		6.9000e-004	6.9000e-004	0.0000	2.3492	2.3492	6.8000e-004	0.0000	2.3663
Paving	1.7000e-004					0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Total	1.7900e-003	0.0148	0.0176	3.0000e-005		7.4000e-004	7.4000e-004		6.9000e-004	6.9000e-004	0.0000	2.3492	2.3492	6.8000e-004	0.0000	2.3663

Unmitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Worker	1.8000e-004	1.3000e-004	1.4500e-003	0.0000	4.9000e-004	0.0000	5.0000e-004	1.3000e-004	0.0000	1.3000e-004	0.0000	0.4146	0.4146	1.0000e-005	0.0000	0.4149
Total	1.8000e-004	1.3000e-004	1.4500e-003	0.0000	4.9000e-004	0.0000	5.0000e-004	1.3000e-004	0.0000	1.3000e-004	0.0000	0.4146	0.4146	1.0000e-005	0.0000	0.4149

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

3.5 Paving - 2022**Mitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Off-Road	1.6200e-003	0.0148	0.0176	3.0000e-005		7.4000e-004	7.4000e-004		6.9000e-004	6.9000e-004	0.0000	2.3492	2.3492	6.8000e-004	0.0000	2.3663
Paving	1.7000e-004					0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Total	1.7900e-003	0.0148	0.0176	3.0000e-005		7.4000e-004	7.4000e-004		6.9000e-004	6.9000e-004	0.0000	2.3492	2.3492	6.8000e-004	0.0000	2.3663

Mitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Worker	1.8000e-004	1.3000e-004	1.4500e-003	0.0000	4.9000e-004	0.0000	5.0000e-004	1.3000e-004	0.0000	1.3000e-004	0.0000	0.4146	0.4146	1.0000e-005	0.0000	0.4149
Total	1.8000e-004	1.3000e-004	1.4500e-003	0.0000	4.9000e-004	0.0000	5.0000e-004	1.3000e-004	0.0000	1.3000e-004	0.0000	0.4146	0.4146	1.0000e-005	0.0000	0.4149

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

3.6 Architectural Coating - 2022**Unmitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Archit. Coating	0.0150					0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Off-Road	5.1000e-004	3.5200e-003	4.5300e-003	1.0000e-005		2.0000e-004	2.0000e-004		2.0000e-004	2.0000e-004	0.0000	0.6383	0.6383	4.0000e-005	0.0000	0.6394
Total	0.0155	3.5200e-003	4.5300e-003	1.0000e-005		2.0000e-004	2.0000e-004		2.0000e-004	2.0000e-004	0.0000	0.6383	0.6383	4.0000e-005	0.0000	0.6394

Unmitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Worker	1.0000e-005	1.0000e-005	8.0000e-005	0.0000	3.0000e-005	0.0000	3.0000e-005	1.0000e-005	0.0000	1.0000e-005	0.0000	0.0230	0.0230	0.0000	0.0000	0.0231
Total	1.0000e-005	1.0000e-005	8.0000e-005	0.0000	3.0000e-005	0.0000	3.0000e-005	1.0000e-005	0.0000	1.0000e-005	0.0000	0.0230	0.0230	0.0000	0.0000	0.0231

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

3.6 Architectural Coating - 2022**Mitigated Construction On-Site**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Archit. Coating	0.0150					0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Off-Road	5.1000e-004	3.5200e-003	4.5300e-003	1.0000e-005		2.0000e-004	2.0000e-004		2.0000e-004	2.0000e-004	0.0000	0.6383	0.6383	4.0000e-005	0.0000	0.6394
Total	0.0155	3.5200e-003	4.5300e-003	1.0000e-005		2.0000e-004	2.0000e-004		2.0000e-004	2.0000e-004	0.0000	0.6383	0.6383	4.0000e-005	0.0000	0.6394

Mitigated Construction Off-Site

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Hauling	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Vendor	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Worker	1.0000e-005	1.0000e-005	8.0000e-005	0.0000	3.0000e-005	0.0000	3.0000e-005	1.0000e-005	0.0000	1.0000e-005	0.0000	0.0230	0.0230	0.0000	0.0000	0.0231
Total	1.0000e-005	1.0000e-005	8.0000e-005	0.0000	3.0000e-005	0.0000	3.0000e-005	1.0000e-005	0.0000	1.0000e-005	0.0000	0.0230	0.0230	0.0000	0.0000	0.0231

4.0 Operational Detail - Mobile

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

4.1 Mitigation Measures Mobile

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Mitigated	0.1593	0.8121	1.4842	4.9000e-003	0.3769	4.0400e-003	0.3810	0.1010	3.7700e-003	0.1048	0.0000	453.8737	453.8737	0.0258	0.0000	454.5180
Unmitigated	0.1593	0.8121	1.4842	4.9000e-003	0.3769	4.0400e-003	0.3810	0.1010	3.7700e-003	0.1048	0.0000	453.8737	453.8737	0.0258	0.0000	454.5180

4.2 Trip Summary Information

Land Use	Average Daily Trip Rate			Unmitigated	Mitigated
	Weekday	Saturday	Sunday	Annual VMT	Annual VMT
Automobile Care Center	740.52	740.52	740.52	991,965	991,965
Parking Lot	0.00	0.00	0.00		
Total	740.52	740.52	740.52	991,965	991,965

4.3 Trip Type Information

Land Use	Miles			Trip %			Trip Purpose %		
	H-W or C-W	H-S or C-C	H-O or C-NW	H-W or C-W	H-S or C-C	H-O or C-NW	Primary	Diverted	Pass-by
Automobile Care Center	16.60	8.40	6.90	33.00	48.00	19.00	21	51	28
Parking Lot	16.60	8.40	6.90	0.00	0.00	0.00	0	0	0

4.4 Fleet Mix

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

Land Use	LDA	LDT1	LDT2	MDV	LHD1	LHD2	MHD	HHD	OBUS	UBUS	MCY	SBUS	MH
Automobile Care Center	0.549559	0.042893	0.201564	0.118533	0.015569	0.005846	0.021394	0.034255	0.002099	0.001828	0.004855	0.000709	0.000896
Parking Lot	0.549559	0.042893	0.201564	0.118533	0.015569	0.005846	0.021394	0.034255	0.002099	0.001828	0.004855	0.000709	0.000896

5.0 Energy Detail

Historical Energy Use: N

5.1 Mitigation Measures Energy

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Electricity Mitigated						0.0000	0.0000		0.0000	0.0000	0.0000	117.9314	117.9314	4.8700e-003	1.0100e-003	118.3534
Electricity Unmitigated						0.0000	0.0000		0.0000	0.0000	0.0000	117.9314	117.9314	4.8700e-003	1.0100e-003	118.3534
NaturalGas Mitigated	6.5100e-003	0.0592	0.0497	3.6000e-004		4.5000e-003	4.5000e-003		4.5000e-003	4.5000e-003	0.0000	64.4179	64.4179	1.2300e-003	1.1800e-003	64.8007
NaturalGas Unmitigated	6.5100e-003	0.0592	0.0497	3.6000e-004		4.5000e-003	4.5000e-003		4.5000e-003	4.5000e-003	0.0000	64.4179	64.4179	1.2300e-003	1.1800e-003	64.8007

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

5.2 Energy by Land Use - NaturalGas**Unmitigated**

	NaturalGas Use	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Land Use	kBTU/yr	tons/yr										MT/yr					
Automobile Care Center	1.20715e+006	6.5100e-003	0.0592	0.0497	3.6000e-004		4.5000e-003	4.5000e-003		4.5000e-003	4.5000e-003	0.0000	64.4179	64.4179	1.2300e-003	1.1800e-003	64.8007
Parking Lot	0	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Total		6.5100e-003	0.0592	0.0497	3.6000e-004		4.5000e-003	4.5000e-003		4.5000e-003	4.5000e-003	0.0000	64.4179	64.4179	1.2300e-003	1.1800e-003	64.8007

Mitigated

	NaturalGas Use	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Land Use	kBTU/yr	tons/yr										MT/yr					
Automobile Care Center	1.20715e+006	6.5100e-003	0.0592	0.0497	3.6000e-004		4.5000e-003	4.5000e-003		4.5000e-003	4.5000e-003	0.0000	64.4179	64.4179	1.2300e-003	1.1800e-003	64.8007
Parking Lot	0	0.0000	0.0000	0.0000	0.0000		0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Total		6.5100e-003	0.0592	0.0497	3.6000e-004		4.5000e-003	4.5000e-003		4.5000e-003	4.5000e-003	0.0000	64.4179	64.4179	1.2300e-003	1.1800e-003	64.8007

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

5.3 Energy by Land Use - Electricity**Unmitigated**

	Electricity Use	Total CO2	CH4	N2O	CO2e
Land Use	kWh/yr	MT/yr			
Automobile Care Center	368030	117.2623	4.8400e-003	1.0000e-003	117.6819
Parking Lot	2100	0.6691	3.0000e-005	1.0000e-005	0.6715
Total		117.9314	4.8700e-003	1.0100e-003	118.3534

Mitigated

	Electricity Use	Total CO2	CH4	N2O	CO2e
Land Use	kWh/yr	MT/yr			
Automobile Care Center	368030	117.2623	4.8400e-003	1.0000e-003	117.6819
Parking Lot	2100	0.6691	3.0000e-005	1.0000e-005	0.6715
Total		117.9314	4.8700e-003	1.0100e-003	118.3534

6.0 Area Detail**6.1 Mitigation Measures Area**

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
Category	tons/yr										MT/yr					
Mitigated	0.0130	0.0000	2.3000e-004	0.0000		0.0000	0.0000		0.0000	0.0000	0.0000	4.5000e-004	4.5000e-004	0.0000	0.0000	4.8000e-004
Unmitigated	0.0130	0.0000	2.3000e-004	0.0000		0.0000	0.0000		0.0000	0.0000	0.0000	4.5000e-004	4.5000e-004	0.0000	0.0000	4.8000e-004

6.2 Area by SubCategory

Unmitigated

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
SubCategory	tons/yr										MT/yr					
Architectural Coating	1.5000e-003					0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Consumer Products	0.0114					0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Landscaping	2.0000e-005	0.0000	2.3000e-004	0.0000		0.0000	0.0000		0.0000	0.0000	0.0000	4.5000e-004	4.5000e-004	0.0000	0.0000	4.8000e-004
Total	0.0130	0.0000	2.3000e-004	0.0000		0.0000	0.0000		0.0000	0.0000	0.0000	4.5000e-004	4.5000e-004	0.0000	0.0000	4.8000e-004

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

6.2 Area by SubCategory**Mitigated**

	ROG	NOx	CO	SO2	Fugitive PM10	Exhaust PM10	PM10 Total	Fugitive PM2.5	Exhaust PM2.5	PM2.5 Total	Bio- CO2	NBio- CO2	Total CO2	CH4	N2O	CO2e
SubCategory	tons/yr										MT/yr					
Architectural Coating	1.5000e-003					0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Consumer Products	0.0114					0.0000	0.0000		0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Landscaping	2.0000e-005	0.0000	2.3000e-004	0.0000		0.0000	0.0000		0.0000	0.0000	0.0000	4.5000e-004	4.5000e-004	0.0000	0.0000	4.8000e-004
Total	0.0130	0.0000	2.3000e-004	0.0000		0.0000	0.0000		0.0000	0.0000	0.0000	4.5000e-004	4.5000e-004	0.0000	0.0000	4.8000e-004

7.0 Water Detail**7.1 Mitigation Measures Water**

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

	Total CO2	CH4	N2O	CO2e
Category	MT/yr			
Mitigated	7.4479	3.1000e-004	6.0000e-005	7.4746
Unmitigated	7.4479	3.1000e-004	6.0000e-005	7.4746

7.2 Water by Land Use**Unmitigated**

	Indoor/Outdoor Use	Total CO2	CH4	N2O	CO2e
Land Use	Mgal	MT/yr			
Automobile Care Center	0 / 2.104	7.4479	3.1000e-004	6.0000e-005	7.4746
Parking Lot	0 / 0	0.0000	0.0000	0.0000	0.0000
Total		7.4479	3.1000e-004	6.0000e-005	7.4746

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

7.2 Water by Land Use**Mitigated**

	Indoor/Outdoor Use	Total CO2	CH4	N2O	CO2e
Land Use	Mgal	MT/yr			
Automobile Care Center	0 / 2.104	7.4479	3.1000e-004	6.0000e-005	7.4746
Parking Lot	0 / 0	0.0000	0.0000	0.0000	0.0000
Total		7.4479	3.1000e-004	6.0000e-005	7.4746

8.0 Waste Detail**8.1 Mitigation Measures Waste****Category/Year**

	Total CO2	CH4	N2O	CO2e
	MT/yr			
Mitigated	2.3730	0.1402	0.0000	5.8789
Unmitigated	2.3730	0.1402	0.0000	5.8789

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

8.2 Waste by Land Use**Unmitigated**

	Waste Disposed	Total CO2	CH4	N2O	CO2e
Land Use	tons	MT/yr			
Automobile Care Center	11.69	2.3730	0.1402	0.0000	5.8789
Parking Lot	0	0.0000	0.0000	0.0000	0.0000
Total		2.3730	0.1402	0.0000	5.8789

Mitigated

	Waste Disposed	Total CO2	CH4	N2O	CO2e
Land Use	tons	MT/yr			
Automobile Care Center	11.69	2.3730	0.1402	0.0000	5.8789
Parking Lot	0	0.0000	0.0000	0.0000	0.0000
Total		2.3730	0.1402	0.0000	5.8789

9.0 Operational Offroad

Equipment Type	Number	Hours/Day	Days/Year	Horse Power	Load Factor	Fuel Type
----------------	--------	-----------	-----------	-------------	-------------	-----------

20-10163 Long Beach Car Wash Project - South Coast AQMD Air District, Annual

10.0 Stationary Equipment

Fire Pumps and Emergency Generators

Equipment Type	Number	Hours/Day	Hours/Year	Horse Power	Load Factor	Fuel Type
----------------	--------	-----------	------------	-------------	-------------	-----------

Boilers

Equipment Type	Number	Heat Input/Day	Heat Input/Year	Boiler Rating	Fuel Type
----------------	--------	----------------	-----------------	---------------	-----------

User Defined Equipment

Equipment Type	Number
----------------	--------

11.0 Vegetation

Appendix B

On-site Exhaust Emissions Calculations

Car Wash Calculations

Time in Queue (Min) 10.00
Time in Queue (Hr) 0.167
gram to lbs 0.00220462
Miles traveled 5

Pollutant	grams/mile-vehicle	Per Vehicle (lbs/hour)	Per vehicle (lbs/vehicle trip)	369 vehicles (pounds per day)
ROG	0.015	0.00017	0.00003	0.010
NOX	0.018	0.00020	0.00003	0.012
CO	0.238	0.00263	0.00044	0.162
SOX	0.001	0.00001	0.00000	0.001
PM10	0.001	0.00002	0.00000	0.001
PM2.5	0.001	0.00001	0.00000	0.001

Car Wash Calculations

Time in Queue (Min) 10.00

Time in Queue (Hr) 0.167

gram to lbs 0.00220462

Miles traveled 5

Pollutant	grams/mile-vehicle	Per Vehicle (lbs/hour)	Per vehicle (lbs/vehicle trip)	Vehicle Emissions (pounds per day)
ROG	0.015	0.00017	0.00003	10.349
NOX	0.018	0.00020	0.00003	12.426
CO	0.238	0.00263	0.00044	164.297
SOX	0.001	0.00001	0.00000	0.642
PM10	0.001	0.00002	0.00000	1.003
PM2.5	0.001	0.00001	0.00000	0.923

Number of Vehicles 375000



20201 SW Birch Street, Suite 150
 Newport Beach, CA 92660
 P: 714-272-2302
Mike.Holritz@BridgeNet.us

July 28, 2022

Mr. Ahmad Ghaderi
A & S Engineering

Revised site design at the *5005 Long Beach Boulevard Car Wash* project
 Long Beach, California

Dear Mr. Ghaderi:

BridgeNet International previously performed an assessment of the projected car wash noise levels at the noise-sensitive areas (Dooley Elementary School) adjacent to the *5005 Long Beach Boulevard Car Wash* project (Report #2019-003-C; May 31, 2020). With the planned site design and equipment, the projected noise levels are listed in Table 1.

Table 1
PROJECTED NOISE LEVELS
(Original Site Design)

Location	L50 (dBA)
<u>Exit End</u>	
School Building to NW	43.0
School Playground to NW	51.7
School Playground to N	52.2
<u>Entrance End</u>	
School Playground to N	50.2
School Playground to NE	47.1
School Building to N	26.5

With the planned site design and equipment, the noise levels would meet the City's adjusted Noise Ordinance limits (i.e., with the adjustment for the measured ambient levels, the L50 standard would be 60 dBA).

Subsequently, the City requested that the developer go beyond the Noise Ordinance requirements, and that the project be designed to generate noise levels 7 dB below the adjusted Noise Ordinance limits. We performed a revised assessment (Report #2019-003-D; June 22, 2021) to determine the mitigation needed to accomplish this. In order to comply with this request, absorption (2,350 square feet of QuietFiber QF4) was included in the modeling of the car wash interior to absorb some of the noise. With this absorption, the noise levels would be reduced by approximately 7.5 dB, and the projected noise levels are listed in Table 2.

Table 2
PROJECTED NOISE LEVELS
(Original Site Design with Added Absorption)

Location	L50 (dBA)
<u>Exit End</u>	
School Building to NW	35.5
School Playground to NW	44.2
School Playground to N	44.7
<u>Entrance End</u>	
School Playground to N	42.7
School Playground to NE	37.6
School Building to N	19.0

The revised analysis showed that with the planned site design and equipment, and with the specified absorption added to the interior of the car wash building, the noise levels would be at least 7 dB below the City's adjusted Noise Ordinance limits (i.e., with the adjustment for the measured ambient levels, the L50 standard would be 60 dBA). It should be noted that these levels also meet the City's regular 50 dBA L50 standard (with no adjustment for measured ambient levels).

Since the preparation of that report, the developer has revised the site design. The current design calls for the exit end to be entirely enclosed, with solid walls and a solid roof. The exit opening will now face south (away from the school). Artist renderings of the project show roll-up doors at both the entrance and exit ends. However, these doors will remain open during car wash operations. With the current design, noise levels from the car wash operations are expected to be reduced by at least another 10 dB for receptors in the school area near the exit end. (Noise levels near the entrance end would not change significantly). The projected noise levels are listed in Table 3.

Table 3
PROJECTED NOISE LEVELS
(New Site Design with Added Absorption)

Location	L50 (dBA)
<u>Exit End</u>	
School Building to NW	25.5
School Playground to NW	34.2
School Playground to N	34.7
<u>Entrance End</u>	
School Playground to N	42.7
School Playground to NE	37.6
School Building to N	19.0

The most stringent noise standard is the 50 dBA L50 limit. With this revised site design and added absorption, noise levels from the car wash are now expected to be far below the Noise Ordinance limits (without including any adjustment for ambient).


With the new design, we would recommend that at least 50% of the added absorption be located in the exit area (after the blowers).

If you have any questions or require additional information, please do not hesitate to contact me.

Mike Holritz, INCE
Environmental Specialist
BridgeNet | A Tetra Tech Company

Report #2019-003-B

Revised March 11, 2020



Noise Analysis

5005 Long Beach Boulevard Car Wash
Long Beach, California

Prepared for:

A & S Engineering
28405 Sand Canyon Road, Suite B
Canyon Country, CA 91387



Mike Holritz, INCE

20201 SW Birch Street, Suite 250
Newport Beach, CA 92660
714-272-2302

Mike.Holritz@AirportNetwork.com

1.0 Definitions

- **Noise** is undesired sound.
- **Sound** is defined as vibrations traveling through the air or another medium that can be heard when they reach the ear.
- **Decibel (dB)** is a unit used to measure the level of a sound by comparing it with a given reference level on a logarithmic scale. One decibel equals 10 times the common logarithm of the power ratio.
- **“A-Weighting”** is a frequency correction that correlates overall sound pressure levels with the frequency response of the human ear.
- **L_{max}** is the highest sound pressure level during a measurement period.
- **L(N)** or **L%** is a statistical method of describing noise which accounts for variance in noise levels throughout a given measurement period. L(N) is a way of expressing the noise level exceeded for a percentage of time in a given measurement period. For example, since 5 minutes is 25% of 20 minutes, L(25) is the noise level that is equal to or exceeded for five minutes in a twenty-minute measurement period.

2.0 Introduction

This report addresses the potential noise impacts of the planned 5005 Long Beach Boulevard Car Wash on the adjacent properties. The car wash location is shown in Figure 1. The site plan is shown in Figure 2. Figure 3 depicts the project site on an aerial with the adjacent school shown. The facility is planning to use Motor City Air One blowers. Noise levels from the proposed car wash will be determined at the adjacent school. These noise levels will then be compared to the City of Long Beach Noise Ordinance limits.

3.0 Noise Standards

The project site is adjacent to the Dooley Elementary School to the north. Section 8.80.150 of the Long Beach Noise Ordinance specifies the City’s exterior noise standards. Section 8.80.170 of the Noise Ordinance specifies the interior noise standards.

The criteria contained in the City’s Noise Ordinance are given in terms of allowable noise levels for a given period of time at the affected property. It is our understanding that the City will require noise levels at the school playground to meet the exterior standards. The interior standards would apply at the school buildings. These standards are applied any time school is in session. The City of Long Beach Noise Ordinance limits are presented below in Table 1 and Table 2.

Figure 2 – Project Site Plan

Dooley Elementary School




Figure 3 – Project Site Plan on Aerial




Table 1
CITY OF LONG BEACH
EXTERIOR NOISE ORDINANCE CRITERIA

Time Period	Lmax	L1.7	L8.3	L25	L50
During School Session	70	65	60	55	50

Table 2
CITY OF LONG BEACH
INTERIOR NOISE ORDINANCE CRITERIA

Time Period	Lmax	L1.7	L8.3
During School Session	55	50	45

The ordinance states that if the ambient conditions are louder than the ordinance limits, then the ambient conditions become the new ordinance limits.

5.0 Ambient Noise Levels

The ordinance states that if the measured ambient level already exceeds the allowable limit, then the ambient level becomes the limit. Ambient noise measurements were performed at a location representing the boundary between the car wash and the school. Since access to the school playground was not possible, measurements were conducted in the Sizzler parking lot, very close to the location of the exit end of the tunnel. A 9.5' masonry wall mitigates the traffic noise from Del Amo Boulevard. Therefore, traffic noise from Del Amo Boulevard was subtracted out, so the measured noise levels at this location represent the ambient noise levels from Long Beach Boulevard at the nearest playground area.

Three noise measurements were made for approximately thirty minutes each on February 28, 2020, at a normal receptor height of 5 feet above the ground. The measurements were performed during the daytime period, between 8:00 a.m. and 1:30 p.m. The measurements were made with a Brüel & Kjær Type 2270 Sound Level Meter, which was calibrated before and after the measurements. This noise measurement system meets the American National Standards Institute "Type 1" specifications, which is the most accurate type of sound level meter available for community noise measurements. The meter and calibrator have current certification traceable to the National Institute of Standards and Technology (NIST). The results of the ambient noise measurements are presented below in Table 3.

Table 3
AMBIENT NOISE MEASUREMENT RESULTS

Time Period	Lmax	L1.7	L8.3	L25	L50
8:10 to 8:40 a.m.	74.8	64.3	60.2	58.5	56.5
10:00 to 10:30 a.m.	80.4	65.9	60.2	58.0	56.5
1:00 to 1:30 p.m.	75.4	67.0	62.0	60.0	58.8
Adjusted (Lowest Measured Ambient)	74.8	N/A	60.2	58.0	56.5

The measured noise levels were caused by traffic on Long Beach Boulevard and by jet overflights.

The measured ambient traffic noise levels for some metrics (The Lmax, L8.3, L25, and L50) exceed the Noise Ordinance limits, so the Noise Ordinance limits for some metrics will be adjusted to these levels. To be conservative, for each metric, we have used the lowest measured ambient as the adjusted Noise Ordinance limit. The adjusted Noise Ordinance limits are shown below in Table 4.

Table 4
ADJUSTED EXTERIOR NOISE ORDINANCE CRITERIA

Location	Lmax	L1.7	L8.3	L25	L50
School Playground	74.8	65	60.2	58.0	56.5

6.0 Noise Exposure

The project calls for the construction of a car wash facility very similar to an existing car wash at 4294 University Parkway in San Bernardino, California. Noise measurements were conducted at this facility on February 11, 2019 to determine the noise levels expected at the Long Beach car wash site. The major noise-producing components are the blowers for the dryer section. This facility uses 11 Motor City Air One blowers. The blowers are set back approximately 21 feet from the exit end of the tunnel. The vacuum equipment is located in the equipment room. Therefore, noise from this source is not expected to be significant.

Using the Motor City Air One blowers, the noise levels would slightly exceed the City's Noise Ordinance limits. Therefore, the developer plans to use Aerodry Model A120 Blowers. Data provided by the manufacturer shows that these blowers are 6 dB quieter than the Motor City dryers. With this equipment, the noise levels from the car wash (including the effect of the existing 9.5' high wall) are projected to be 52.2 dBA at the nearest receptor at the school playground. To represent a worst-case scenario, the equipment was assumed to run continuously. Therefore, the noise level for all metrics would be 52.2 dBA. This meets the strictest adjusted limit of 56.5 dBA. To meet the exterior standards, the Aerodry equipment must be used. With the Aerodry equipment, no additional mitigation measures are required in order to meet the exterior noise standards. The remaining analysis is based on the use of Aerodry blowers.


Two school buildings were analyzed, and these are shown in the Appendix. The nearest building is 150 feet to the northwest of the exit end of the tunnel, at an orientation of approximately 45 degrees off-axis to the tunnel. The measurements at the San Bernardino site showed that at this orientation, the sound level at a distance of 15 feet from the tunnel end would 83 dBA. Extrapolating this to a distance of 150 feet yields a noise level of 63 dBA. With 5 dBA of reduction provided by the existing masonry wall, the noise level at the building face would be 58 dBA. The Aerodry equipment is 6 dB quieter, so the resulting exterior noise level is projected to be 52 dBA.


Another building is 200 feet to the north of the entrance end of the tunnel, at an orientation of approximately 80 degrees off-axis to the tunnel. The measurements at the San Bernardino site showed that at this orientation, the sound level at a distance of 15 feet from the tunnel end was 71 dBA. Extrapolating this to a distance of 210 feet yields a noise level of 48 dBA. With 5 dBA of reduction provided by the existing masonry wall, the noise level at the building face would be 43 dBA. The Aerodry equipment is 6 dB quieter, so the resulting exterior noise level is projected to be 37 dBA.

With windows open, the noise reduction of a typical building is at least 12 dBA. Therefore, the interior noise levels at these buildings are expected to be 40 dBA and 25 dBA, respectively. These levels meet the City's strictest (L8.3) noise standard of 45 dBA. Therefore, with the Aerodry Model A120 equipment, the 5005 Long Beach Boulevard car wash is projected to meet all the City's noise standards without any additional mitigation measures.

APPENDIX

RECEPTOR LOCATIONS AND PROJECTED EXTERIOR NOISE LEVELS (including effect of existing 9.5-foot-high masonry wall)





Construction Noise Analysis

5005 Long Beach Boulevard Car Wash
Long Beach, California

Prepared for:

A&S Engineering
28405 Sand Canyon Road, Suite B
Canyon Country, CA 90071



Mike Holritz, INCE

20201 SW Birch Street, Suite 250
Newport Beach, CA 92660
714-272-2302
Mike.Holritz@AirportNetwork.com

1.0 Definitions


- **Noise** is undesired sound.
- **Sound** is defined as vibrations traveling through the air or another medium that can be heard when they reach the ear.
- **Decibel (dB)** is a unit used to measure the level of a sound by comparing it with a given reference level on a logarithmic scale. One decibel equals 10 times the common logarithm of the power ratio.
- **Time-Weighted** refers to the fact that noise occurring during certain time periods is given more significance because it occurs at times when people are more sensitive to noise.
- **“A-Weighting”** is a frequency correction that correlates overall sound pressure levels with the frequency response of the human ear.
- **A-Weighting** is a frequency correction that correlates overall sound pressure levels with the frequency response of the human ear.
- **L(N)** or **L%** is a statistical method of describing noise that accounts for fluctuating noise levels. **L%** is a way of expressing the noise level exceeded for a percentage of time during a given period. For example, since 5 minutes is 50% of 10 minutes, **L50** is the noise level that is exceeded for five minutes in a ten-minute period.
- **Lmax** is the highest instantaneous sound pressure level during a specific time period.

2.0 Introduction

The purpose of this report is to address the potential construction noise impacts on existing noise sensitive uses in the vicinity of the planned *5005 Long Beach Boulevard Car Wash* project. The project is located in the City of Long Beach as shown in Figure 1. There are single-family homes located to the west of the project site, and Dooley Elementary School is located directly north of the project site. The site plan is shown in Figure 2.

The map displays a grid of streets in Long Beach, California. The primary intersection shown is West Del Amo Boulevard and Long Beach Boulevard, marked with a red pin. To the north of this intersection is Dooley Elementary School and the Sizzler restaurant. To the south are Tom's Tropical Fish, Travel King, Walls Motel Long Beach, Arbor Mobile Home Park, and Wayside Trailer & RV Park. The map includes a compass rose in the bottom left corner, indicating North (N), South (S), East (E), and West (W). The streets shown include W 51st St, W 50th St, W 49th St, W 48th St, W 47th St, W 46th St, W 45th St, W 44th St, W 43rd St, W 42nd St, W 41st St, W 40th St, W 39th St, W 38th St, W 37th St, W 36th St, W 35th St, W 34th St, W 33rd St, W 32nd St, W 31st St, W 30th St, W 29th St, W 28th St, W 27th St, W 26th St, W 25th St, W 24th St, W 23rd St, W 22nd St, W 21st St, W 20th St, W 19th St, W 18th St, W 17th St, W 16th St, W 15th St, W 14th St, W 13th St, W 12th St, W 11th St, W 10th St, W 9th St, W 8th St, W 7th St, W 6th St, W 5th St, W 4th St, W 3rd St, W 2nd St, W 1st St, W Main St, W Ocean Blvd, W Del Amo Blvd, W Long Beach Blvd, W Pacific Blvd, W Carson St, W Atlantic St, W Broadway St, W Hill St, W Grand St, W Madison St, W Monroe St, W P St, W R St, W S St, W T St, W U St, W V St, W W St, W X St, W Y St, W Z St, W AA St, W AB St, W AC St, W AD St, W AE St, W AF St, W AG St, W AH St, W AI St, W AJ St, W AK St, W AL St, W AM St, W AN St, W AO St, W AP St, W AQ St, W AR St, W AS St, W AT St, W AU St, W AV St, W AW St, W AX St, W AY St, W AZ St, W BA St, W BB St, W BC St, W BD St, W BE St, W BF St, W BG St, W BH St, W BI St, W BJ St, W BK St, W BL St, W BM St, W BN St, W BO St, W BP St, W BQ St, W BR St, W BS St, W BT St, W BU St, W BV St, W BW St, W BX St, W BY St, W BZ St, W CA St, W CB St, W CC St, W CD St, W CE St, W CF St, W CG St, W CH St, W CI St, W CJ St, W CK St, W CL St, W CM St, W CN St, W CO St, W CP St, W CQ St, W CR St, W CS St, W CT St, W CU St, W CV St, W CW St, W CX St, W CY St, W CZ St, W DA St, W DB St, W DC St, W DD St, W DE St, W DF St, W DG St, W DH St, W DI St, W DJ St, W DK St, W DL St, W DM St, W DN St, W DO St, W DP St, W DQ St, W DR St, W DS St, W DT St, W DU St, W DV St, W DW St, W DX St, W DY St, W DZ St, W EA St, W EB St, W EC St, W ED St, W EF St, W EG St, W EH St, W EI St, W EJ St, W EK St, W EL St, W EM St, W EN St, W EO St, W EP St, W EQ St, W ER St, W ES St, W ET St, W EU St, W EV St, W EW St, W EX St, W EY St, W EZ St, W FA St, W FB St, W FC St, W FD St, W FE St, W FF St, W FG St, W FH St, W FI St, W FJ St, W FK St, W FL St, W FM St, W FN St, W FO St, W FP St, W FQ St, W FR St, W FS St, W FT St, W FU St, W FV St, W FW St, W FX St, W FY St, W FZ St, W GA St, W GB St, W GC St, W GD St, W GE St, W GF St, W GG St, W GH St, W GI St, W GJ St, W GK St, W GL St, W GM St, W GN St, W GO St, W GP St, W GQ St, W GR St, W GS St, W GT St, W GU St, W GV St, W GW St, W GX St, W GY St, W GZ St, W HA St, W HB St, W HC St, W HD St, W HE St, W HF St, W HG St, W HH St, W HI St, W HJ St, W HK St, W HL St, W HM St, W HN St, W HO St, W HP St, W HQ St, W HR St, W HS St, W HT St, W HU St, W HV St, W HW St, W HX St, W HY St, W HZ St, W IA St, W IB St, W IC St, W ID St, W IE St, W IF St, W IG St, W IH St, W II St, W IJ St, W IK St, W IL St, W IM St, W IN St, W IO St, W IP St, W IQ St, W IR St, W IS St, W IT St, W IU St, W IV St, W IW St, W IX St, W IY St, W IZ St, W JA St, W JB St, W JC St, W JD St, W JE St, W JF St, W JG St, W JH St, W JI St, W JJ St, W JK St, W JL St, W JM St, W JN St, W JO St, W JP St, W JQ St, W JR St, W JS St, W JT St, W JU St, W JV St, W JW St, W JX St, W JY St, W JZ St, W KA St, W KB St, W KC St, W KD St, W KE St, W KF St, W KG St, W KH St, W KI St, W KJ St, W KK St, W KL St, W KM St, W KN St, W KO St, W KP St, W KQ St, W KR St, W KS St, W KT St, W KU St, W KV St, W KW St, W KX St, W KY St, W KZ St, W LA St, W LB St, W LC St, W LD St, W LE St, W LF St, W LG St, W LH St, W LI St, W LJ St, W LK St, W LL St, W LM St, W LN St, W LO St, W LP St, W LQ St, W LR St, W LS St, W LT St, W LU St, W LV St, W LW St, W LX St, W LY St, W LZ St, W MA St, W MB St, W MC St, W MD St, W ME St, W MF St, W MG St, W MH St, W MI St, W MJ St, W MK St, W ML St, W MM St, W MN St, W MO St, W MP St, W MQ St, W MR St, W MS St, W MT St, W MU St, W MV St, W MW St, W MX St, W MY St, W MZ St, W NA St, W NB St, W NC St, W ND St, W NE St, W NF St, W NG St, W NH St, W NI St, W NJ St, W NK St, W NL St, W NM St, W NN St, W NO St, W NP St, W NQ St, W NR St, W NS St, W NT St, W NU St, W NV St, W NW St, W NX St, W NY St, W NZ St, W OA St, W OB St, W OC St, W OD St, W OE St, W OF St, W OG St, W OH St, W OI St, W OJ St, W OK St, W OL St, W OM St, W ON St, W OO St, W OP St, W OQ St, W OR St, W OS St, W OT St, W OU St, W OV St, W OW St, W OX St, W OY St, W OZ St, W PA St, W PB St, W PC St, W PD St, W PE St, W PF St, W PG St, W PH St, W PI St, W PJ St, W PK St, W PL St, W PM St, W PN St, W PO St, W PP St, W PQ St, W PR St, W PS St, W PT St, W PU St, W PV St, W PW St, W PX St, W PY St, W PZ St, W QA St, W QB St, W QC St, W QD St, W QE St, W QF St, W QG St, W QH St, W QI St, W QJ St, W QK St, W QL St, W QM St, W QN St, W QO St, W QP St, W QQ St, W QR St, W QS St, W QT St, W QU St, W QV St, W QW St, W QX St, W QY St, W QZ St, W RA St, W RB St, W RC St, W RD St, W RE St, W RF St, W RG St, W RH St, W RI St, W RJ St, W RK St, W RL St, W RM St, W RN St, W RO St, W RP St, W RQ St, W RR St, W RS St, W RT St, W RU St, W RV St, W RW St, W RX St, W RY St, W RZ St, W SA St, W SB St, W SC St, W SD St, W SE St, W SF St, W SG St, W SH St, W SI St, W SJ St, W SK St, W SL St, W SM St, W SN St, W SO St, W SP St, W SQ St, W SR St, W SS St, W ST St, W SU St, W SV St, W SW St, W SX St, W SY St, W SZ St, W TA St, W TB St, W TC St, W TD St, W TE St, W TF St, W TG St, W TH St, W TI St, W TJ St, W TK St, W TL St, W TM St, W TN St, W TO St, W TP St, W TQ St, W TR St, W TS St, W TT St, W TU St, W TV St, W TW St, W TX St, W TY St, W TZ St, W UA St, W UB St, W UC St, W UD St, W UE St, W UF St, W UG St, W UH St, W UI St, W UJ St, W UK St, W UL St, W UM St, W UN St, W UO St, W UP St, W UQ St, W UR St, W US St, W UT St, W UU St, W UV St, W UW St, W UX St, W UY St, W UZ St, W VA St, W VB St, W VC St, W VD St, W VE St, W VF St, W VG St, W VH St, W VI St, W VJ St, W VK St, W VL St, W VM St, W VN St, W VO St, W VP St, W VQ St, W VR St, W VS St, W VT St, W VU St, W VV St, W VW St, W VX St, W VY St, W VZ St, W WA St, W WB St, W WC St, W WD St, W WE St, W WF St, W WG St, W WH St, W WI St, W WJ St, W WK St, W WL St, W WM St, W WN St, W WO St, W WP St, W WQ St, W WR St, W WS St, W WT St, W WU St, W WV St, W WW St, W WX St, W WY St, W WZ St, W XA St, W XB St, W XC St, W XD St, W XE St, W XF St, W XG St, W XH St, W XI St, W XJ St, W XK St, W XL St, W XM St, W XN St, W XO St, W XP St, W XQ St, W XR St, W XS St, W XT St, W XU St, W XV St, W XW St, W XX St, W XY St, W XZ St, W YA St, W YB St, W YC St, W YD St, W YE St, W YF St, W YG St, W YH St, W YI St, W YJ St, W YK St, W YL St, W YM St, W YN St, W YO St, W YP St, W YQ St, W YR St, W YS St, W YT St, W YU St, W YV St, W YW St, W YX St, W YY St, W YZ St, W ZA St, W ZB St, W ZC St, W ZD St, W ZE St, W ZF St, W ZG St, W ZH St, W ZI St, W ZJ St, W ZK St, W ZL St, W ZM St, W ZN St, W ZO St, W ZP St, W ZQ St, W ZR St, W ZS St, W ZT St, W ZU St, W ZV St, W ZW St, W ZX St, W ZY St, W ZZ St.


Figure 2 – Project Site Plan



3.0 Construction Equipment Source Levels

Construction noise represents a short-term impact on neighborhood noise levels. Noise generated by construction equipment can reach high levels. The highest levels of noise will be generated during site preparation and grading when large pieces of heavy equipment are operated. The ranges of noise levels typically generated by various pieces of construction equipment are presented in Figure 3.

Figure 3 – Typical Construction Noise Levels



Note that these noise levels are based upon worst-case conditions. Typically, noise levels will be less. Noise measurements performed for other projects have shown that the noise levels generated by commonly used grading equipment (i.e., loaders, graders and trucks) generate noise levels that usually do not exceed the typical noise level shown within each range in Figure 3.

Jackhammers or pile drivers are not anticipated to be required during construction of the project. According to the developer, the following equipment is planned for use at the site:

Skid steers
Small Backhoe (15' reach)
Dump truck (10-wheel)
End dump
Concrete pump
Small crane

Of these, the quietest equipment is the backhoe, with a typical noise level of 80 dBA at a distance of 50 feet. The loudest is the dump truck, with a typical noise level of 88 dBA at a distance of 50 feet.

4.0 Noise Ordinance Limits

The City's Noise Ordinance Section 8.80.150, Table IV.I-1 requires that noise levels at outdoor residential areas (District 1) not exceed 50 dBA L50 during the daytime hours (7 a.m. to 10 p.m.) or 45 dBA L50 during nighttime hours (10 p.m. to 7 a.m.). Table IV.I-2 requires that interior noise levels be limited to 45 dBA L50 during daytime hours, and 35 dBA L50 at night.

The City's Noise Ordinance Section 8.80.150, Table IV.I-2 requires that noise impacting indoor school areas not exceed an L50 level of 45 dBA while school is in session.

5.0 Projected Noise Levels

Calculations show that at the nearest residential area to the west (at a distance of 225 feet from the nearest construction equipment location), the noise levels would range between 51 dBA and 59 dBA. This exceeds the City's noise Ordinance limits.

At the nearest school building to the north (at a distance of 158 feet from the nearest construction equipment location), the noise levels at the building face would range between 54 dBA and 62 dBA. Assuming a building noise reduction of 20 dB, indoor noise levels at this building are projected to range between 34 dBA and 42 dBA. This meets the City's noise limits.

6.0 Allowable Construction Hours

Construction of the project would result in noise levels in excess of the City's Noise Ordinance limits at the residential area to the west. However, the City's Noise Ordinance (Section 8.80.202) appears to allow construction to take place provided activities do not occur during specified days and hours. The construction time limits are stated as follows:

8.80.202 - Construction Activity – Noise Regulations


- (A) *Weekdays and federal holidays.* No person shall operate or permit the operation of any tools or equipment used for construction, alteration, repair, remodeling, drilling, demolition or any other related building activity which produce loud or unusual noise which annoys or disturbs a reasonable person of normal sensitivity between the hours of 7 p.m. and 7 a.m. the following day on weekdays, except for emergency work authorized by the building official. For purposes of this section, a federal holiday shall be considered a weekday.
- (B) *Saturdays.* No person shall operate or permit the operation of any tools or equipment used for construction, alteration, repair, remodeling, drilling, demolition or any other related building activity which produce loud or unusual noise which annoys or disturbs a reasonable person of normal sensitivity between the hours of 7 p.m. (Friday) and 9 a.m. on Saturday and after 6 p.m. on Saturday, except for emergency work authorized by the building official.
- (C) *Sundays.* No person shall operate or permit the operation of any tools or equipment used for construction, alteration, repair, remodeling, drilling, demolition or any other related building activity at any time on Sunday, except for emergency work authorized by the building official or except for work authorized by permit issued by the noise control office.

The City's Noise Ordinance appears to allow construction on weekdays between 7 a.m. and 7 p.m., and on Saturdays between 9 a.m. and 6 p.m.

6.0 Recommendations

The following mitigation measures are best management practice and will help ensure that the noise impacts from construction activities are minimized.

- Limit the loudest construction activities, such as concrete breaking, jackhammering, pile driving, to the middle of the day when the sensitivity to such noises will be at its lowest.
- Use updated equipment which incorporates quiet technology and advanced muffler design.
- Update older equipment with either new equipment or incorporate new noise control features when possible.
- Maintain older equipment to minimize the level of noise from normal wear and tear that can cause excessive noise from the equipment.
- Use electrically powered construction equipment when practical.
- Restrict the use of equipment at the project boundaries when possible.
- Ensure that the equipment power is appropriate for the construction activity – neither overpowered or underpowered.
- Use temporary noise barriers around fixed noise sources such as pumps and compressors when necessary.
- Use on-site trailers, containers, aggregate as temporary barriers between a fixed construction noise source and the nearby residences.
- Locate fixed noise generating equipment (i.e. pumps, compressors) as far from the noise sensitive land uses as is practical.
- Limit the level and use of music generating devices (i.e. radios) on the project site.
- Consider the use of back up alarms which incorporate white noise or flashing lights.
- Haul truck deliveries and departures shall be subject to the same hours specified for construction equipment.
- Provide a phone number people can call should they have noise complaints. If complaints arise, initiate a construction noise monitoring plan to ensure the construction noise levels at the nearest noise sensitive land uses are compliance with the noise ordinance.



Construction Noise Analysis

5005 Long Beach Boulevard Car Wash
Long Beach, California

Prepared for:

A&S Engineering
28405 Sand Canyon Road, Suite B
Canyon Country, CA 90071



Mike Holritz, INCE

20201 SW Birch Street, Suite 250
Newport Beach, CA 92660
714-272-2302
Mike.Holritz@AirportNetwork.com


1.0 Definitions

- **Noise** is undesired sound.
- **Sound** is defined as vibrations traveling through the air or another medium that can be heard when they reach the ear.
- **Decibel (dB)** is a unit used to measure the level of a sound by comparing it with a given reference level on a logarithmic scale. One decibel equals 10 times the common logarithm of the power ratio.
- **Time-Weighted** refers to the fact that noise occurring during certain time periods is given more significance because it occurs at times when people are more sensitive to noise.
- **“A-Weighting”** is a frequency correction that correlates overall sound pressure levels with the frequency response of the human ear.
- **A-Weighting** is a frequency correction that correlates overall sound pressure levels with the frequency response of the human ear.
- **L(N)** or **L%** is a statistical method of describing noise that accounts for fluctuating noise levels. **L%** is a way of expressing the noise level exceeded for a percentage of time during a given period. For example, since 5 minutes is 50% of 10 minutes, **L50** is the noise level that is exceeded for five minutes in a ten-minute period.
- **Lmax** is the highest instantaneous sound pressure level during a specific time period.

2.0 Introduction

The purpose of this report is to address the potential construction noise impacts on existing noise sensitive uses in the vicinity of the planned *5005 Long Beach Boulevard Car Wash* project. The project is located in the City of Long Beach as shown in Figure 1. There are single-family homes located to the west of the project site, and Dooley Elementary School is located directly north of the project site. The site plan is shown in Figure 2.


Figure 2 – Project Site Plan



3.0 Construction Equipment Source Levels

Construction noise represents a short-term impact on neighborhood noise levels. Noise generated by construction equipment can reach high levels. The highest levels of noise will be generated during site preparation and grading when large pieces of heavy equipment are operated. The ranges of noise levels typically generated by various pieces of construction equipment are presented in Figure 3.

Figure 3 – Typical Construction Noise Levels



Note that these noise levels are based upon worst-case conditions. Typically, noise levels will be less. Noise measurements performed for other projects have shown that the noise levels generated by commonly used grading equipment (i.e., loaders, graders and trucks) generate noise levels that usually do not exceed the typical noise level shown within each range in Figure 3.

Jackhammers or pile drivers are not anticipated to be required during construction of the project. According to the developer, the following equipment is planned for use at the site:

Skid steers
Small Backhoe (15' reach)
Dump truck (10-wheel)
End dump
Concrete pump
Small crane

Of these, the quietest equipment is the backhoe, with a typical noise level of 80 dBA at a distance of 50 feet. The loudest is the dump truck, with a typical noise level of 88 dBA at a distance of 50 feet.

4.0 Noise Ordinance Limits

The City's Noise Ordinance Section 8.80.150, Table IV.I-1 requires that noise levels at outdoor residential areas (District 1) not exceed 50 dBA L50 during the daytime hours (7 a.m. to 10 p.m.) or 45 dBA L50 during nighttime hours (10 p.m. to 7 a.m.). Table IV.I-2 requires that interior noise levels be limited to 45 dBA L50 during daytime hours, and 35 dBA L50 at night.

The City's Noise Ordinance Section 8.80.150, Table IV.I-2 requires that noise impacting indoor school areas not exceed an L50 level of 45 dBA while school is in session.

5.0 Projected Noise Levels

Calculations show that at the nearest residential area to the west (at a distance of 225 feet from the nearest construction equipment location), the noise levels would range between 51 dBA and 59 dBA. This exceeds the City's noise Ordinance limits.

At the nearest school building to the north (at a distance of 158 feet from the nearest construction equipment location), the noise levels at the building face would range between 54 dBA and 62 dBA. Assuming a building noise reduction of 20 dB, indoor noise levels at this building are projected to range between 34 dBA and 42 dBA. This meets the City's noise limits.

6.0 Allowable Construction Hours

Construction of the project would result in noise levels in excess of the City's Noise Ordinance limits at the residential area to the west. However, the City's Noise Ordinance (Section 8.80.202) appears to allow construction to take place provided activities do not occur during specified days and hours. The construction time limits are stated as follows:

8.80.202 - Construction Activity – Noise Regulations

- (A) *Weekdays and federal holidays.* No person shall operate or permit the operation of any tools or equipment used for construction, alteration, repair, remodeling, drilling, demolition or any other related building activity which produce loud or unusual noise which annoys or disturbs a reasonable person of normal sensitivity between the hours of 7 p.m. and 7 a.m. the following day on weekdays, except for emergency work authorized by the building official. For purposes of this section, a federal holiday shall be considered a weekday.
- (B) *Saturdays.* No person shall operate or permit the operation of any tools or equipment used for construction, alteration, repair, remodeling, drilling, demolition or any other related building activity which produce loud or unusual noise which annoys or disturbs a reasonable person of normal sensitivity between the hours of 7 p.m. (Friday) and 9 a.m. on Saturday and after 6 p.m. on Saturday, except for emergency work authorized by the building official.
- (C) *Sundays.* No person shall operate or permit the operation of any tools or equipment used for construction, alteration, repair, remodeling, drilling, demolition or any other related building activity at any time on Sunday, except for emergency work authorized by the building official or except for work authorized by permit issued by the noise control office.

The City's Noise Ordinance appears to allow construction on weekdays between 7 a.m. and 7 p.m., and on Saturdays between 9 a.m. and 6 p.m.

6.0 Recommendations

The following mitigation measures are best management practice and will help ensure that the noise impacts from construction activities are minimized.

- Limit the loudest construction activities, such as concrete breaking, jackhammering, pile driving, to the middle of the day when the sensitivity to such noises will be at its lowest.
- Use updated equipment which incorporates quiet technology and advanced muffler design.
- Update older equipment with either new equipment or incorporate new noise control features when possible.
- Maintain older equipment to minimize the level of noise from normal wear and tear that can cause excessive noise from the equipment.
- Use electrically powered construction equipment when practical.
- Restrict the use of equipment at the project boundaries when possible.
- Ensure that the equipment power is appropriate for the construction activity – neither overpowered or underpowered.
- Use temporary noise barriers around fixed noise sources such as pumps and compressors when necessary.
- Use on-site trailers, containers, aggregate as temporary barriers between a fixed construction noise source and the nearby residences.
- Locate fixed noise generating equipment (i.e. pumps, compressors) as far from the noise sensitive land uses as is practical.
- Limit the level and use of music generating devices (i.e. radios) on the project site.
- Consider the use of back up alarms which incorporate white noise or flashing lights.
- Haul truck deliveries and departures shall be subject to the same hours specified for construction equipment.
- Provide a phone number people can call should they have noise complaints. If complaints arise, initiate a construction noise monitoring plan to ensure the construction noise levels at the nearest noise sensitive land uses are compliance with the noise ordinance.



October XX, 2020

Mr. Ahmad Ghaderi
A & S Engineering

20201 SW Birch Street, Suite 250
Newport Beach, CA 92660
P: 714-272-2302

Mike.Holritz@AirportNetwork.com

Response to Comments, 5005 Long Beach Boulevard Car Wash, Long Beach, California

Dear Mr. Ghaderi:

BridgeNet International has reviewed LSA's comments pertaining to our noise analysis for the 5005 Long Beach Boulevard Car Wash project (Report #219-5024 Task 3; June 30, 2020). This memo contains our responses to those comments. The comment is quoted, followed by our response in blue.

1 (Operational Noise) - LSA Senior Noise Staff has reviewed the *Construction Noise Analysis for the 5005 Long Beach Boulevard Car Wash* (noise analysis) (BridgeNet International, June 2020). The initial observation of the noise analysis is that it has only assessed off-site construction noise impacts. For a project that would incorporate significant noise sources such as the car wash and automobile vacuum cleaners, LSA's professional opinion is that operational noise should be analyzed, and any noise reduction measures to reduce noise impacts to achieve the necessary standards should be recommended. Given the proximity of the proposed car wash to surrounding sensitive uses, specifically Dooley Elementary School to the north and west, it would seem insufficient to not assess the potential operational impacts.

BridgeNet did perform an analysis of operational noise levels (Report #2019-003-C; May 31, 2020). The report determined that using the specified Aerodry A120 blowers, and including the effect of the existing noise barrier at the project property line, the project would meet the City's Noise Ordinance standards (adjusted for existing ambient conditions) at all nearby areas.

2 (Vibration) - Furthermore, there is no assessment of vibration during construction or operation of the proposed project. While it is highly likely there would be no damage resulting from vibration impacts during construction, there is the potential for vibration impacts to occur at the playground and sports fields immediately to the north of the proposed project site.

We were not requested to perform any vibration analysis for the project. We find it highly unlikely that significant vibration impacts would occur during operation of the project.

Vibration from construction equipment at the site may be felt at the nearest exterior areas of the school site. This is probably not a significant impact since these areas are sports fields and playground areas. However, if this is a concern, the most feasible mitigation would be to limit the hours of heavy construction to time periods when school is not in session.

3 (Construction Noise) - Lastly, since the specific construction calculations are not provided in the noise analysis, LSA was not able to reconcile the numbers presented. Utilizing the reference noise levels presented in the analysis along with industry standard usage factors and attenuation equations, it was calculated that construction noise levels at the nearest school building would be approximately 71 dBA Leq (equivalent continuous sound level measured in A-weighted decibels). If the assumption of exterior- to-interior noise reduction presented in the study is used, 20 dBA, interior levels would be 51 dBA Leq and would exceed the City's interior noise standard of 45 dBA Leq. While the City's noise standard is L50, because the average construction noise (Leq) would occur for the duration of an hour, the L50 and Leq would be interchangeable.

The results of our calculations are presented in Section 5.0 (Page 6) of the construction noise analysis report. The noise levels would exceed the 50 dBA exterior noise standard at the nearby residential areas. Construction noise often exceeds noise ordinance limits, and this is generally deemed an unavoidable impact. It was assumed that would be mitigated by limiting the hours of construction.

It appears that LSA did not include any noise reduction for the existing masonry wall at the property line. This would explain the difference in the projected construction noise levels between the two consultants.

*The calculation sheet is included at the end of this memo.
Here is a brief summary of the noise level analysis at the school buildings:*

The loudest piece of equipment (truck) produces a noise level of 88 dBA at a distance of 50 feet. The nearest building is 158 feet from the source. At this distance, the adjusted unmitigated noise level would be 78 dBA. The existing masonry wall at the property line provides approximately 16 dBA of noise reduction, yielding an exterior noise level of 62 dBA at the building face. Finally, the building provides a noise reduction of at least 20 dBA. This results in an interior noise level of 42 dBA in the school building, which meets the 45 dBA interior noise standard.

If you have any questions or require additional information, please do not hesitate to contact me.

Mike Holritz, INCE
Environmental Specialist
BridgeNet | A Tetra Tech Company

AT RESIDENTIAL AREA			
CASE:	1		
Source:	Truck (loudest)		
REFERENCE NZ SOURCE LEVEL	88.0	dBA	Mid
AT REFERENCE DISTANCE OF	50	feet	
NUMBER OF SOURCES	1		
REFERENCE LEVEL	88.0		
AT REFERENCE DISTANCE OF	50	feet	
dB / DOUBLING OF DISTANCE	6	Point Source	
dB / DECADE OF DISTANCE	20		
NOISE REDUCTION (Building, Shielding)	0		
WALL NR	16		
DISTANCE TO NEAREST EQUIP	225	Quietest (Backhoe)	
NOISE LEVEL THERE	58.9	50.9	
DX TO CENTER OF WORK AREA	343		
NOISE LEVEL THERE	55.3		
NZ ORD LIMIT	50	day	

51 dBA to 59 dBA at Residential Area

47 dBA to 55 dBA at Residential Area

AT SCHOOL BLDG			
CASE:	1		
Source:	Truck (loudest)		
REFERENCE NZ SOURCE LEVEL	88.0	dBA	Mid
AT REFERENCE DISTANCE OF	50	feet	
NUMBER OF SOURCES	1		
REFERENCE LEVEL	88.0		
AT REFERENCE DISTANCE OF	50	feet	
dB / DOUBLING OF DISTANCE	6	Point Source	
dB / DECADE OF DISTANCE	20		
NOISE REDUCTION (Building, Shielding)	0		
WALL NR	16		
DISTANCE TO NEAREST EQUIP	158	Quietest (Backhoe)	
NOISE LEVEL THERE	62.0	54.0	
DX TO CENTER OF WORK AREA	200		
NOISE LEVEL THERE	60.0		
NZ ORD LIMIT	45	in session	

54 dBA to 62 dBA at School Bldg Face

assuming 20 dB Bldg NR,

34 dBA to 42 dBA inside School Bldg