

#### **Alamitos Bay Water Quality Enhancement Project**

Marine Advisory Commission – February 9, 2023





## **Alamitos Bay Water Circulation Summary**

#### • Existing Alamitos Bay water circulation

- $\,\circ\,$  Circulation by powerplant cooling pumps (AES & HGS) for over 55 years
- $\,\circ\,$  Supports water quality and public uses
- Phase out of Once through cooling (OTC)
  - $\circ~$  Due to fish impacts (impingement and entrainment)
- No Pumping
  - Immediate effect on circulation
  - Secondary effects on water quality:
    - bacteria concentrations harmful for human contact
    - Increase in temperatures and nutrients harmful for marine life
    - trash accumulation throughout bay
- Alamitos Bay Water Quality Enhancement (ABWQE) Project
  - Maintains existing water quality through circulation
  - Replaces six existing non-fish friendly pump houses with one fish friendly pump house




## Location of Intakes and Outfalls for Once Through Cooling Pumps






3

## **Current Scheduled Dates of Pump Shutdown at AES**





Currently planned shut down dates determined by CEC: AES Unit 1, 2, 6 = Retired AES Unit 3, 4, 5 = December 2023

HGS = December 2029 4 out of 6 units retired






## **Project Update**

- 2020 Draft Conceptual Design considered four alternatives using Unit 6 Existing Intake
- 2021 Unit 6 Existing Intake Inspection
- 2021 Unit 6 Existing Intake Structure Upgrade Evaluation
- 2022 "Pump House" Alternative Conceptual Design
- 2022 Geotechnical Investigation and Survey
- June 21, 2022 City Council Meeting AES MOU Amendment 1
  - \$150K Contribution
  - Site access, term extension, coordination
- 2023 Preliminary Engineering tasks are underway



### "Unit 6 Existing Intake" – Plan View of Inspection Areas





# Water Circulation at AES Facility using a "Pump House"


### **Reduced Fish Impact Pumps**

1.

Replace screen at canal

"fish impingement"






CITY OF

ONGBEACH

### "Pump House" Concept Design – similar to existing large pump stations





## Schedule

#### **Tentative Schedule**

- Existing AES pumps scheduled shutdown December 2023
- 2023 complete Preliminary Engineering
  - Environmental document and regulatory permitting
  - Financial and operational planning

#### **Future Milestones**

- Complete environmental/permitting tasks
- Fund final design, construction, operation
- Complete final design and bid for construction
- Construct



#### Conceptual Design Cost Estimate

 $_{\odot}\,$  To be refined following Preliminary Engineering

#### **Estimated Project Costs**

- $_{\odot}\,$  Circulation System at AES Facility with pump house \$30-45M
  - Currently funded: 30% engineering and initial permitting \$500K
    - AES Contribution \$150K

Estimated Operations, Maintenance and Monitoring • \$2M a year



#### Thank you

Colin Averill, PE Civil Engineer Public Works Engineering Bureau Colin.Averill@longbeach.gov

